
Flexibook

Color Atlas of Physiology

Stefan Silbernagl
Agamemnon Despopoulos

6th edition

basic sciences



Thieme

At a Glance

1	Fundamentals and Cell Physiology	2
2	Nerve and Muscle, Physical Work	42
3	Autonomic Nervous System (ANS)	78
4	Blood	88
5	Respiration	106
6	Acid–Base Homeostasis	138
7	Kidneys, Salt, and Water Balance	148
8	Cardiovascular System	188
9	Thermal Balance and Thermoregulation	224
10	Nutrition and Digestion	228
11	Hormones and Reproduction	268
12	Central Nervous System and Senses	312
13	Appendix	378
	Further Reading	397
	Index	399

Color Atlas of Physiology

6th edition

Stefan Silbernagl, MD
Professor
Institute of Physiology
University of Würzburg
Würzburg, Germany

Agamemnon Despopoulos, MD
Professor
Formerly: Ciba Geigy
Basel

189 color plates by
Ruediger Gay and
Astried Rothenburger



Thieme
Stuttgart · New York

Library of Congress Cataloging-in-Publication Data

Despopoulos, Agamemnon.
[Taschenatlas der Physiologie. English]
Color atlas of physiology / Agamemnon Despopoulos, Stefan Silbernagl; color plates by Ruediger Gay and Astried Rothenburger ; [translator, Suzyon O'Neal Wandrey].
– 6th ed., completely rev. and expanded.
p. ; cm
Includes bibliographical references and index.
Translation of: Taschenatlas der Physiologie. 5th German ed. c2001.
ISBN 978-3-13-545006-3 (alk. paper)
1. Human physiology–Atlases. I. Silbernagl, Stefan. II. Title.
[DNLM: 1. Physiology–Atlases. QT 17 D471c 2009a]
QP34.5.S5313 2009
612–dc22

2008042538

1st German edition 1979
2nd German edition 1983
3rd German edition 1988
4th German edition 1991
5th German edition 2001
6th German edition 2003
7th German edition 2007

1st English edition 1981
2nd English edition 1984
3rd English edition 1986
4th English edition 1991
5th English edition 2003

1st Dutch edition 1981
2nd Dutch edition 2001
3rd Dutch edition 2008

1st Italian edition 1981
2nd Italian edition 2002

1st Japanese edition 1982
2nd Japanese edition 1992
3rd Japanese edition 2005

1st Serbian edition 2006

1st Spanish edition 1982
2nd Spanish edition 1985
3rd Spanish edition 1994
4th Spanish edition 2001

1st Czech edition 1984
2nd Czech edition 1994
3rd Czech edition 2004

1st French edition 1985
2nd French edition 1992
3rd French edition 2001

1st Turkish edition 1986
2nd Turkish edition 1997

1st Greek edition 1989

1st Chinese edition 1991

1st Polish edition 1994

1st Portuguese edition 2003

1st Hungarian edition 1994
2nd Hungarian edition 1996

1st Indonesion edition 2000

Translated by Suzyon O'Neal Wandrey and Rachel Swift

Illustrated by Atelier Gay + Rothenburger, Sternenfels, Germany

© 1981, 2009 Georg Thieme Verlag KG
Rüdigerstraße 14, 70469 Stuttgart, Germany
http://www.thieme.de
Thieme New York, 333 Seventh Avenue,
New York, NY 10001, USA
http://www.thieme.com

Cover design: Thieme Publishing Group
Typesetting by: Druckhaus Götz GmbH,
Ludwigsburg, Germany
Printed in Germany by: Offizin Anderson Nexö, Zwenkau

ISBN 978-3-13-545006-3 1 2 3 4 5

Important Note: Medicine is an ever-changing science undergoing continual development. Research and clinical experience are continually expanding our knowledge, in particular our knowledge of proper treatment and drug therapy. Insofar as this book mentions any dosage or application, readers may rest assured that the authors, editors, and publishers have made every effort to ensure that such references are in accordance with **the state of knowledge at the time of production of the book**.

Nevertheless, this does not involve, imply, or express any guarantee or responsibility on the part of the publishers in respect to any dosage instructions and forms of applications stated in the book. **Every user is requested to examine carefully** the manufacturers' leaflets accompanying each drug and to check, if necessary in consultation with a physician or specialist, whether the dosage schedules mentioned therein or the contraindications stated by the manufacturers differ from the statements made in the present book. Such examination is particularly important with drugs that are either rarely used or have been newly released on the market. Every dosage schedule or every form of application used is entirely at the user's own risk and responsibility. The authors and publishers request every user to report to the publishers any discrepancies or inaccuracies noticed. If errors in this work are found after publication, errata will be posted at www.thieme.com on the product description page.

Some of the product names, patents, and registered designs referred to in this book are in fact registered trademarks or proprietary names even though specific reference to this fact is not always made in the text. Therefore, the appearance of a name without designation as proprietary is not to be construed as a representation by the publisher that it is in the public domain.

This book, including all parts thereof, is legally protected by copyright. Any use, exploitation, or commercialization outside the narrow limits set by copyright legislation, without the publisher's consent, is illegal and liable to prosecution. This applies in particular to photostat reproduction, copying, mimeographing or duplication of any kind, translating, preparation of microfilms, and electronic data processing and storage.

Preface to the Sixth Edition

The base of knowledge in many sectors of physiology has again grown considerably in magnitude and depth since the last edition of this book was published. Many advances, especially the successful application of the methods of molecular biology and gene technology brought completely new insight into cell signalling and communication as well as into many integrative functions of the body. This made it necessary to edit and, in some cases, enlarge some parts of the book, especially the chapters on blood clotting, water homeostasis, regulation of body weight, iron metabolism, sleep-wake cycle, memory and sound reception.

In recent years, more pathophysiological aspects and clinical examples have been added to the curricula of medical physiology. To make allowance for this development also in this color atlas, the numerous references to clinical medicine are marked by **blue margin bars**, and **pathophysiological and clinical key-words** are attached at the bottom of each text page. They should make it easier to recognize the relevance of the physiological facts for clinical medicine at a glance, and to find quickly more information on these topics in textbooks of pathophysiology (e.g. in our *Color Atlas of Pathophysiology*) and clinical medicine.

I am very grateful for the many helpful comments from attentive readers and for the welcome feedback from my peers, this time especially from Prof. R. *Renate Lüllmann-Rauch*, Kiel, Prof. *Gerhardt Burckhardt*, Göttingen, Prof. *Detlev Drenckhahn*, Würzburg, and Dr. *Michael Fischer*, Mainz as well as from my colleagues and staff at the Department of Physiology in Würzburg. It was again a great pleasure to work with *Rüdiger Gay* and *Astried Rothenburger*, to whom I am deeply indebted for revising many illustrations in the book and for designing a number of new color plates. To them I extent my sincere thanks. I am also indebted to the publishing staff, *Rachel Swift*, a very competent editor, and *Elisabeth Kurz*, for invaluable production assistance. I would also like to thank *Katharina Völker* for her ever observant and conscientious assistance in preparing the index.

I hope that also the 6th Edition of the *Color Atlas of Physiology* will prove to be a valuable tool for helping students better understand physiological correlates, and that it will be a valuable reference for practicing physicians and scientists, to help them recall previously learned information and gain new insights in physiology.

Würzburg, September 2008
*Stefan Silbernagl**

* e-mail: stefan.silbernagl@mail.uni-wuerzburg.de

Preface to the First Edition

In the modern world, visual pathways have outdistanced other avenues for informational input. This book takes advantage of the economy of visual representation to indicate the simultaneity and multiplicity of physiological phenomena. Although some subjects lend themselves more readily than others to this treatment, inclusive rather than selective coverage of the key elements of physiology has been attempted.

Clearly, this book of little more than 300 pages, only half of which are textual, cannot be considered as a primary source for the serious student of physiology. Nevertheless, it does contain most of the basic principles and facts taught in a medical school introductory course. Each unit of text and illustration can serve initially as an overview for introduction to the subject and subsequently as a concise review of the material. The contents are as current as the publishing art permits and include both classical information for the beginning students as well as recent details and trends for the advanced student.

A book of this nature is inevitably derivative, but many of the representations are new and, we hope, innovative. A number of people have contributed directly and indirectly to the completion of this volume, but none more than *Sarah Jones*, who gave much more than editorial assistance. Acknowledgement of helpful criticism and advice is due also to Drs. *R. Greger, A. Ratner, J. Weiss,* and *S. Wood,* and Prof. *H. Seller*. We are grateful to *Joy Wieser* for her help in checking the proofs. *Wolf-Rüdiger* and *Barbara Gay* are especially recognized, not only for their art work, but for their conceptual contributions as well. The publishers, Georg Thieme Verlag and Deutscher Taschenbuch Verlag, contributed valuable assistance based on extensive experience; an author could wish for no better relationship. Finally, special recognition to Dr. *Walter Kumpmann* for inspiring the project and for his unquestioning confidence in the authors.

Basel and Innsbruck, Summer 1979
Agamemnon Despopoulos
Stefan Silbernagl

From the Preface to the Third Edition

The first German edition of this book was already in press when, on November 2nd, 1979, *Agamennon Despopoulos* and his wife, *Sarah Jones-Despopoulos* put to sea from Bizerta, Tunisia. Their intention was to cross the Atlantic in their sailing boat. This was the last that was ever heard of them and we have had to abandon all hope of seeing them again.

Without the creative enthusiasm of Agamennon Despopoulos, it is doubtful whether this book would have been possible; without his personal support it has not been easy to continue with the project. Whilst keeping in mind our original aims, I have completely revised the book, incorporating the latest advances in the field of physiology as well as the welcome suggestions provided by readers of the earlier edition, to whom I extend my thanks for their active interest.

Würzburg, Fall 1985
Stefan Silbernagl



Dr. Agamemnon Despopoulos

Born 1924 in New York; Professor of Physiology at the University of New Mexico. Albuquerque, USA, until 1971; thereafter scientific adviser to CIBA-GEIGY, Basel.

Table of Contents

1 Fundamentals and Cell Physiology 2

The Body: an Open System with an Internal Environment ⋯ **2**
Control and Regulation ⋯ **4**
The Cell ⋯ **8**
Transport In, Through and Between Cells ⋯ **16**
Passive Transport by Means of Diffusion ⋯ **20**
Osmosis, Filtration and Convection ⋯ **24**
Active Transport ⋯ **26**
Cell Migration ⋯ **30**
Electrical Membrane Potentials and Ion Channels ⋯ **32**
Role of Ca^{2+} in Cell Regulation ⋯ **36**
Energy Production and Metabolism ⋯ **38**

2 Nerve and Muscle, Physical Work 42

Neuron Structure and Function ⋯ **42**
Resting Membrane Potential ⋯ **44**
Action Potential ⋯ **46**
Propagation of Action Potentials in Nerve Fiber ⋯ **48**
Artificial Stimulation of Nerve Cells ⋯ **50**
Synaptic Transmission ⋯ **50**
Motor End-plate ⋯ **56**
Motility and Muscle Types ⋯ **58**
Motor Unit of Skeletal Muscle ⋯ **58**
Contractile Apparatus of Striated Muscle ⋯ **60**
Contraction of Striated Muscle ⋯ **62**
Mechanical Features of Skeletal Muscle ⋯ **66**
Smooth Muscle ⋯ **70**
Energy Supply for Muscle Contraction ⋯ **72**
Physical Work ⋯ **74**
Physical Fitness and Training ⋯ **76**

3 Autonomic Nervous System (ANS) 78

Organization of the Autonomic Nervous System (ANS) ⋯ **78**
Acetylcholines and Cholinergic Transmission ⋯ **82**
Catecholamines, Adrenergic Transmission and Adrenoceptors ⋯ **84**
Adrenal Medulla ⋯ **86**
Non-cholinergic, Non-adrenergic Transmitters ⋯ **86**

4 Blood 88

Composition and Function of Blood ⋯ **88**
Iron Metabolism and Erythropoiesis ⋯ **90**
Flow Properties of Blood ⋯ **92**
Plasma, Ion Distribution ⋯ **92**

Immune System ⋯ **94**
Hypersensitivity Reactions (Allergies) ⋯ **100**
Blood Groups ⋯ **100**
Hemostasis ⋯ **102**
Fibrinolysis and Thromboprotection ⋯ **104**

5 Respiration **106**

Lung Function, Respiration ⋯ **106**
Mechanics of Breathing ⋯ **108**
Purification of Respiratory Air ⋯ **110**
Artificial Respiration ⋯ **110**
Pneumothorax ⋯ **110**
Lung Volumes and their Measurement ⋯ **112**
Dead Space, Residual Volume, Airway Resistance ⋯ **114**
Pressure–Volume Curve, Respiratory Work ⋯ **116**
Surface Tension, Surfactant ⋯ **118**
Dynamic Lung Function Tests ⋯ **118**
Pulmonary Gas Exchange ⋯ **120**
Pulmonary Blood Flow, Ventilation–Perfusion Ratio ⋯ **122**
CO_2 Transport in Blood ⋯ **124**
CO_2 Binding in Blood, CO_2 in CSF ⋯ **126**
CO_2 in Cerebrospinal Fluid ⋯ **126**
Binding and Transport of O_2 in Blood ⋯ **128**
Internal (Tissue) Respiration, Hypoxia ⋯ **130**
Respiratory Control and Stimulation ⋯ **132**
Effects of Diving on Respiration ⋯ **134**
Effects of High Altitude on Respiration ⋯ **136**
Oxygen Toxicity ⋯ **136**

6 Acid–Base Homeostasis **138**

pH, pH Buffers, Acid–Base Balance ⋯ **138**
Bicarbonate/Carbon Dioxide Buffer ⋯ **140**
Acidosis and Alkalosis ⋯ **142**
Assessment of Acid–Base Status ⋯ **146**

7 Kidneys, Salt, and Water Balance **148**

Kidney Structure and Function ⋯ **148**
Renal Circulation ⋯ **150**
Glomerular Filtration and Clearance ⋯ **152**
Transport Processes at the Nephron ⋯ **154**
Reabsorption of Organic Substances ⋯ **158**
Excretion of Organic Substances ⋯ **160**
Reabsorption of Na^+ and Cl^- ⋯ **162**
Reabsorption of Water, Formation of Concentrated Urine ⋯ **164**
Body Fluid Homeostasis ⋯ **168**
Salt and Water Regulation ⋯ **170**
Diuresis and Diuretics ⋯ **174**
The Kidney and Acid–Base Balance ⋯ **176**

Reabsorption and Excretion of Phosphate, Ca^{2+} and Mg^{2+} ⋯ **180**
Potassium Balance ⋯ **182**
Tubuloglomerular Feedback, Renin–Angiotensin System ⋯ **186**

8 Cardiovascular System **188**

Overview ⋯ **188**
Blood Vessels and Blood Flow ⋯ **190**
Cardiac Cycle ⋯ **192**
Cardiac Impulse Generation and Conduction ⋯ **194**
Electrocardiogram (ECG) ⋯ **198**
Excitation in Electrolyte Disturbances ⋯ **200**
Cardiac Arrhythmias ⋯ **202**
Ventricular Pressure–Volume Relationships ⋯ **204**
Cardiac Work and Cardiac Power ⋯ **204**
Regulation of Stroke Volume ⋯ **206**
Venous Return ⋯ **206**
Arterial Blood Pressure ⋯ **208**
Endothelial Exchange Processes ⋯ **210**
Myocardial Oxygen Supply ⋯ **212**
Regulation of the Circulation ⋯ **214**
Circulatory Shock ⋯ **220**
Fetal and Neonatal Circulation ⋯ **222**

9 Thermal Balance and Thermoregulation **224**

Thermal Balance ⋯ **224**
Thermoregulation ⋯ **226**

10 Nutrition and Digestion **228**

Nutrition ⋯ **228**
Energy Metabolism and Calorimetry ⋯ **230**
Energy Homeostasis and Body Weight ⋯ **232**
Gastrointestinal (GI) Tract: Overview, Immune Defense, Blood Flow ⋯ **234**
Neural and Hormonal Integration ⋯ **236**
Saliva ⋯ **238**
Deglutition ⋯ **240**
Vomiting ⋯ **240**
Stomach Structure and Motility ⋯ **242**
Gastric Juice ⋯ **244**
Small Intestinal Function ⋯ **246**
Pancreas ⋯ **248**
Bile ⋯ **250**
Excretory Liver Function, Bilirubin ⋯ **252**
Lipid Digestion ⋯ **254**
Lipid Distribution and Storage ⋯ **256**
Digestion and Absorption of Carbohydrates and Protein ⋯ **260**
Vitamin Absorption ⋯ **262**
Water and Mineral Absorption ⋯ **264**
Large Intestine, Defecation, Feces ⋯ **266**

11 Hormones and Reproduction 268

Integrative Systems of the Body ⋯ **268**
Hormones ⋯ **270**
Humoral Signals: Control and Effects ⋯ **274**
Cellular Transmission of Signals from Extracellular Messengers ⋯ **276**
Hypothalamic–Pituitary System ⋯ **282**
Carbohydrate Metabolism and Pancreatic Hormones ⋯ **284**
Thyroid Hormones ⋯ **288**
Calcium and Phosphate Metabolism ⋯ **292**
Biosynthesis of Steroid Hormones ⋯ **296**
Adrenal Cortex and Glucocorticoid Synthesis ⋯ **298**
Oogenesis and the Menstrual Cycle ⋯ **300**
Hormonal Control of the Menstrual Cycle ⋯ **302**
Estrogens, Progesterone ⋯ **304**
Progesterone, Prolactin, Oxytocin ⋯ **305**
Hormonal Control of Pregnancy and Birth ⋯ **306**
Androgens and Testicular Function ⋯ **308**
Sexual Response, Intercourse and Fertilization ⋯ **310**

12 Central Nervous System and Senses 312

Central Nervous System ⋯ **312**
Cerebrospinal Fluid ⋯ **312**
Stimulus Reception and Processing ⋯ **314**
Sensory Functions of the Skin ⋯ **316**
Proprioception, Stretch Reflex ⋯ **318**
Nociception and Pain ⋯ **320**
Polysynaptic Reflexes ⋯ **322**
Synaptic Inhibition ⋯ **322**
Central Conduction of Sensory Input ⋯ **324**
Movement ⋯ **326**
Hypothalamus, Limbic System ⋯ **332**
Cerebral Cortex, Electroencephalogram (EEG) ⋯ **334**
Circadian Rhythms, Sleep–Wake Cycle ⋯ **336**
Consciousness, Sleep ⋯ **338**
Learning, Memory, Language ⋯ **340**
Glia ⋯ **344**
Sense of Taste ⋯ **344**
Sense of Smell ⋯ **346**
Sense of Balance ⋯ **348**
Eye Structure, Tear Fluid, Aqueous Humor ⋯ **350**
Optical Apparatus of the Eye ⋯ **352**
Visual Acuity, Photosensors ⋯ **354**
Adaptation of the Eye to Different Light Intensities ⋯ **358**
Retinal Processing of Visual Stimuli ⋯ **360**
Color Vision ⋯ **362**
Visual Field, Visual Pathway, Central Processing of Visual Stimuli ⋯ **364**
Eye Movements, Stereoscopic Vision, Depth Perception ⋯ **366**
Physical Principles of Sound—Sound Stimulus and Perception ⋯ **368**
Conduction of Sound, Sound Sensors ⋯ **370**

Central Processing of Acoustic Information ⋯ **374**
Voice and Speech ⋯ **376**

13 Appendix **378**

Dimensions and Units ⋯ **378**
Powers and Logarithms ⋯ **386**
Logarithms, Graphic Representation of Data ⋯ **387**
Reference Values in Physiology ⋯ **390**
Important Equations in Physiology ⋯ **394**

Further Reading **397**

Index **399**

Color Atlas of Physiology

6th edition

The Body: an Open System with an Internal Environment

"… If we break up a living organism by isolating its different parts, it is only for the sake of ease in analysis and by no means in order to conceive them separately. Indeed, when we wish to ascribe to a physiological quality its value and true significance, we must always refer it to the whole and draw our final conclusions only in relation to its effects on the whole."

Claude Bernard (1865)


The existence of unicellular organisms is the epitome of life in its simplest form. Even simple protists must meet two basic but essentially conflicting demands in order to survive. A unicellular organism must, on the one hand, isolate itself from the seeming disorder of its inanimate surroundings, yet, as an "open system" (→ p. 40), it is dependent on its environment for the exchange of heat, oxygen, nutrients, waste materials, and information.

"Isolation" is mainly ensured by the cell membrane, the hydrophobic properties of which prevent the potentially fatal mixing of hydrophilic components in watery solutions inside and outside the cell. Protein molecules within the cell membrane ensure the permeability of the membrane barrier. They may exist in the form of *pores* (*channels*) or as more complex transport proteins known as *carriers* (→ p. 26 ff.). Both types are selective for certain substances, and their activity is usually regulated. The cell membrane is relatively well permeable to hydrophobic molecules such as gases. This is useful for the exchange of O_2 and CO_2 and for the uptake of lipophilic signal substances, yet exposes the cell to poisonous gases such as carbon monoxide (CO) and lipophilic noxae such as organic solvents. The cell membrane also contains other proteins—namely, receptors and enzymes. *Receptors* receive signals from the external environment and convey the information to the interior of the cell (signal transduction), and *enzymes* enable the cell to metabolize extracellular substrates.


Let us imagine the primordial sea as the external environment of the unicellular organism (→ **A**). This milieu remains more or less constant, although the organism absorbs nutrients from it and excretes waste into it. In spite of its simple structure, the unicellular organism is capable of eliciting motor responses to signals from the environment. This is achieved by moving its pseudopodia or flagella, for example, in response to changes in the food concentration.

The evolution from unicellular organisms to multicellular organisms, the transition from specialized cell groups to organs, the emergence of the two sexes, the coexistence of individuals in social groups, and the transition from water to land have tremendously increased the efficiency, survival, radius of action, and independence of living organisms. This process required the simultaneous development of a complex infrastructure within the organism. Nonetheless, the individual cells of the body still need a milieu like that of the primordial sea for life and survival. Today, the **extracellular fluid** is responsible for providing constant environmental conditions (→ **B**), but the volume of the fluid is no longer infinite. In fact, it is even smaller than the intracellular volume (→ p. 168). Because of their metabolic activity, the cells would quickly deplete the oxygen and nutrient stores within the fluids and flood their surroundings with waste products if organs capable of maintaining a **stable internal environment** had not developed. This is achieved through **homeostasis**, a process by which physiologic self-regulatory mechanisms (see below) maintain steady states in the body through coordinated physiological activity. Specialized organs ensure the continuous absorption of nutrients, electrolytes and water and the excretion of waste products via the urine and feces. The *circulating blood* connects the organs to every inch of the body, and the exchange of materials between the blood and the intercellular spaces (*interstices*) creates a stable environment for the cells. Organs such as the digestive tract and liver absorb nutrients and make them available by processing, metabolizing and distributing them throughout the body. The lung is responsible for the exchange of gases (O_2 intake, CO_2 elimination), the liver and kidney for the ▶

A. Unicellular organism in the constant external environment of the primordial sea



B. Maintenance of a stable internal environment in humans



▶ excretion of waste and foreign substances, and the skin for the release of heat. The kidney and lungs also play an important role in regulating the internal environment, e.g., water content, osmolality, ion concentrations, pH (kidney, lungs) and O_2 and CO_2 pressure (lungs) (→ **B**).


The specialization of cells and organs for specific tasks naturally requires **integration**, which is achieved by convective transport over long distances (circulation, respiratory tract), humoral transfer of information (hormones), and transmission of electrical signals in the nervous system, to name a few examples. These mechanisms are responsible for supply and disposal and thereby maintain a stable internal environment, even under conditions of extremely high demand and stress. Moreover, they control and regulate functions that ensure survival in the sense of **preservation of the species**. Important factors in this process include not only the timely development of reproductive organs and the availability of fertilizable gametes at sexual maturity, but also the control of erection, ejaculation, fertilization, and nidation. Others include the coordination of functions in the mother and fetus during pregnancy and regulation of the birth process and the lactation period.

The **central nervous system** (CNS) processes signals from peripheral sensors (single sensory cells or sensory organs), activates outwardly directed effectors (e.g., **skeletal muscles**), and influences the endocrine **glands**. The CNS is the focus of attention when studying human or animal **behavior**. It helps us to locate food and water and protects us from heat or cold. The central nervous system also plays a role in partner selection, concern for offspring even long after their birth, and integration into social systems. The CNS is also involved in the development, expression, and processing of emotions such as desire, listlessness, curiosity, wishfulness, happiness, anger, wrath, and envy and of traits such as creativeness, inquisitiveness, self-awareness, and responsibility. This goes far beyond the scope of physiology—which in the narrower sense is the study of the functions of the body—and, hence, of this book. Although behavioral science, sociology, and psychology are disciplines that border on physiology, true bridges between them and physiology have been established only in exceptional cases.


Control and Regulation

In order to have useful cooperation between the specialized organs of the body, their functions must be adjusted to meet specific needs. In other words, the organs must be subject to control and regulation. **Control** implies that a *controlled variable* such as the blood pressure is subject to selective external modification, for example, through alteration of the heart rate (→ p. 218). Because many other factors also affect the blood pressure and heart rate, the controlled variable can only be kept constant by continuously measuring the current blood pressure, comparing it with the reference signal (*set point*), and continuously correcting any deviations. If the blood pressure drops—due, for example, to rapidly standing up from a recumbent position—the heart rate will increase until the blood pressure has been reasonably adjusted. Once the blood pressure has risen above a certain limit, the heart rate will decrease again and the blood pressure will normalize. This type of *closed-loop control* is called a **negative feedback control system** or a **control circuit** (→ **C1**). It consists of a *controller* with a programmed *set-point* value (target value) and *control elements* (*effectors)* that can adjust the *controlled variable* to the set point. The system also includes *sensors* that continuously measure the actual value of the controlled variable of interest and report it (feedback) to the controller, which compares the actual value of the controlled variable with the set-point value and makes the necessary adjustments if disturbance-related discrepancies have occurred. The control system operates either from within the organ itself (*autoregulation*) or via a *superordinate organ* such as the central nervous system or hormone glands. Unlike simple control, the elements of a control circuit can work rather imprecisely without causing a deviation from the set point (at least on average). Moreover, control circuits are capable of responding to unexpected disturbances. In the case of blood pressure regulation (→ **C2**), for example, the system can respond to events such as orthostasis (→ p. 204) or sudden blood loss. ▶

C. Control circuit



1
Control circuit: principle



2
Control circuit: blood pressure


▶ The type of control circuits described above keep the controlled variables constant when **disturbance variables** cause the controlled variable to deviate from the set point (→ **D2**). Within the body, the set point is rarely invariable, but can be "shifted" when requirements of higher priority make such a change necessary. In this case, it is the **variation of the set point** that creates the discrepancy between the nominal and actual values, thus leading to the activation of regulatory elements (→ **D3**). Since the regulatory process is then triggered by variation of the set point (and not by disturbance variables), this is called **servocontrol** or **servomechanism**. Fever (→ p. 226) and the adjustment of muscle length by muscle spindles and γ-motor neurons (→ p. 318) are examples of servocontrol.

In addition to relatively simple variables such as blood pressure, cellular pH, muscle length, body weight and the plasma glucose concentration, the body also regulates complex sequences of events such as fertilization, pregnancy, growth and organ differentiation, as well as sensory stimulus processing and the motor activity of skeletal muscles, e.g., to maintain equilibrium while running. The regulatory process may take parts of a second (e.g., purposeful movement) to several years (e.g., the growth process).


In the control circuits described above, the controlled variables are kept constant on average, with variably large, wave-like deviations. The sudden emergence of a disturbance variable causes larger deviations that quickly normalize in a stable control circuit (→ **E**, test subject no. 1). The **degree of deviation** may be slight in some cases but substantial in others. The latter is true, for example, for the blood glucose concentration, which nearly doubles after meals. This type of regulation obviously functions only to prevent extreme rises and falls (e.g., hyper- or hypoglycemia) or chronic deviation of the controlled variable. More precise maintenance of the controlled variable requires a higher level of regulatory sensitivity (*high amplification factor*). However, this extends the settling time (→ **E**, subject no. 3) and can lead to regulatory instability, i.e., a situation where the actual value oscillates back and forth between extremes (*unstable oscillation*, → **E**, subject no. 4).

Oscillation of a controlled variable in response to a disturbance variable can be *attenuated* by either of two mechanisms. First, sensors with differential characteristics (*D sensors*) ensure that the intensity of the sensor signal increases in proportion with the **rate of deviation** of the controlled variable from the set point (→ p. 314 ff.). Second, **feedforward control** ensures that information regarding the expected intensity of disturbance is reported to the controller *before* the value of the controlled variable has changed at all. Feedforward control can be explained by example of physiologic thermoregulation, a process in which cold receptors on the skin trigger counterregulation before a change in the controlled value (core temperature of the body) has actually occurred (→ p. 226). The disadvantage of having *only* D sensors in the control circuit can be demonstrated by example of arterial pressosensors (= pressoreceptors) in acute blood pressure regulation. Very slow but steady changes, as observed in the development of arterial hypertension, then escape regulation. In fact, a rapid drop in the blood pressure of a hypertensive patient will potentially cause a counterregulatory increase in blood pressure. Therefore, other control systems are needed to ensure proper long-term blood pressure regulation.

D. Control circuit response to disturbance or set point (SP) deviation



E. Blood pressure control after suddenly standing erect



The cell is the smallest functional unit of a living organism. In other words, a cell (and no smaller unit) is able to perform essential vital functions such as metabolism, growth, movement, reproduction, and hereditary transmission (W. Roux) (→ p. 4). Growth, reproduction, and hereditary transmission can be achieved by *cell division*.


Cell components: All cells consist of a cell membrane, cytosol or cytoplasm (ca. 50 vol.%), and membrane-bound subcellular structures known as *organelles* (→ **A, B**). The organelles of eukaryotic cells are highly specialized. For instance, the genetic material of the cell is concentrated in the cell nucleus, whereas "digestive" enzymes are located in the lysosomes. Oxidative ATP production takes place in the mitochondria.

The **cell nucleus** contains a liquid known as karyolymph, a nucleolus, and chromatin. Chromatin contains deoxyribonucleic acids (**DNA**), the carriers of genetic information. Two strands of DNA forming a *double helix* (up to 7 cm in length) are twisted and folded to form chromosomes 10 μm in length. Humans normally have 46 chromosomes, consisting of 22 autosomal pairs and the chromosomes that determine the sex (XX in females, XY in males). DNA is made up of a strand of three-part molecules called *nucleotides*, each of which consists of a pentose (deoxyribose) molecule, a phosphate group, and a base. Each sugar molecule of the monotonic sugar–phosphate backbone of the strands (…deoxyribose – phosphate–deoxyribose…) is attached to one of four different bases. The sequence of bases represents the **genetic code** for each of the roughly 100 000 different proteins that a cell produces during its lifetime (**gene expression**). In a DNA double helix, each base in one strand of DNA is bonded to its complementary base in the other strand according to the rule: adenine (A) with thymine (T) and guanine (G) with cytosine (C). The base sequence of one strand of the double helix (→ **E**) is always a "mirror image" of the opposite strand. Therefore, one strand can be used as a template for making a new complementary strand, the information content of which is identical to that of the original. In cell division, this process is the means by which duplication of genetic information (**replication**) is achieved.

Messenger RNA (**mRNA**) is responsible for code transmission, that is, passage of coding sequences from DNA in the nucleus (base sequence) for protein synthesis in the cytosol (amino acid sequence) (→ **C1**). mRNA is formed in the nucleus and differs from DNA in that it consists of only a single strand and that it contains ribose instead of deoxyribose, and uracil (U) instead of thymine. In DNA, each amino acid (e.g., glutamate, → **E**) needed for synthesis of a given protein is coded by a set of three adjacent bases called a *codon* or *triplet* (C–T–C in the case of glutamate). In order to transcribe the DNA triplet, mRNA must form a complementary codon (e.g., G–A–G for glutamate). The relatively small transfer RNA (**tRNA**) molecule is responsible for reading the codon in the ribosomes (→ **C2**). tRNA contains a complementary codon called the *anticodon* for this purpose. The anticodon for glutamate is C–U–C (→ **E**).

RNA synthesis in the nucleus is controlled by *RNA polymerases* (types I–III). Their effect on DNA is normally blocked by a *repressor protein*. Phosphorylation of the polymerase occurs if the repressor is eliminated (de-repression) and the *general transcription factors* attach to the so-called promoter sequence of the DNA molecule (T–A–T–A in the case of polymerase II). Once activated, it separates the two strands of DNA at a particular site so that the code on one of the strands can be read and transcribed to form mRNA (**transcription**, → **C1a, D**). The heterogeneous nuclear RNA (*hnRNA*) molecules synthesized by the polymerase have a characteristic "cap" at their 5′ end and a polyadenine "tail" (A–A–A–…) at the 3′ end (→ **D**). Once synthesized, they are immediately "enveloped" in a protein coat, yielding heterogeneous nuclear ribonucleoprotein (*hnRNP*) particles. The *primary RNA* or *pre-mRNA* of hnRNA contains both coding sequences (*exons*) and non-coding sequences (*introns*). The exons code for amino acid sequences of the proteins to be synthesized, whereas the introns are not involved in the coding process. Introns may contain 100 to 10 000 nucleotides; they are removed from the primary mRNA strand by **splicing** (→ **C1b, D**) and then degraded. The introns, themselves, contain the information on the exact splicing site. Splicing is ATP-dependent and requires ▶

A. Cell organelles (epithelial cell)



B. Cell structure (epithelial cell) in electron micrograph




Photo: W. Pfaller

▶ the interaction of a number of proteins within a ribonucleoprotein complex called the *spliceosome*. Introns usually make up the lion's share of pre-mRNA molecules. For example, they make up 95% of the nucleotide chain of coagulation factor VIII, which contains 25 introns. mRNA can also be modified (e.g., through methylation) during the course of **posttranscriptional modification**.


RNA now exits the nucleus through **nuclear pores** (around 4000 per nucleus) and enters the cytosol (→ **C1c**). Nuclear pores are high-molecular-weight protein complexes (125 MDa) located within the nuclear envelope. They allow large molecules such as transcription factors, RNA polymerases or cytoplasmic steroid hormone receptors to pass into the nucleus, nuclear molecules such as mRNA and tRNA to pass out of the nucleus, and other molecules such as ribosomal proteins to travel both ways. The (ATP-dependent) passage of a molecule in either direction cannot occur without the help of a specific signal that guides the molecule into the pore. The abovementioned *5′ cap* is responsible for the exit of mRNA from the nucleus, and one or two specific sequences of a few (mostly cationic) amino acids are required as the signal for the entry of proteins into the nucleus. These sequences form part of the peptide chain of such *nuclear proteins* and probably create a peptide loop on the protein's surface. In the case of the cytoplasmic receptor for glucocorticoids (→ p. 280), the *nuclear localization signal* is masked by a chaperone protein (heat shock protein 90, hsp90) in the absence of the glucocorticoid, and is released only after the hormone binds, thereby freeing hsp90 from the receptor. The "activated" receptor then reaches the cell nucleus, where it binds to specific DNA sequences and controls specific genes.

The **nuclear envelope** consists of *two* membranes (= two phospholipid bilayers) that merge at the nuclear pores. The two membranes consist of different materials. The external membrane is continuous with the membrane of the endoplasmic reticulum (ER), which is described below (→ **F**).


The mRNA exported from the nucleus travels to the **ribosomes** (→ **C1**), which either float freely in the cytosol or are bound to the cytosolic side of the endoplasmic reticulum, as described below. Each ribosome is made up of dozens of proteins associated with a number of structural RNA molecules called *ribosomal RNA* (**rRNA**). The two subunits of the ribosome are first transcribed from numerous rRNA genes in the **nucleolus**, then separately exit the cell nucleus through the nuclear pores. Assembled together to form a ribosome, they now comprise the biochemical "machinery" for **protein synthesis** (**translation**) (→ **C2**). Synthesis of a peptide chain also requires the presence of specific tRNA molecules (at least one for each of the 21 proteinogenous amino acids). In this case, the target amino acid is bound to the C–C–A end of the tRNA molecule (same in all tRNAs), and the corresponding anticodon that recognizes the mRNA codon is located at the other end (→ **E**). Each ribosome has two tRNA binding sites: one for the last incorporated amino acid and another for the one beside it (not shown in **E**). Protein synthesis begins when the *start codon* is read and ends once the *stop codon* has been reached. The ribosome then breaks down into its two subunits and releases the mRNA (→ **C2**). Ribosomes can add approximately 10–20 amino acids per second. However, since an mRNA strand is usually translated simultaneously by many ribosomes (*polyribosomes* or *polysomes*) at different sites, a protein is synthesized much faster than its mRNA. In the bone marrow, for example, a total of around 5×10^{14} hemoglobin copies containing 574 amino acids each are produced per second.

The **endoplasmic reticulum** (**ER**, → **C, F**) plays a central role in the *synthesis of proteins and lipids*; it also serves as an intracellular Ca^{2+} *store* (→ p. 17 A). The ER consists of a net-like system of interconnected branched channels and flat cavities bounded by a membrane. The enclosed spaces (*cisterns*) make up around 10% of the cell volume, and the membrane comprises up to 70% of the membrane mass of a cell. *Ribosomes* can attach to the cytosolic surface of parts of the ER, forming a **rough endoplasmic reticulum** (RER). These ribosomes synthesize export proteins as well as transmembrane proteins (→ **G**) for the plasma membrane, endoplasmic reticulum, Golgi appara- ▶


C. Transcription and translation



D. Transcription and splicing



E. Protein coding in DNA and RNA



▶ tus, lysosomes, etc. The start of protein synthesis (at the amino end) by such ribosomes (still unattached) induces a *signal sequence* to which a signal recognition particle (SRP) in the cytosol attaches. As a result, (a) synthesis is temporarily halted and (b) the ribosome (mediated by the SRP and a SRP receptor) attaches to a ribosome receptor on the ER membrane. After that, synthesis continues. In *synthesis of export protein*, a translocator protein conveys the peptide chain to the cisternal space once synthesis is completed. *Synthesis* of *membrane proteins* is interrupted several times (depending on the number of membrane-spanning domains (→ **G2**) by translocator protein closure, and the corresponding (hydrophobic) peptide sequence is pushed into the phospholipid membrane. The **smooth endoplasmic reticulum** (**SER**) contains no ribosomes and is the *production site of lipids* (e.g., for lipoproteins, → p. 256 ff.) and other substances. The ER membrane containing the synthesized membrane proteins or export proteins forms vesicles which are transported to the Golgi apparatus.

The Golgi complex or **Golgi apparatus** (→ **F**) has sequentially linked functional compartments for further processing of products from the endoplasmic reticulum. It consists of a *cis*-Golgi network (entry side facing the ER), stacked flattened cisternae (Golgi stacks) and a *trans*-Golgi network (sorting and distribution). Functions of the Golgi complex:

- polysaccharide synthesis;
- protein processing (**posttranslational modification**), e.g., glycosylation of membrane proteins on certain amino acids (in part in the ER) that are later borne as glycocalyces on the external cell surface (see below) and γ-carboxylation of glutamate residues (→ p. 102);
- phosphorylation of sugars of glycoproteins (e.g., to mannose-6-phosphate, as described below);
- "packaging" of proteins meant for export into *secretory vesicles* (secretory granules), the contents of which are exocytosed into the extracellular space (see p. 248, for example).


Hence, the Golgi apparatus represents a central **modification, sorting and distribution center** for proteins and lipids received from the endoplasmic reticulum.

Regulation of gene expression takes place on the level of transcription (→ **C1a**), RNA modification (→ **C1b**), mRNA export (→ **C1c**), RNA degradation (→ **C1d**), translation (→ **C1e**), modification and sorting (→ **F,f**), and protein degradation (→ **F,g**).

The **mitochondria** (→ **A, B**; p. 17 B) are the site of oxidation of carbohydrates and lipids to CO_2 and H_2O and associated O_2 expenditure. The Krebs cycle (citric acid cycle), respiratory chain and related ATP synthesis also occur in mitochondria. Cells intensely active in metabolic and transport activities are rich in mitochondria—e.g., hepatocytes, intestinal cells, and renal epithelial cells. Mitochondria are enclosed in a double membrane consisting of a smooth outer membrane and an inner membrane. The latter is deeply infolded, forming a series of projections (cristae); it also has important transport functions (→ p. 17 B). Mitochondria probably evolved as a result of symbiosis between aerobic bacteria and anaerobic cells (*symbiosis hypothesis*). The mitochondrial DNA (mtDNA) of bacterial origin and the double membrane of mitochondria are relicts of their ancient history. Mitochondria also contain ribosomes which synthesize all proteins encoded by mtDNA.

Lysosomes are vesicles (→ **F, g**) that arise from the ER (via the Golgi apparatus) and are involved in the intracellular digestion of macromolecules. These are taken up into the cell either by *endocytosis* (e.g., uptake of albumin into the renal tubules; → p. 158) or by *phagocytosis* (e.g., uptake of bacteria by macrophages; → p. 94 ff.). They may also originate from the degradation of a cell's own organelles (autophagia, e.g., of mitochondria) delivered inside autophagosomes (→ **B, F**). A portion of the endocytosed membrane material recycles (e.g., receptor recycling in receptor-mediated endocytosis; → p. 28). *Early* and *late* **endosomes** are intermediate stages in this *vesicular transport*. Late endosomes and lysosomes contain acidic hydrolases (proteases, nucleases, lipases, glycosidases, phosphatases, etc., that are active only under acidic conditions). The membrane contains an *H^+-ATPase* that creates an acidic (pH 5) interior environment within the lysosomes and assorted *transport proteins* that (a) release the products of digestion (e.g., ▶

F. Protein synthesis, sorting, recycling, and breakdown




▶ amino acids) into the cytoplasm and (b) ensure charge compensation during H^+ uptake (Cl^- channels). These enzymes and transport proteins are delivered in *primary lysosomes* from the Golgi apparatus. Mannose-6-phosphate (M6 P) serves as the "label" for this process; it binds to M6 P receptors in the Golgi membrane which, as in the case of receptor-mediated endocytosis (→ p. 28), cluster in the membrane with the help of a clathrin framework. In the acidic environment of the lysosomes, the enzymes and transport proteins are separated from the receptor, and M6 P is dephosphorylated. The M6 P receptor returns to the Golgi apparatus (recycling, → **F**). The M6 P receptor no longer recognizes the dephosphorylated proteins, which prevents them from returning to the Golgi apparatus.

Peroxisomes are microbodies containing enzymes (imported via a signal sequence) that permit the oxidation of certain organic molecules (R-H_2), such as amino acids and fatty acids: R-H_2 + O_2 → R + H_2O_2. The peroxisomes also contain catalase, which transforms 2 H_2O_2 into O_2 + H_2O and oxidizes toxins, such as alcohol and other substances.

Whereas the membrane of organelles is responsible for intracellular compartmentalization, the main job of the **cell membrane** (→ **G**) is to separate the cell interior from the extracellular space (→ p. 2). The cell membrane is a **phospholipid bilayer** (→ **G1**) that may be either smooth or deeply infolded, like the brush border or the basal labyrinth (→ **B**). Depending on the cell type, the cell membrane contains variable amounts of *phospholipids*, *cholesterol*, and *glycolipids* (e.g., cerebrosides). The phospholipids mainly consist of phosphatidylcholine (→ **G3**), phosphatidylserine, phosphatidylethanolamine, and sphingomyelin. The hydrophobic components of the membrane face each other, whereas the hydrophilic components face the watery surroundings, that is, the extracellular fluid or cytosol (→ **G4**). The lipid composition of the two layers of the membrane differs greatly. Glycolipids are present only in the external layer, as described below. Cholesterol (present in both layers) reduces both the fluidity of the membrane and its permeability to polar substances. Within the two-dimensionally fluid phospholipid membrane are **proteins** that make up 25% (myelin membrane) to 75% (inner mitochondrial membrane) of the membrane mass, depending on the membrane type. Many of them span the entire lipid bilayer once (→ **G1**) or several times (→ **G2**) (*transmembrane proteins*), thereby serving as ion channels, carrier proteins, hormone receptors, etc. The proteins are anchored by their lipophilic amino acid residues, or attached to already anchored proteins. Some proteins can move about freely within the membrane, whereas others, like the anion exchanger of red cells, are anchored to the cytoskeleton. The cell surface is largely covered by the *glycocalyx*, which consists of sugar moieties of glycoproteins and glycolipids in the cell membrane (→ **G1,4**) and of the extracellular matrix. The glycocalyx mediates cell–cell interactions (surface recognition, cell docking, etc.). For example, components of the glycocalyx of neutrophils dock onto endothelial membrane proteins, called *selectins* (→ p. 94).


The **cytoskeleton** allows the cell to maintain and change its shape (during cell division, etc.), make selective movements (migration, cilia), and conduct intracellular transport activities (vesicle, mitosis). It contains *actin filaments* as well as *microtubules* and *intermediate filaments* (e.g., vimentin and desmin filaments, neurofilaments, keratin filaments) that extend from the centrosome.

G. Cell membrane




1 Membrane constituents

2 Multiple membrane-spanning integral protein



3 Phospholipid (phosphatidylcholine)



4 Membrane lipids

The lipophilic cell membrane protects the cell interior from the extracellular fluid, which has a completely different composition (→ p. 2). This is imperative for the creation and maintenance of a *cell's internal environment* by means of metabolic energy expenditure. Channels (pores), carriers, ion pumps (→ p. 26ff.) and the process of cytosis (→ p. 28) allow **transmembrane transport** of selected substances. This includes the import and export of metabolic substrates and metabolites and the selective transport of ions used to create or modify the *cell potential* (→ p. 32), which plays an essential role in excitability of nerve and muscle cells. In addition, the effects of substances that readily penetrate the cell membrane in most cases (e.g., water and CO_2) can be mitigated by selectively transporting certain other substances. This allows the cell to compensate for undesirable changes in the cell volume or pH of the cell interior.

Intracellular Transport

The cell interior is divided into different compartments by the organelle membranes. In some cases, very broad intracellular spaces must be crossed during transport. For this purpose, a variety of specific intracellular transport mechanisms exist, for example:

- Nuclear pores in the nuclear envelope provide the channels for RNA export out of the nucleus and protein import into it (→ p. 11 C);
- *Protein transport* from the rough endoplasmic reticulum to the Golgi complex (→ p. 13 F);
- *Axonal transport* in the nerve fibers, in which distances of up to 1 meter can be crossed (→ p. 42). These transport processes mainly take place along the filaments of the cytoskeleton. Example: while expending ATP, the microtubules set dynein-bound vesicles in motion in the one direction, and kinesin-bound vesicles in the other (→ p. 13 F).


Main sites of Intracellular Transmembrane Transport are:

- *Lysosomes*: Uptake of H^+ ions from the cytosol and release of metabolites such as amino acids into the cytosol (→ p. 12);
- *Endoplasmic reticulum (ER)*: In addition to a translocator protein (→ p. 10), the ER has two other proteins that transport Ca^{2+} (→ **A**). Ca^{2+} can be pumped from the cytosol into the ER by a Ca^{2+}-ATPase called *SERCA* (sarcoplasmic endoplasmic reticulum Ca^{2+}-transporting ATPase). The resulting Ca^{2+} stores can be released into the cytosol via a *Ca^{2+} channel* (ryanodine receptor, RyR) in response to a triggering signal (→ p. 36).
- *Mitochondria*: The outer membrane contains large pores called *porins* that render it permeable to small molecules (< 5 kDa), and the inner membrane has high concentrations of specific carriers and enzymes (→ **B**). Enzyme complexes of the *respiratory chain* transfer electrons (e^-) from high to low energy levels, thereby pumping H^+ ions from the matrix space into the intermembrane space (→ **B1**), resulting in the formation of an *H^+ ion gradient* directed into the matrix. This not only drives ATP synthetase (ATP production; → **B2**), but also promotes the inflow of pyruvate$^-$ and anorganic phosphate, P_i^- (symport; → **B2b,c** and p. 28). *Ca^{2+} ions* that regulate Ca^{2+}-sensitive mitochondrial enzymes in muscle tissue can be pumped into the matrix space with ATP expenditure (→ **B2**), thereby allowing the mitochondria to form a sort of Ca^{2+} buffer space for protection against dangerously high concentrations of Ca^{2+} in the cytosol. The inside-negative *membrane potential* (caused by H^+ release) drives the uptake of ADP^{3-} in exchange for ATP^{4-} (potential-driven transport; → **B2a** and p. 22).


Transport between Adjacent Cells

In the body, transport between adjacent cells occurs either via diffusion through the extracellular space (e.g., paracrine hormone effects) or through channel-like connecting structures (**connexons**) located within a so-called **gap junction** or **nexus** (→ **C**). A connexon is a hemichannel formed by six connexin molecules (→ **C2**). One connexon docks with another connexon on an adjacent cell, thereby forming a common channel through which substances with molecular masses of up to around 1 kDa can pass. Since this applies not only for ions such as Ca^{2+}, but also for a number of organic substances such as ATP, these types of cells are united to form a close electrical and metabolic unit (**syncytium**), as is present in the epithelium, many smooth muscles (single- ▶

A. Ca^{2+} transport through the ER membrane



B. Mitochondrial transport



▶ unit type, →p. 70), the myocardium, and the glia of the central nervous system. Electric coupling permits the transfer of excitation, e.g., from excited *muscle cells* to their adjacent cells, making it possible to trigger a wave of excitation across wide regions of an organ, such as the stomach, intestine, biliary tract, uterus, ureter, atrium, and ventricles of the heart, but not skeletal muscles. Certain neurons of the retina and CNS also communicate in this manner (*electric synapses*). Gap junctions in the glia (→p. 344) and epithelia help to distribute the stresses that occur in the course of transport and barrier activities (see below) throughout the entire cell community. However, the connexons close when the concentration of Ca^{2+} (in an extreme case, due to a hole in cell membrane) or H^+ concentration increases too rapidly (→**C3**). In other words, the individual (defective) cell is left to deal with its own problems when necessary to preserve the functionality of the cell community.


Transport through Cell Layers

In single cells, the cell membrane is responsible for separating the "interior" from the "exterior." In the multicellular organism, with its larger compartments, *cell layers* provide this function. The *epithelia* of skin and gastrointestinal, urogenital and respiratory tracts, the *endothelia* of blood vessels, and *neuroglia* are examples of this type of extensive barrier. They separate the immediate extracellular space from other spaces that are greatly different in composition, e.g., those filled with air (skin, bronchial epithelia), gastrointestinal contents, urine or bile (tubules, urinary bladder, gallbladder), aqueous humor of the eye, blood (endothelia) and cerebrospinal fluid (blood–cerebrospinal fluid barrier), and from the extracellular space of the CNS (blood–brain barrier). Nonetheless, certain substances must be able to pass through these cell layers. This requires selective **transcellular transport** with import into the cell followed by export from the cell. Unlike cells with a completely uniform plasma membrane (e.g., blood cells), epi- and endothelial cells are *polar cells,* as defined by their structure (→p. 9A and B) and transport function. Hence, the *apical membrane* (facing exterior) of an epithelial cell has a different set of transport proteins from the *basolateral membrane* (facing the blood). So called tight junctions (zonulae occludentes), at which the cells are held together, prevent mixing of the two membrane types (→**D2**).


In addition to transcellular transport, cellular barriers also permit **paracellular transport** which takes place between cells. Certain *epithelia* (e.g., in the small intestinal and proximal renal tubules) are relatively permeable to small molecules (leaky), whereas others are less leaky (e.g., distal nephron, colon). The degree of permeability depends on the strength of the *tight junctions* and the types of proteins contained within: occludins, JAM [junction adhesion molecule], *claudins*. So far 16 claudins are known to determine the specific permeability: for example intact claudin 16 is required for the paracellular resorption of Mg^{2-} in the Henle's loop section of the renal tubule (→p. 180). The paracellular path and the degree of its permeability (for example cationic or anionic specificity) are essential functional elements of the various epithelia. Macromolecules can cross the barrier formed by the *endothelium* of the vessel wall by transcytosis (→p. 28), yet paracellular transport also plays an essential role, especially in the fenestrated endothelium. Anionic macromolecules like albumin, which must remain in the bloodstream because of its colloid osmotic action (→p. 210), are held back by the wall charges at the intercellular spaces and, in some cases, at the fenestra.

Long-distance transport between the various organs of the body and between the body and the outside world is also necessary. *Convection* is the most important transport mechanism involved in long-distance transport (→p. 24).

C. Gap junction



D. Apical functional complex



Photos: H. Lodish. Reproduced with permission from Scientific American Books, New York, 1995.

Diffusion is movement of a substance owing to the random thermal motion (brownian movement) of its molecules or ions (→ **A1**) in all directions throughout a solvent. *Net diffusion* or selective transport can occur only when the solute concentration at the starting point is higher than at the target site. (*Note:* unidirectional fluxes also occur in absence of a concentration gradient—i.e., at equilibrium—but net diffusion is zero because there is equal flux in both directions.) The driving force, "force" not to be taken in a physical sense, of diffusion is, therefore, a **concentration gradient**. Hence, diffusion equalizes concentration differences and requires a driving force: **passive transport** (= downhill transport).

Example: When a layer of O_2 gas is placed on water, the O_2 quickly diffuses into the water along the initially high gas pressure gradient (→ **A2**). As a result, the partial pressure of O_2 (Po_2) rises, and O_2 can diffuse further downward into the next O_2-poor layer of water (→ **A1**). (*Note:* with gases, partial pressure is used in lieu of concentration.) However, the steepness of the Po_2 profile or gradient (dPo_2/dx) decreases (exponentially) in each subsequent layer situated at distance x from the O_2 source (→ **A3**), which indicates a decrease of the so-called diffusion rate (= diffusing amount of substance per unit of time). Therefore, diffusion is only feasible for **transport across short distances** within the body. Diffusion in liquids is slower than in gases.

The diffusion rate, J_{diff} ($mol \cdot s^{-1}$), is also proportional to the area available for diffusion (A) and the absolute temperature (T) and is inversely proportional to the viscosity (η) of the solvent and the radius (r) of the diffused particles.

According to the *Stokes–Einstein equation*, the *coefficient of diffusion* (D) is derived from T, η, and r as

$$D = \frac{R \cdot T}{N_A \cdot 6\pi \cdot r \cdot \eta}\,[m^2 \cdot s^{-1}], \qquad [1.1]$$

where R is the general gas constant ($8.3144\,J \cdot K^{-1} \cdot mol^{-1}$) and N_A Avogadro's constant (→ p. 380). In Fick's first law of diffusion (Adolf Fick, 1855), the diffusion rate is expressed as

$$J_{diff} = A \cdot D \cdot \left(\frac{dC}{dx}\right)\,[mol \cdot s^{-1}] \qquad [1.2]$$

where C is the molar concentration and *x* is the distance traveled during diffusion. Since the *driving "force"*—i.e., the concentration gradient (dC/dx)—decreases with distance, as was explained above, the *time* required for diffusion increases exponentially with the distance traveled ($t \sim x^2$). If, for example, a molecule travels the first μm in 0.5 ms, it will require 5 s to travel 100 μm and a whopping 14 h for 1 cm.

Returning to the previous example (→ **A2**), if the above-water partial pressure of free O_2 diffusion (→ **A2**) is kept constant, the Po_2 in the water and overlying gas layer will eventually equalize and net diffusion will cease (*diffusion equilibrium*). This process takes place within the body, for example, when O_2 diffuses from the alveoli of the lungs into the bloodstream and when CO_2 diffuses in the opposite direction (→ p. 120).


Let us imagine two spaces, a and b (→ **B1**) supposedly containing different concentrations ($C_a > C_b$) of an uncharged solute. The membrane separating the solutions has pores Δx in length and with total cross-sectional area of A. Since the pores are permeable to the molecules of the dissolved substance, the molecules will diffuse from a to b, with $C^a - C^b = \Delta C$ representing the concentration gradient as the driving "force". If we consider only the spaces a and b (while ignoring the gradients dC/dx in the pore, as shown in **B2**, for the sake of simplicity), **Fick's first law of diffusion** (Eq. 1.2) can be modified as follows:

$$\mathbf{J_{diff}} = \mathbf{A} \cdot \mathbf{D} \cdot \frac{\Delta \mathbf{C}}{\Delta \mathbf{x}}\,[mol \cdot s^{-1}]. \qquad [1.3]$$


In other words, the rate of diffusion increases as A, D, and ΔC increase, and decreases as the thickness of the membrane (Δx) increases.

When diffusion occurs through the **lipid membrane** of a cell, one must consider that hydrophilic substances in the membrane are sparingly soluble (compare intramembrane gradient in **C1** to **C2**) and, accordingly, have a hard time penetrating the membrane by means of *"simple" diffusion*. The *oil-and-water partition coefficient* (*k*) is a measure of the lipid solubility of a substance (→ **C**). ▶


A. Diffusion in homogeneous media



B. Diffusion through porous membranes



C. Diffusion through lipid membranes



$$k = \frac{\text{Equilibrium concentration in olive oil}}{\text{Equilibrium concentration in water}}$$

(Partly after S. G. Schultz)

▶ The higher the *k* value, the more quickly the substance will diffuse through a pure phospholipid bilayer membrane. Substitution into Eq. 1.3 gives

$$J_{diff} = k \cdot A \cdot D \cdot \frac{\Delta C}{\Delta x} [mol \cdot s^{-1}]; \quad [1.4]$$

Whereas the molecular radius *r* (→ Eq. 1.1) still largely determines the magnitude of D when *k* remains constant (cf. diethylmalonamide with ethylurea in **D**), *k* can vary by many powers of ten when *r* remains constant (cf. urea with ethanol in **D**) and can therefore have a decisive effect on the permeability of the membrane.

Since the value of the variables k, D, and Δx within the body generally cannot be determined, they are usually summarized as the *permeability coefficient P*, where

$$P = k \cdot \frac{D}{\Delta x} [m \cdot s^{-1}]. \quad [1.5]$$

If the diffusion rate, J_{diff} [mol·s^{-1}], is related to area A, Eq. 1.4 is transformed to yield

$$\frac{J_{diff}}{A} = \mathbf{P} \cdot \Delta \mathbf{C} [mol \cdot m^{-2} \cdot s^{-1}]. \quad [1.6]$$

The quantity of substance (net) diffused per unit area and time is therefore proportional to ΔC and P (→ **E**, blue line with slope P).

When considering the **diffusion of gases**, ΔC in Eq. 1.4 is replaced by α· ΔP (solubility coefficient times partial pressure difference; → p. 126) and J_{diff} [mol · s^{-1}] by $\dot{V}_{diff}$ [m^3· s^{-1}]. $k \cdot \alpha \cdot D$ is then summarized as diffusion conductance, or *Krogh's diffusion coefficient* K [m^2 · s^{-1} · Pa^{-1}]. Substitution into Fick's first diffusion equation yields

$$\frac{\dot{V}_{diff}}{A} = K \cdot \frac{\Delta P}{\Delta x} [m \cdot s^{-1}]. \quad [1.7]$$

Since A and Δx of alveolar gas exchange (→ p. 120) cannot be determined in living organisms, $K \cdot F/\Delta x$ for O_2 is often expressed as the *O_2 diffusion capacity* of the lung, D_L:

$$\dot{V}_{O_2\,diff} = D_L \cdot \Delta P_{O_2} [m^3 \cdot s^{-1}]. \quad [1.8]$$

Nonionic diffusion occurs when the uncharged form of a weak base (e.g., ammonia = NH_3) or acid (e.g., formic acid, HCOOH) passes through a membrane more readily than the charged form (→ **F**). In this case, the membrane would be more permeable to NH_3 than to NH_4^+ (→ p. 176 ff.). Since the pH of a solution determines whether these substances will be charged or not (pK value; → p. 384), the diffusion of weak acids and bases is clearly dependent on the pH.

The previous equations have not made allowances for the diffusion of electrically charged particles (**ions**). In their case, the **electrical potential difference** at cell membranes must also be taken into account. The electrical potential difference can be an additional driving force of diffusion (*electrodiffusion*). In that case, positively charged ions (cations) will then migrate to the negatively charged side of the membrane, and negatively charged ions (anions) will migrate to the positively charged side. The prerequisite for this type of transport is, of course, that the membrane contain ion channels (→ p. 32 ff.) that make it permeable to the transported ions. Inversely, every ion diffusing along a concentration gradient carries a charge and thus creates an electric *diffusion potential* (→ p. 32 ff.).

As a result of the electrical charge of an ion, the permeability coefficient of the ion x (= P_x) can be transformed into the **electrical conductance** of the membrane for this ion, $\mathbf{g_x}$ (→ p. 32):


$$g_x = \frac{P_x \cdot z_x^2 \cdot F^2}{R \cdot T} \cdot \bar{c}_x [S \cdot m^{-2}], \quad [1.9]$$


where R and T have their usual meaning (explained above) and z_x equals the charge of the ion, F equals the *Faraday constant* (9,65 · 10^4 A · s · mol^{-1}), and $\bar{c}_x$ equals the mean ionic activity in the membrane. Furthermore,


$$\bar{c} = \frac{c_1 - c_2}{\ln c_1 - \ln c_2} \quad [1.10]$$


where index 1 = one side and index 2 = the other side of the membrane. Unlike P, *g is concentration-dependent*. If, for example, the extracellular K^+ concentration rises from 4 to 8 mmol/kg H_2O (cytosolic concentration remains constant at 160 mmol/kg H_2O), $\bar{c}$ and, therefore, g_x will increase by 20%.

Since most of the biologically important substances are so polar or lipophobic (*small k value*) that simple diffusion of the substances through the membrane would proceed much too slowly, other membrane transport proteins called **carriers** or **transporters** exist in addition to ion channels. Carriers bind the target molecule (e.g., glucose) on one side of the membrane and detach from it on the other side (after a conformational change) (→ **G**). As in









simple diffusion, a concentration gradient is necessary for such carrier-mediated transport (passive transport), e.g., with GLUT uniporters for glucose (→ p. 158). On the other hand, this type of "facilitated diffusion" is subject to *saturation* and is *specific* for structurally similar substances that may *competitively inhibit* one another. The carriers in both passive and active transport have the latter features in common (→ p. 26).

Water flow or *volume flow* ($\mathbf{J_V}$) across a wall of partition (membrane or cell layer), in living organisms is achieved through *osmosis* (diffusion of water) or *filtration*. They can occur only if the wall is water-permeable. This allows osmotic and hydrostatic pressure differences ($\Delta\pi$ and ΔP) across the wall to drive the fluids through it.

Osmotic flow equals the hydraulic conductivity (K_f) times the osmotic pressure difference ($\Delta\pi$) (→ **A**):

$$\mathbf{J_V = K_f \cdot \Delta\pi} \quad [1.11]$$

The **osmotic pressure difference ($\Delta\pi$)** can be calculated using *van't Hoff's* law, as modified by *Staverman*:

$$\Delta\pi = \sigma \cdot R \cdot T \cdot \Delta C_{osm}, \quad [1.12]$$

where σ is the reflection coefficient of the particles (see below), R is the universal gas constant (→ p. 20), T is the absolute temperature, and ΔC_{osm} [osm · kgH_2O^{-1}] is the difference between the lower and higher particle concentrations, $C^a_{osm} - C^b_{osm}$ (→ **A**). Since ΔC_{osm}, the *driving force for osmosis*, is a negative value, J_V is also negative (Eq. 1.11). The water therefore flows against the concentration gradient of the solute particles. In other words, the higher concentration, C^b_{osm}, *attracts* the water. When the *concentration of water* is considered in osmosis, the H_2O concentration in **A,a**, $C^a_{H_2O}$, is greater than that in **A,b**, $C^b_{H_2O}$. $C^a_{H_2O} - C^b_{H_2O}$ is therefore the *driving force for H_2O diffusion* (→ **A**). Osmosis also cannot occur unless the reflection coefficient is greater than zero ($\sigma > 0$), that is, unless the wall of partition is less permeable to the solutes than to water.

Aquaporins (AQP) are *water channels* that permit the passage of water in many cell membranes. A chief cell in the renal collecting duct contains a total of ca. 107 water channels, comprising AQP2 (regulated) in the luminal membrane, and AQP3 and 4 (permanent) in the basolateral membrane. The permeability of the epithelium of the renal collecting duct to water (→ **A**, right panel) is controlled by the *insertion and removal of AQP2*, which is stored in the membrane of intracellular vesicles. In the presence of the antidiuretic hormone ADH (V_2 receptors, cAMP; → p. 276), water channels are inserted in the luminal membrane within minutes, thereby increasing the water permeability of the membrane to around 1.5×10^{-17} L s^{-1} per channel.

In **filtration** (→ **B**),

$$\mathbf{J_V = K_f \cdot (\Delta P - \Delta\pi) = K_f \cdot P_{eff}} \quad [1.13]$$

Filtration occurs mainly through *capillary walls*, which allow the passage of small ions and molecules ($\sigma = 0$; see below), but not of plasma proteins (→ **B**, molecule X). Their concentration difference leads to an oncotic pressure difference ($\Delta\pi$) that opposes ΔP. Therefore, filtration can occur only if $\Delta P > \Delta\pi$ (→ **B**, p. 152, p. 210).

Solvent drag occurs when solute particles are carried along with the water flow of osmosis or filtration. The amount of solvent drag for solute X (J_X) depends mainly on osmotic flow (J_V) and the mean *solute activity* $\bar{a}_x$ (→ p. 382) at the site of penetration, but also on the degree of particle reflection from the membrane, which is described using the **reflection coefficient (σ)**. Solvent drag for solute X (J_X) is therefore calculated as

$$J_x = J_V (1 - \sigma)\, \bar{a}_x \,[\text{mol} \cdot \text{s}^{-1}] \quad [1.14]$$

Larger molecules such as proteins are entirely reflected, and $\sigma = 1$ (→ **B**, molecule X). Reflection of smaller molecules is lower, and $\sigma < 1$. When urea passes through the wall of the proximal renal tubule, for example, σ = 0.68. The value (1–σ) is also called the *sieving coefficient* (→ p. 154).


Plasma protein binding occurs when small-molecular substances in plasma bind to proteins (→ **C**). This hinders the free penetration of the substances through the endothelium or the glomerular filter (→ p. 154 ff.). At a glomerular filtration fraction of 20%, 20% of a freely filterable substance is filtered out. If, however, 9/10 of the substance is bound to plasma proteins, only 2% will be filtered during each renal pass.

Convection functions to transport solutes over *long distances*—e.g., in the circulation or urinary tract. The solute is then carried along like a piece of driftwood. The quantity of solute transported over time (J_{conv}) is the product of volume flow J_V (in $m^3 \cdot s^{-1}$) and the solute concentration C ($mol \cdot m^{-3}$):


$$\mathbf{J_{conv} = J_V \cdot C}\ [\text{mol} \cdot \text{s}^{-1}]. \quad [1.15]$$

The flow of gases in the respiratory tract, the transmission of heat in the blood and the release of heat in the form of warmed air occurs through convection (→ p. 224).


A. Osmosis (water diffusion)




Example




B. Filtration



Example



C. Plasma protein binding



Prevents excretion
(e.g., by binding of heme by hemopexin)

Transports substances in blood
(e.g., binding of Fe^{3+} ions by apotransferrin)

Provides rapid access ion stores
(e.g., of Ca^{2+} or Mg^{2+})

Helps to dissolve lipophilic substances in blood
(e.g., unconjugated bilirubin)

Affects certain **medications** (e.g., many sulfonamides):
Protein-bound fraction
– not pharmacologically active
– not filterable (delays renal excretion)
– functions as an allergen (hapten)

Active transport occurs in many parts of the body when solutes are transported against their concentration gradient (*uphill transport*) and/or, in the case of ions, against an electrical potential (→ p. 22). All in all, active transport occurs against the *electrochemical gradient* or *potential* of the solute. Since passive transport mechanisms represent "downhill" transport (→ p. 20 ff.), they are not appropriate for this task. Active transport requires the **expenditure of energy**. A large portion of chemical energy provided by foodstuffs is utilized for active transport once it has been made readily available in the form of ATP (→ p. 41). The energy created by ATP hydrolysis is used to drive the transmembrane transport of numerous ions, metabolites, and waste products. According to the laws of thermodynamics, the energy expended in these reactions produces *order* in cells and organelles—a prerequisite for survival and normal function of cells and, therefore, for the whole organism (→ p. 38 ff.).


In **primary active transport**, the energy produced by hydrolysis of ATP goes *directly* into ion transport through an ion pump. This type of ion pump is called an **ATPase**. They establish the electrochemical gradients rather slowly, e.g., at a rate of around $1\,\mu mol \cdot s^{-1} \cdot m^{-2}$ of membrane surface area in the case of Na^+-K^+-ATPase. The gradient can be exploited to achieve *rapid (passive) ionic currents* in the opposite direction after the permeability of ion channels has been increased (→ p. 32 ff.). Na^+ can, for example, be driven into a nerve cell at a rate of up to $1000\,\mu mol \cdot s^{-1} \cdot m^{-2}$ during an action potential.

ATPases occur ubiquitously in cell membranes (Na^+-K^+-ATPase) and in the endoplasmic reticulum and plasma membrane (Ca^{2+}-ATPase), renal collecting duct and stomach glands (H^+,K^+ -ATPase), and in lysosomes (H^+-ATPase). They transport Na^+, K^+, Ca^{2+} and H^+, respectively, by primarily active mechanisms. All except H^+-ATPase consist of 2 α-subunits and 2 β-subunits (P-type ATPases). The α-subunits are phosphorylated and form the ion transport channel (→ **A1**).

Na^+-K^+-ATPase is responsible for maintenance of *intracellular Na^+ and K^+ homeostasis* and, thus, for maintenance of the *cell membrane potential*. During each transport cycle (→ **A1, A2**), 3 Na^+ and 2 K^+ are "pumped" out of and into the cell, respectively, while 1 ATP molecule is used to phosphorylate the carrier protein (→ **A2b**). Phosphorylation first changes the conformation of the protein and subsequently alters the affinities of the Na^+ and K^+ binding sites. The conformational change is the actual ion transport step since it moves the binding sites to the opposite side of the membrane (→ **A2b ⇒ d**). Dephosphorylation restores the pump to its original state (→ **A2e ⇒ f**). The pumping rate of the Na^+-K^+-ATPase increases when the cytosolic Na^+ concentration rises—due, for instance, to increased Na^+ influx, or when the extracellular K^+ rises. Therefore, Na^+,K^+-*activatable* ATPase is the full name of the pump. Na-$^+$K$^+$-ATPase is inhibited by *ouabain* and *cardiac glycosides*.

Secondary active transport occurs when uphill transport of a compound (e.g., glucose) via a carrier protein (e.g., sodium glucose transporter type 2, SGLT2) is coupled with the passive (downhill) transport of an ion (in this example Na^+; → **B1**). In this case, the electrochemical Na^+ gradient into the cell (created by Na^+-K^+-ATPase at another site on the cell membrane; → **A**) provides the driving force needed for secondary active uptake of glucose into the cell. Coupling of the transport of compounds across a membrane is called **cotransport**, which may be in the form of symport or antiport. **Symport** occurs when the compound and driving ion are transported across the membrane in the same direction (→ **B1–3**). **Antiport** (countertransport) occurs when they are transported in opposite directions. Antiport occurs, for example, when an electrochemical Na^+ gradient drives H^+ in the opposite direction by secondary active transport (→ **B4**). The resulting H^+ gradient can then be exploited for *tertiary active symport* of molecules such as peptides (→ **B5**) or Fe ions (→ p. 90).

Electroneutral transport occurs when the net electrical charge remains balanced during transport, e.g., during Na^+/H^+ antiport (→ **B4**) and Na^+-Cl^- symport (→ **B2**). Charge transport occurs in **electrogenic (rheogenic) transport**, e.g., in Na^+-glucose^0 symport (→ **B1**), Na^+-amino acid^0 symport (→ **B3**), 2 Na^+-amino acid$^-$ symport, or H^+-peptide^0 symport (→ **B5**). The chemical Na^+ gradient provides the sole ▶


A. Na+-K+-ATPase
1
3 Na+
Outside
[Na+]o
[K+]o
β
α
α
β
Cell membrane
Cytosol
[Na+]i
ADP
ATP
[K+]i
2 K+
2
a
Na+ binding,
K+ discharge
b
P
ATP
Phosphorylation
Confor-
mational
change
High affinity
for K+
c
Na+
P
Conformation E1
Conformation E2
f
K+
High affinity
for Na+
Conformational
change
d
Na+ discharge,
K+ binding
P
e
Pi
Dephosphorylation
(Partly after P. Läuger)

▶ driving force for **electroneutral transport** (e.g., Na^+/H^+ antiport), whereas the negative membrane potential (→ p. 32 ff.) provides an additional driving force for rheogenic cotransport into the cell. When secondary active transport (e.g., of glucose) is coupled with the influx of not one but two Na^+ ions (e.g., SGLT1 symporter), the driving force is doubled. The aid of ATPases is necessary, however, if the required "uphill" concentration ratio is several decimal powers large, e.g., 10^6 in the extreme case of H^+ ions across the luminal membrane of parietal cells in the stomach. ATPase-mediated transport can also be electrogenic or electroneutral, e.g., Na^+-K^+-ATPase (3 Na^+/2 K^+; cf. p. 46) or H^+-K^+-ATPase (1 H^+/1 K^+), respectively.

Characteristics of active transport:

◆ It can be saturated, i.e., it has a limited *maximum capacity* (J_{max}).

◆ It is more or less *specific*, i.e., a carrier molecule will transport only certain chemically similar substances which inhibit the transport of each other (*competitive inhibition*).

◆ Variable quantities of the similar substances are transported at a given concentration, i.e., each has a different *affinity* (~1/K_M, see below) to the transport system.

◆ Active transport is inhibited when the *energy supply* to the cell is disrupted.

All of these characteristics except the last apply to passive carriers, that is, to uniporter-mediated (facilitated) diffusion (→ p. 22).

The **transport rate** of saturable transport (J_{sat}) is usually calculated according to Michaelis–Menten kinetics:


$$J_{sat} = J_{max} \cdot \frac{C}{K_M + C}\,[mol \cdot m^{-2} \cdot s^{-1}], \qquad [1.16]$$

where C is the concentration of the substrate in question, J_{max} is its maximum transport rate, and K_M (Michaelis constant) is the substrate concentration that produces one-half J_{max} (→ p. 389 ff).


Cytosis is a completely different type of active transport involving the formation of membrane-bound vesicles with a diameter of 50–400 nm. **Vesicles** are either pinched off from the plasma membrane (*exocytosis*) or incorporated into it by invagination (*endocytosis*) in conjunction with the expenditure of ATP. In cytosis, the uptake and release of *macromolecules* such as proteins, lipoproteins, polynucleotides, and polysaccharides into and out of a cell occurs by specific mechanisms similar to those involved in intracellular transport (→ p. 12 ff.).

Endocytosis (→ p. 13) can be broken down into different types, including pinocytosis, receptor-mediated endocytosis, and phagocytosis. **Pinocytosis** is characterized by the continuous unspecific uptake of extracellular fluid and molecules dissolved in it through relatively small vesicles. **Receptor-mediated endocytosis** (→ **C**) involves the selective uptake of specific macromolecules with the aid of receptors. This usually begins at small depressions (*pits*) on the plasma membrane surface. Since the insides of the pits are often densely coated with the protein *clathrin*, they are called *clathrin-coated pits*. The **receptors** involved are integral cell membrane proteins such as those for low-density lipoprotein (LPL; e.g., in hepatocytes) or intrinsic factor-bound cobalamin (e.g., in ileal epithelial cells). Thousands of the same receptor type or of different receptors can converge at coated pits (→ **C**), yielding a tremendous increase in the efficacy of ligand uptake. The endocytosed vesicles are initially coated with clathrin, which is later released. The vesicles then transform into *early endosomes*, and most of the associated receptors circulate back to the cell membrane (→ **C** and p. 13). The endocytosed ligand is either exocytosed on the opposite side of the cell (*transcytosis*, see below), or is digested by *lysosomes* (→ **C** and p. 13). **Phagocytosis** involves the endocytosis of particulate matter, such as microorganisms or cell debris, by phagocytes (→ p. 94 ff.) in conjunction with lysosomes. Small digestion products, such as amino acids, sugars and nucleotides, are transported out of the lysosomes into the cytosol, where they can be used for cellular metabolism or secreted into the extracellular fluid. When certain hormones such as *insulin* (→ p. 284) bind to receptors on the surface of target cells, hormone-receptor complexes can also enter the coated pits and are endocytosed (*internalized*) and digested by lysosomes. This reduces the density of receptors available for hormone binding. In other words, an increased hormone supply *down-regulates* the receptor density. ▶

B. Secondary and tertiary active transport



C. Receptor-mediated endocytosis



▶ **Exocytosis** (→ p. 13 see Table F) is a method for selective export of macromolecules out of the cell (e.g., pancreatic enzymes; → p. 248 ff.) and for release of many hormones (e.g., posterior pituitary hormone; → p. 282) or neurotransmitters (→ p. 50 ff.). These substances are kept "packed" and readily available in (clathrin-coated) *secretory vesicles*, waiting to be released when a certain signal is received (increase in cytosolic Ca^{2+}). The "packing material" (vesicle membrane) is later re-endocytosed and *recycled*. Exocytotic membrane fusion also helps to insert vesicle-bound proteins into the plasma membrane (→ p. 13, Table F).The liquid contents of the vesicle then are automatically emptied in a process called **constitutive exocytosis** (→ **D**).

In constitutive exocytosis, the protein complex *coatomer* (coat assembly protomer) takes on the role of clathrin (see above). Within the Golgi membrane, GNRP (guanine nucleotide-releasing protein) phosphorylates the GDP of the ADP-ribosylation factor (ARF) to GTP → **D1**), resulting in the dispatch of vesicles from the trans-Golgi network. ARF-GTP complexes then anchor on the membrane and bind with coatomer (→ **D2**), thereby producing **coatomer-coated vesicles** (→ **D3**). The membranes of the vesicles contain v-SNAREs (vesicle synaptosome-associated protein receptors), which recognize t-SNAREs (target-SNAREs) in the target membrane (the plasma membrane, in this case). This results in cleavage of ARF-GTP, dissociation of ARF-GDP and coatomer molecules and, ultimately, to membrane fusion and exocytosis (→ **D4, D5**) to the extracellular space (ECS).

Transcytosis is the uptake of macromolecules such as proteins and hormones by endocytosis on one side of the cell, and their release on the opposite side. This is useful for *transcellular transport of the macromolecules* across cell layers such as endothelia.

Cell Migration


Most cells in the body are theoretically able to move from one place to another or *migrate* (→ **E**), but only a few cell species actually do so. The *sperm* are probably the only cells with a special propulsion mechanism. By waving their whip-like tail, the sperm can travel at speeds of up to around 2000 μm/min. Other cells also migrate, but at much slower rates. *Fibroblasts*, for example, move at a rate of around 1.2 μm/min. When an injury occurs, fibroblasts migrate to the wound and aid in the formation of scar tissue. Cell migration also plays a role in *embryonal development*. Chemotactically attracted *neutrophil granulocytes* and *macrophages* can even migrate through vessel walls to attack invading bacteria (→ p. 94ff.). Cells of some tumors can also migrate to various tissues of the body or *metastasize*, thereby spreading their harmful effects.


Cells migrate by "crawling" on a stable surface (→ **E1**). The following activities occur during cell migration:

◆ *Back end of the cell*: (a) Depolymerization of actin and tubulin in the cytoskeleton; (b) endocytosis of parts of the cell membrane, which are then propelled forward as endocytotic vesicles to the front of the cell, and (c) release of ions and fluids from the cell.

◆ *Front end of the cell (lamellipodia)*: (a) Polymerization of actin monomers is achieved with the aid of profilin (→ **E2**). The monomers are propelled forward with the help of plasma membrane-based myosin I (fueled by ATP); (b) reinsertion of the vesicles in the cell membrane; (c) uptake of ions and fluids from the environment.

Parts of the cell membrane that are not involved in cytosis are conveyed from front to back, as on a track chain. Since the cell membrane is attached to the stable surface (primarily fibronectin of the extracellular matrix in the case of fibroblasts), the cell moves forward relative to the surface. This is achieved with the aid of specific receptors, such as fibronectin receptors in the case of fibroblasts.


D. Constitutive exocytosis
Trans-Golgi network
1 Activation of ARF
v-SNARE
GNRP
GTP
GDP
GTP
GDP
ARF-GTP (active)
ARF-GDP (inactive)
2 Coating
3 Coatomer-coated vesicle
ARF-GDP (inactive)
Coatomer
P_i
4 Membrane fusion
5 Exocytosis
t-SNARE
Plasma membrane
ECS


E. Cell migration
1
K^+, Cl^-
K^+, Cl^-
Lamellipodium
Cell
Support
Attachment points
See 2
(After A. Schwab et al.)
d 15 min
20 µm
c 10 min
b 5 min
a 0 min
Photos: K. Gabriel
Actin monomer
Profilin
Actin polymer
Cross-link protein
Myosin I
2
(Partly after H. Lodish et al.)

An **electrical potential difference** occurs due to the *net movement of charge during ion transport*. A **diffusion potential** develops for instance, when ions (e.g., K^+) diffuse (down a chemical gradient; → p. 20ff.) out of a cell, making the cell interior negative relative to the outside. The rising diffusion potential then drives the ions back into the cell (potential-driven ion transport; → p. 22). Outward K^+ diffusion persists until equilibrium is reached. At equilibrium, the two opposing forces become equal in size. In other words, the sum of the two or the **electrochemical gradient** (and thereby the electrochemical potential) equals zero, and there is no further net movement of ions (*equilibrium concentration*) at a certain voltage (*equilibrium potential*).

The **equilibrium potential (E_x)** for any species of ion X distributed inside (i) and outside (o) a cell can be calculated using the Nernst equation:

$$E_X = \frac{R \cdot T}{F \cdot z_X} \cdot \ln \frac{[X]_o}{[X]_i} \; [V] \qquad [1.17]$$

where R is the universal gas constant (= 8.314 $J \cdot K^{-1} \cdot mol^{-1}$), T is the absolute temperature (310 °K in the body), F is the Faraday constant or charge per mol (= 9.65×10^4 $A \cdot s \cdot mol^{-1}$), z is the valence of the ion in question (+ 1 for K^+, + 2 for Ca^{2+}, – 1 for Cl^-, etc.), ln is the natural logarithm, and [X] is the effective concentration = *activity* of the ion X (→ p. 382). $R \cdot T/F = 0.0267$ V^{-1} at body temperature (310 °K). It is sometimes helpful to convert $\ln([X]_o/[X]_i)$ into $-\ln([X]_i/[X]_o)$, V into mV and ln into log before calculating the equilibrium potential (→ p. 386f). After insertion into Eq. 1.17, the **Nernst equation** then becomes

$$\mathbf{E_X = -61 \cdot \frac{1}{z_X} \cdot \log \frac{[X]_i}{[X]_o} \; [mV]} \qquad [1.18]$$

If the ion of species X is K^+, and $[K^+]_i = 140$, and $[K^+]_o = 4.5$ mmol/kg H_2O, the equilibrium potential $E_K = -61 \cdot \log 31$ mV or – 91 mV. If the cell membrane is permeable only to K^+, the **membrane potential (E_m)** will eventually reach a value of – 91 mV, and E_m will equal E_K (→ **A1**).

At equilibrium potential of ion X, the chemical gradient will drive just as many ions of species X in the one direction as the electrical potential does in the opposite direction. The **electrochemical potential ($E_m - E_x$)** or so-called electrochemical driving "force", will equal zero, and the sum of ionic inflow and outflow or the **net flux (I_x)** will also equal zero.

Membrane conductance (g_x), a concentration-dependent variable, is generally used to describe the permeability of a cell membrane to a given ion instead of the permeability coefficient P (see Eq. 1.5 on p. 22 for conversion). Since it is relative to membrane surface area, g_x is expressed in siemens ($S = 1/\Omega$) per m^2 (→ p. 22, Eq. 1.9).

Ohm's law defines the net ion current per unit of membrane surface area I_x [$A \cdot m^{-2}$] as

$$\mathbf{I_X = g_X \cdot (E_m - E_X)} \qquad [1.19]$$


I_x will therefore differ from zero when the prevailing membrane potential, E_m, does not equal the equilibrium potential, E_x. This occurs, for example, after strong transient activation of Na^+-K^+-ATPase (electrogenic; → p. 26): hyperpolarization of the membrane (→ **A2**), or when the cell membrane conducts more than one ion species, e.g., K^+ as well as Cl^- and Na^+: depolarization (→ **A3**). If the membrane is permeable to different ion species, the *total conductance* of the membrane (g_m) equals the sum of all parallel conductances ($g_1 + g_2 + g_3 + ...$). The **fractional conductance** for the ion species X **(f_x)** can be calculated as


$$f_X = g_X/g_m \qquad [1.20]$$

The membrane potential, E_m, can be determined if the fractional conductances and equilibrium potentials of the conducted ions are known (see Eq. 1.18). Assuming K^+, Na^+, and Cl^- are the ions in question,

$$E_m = (E_K \cdot f_K) + (E_{Na} \cdot f_{Na}) + (E_{Cl} \cdot f_{Cl}) \qquad [1.21]$$

Realistic values in *resting nerve cells* are: $f_K = 0.90$, $f_{Na} = 0.03$, $f_{Cl} = 0.07$; $E_K = -90$ mV, $E_{Na} = +70$ mV, $E_{Cl} = -83$ mV. Inserting these values into equation 1.21 results in an *E_m of – 85 mV*. Thus, the driving forces (= electrochemical potentials = $E_m - E_x$), equal + 5 mV for K^+, – 145 mV for Na^+, and – 2 mV for Cl^-. The driving force for K^+ efflux is therefore low, though g_K is high. Despite a high driving force for Na^+, Na^+ influx is low because the g_{Na} and f_{Na} of resting cells are relatively small. Nonetheless, the sodium current, I_{Na}, can rise tremendously when large numbers of Na^+ channels open during an action potential (→ p. 46). ▶


A. Electrochemical potential ($E_m - E_K$) and ionic currents
Nernst equation
$E_K = -61 \cdot \log \frac{140}{4.5}$
$= -91$ mV
$[K]_o$ = 4.5 mmol/kg H_2O
$[K]_i$ = 140 mmol/kg H_2O
$E_m - E_K = 0$
Net current $I_K = g_K \cdot (E_m - E_K)$
1. $E_m = E_K$
Outside
Inside
E_m
Equilibrium: $I_K = 0$
(K^+ efflux = K^+ influx)
2. Hyperpolarization
(e.g., due to very high Na^+-K^+-ATPase activity)
$[K]_o$ = 4.5
$[K]_i$ = 140
3 Na^+
2 K^+
$E_m - E_K$ = negative
Net K^+ influx
(I_K negative)
3. Depolarization
(e.g., due to Na^+ influx)
$[K]_o$ = 4.5
$[K]_i$ = 140
Na^+
$E_m - E_K$ = positive
Net K^+ efflux
(I_K positive)


B. Single-channel recording (patch-clamp technique)
1 Experimental set-up
Electrode
Measuring unit
Pipette solution:
150 mmol/L NaCl
+ 5 mmol/L KCl
Pipette
K^+ channel
Cytosolic side
Membrane patch
Bath solution:
5 mmol/L NaCl
+150 mmol/L KCl
2 µm
Oscillograph
200 ms
pA
Burst
Clamp voltage +20 mV
Clamp voltage 0 mV
Clamp voltage –20 mV
Clamp voltage –40 mV
2 Single-channel current recording
3 Data analysis
Current (pA)
Voltage (mV)
–50
–25
0
–25
(After R. Greger)

▶ **Electrodiffusion.** The potential produced by the transport of one ion species can also drive other cations or anions through the cell membrane (→ p. 22), provided it is permeable to them. The K^+diffusion potential leads to the efflux of Cl^-, for example, which continues until $E_{Cl} = E_m$. According to Equation 1.18, this means that the cytosolic Cl^- concentration is reduced to 1/25 th of the extracellular concentration (*passive distribution* of Cl^- between cytosol and extracellular fluid). In the above example, there was a small electrochemical Cl^- potential driving Cl^- out of the cell ($E_m - E_{Cl} = -2$ mV). This means that the cytosolic Cl^- concentration is higher than in passive Cl^- distribution ($E_{Cl} = E_m$). Therefore, Cl^- ions must have been actively taken up by the cell, e.g., by a Na^+- Cl^- symport carrier (→ p. 29 B): *active distribution* of Cl^- .

To achieve ion transport, membranes have a variable number of **channels** (pores) specific for different ion species (Na^+, Ca^{2+}, K^+, Cl^-, etc.). The conductance of the cell membrane is therefore determined by the type and number of ion channels that are momentarily open. *Patch-clamp techniques* permit the direct measurement of *ionic currents through single ion channels* (→ **B**). Patch-clamp studies have shown that the conductance of a membrane does not depend on the change of the pore diameter of its ion channels, but on their average frequency of opening. The ion permeability of a membrane is therefore related to the **open-probability** of the channels in question. Ion channels open in frequent bursts (→ **B2**). Several ten thousands of ions pass through the channel during each individual burst, which lasts for only a few milliseconds.

During a **patch-clamp recording**, the opening (0.3–3 μm in diameter) of a glass electrode is placed over a cell membrane in such a way that the opening covers only a small part of the membrane (*patch*) containing only one or a small number of ion channels. The whole cell can either be left intact, or a membrane patch can excised for isolated study (→ **B1**). In *single-channel recording*, the membrane potential is kept at a preset value (*voltage clamp*). This permits the measurement of ionic current in a single channel. The measurements are plotted (→ **B3**) as current (I) over voltage (V). The slope of the *I/V curve* corresponds to the conductance of the channel for the respective ion species (see Eq. 1.18). The *zero-current potential* is defined as the voltage at which the I/V curve intercepts the x-axis of the curve (I = 0). The ion species producing current I can be deduced from the zero-current potential. In example **B**, the zero-current potential equals – 90 mV. Under the conditions of this experiment, an electrochemical gradient exists only for Na^+ and K^+, but not for Cl^- (→ **B**). At these gradients, $E_K = -90$ mV and $E_{Na} = +90$ mV. As E_K equals the zero-current potential, the channel is exclusively permeable to K^+ and does not allow other ions like Na^+ to pass. The channel type can also be determined by adding specific channel blockers to the system.

Control of ion channels (→ **C**). Channel open-probability is controlled by five main factors:

◆ *Membrane potential*, especially in Na^+, Ca^{2+} and K^+ channels in nerve and muscle fibers (→ **C1**; pp. 46 and 50).

◆ *External ligands* that bind with the channel (→ **C2**). This includes acetylcholine on the postsynaptic membrane of nicotinic synapses (cation channels), glutamate (cation channels), and glycine or GABA (Cl^- channels).


◆ *Intracellular messenger substances* (→ **C3**) such as:

— cAMP (e.g., in Ca^{2+} channels in myocardial cells and Cl^- channels in epithelial cells);
— cGMP (plays a role in muscarinergic effects of acetylcholine and in excitation of the retinal rods);
— IP_3 (e.g. opening of Ca^{2+} channels of intracellular Ca^{2+} stores);
— Small G-proteins (e.g. Ca^{2+} channels of the cell membrane);
— Tyrosine kinases (e.g. Cl^- and K^+ channels during apoptosis);
— Ca^{2+} (affects, for instance, K^+ channels and degree of activation of rapid Na^+ channels; → p. 46).

◆ *Intracellular metabolites* (→ **C4**) such as ATP (e.g., in K^+ channels in the heart and B cells in pancreatic islets) or *H+ ions* (e.g., in K^+ channels in renal epithelial cells);

◆ *Membrane stretch* (→ **C5**), the direct or indirect (?) effects of which play a role in Ca^{2+} channels of smooth muscle fibers and generally in normal K^+ and Cl^- channels in swelling cells.

C. Control of ion channels



The **cytosolic Ca^{2+} concentration, $[Ca^{2+}]_i$,** (ca. 0.1 to 0.01 μmol/L) is several decimal powers lower than the extracellular Ca^{2+} concentration **$[Ca^{2+}]_o$** (ca. 1.3 mmol/L). This is because Ca^{2+} is continuously pumped from the cytosol into **intracellular Ca^{2+} stores** such as the endoplasmic and sarcoplasmic reticulum (→ p. 17 A), vesicles, mitochondria and nuclei or is *transported out of the cell*. Both processes occur by primary active transport (Ca^{2+}-ATPases) and, in the case of efflux, by additional secondary active transport through Ca^{2+}/3 Na^+ antiporters (→ **A1**).

To **increase the cytosolic Ca^{2+} concentration**, **Ca^{2+} channels** conduct Ca^{2+} from intracellular stores and the extracellular space into the cytosol (→ **A2**). The frequency of Ca^{2+} channel opening in the cell membrane is increased by

- *Depolarization* of the cell membrane (nerve and muscle cells);
- *Ligands* (e.g., via G_o proteins; → p. 276);
- *Intracellular messengers* (e.g., IP_3 and cAMP; → p. 276ff.);
- *Stretching or heating* of the cell membrane.


The Ca^{2+} channels of the endoplasmic and sarcoplasmic reticulum open more frequently in response to signals such as a rise in $[Ca^{2+}]_i$ (influx of external Ca^{2+} works as the "spark" or trigger) or inositol *tris*-phosphate (IP_3; → **A2** and p. 278).

A **rise in $[Ca^{2+}]_i$ is a signal** for many important cell functions (→ **A**), including myocyte contraction, exocytosis of neurotransmitters in presynaptic nerve endings, endocrine and exocrine hormone secretion, the excitation of certain sensory cells, the closure of gap junctions in various cells (→ p. 19 C), the opening of other types of ion channels, and the migration of leukocytes and tumor cells (→ p. 30) as well as thrombocyte activation and sperm mobilization. Some of these activities are mediated by **calmodulin**. A calmodulin molecule can bind up to 4 Ca^{2+} ions when the $[Ca^{2+}]_i$ rises (→ **A2**). The *Ca^{2+}-calmodulin complexes* activate a number of different enzymes, including calmodulin-dependent protein kinase II (CaM-kinase II) and myosin light chain kinase (MLCK), which is involved in smooth muscle contraction (→ p. 70).


$[Ca^{2+}]_i$ oscillation is characterized by multiple brief and regular $[Ca^{2+}]_i$ increases (Ca^{2+} spikes) in response to certain stimuli or hormones (→ **B**). The frequency, not amplitude, of $[Ca^{2+}]_i$ oscillation is the quantitative signal for cell response. When low-frequency $[Ca^{2+}]_i$ oscillation occurs, CaM-kinase II, for example, is activated and phosphorylates only its target proteins, but is quickly and completely deactivated (→ **B1**, **B3**). High-frequency $[Ca^{2+}]_i$ oscillation results in an increasing degree of autophosphorylation and progressively delays the deactivation of the enzyme (→ **B3**). As a result, the activity of the enzyme decays more and more slowly between $[Ca^{2+}]_i$ signals, and each additional $[Ca^{2+}]_i$ signal leads to a summation of enzyme activity (→ **B2**). As with action potentials (→ p. 46), this frequency-borne, digital *all-or-none* type of signal transmission provides a much clearer message than the $[Ca^{2+}]_i$ amplitude, which is influenced by a number of factors.

Ca^{2+} sensors. The extracellular Ca^{2+} concentration $[Ca^{2+}]_o$ plays an important role in blood coagulation and bone formation as well as in nerve and muscle excitation. $[Ca^{2+}]_o$ is tightly controlled by hormones such as PTH, calcitriol and calcitonin (→ p. 292), and represents the feedback signal in this control circuit (→ p. 292). The involved Ca^{2+}sensors are membrane proteins that detect **high $[Ca^{2+}]_o$ levels** on the cell surface and dispatch IP_3 and DAG (diacylglycerol) as intracellular second messengers with the aid of a G_q protein (→ **C1** and p. 276ff.). IP_3 triggers an increase in the $[Ca^{2+}]_i$ of parafollicular C cells of the thyroid gland. This induces the exocytosis of calcitonin, a substance that *reduces* $[Ca^{2+}]_o$ (→ **C2**). In parathyroid cells, on the other hand, a high $[Ca^{2+}]_o$ reduces the secretion of PTH, a hormone that increases the $[Ca^{2+}]_o$. This activity is mediated by DAG and PKC (protein kinase C) and, perhaps, by a (G_i protein-mediated; → p. 276) reduction in the cAMP concentration (→ **C3**). Ca^{2+} sensors are also located on osteoclasts as well as on renal and intestinal epithelial cells.


A. Role of Ca^{2+} in cell regulation



B. Ca^{2+} oscillation



C. Ca^{2+} sensor



Energy is the ability of a system to perform *work*; both are expressed in joules (J). A **potential difference** (potential gradient) is the so-called *driving "force"* that mobilizes the matter involved in the work. Water falling from height X (in meters) onto a power generator, for example, represents the potential gradient in mechanical work. In electrical and chemical work, potential gradients are provided respectively by voltage (V) and a change in free enthalpy ΔG ($J \cdot mol^{-1}$). The amount of work performed can be determined by multiplying the potential difference (*intensity factor*) by the corresponding *capacity factor*. In the case of the water fall, the work equals the height the water falls (m) times the force of the falling water (in N). In the other examples, the amount work performed equals the voltage (V) times the amount of charge (C). Chemical work performed = ΔG times the amount of substance (mol).

Living organisms cannot survive without an adequate supply of energy. Plants utilize solar energy to convert atmospheric CO_2 into oxygen and various organic compounds. These, in turn, are used to fill the energy needs of humans and animals. This illustrates how energy can be converted from one form into another. If we consider such a transformation taking place in a **closed system (**exchange of energy, but not of matter, with the environment), energy can neither appear nor disappear spontaneously. In other words, when energy is converted in a closed system, the total energy content remains constant. This is described in the **first law of thermodynamics**, which states that the change of internal energy (= change of energy content, ΔU) of a system (e.g. of a chemical reaction) equals the sum of the work absorbed (+W) or performed (–W) by a system and the heat lost (–Q) or gained (+Q) by the system. This is described as:

ΔU = heat gained (Q) − work performed (W) [J] and [1.22]

ΔU = work absorbed (W) − heat lost (Q) [J]. [1.23]

(By definition, the signs indicate the direction of flow with respect to the system under consideration.)

Heat is transferred in all chemical reactions. The amount of heat produced upon conversion of a given substance into product X is the same, *regardless of the reaction pathway* or whether the system is closed or open, as in a biological system. For caloric values, see p. 230.

Enthalpy change (ΔH) is the heat gained or lost by a system at constant pressure and is related to work, pressure, and volume ($\Delta H = \Delta U + p \cdot \Delta V$). Heat is lost and ΔH is negative in **exothermic** reactions, while heat is gained and ΔH is positive in **endothermic** reactions. The **second law of thermodynamics** states that the total disorder (randomness) or entropy (S) of a closed system increases in any spontaneous process, i.e., **entropy change (ΔS)** > 0. This must be taken into consideration when attempting to determine how much of ΔH is freely available. This free energy or free enthalpy (ΔG) can be used, for example, to drive a chemical reaction. The heat produced in the process is the product of absolute temperature and entropy change ($T \cdot \Delta S$).


Free enthalpy (ΔG) can be calculated using the Gibbs-Helmholtz equation:

$$\mathbf{\Delta G = \Delta H - T \cdot \Delta S.} \quad [1.24]$$

ΔG and ΔH are approximately equal when ΔS approaches zero. The maximum chemical work of glucose in the body can therefore be deduced based on heat transfer, ΔH, measured during the combustion of glucose in a calorimeter (see p. 230). Equation 1.24 also defines the conditions under which chemical reactions can occur. **Exergonic** reactions ($\Delta G < 0$) are characterized by the release of energy and can proceed spontaneously, whereas **endergonic** reactions ($\Delta G > 0$) require the absorption of energy and are not spontaneous. An endothermic reaction ($\Delta H > 0$) can also be exergonic ($\Delta G < 0$) when the entropy change ΔS is so large that $\Delta H - T \cdot \Delta S$ becomes negative. This occurs, for example, in the endothermic dissolution of crystalline NaCl in water.


Free enthalpy, ΔG, is a concentration-dependent variable that can be calculated from the change in **standard free enthalpy (ΔG^0)** and the prevailing concentrations of the substances in question. ΔG^0 is calculated assuming for all reaction partners that concentration = 1 mol/L, pH = 7.0, T = 298 K, and p = 1013 hPa. ▶

A. Activation energy (E_a)


Energy required for reaction to occur (P_a)
Chemical potential
Transitional state F
Uncatalyzed activation energy $E_a = P_a - P_e$
No reaction
P_a'
Catalyzed activation energy $E_a' = P_a' - P_e$
Educt A
Energy level of educt (P_e)
Free enthalpy $\Delta G^0 = P_p - P_e$
Product B
Energy level of product (P_p)
Reaction pathway


(Partly after J. Koolman and K.-H. Röhm)

B. Molecular fraction (F) when $P_e > P_a$



(After J. Koolman and K.-H. Röhm)

C. Aerobic ATP production



(see plate 1.8**B**)

▶ Given the reaction

$$A \rightleftharpoons B + C, \quad [1.25]$$

where A is the educt and B and C are the products, ΔG^0 is converted to ΔG as follows:

$$\Delta G = \Delta G^0 + R \cdot T \cdot \ln \frac{[B] + [C]}{[A]} \quad [1.26]$$

or, at a temperature of 37 °C,

$$\Delta G = \Delta G^0 + 8.31 \cdot 310 \cdot 2.3 \cdot \log \frac{[B] + [C]}{[A]} \; [J \cdot mol^{-1}] \quad [1.27]$$

Assuming the ΔG^0 of a reaction is $+20\ kJ \cdot mol^{-1}$ (endergonic reaction), ΔG will be exergonic (< 0) if $[B] \cdot [C]$ is 10^4 times smaller than A:

$$\Delta G = 20000 + 5925 \cdot \log 10^{-4} = -3.7\ kJ \cdot mol^{-1}. \quad [1.28]$$

In this case, A is converted to B and C and reaction 1.25 proceeds to the right.

If $[B] \cdot [C]/[A] = 4.2 \times 10^{-4}$, ΔG will equal zero and the reaction will come to equilibrium (no net reaction). This numeric ratio is called the **equilibrium constant (K_{eq})** of the reaction. K_{eq} can be converted to ΔG^0 and vice versa using Equation 1.26:

$$0 = \Delta G^0 + R \cdot T \cdot \ln K_{eq} \text{ or}$$

$$\Delta G^0 = -R \cdot T \cdot \ln K_{eq} \quad [1.29]$$

or

$$K_{eq} = e^{-\Delta G^\circ/(R \cdot T)}. \quad [1.30]$$

Conversely, when $[B] \cdot [C]/[A] > 4.2 \times 10^{-4}$, ΔG will be > 0, the net reaction will proceed backwards, and A will arise from B and C.

ΔG is therefore a measure of the direction of a reaction and of its *distance from equilibrium*. Considering the concentration-dependency of ΔG and assuming the reaction took place in an open system (see below) where reaction products are removed continuously, e.g., in subsequent metabolic reactions, it follows that ΔG would be a large negative value, and that the reaction would persist without reaching equilibrium.

The magnitude of ΔG^0, which represents the difference between the energy levels (chemical potentials) of the product P_p and educt P_e (→ **A**), does not tell us anything about the **rate of the reaction**. A reaction may be very slow, even if $\Delta G^0 < 0$, because the reaction rate also depends on the energy level (P_a) needed *transiently* to create the necessary transitional state. P_a is higher than P_e (→ **A**). The additional amount of energy required ($P_a - P_e$) to reach this level is called the **activation energy E_a**. It is usually so large ($\approx 50\ kJ \cdot mol^{-1}$) that only a tiny fraction ($F \approx 10^{-9}$) of the educt molecules are able to provide it (→ **A, B**). The energy levels of these individual educt molecules are incidentally higher than P_e, which represents the mean value for all educt molecules. The size of **fraction F** is temperature-dependent (→ **B**). A 10 °C decrease or rise in temperature lowers or raises F (and usually the reaction rate) by a factor of 2 to 4, i.e. the **Q_{10} value** of the reaction is 2 to 4.

Considering the high E_a values of many non-catalyzed reactions, the development of **enzymes** as biological catalysts was a very important step in evolution. Enzymes enormously accelerate reaction rates by lowering the activation energy E_a (→ **A**). According to the Arrhenius equation, the **rate constant k** (s^{-1}) of a unimolecular reaction is proportional to $e^{-E_a/(R \cdot T)}$. For example, if a given enzyme reduces the E_a of a unimolecular reaction from 126 to 63 $kJ \cdot mol^{-1}$, the rate constant at 310 °K (37 °C) will rise by $e^{-63000/(8.31 \cdot 310)}/e^{-126000/(8.31 \cdot 310)}$, i.e., by a factor of $4 \cdot 10^{10}$. The enzyme would therefore reduce the time required to metabolize 50% of the starting materials ($t^1/_2$) from, say, 10 years to 7 msec! The forward rate of a reaction ($mol \cdot L^{-1} \cdot s^{-1}$) is related to the product of the rate constant (s^{-1}) and the starting substrate concentration ($mol \cdot L^{-1}$).

The second law of thermodynamics also implies that a continuous loss of free energy occurs as the total disorder or entropy (S) of a closed system increases. A living organism represents an **open system** which, by definition, can absorb energy-rich nutrients and discharge end products of metabolism. While the entropy of a closed system (organism + environment) increases in the process, an open system (organism) can either maintain its entropy level or reduce it using free enthalpy. This occurs, for example, when ion gradients or hydraulic pressure differences are created within the body. A closed system therefore has a maximum entropy, is in a true state of chemical equilibrium, and can perform work only once. An open system such as the body can *continuously* perform work while producing only a minimum of entropy. A true state of equilibrium is achieved in only a very few processes within the body, e.g., in the reaction

$CO_2 + H_2O \rightleftharpoons HCO_3^- + H^+$. In most cases (e.g. metabolic pathways, ion gradients), only a *steady state* is reached. Such metabolic pathways are usually *irreversible* due, for example, to excretion of the end products. The thought of reversing the "reaction" germ cell → adult illustrates just how impossible this is.

At **steady state**, the *rate* of a reaction is more important than its equilibrium. The regulation of body functions is achieved by controlling reaction rates. Some reactions are so slow that it is impossible to achieve a sufficient reaction rate with enzymes or by reducing the concentration of the reaction products. These are therefore endergonic reactions that require the input of outside energy. This can involve "activation" of the educt by attachment of a high-energy phosphate group to raise the P_e.

ATP (adenosine triphosphate) is the universal carrier and transformer of free enthalpy within the body. ATP is a nucleotide that derives its chemical energy from energy-rich nutrients (→ **C**). Most ATP is produced by **oxidation** of energy-rich biological molecules such as glucose. In this case, oxidation means the removal of electrons from an electron-rich (reduced) donor which, in this case, is a carbohydrate. CO_2 and H_2O are the end products of the reaction. In the body, oxidation (or electron transfer) occurs in several stages, and a portion of the liberated energy can be simultaneously used for ATP synthesis. This is therefore a **coupled reaction** (→ **C** and p. 17 B). The standard free enthalpy ΔG^0 of **ATP hydrolysis**,

$$ATP \rightleftharpoons ADP + P_i \qquad [1.31]$$

is $-30.5\ kJ \cdot mol^{-1}$. According to Eq. 1.27, the ΔG of reaction 1.31 should increase when the ratio $([ADP] \cdot [P_i])/[ATP]$ falls below the equilibrium constant K_{eq} of ATP hydrolysis. The fact that a high cellular ATP concentration does indeed yield a ΔG of approximately -46 to $-54\ kJ \cdot mol^{-1}$ shows that this also applies in practice.

Some substances have a much higher ΔG^0 of hydrolysis than ATP, e.g., *creatine phosphate* ($-43\ kJ \cdot mol^{-1}$). These compounds react with ADP and P_i to form ATP. On the other hand, the energy of ATP can be used to synthesize other compounds such as UTP, GTP and glucose-6-phosphate. The energy content of these substances is lower than that of ATP, but still relatively high.

The free energy liberated upon hydrolysis of ATP is used to drive hundreds of reactions within the body, including the active transmembrane transport of various substances, protein synthesis, and muscle contraction. According to the laws of thermodynamics, the expenditure of energy in all of these reactions leads to increased order in living cells and, thus, in the organism as a whole. Life is therefore characterized by the continuous reduction of entropy associated with a corresponding increase in entropy in the immediate environment and, ultimately, in the universe.

An excitable cell reacts to stimuli by altering its membrane characteristics (→ p. 32). There are two types of excitable cells: *nerve cells*, which transmit and modify impulses within the nervous system, and *muscle cells*, which contract either in response to nerve stimuli or autonomously (→ p. 59).

The human nervous system consists of more than 10^{10} nerve cells or neurons. The **neuron** is the *structural and functional unit of the nervous system*. A typical neuron (motor neuron, → **A1**) consists of the *soma* or cell body and two types of processes: the *axon* and *dendrites*. Apart from the usual intracellular organelles (→ p. 8 ff.), such as a nucleus and mitochondria (→ **A2**), the neuron contains *neurofibrils* and *neurotubules*. The neuron receives *afferent signals* (excitatory and inhibitory) from a few to sometimes several thousands of other neurons via its **dendrites** (usually arborescent) and sums the signals along the cell membrane of the soma (*summation*). The **axon** arises from the axon hillock of the soma and is responsible for the transmission of efferent neural signals to nearby or distant *effectors* (muscle and glandular cells) and adjacent neurons. Axons often have branches (*collaterals*) that further divide and terminate in swellings called *synaptic knobs* or *terminal buttons*. If the summed value of potentials at the axon hillock exceeds a certain threshold, an **action potential** (→ p. 46) is generated and sent down the axon, where it reaches the next synapse via the **terminal buttons** (→ **A1,3**) described below.


Vesicles containing materials such as proteins, lipids, sugars, and transmitter substances are conveyed from the Golgi complex of the soma (→ p. 13 F) to the terminal buttons and the tips of the dendrites by *rapid* **axonal transport** (40 cm/day). This type of *anterograde* transport along the neurotubules is promoted by *kinesin*, a myosin-like protein, and the energy required for it is supplied by ATP (→ p. 16). Endogenous and exogenous substances such as nerve growth factor (NGF), herpes virus, poliomyelitis virus, and tetanus toxin are conveyed by *retrograde* transport from the peripheral regions to the soma at a rate of ca. 25 cm/day. *Slow* axon transport (ca. 1 mm/day) plays a role in the regeneration of severed neurites.

Along the axon, the plasma membrane of the soma continues as the axolemma (→ **A1,2**). The axolemma is surrounded by **oligodendrocytes** (→ p. 344) in the central nervous system (CNS), and by **Schwann cells** in the peripheral nervous system (→ **A1,2**). A **nerve fiber** consists of an axon plus its sheath. In some neurons, Schwann cells form multiple concentric double phospholipid layers around an axon, comprising the **myelin sheath** (→ **A1,2**) that insulates the axon from ion currents. The sheath is interrupted every 1.5 mm or so at the **nodes of Ranvier** (→ **A1**). The *conduction velocity* of such myelinated nerve fibers is much higher than that of unmyelinated nerve fibers and increases with the diameter of the nerve fiber (→ p. 49 C).


A **synapse** (→ **A3**) is the site where the axon of a neuron communicates with effectors or other neurons (see also p. 50 ff.). With very few exceptions, **synaptic transmissions** in mammals are mediated by chemicals, not by electrical signals. In response to an electrical signal in the axon, vesicles (→ p. 1.6) on the **presynaptic membrane** release transmitter substances (**neurotransmitters**) by exocytosis (→ p. 30). The transmitter diffuses across the **synaptic cleft** (10–40 nm) to the postsynaptic membrane, where it binds to receptors effecting new electrical changes (→ **A3**). Depending on the type of neurotransmitter and postsynaptic receptor involved, the transmitter will either have an excitatory effect (e.g., acetylcholine in skeletal muscle) or inhibitory effect (e.g., glycine in the CNS) on the postsynaptic membrane. Since the postsynaptic membrane normally does not release neurotransmitters (with only few exceptions, for example p. 346), nerve impulses can pass the synapse in one direction only. The synapse therefore acts like a *valve* that ensures the orderly transmission of signals. Synapses are also the sites at which neuronal signal transmissions can be *modified* by other (excitatory or inhibitory) neurons.

A. Nerve cell structure and function

1 Neuron and synapse




2 Myelinated and unmyelinated nerve fibers



Electron microscopic view,
1:22000 magnification.
Photograph courtesy of Dr. Lauren A. Langford

3 Synapse (diagram)



An electrical potential difference, or **membrane potential** (E_m), can be recorded across the plasma membrane of living cells. The potential of unstimulated muscle and nerve cells, or **resting potential,** amounts to – 50 to – 100 mV (cell interior is negative). A resting potential is caused by a slightly unbalanced distribution of ions between the intracellular fluid (ICF) and extracellular fluid (ECF) (→ **B**). The following factors are involved in establishing the membrane potential (see also p. 32 ff.).

◆ **Maintenance of an unequal distribution of ions:** The Na^+-K^+-ATPase (→ p. 26) continuously "pumps" Na^+ out of the cell and K^+ into it (→ **A2**). As a result, the intracellular K^+ concentration is around 35 times higher and the intracellular Na^+ concentration is roughly 20 times lower than the extracellular concentration (→ **B**). As in any active transport, this process requires energy, which is supplied by ATP. Lack of energy or inhibition of the Na^+-K^+-ATPase results in flattening of the ion concentration gradient and breakdown of the membrane potential.

Because anionic proteins and phosphates present in high concentrations in the cytosol are virtually unable to leave the cell, purely passive mechanisms (*Gibbs–Donnan distribution*) could, to a slight extent, contribute to the unequal distribution of diffusable ions (→ **A1**). For reasons of electroneutrality, $[K^+{+}Na^+]_{ICF} > [K^+{+}Na^+]_{ECF}$ and $[Cl^-]_{ICF} < [Cl^-]_{ECF}$. However, this has practically no effect on the development of resting potentials.

◆ **Low resting Na^+ and Ca^{2+} conductance, g_{Na}, g_{Ca}:** The membrane of a resting cell is only very slightly permeable to Na^+ and Ca^{2+}, and the resting g_{Na} comprises only a small percentage of the total conductance (→ p. 32 ff.). Hence, the Na^+ concentration difference (→ **A3–A5**) cannot be eliminated by immediate passive diffusion of Na^+ back into the cell.


◆ **High K^+conductance, g_K:** It is relatively easy for K^+ ions to diffuse across the cell membrane ($g_K \approx 90\%$ of total conductance; → p. 32 ff.). Because of the steep concentration gradient (→ point 1), K^+ ions diffuse from the ICF to the ECF (→ **A3**). Because of their positive charge, the diffusion of even small amounts of K^+ ions leads to an electrical potential (*diffusion potential*) across the membrane. This (inside negative) diffusion potential drives K^+ back into the cell and rises until large enough to almost completely compensate for the K^+ concentration gradient driving the K^+-ions out of the cell (→ **A4**). As a result, the membrane potential, E_m, is approximately equal to the K^+ equilibrium potential E_K (→ p. 32).

◆ **Cl^- distribution:** Since the cell membrane is also conductive to Cl^- (g_{Cl} greater in muscle cells than in nerve cells), the membrane potential (electrical driving "force") expels Cl^- ions from the cell (→ **A4**) until the Cl^- concentration gradient (chemical driving "force") drives them back into the cell at the same rate, i. e. until the intracellular Cl^- concentration, $[Cl^-]_i$ has reached a value at which the Cl^- equilibrium potential g_{Cl} equals E_m (→ **A5**). This $[Cl^-]_i$ can be calculated using the *Nernst equation* (→ p. 32, Eq. 1.18). Such a "passive" distribution of Cl^- between the intra- and extracellular spaces exists only as long as there is no active Cl^- uptake into the cell (→ p. 34).

◆ **Why is E_m less negative than E_K?** Although the conductances of Na^+ and Ca^{2+} are very low in resting cells, a few Na^+ and Ca^{2+} ions constantly enter the cell (→ **A4, 5**). This occurs because the equilibrium potential for both types of ions extends far into the positive range, resulting in a high outside-to-inside electrical and chemical driving "force" for these ions (→ **B**; → p. 32 f.). This cation influx depolarizes the cell, thereby driving K^+ ions out of the cell (1 K^+ for each positive charge that enters). If Na^+-K^+-ATPase did not restore these gradients continuously (Ca^{2+} indirectly via the 3 Na^+/Ca^{2+} exchanger; → p. 36), the intracellular Na^+ and Ca^{2+} concentrations would increase continuously, whereas $[K^+]_i$ would decrease, and E_K and E_m, therefore, would become less negative.

All living cells have a (resting) membrane potential, but only excitable cells such as nerve and muscle cells are able to greatly change the ion conductance of their membrane in response to a stimulus, as in an *action potential* (→ p. 46).

A. Causes and effects of resting membrane potentials



B. Typical "effective" concentrations and equilibrium potentials of important ions in skeletal muscle (at 37°C)

	"Effective" concentration (mmol/kg H_2O)		Equilibrium potential
	Interstice (ECF)	Cell (ICF)	
K^+	4.5	160	– 95 mV
Na^+	144	7	+ 80 mV
Ca^{2+}	1.3	0.0001 – 0.00001	+125 to +310 mV
H^+	$4 \cdot 10^{-5}$ (pH 7.4)	10^{-4} (pH 7.0)	– 24 mV
Cl^-	114	7	– 80 mV
HCO_3^-	28	10	– 27 mV

(After Conway)

An action potential is a signal passed on through an axon or along a muscle fiber that influences other neurons or induces muscle contraction. **Excitation** of a neuron occurs if the membrane potential, E_m, on the axon hillock of a motor neuron, for example (→ p. 42), or on the motor end-plate of a muscle fiber changes from its resting value (→ p. 44) to a less negative value (slow *depolarization*, → **A1**). This depolarization may be caused by neurotransmitter-induced opening of postsynaptic cation channels (→ p. 50) or by the (electrotonic) transmission of stimuli from the surroundings (→ p. 48). If the E_m of a stimulated cell comes close to a critical voltage or **threshold potential** (→ **A1**), "rapid" voltage-gated Na^+ channels are activated (→ **B4** and **B1** ⇒ **B2**). This results in *increased Na^+ conductance*, g_{Na} (→ p. 32), and a higher entry of Na^+ into the cell (→ **A2**). If the threshold potential is not reached, this process remains a *local (subthreshold) response*.

Once the threshold potential is reached, the cell responds with a fast **all-or-none** depolarization called an **action potential, AP** (→ **A1**). The AP follows a pattern typical of the specific cell type, irregardless of the magnitude of the stimulus that generated it. Large numbers of Na^+ channels are activated, and the influxing Na^+ accelerates depolarization which, in turn, increases g_{Na} and so on (positive feedback). As a result, the E_m rapidly collapses (0.1 ms in nerve cells: fast **depolarization phase** or upsweep) and temporarily reaches positive levels (*overshooting*, + 20 to + 30 mV). The g_{Na} drops before overshooting occurs (→ **A2**) because the Na^+ channels are *inactivated* within 0.1 ms (→ **B2** ⇒ **B3**). The potential therefore reverses, and restoration of the resting potential, the **repolarization phase** of the action potential, begins. Depolarization has increased (relatively slowly) the open-probability of voltage-gated K^+ channels. This has increased the potassium conductance, g_K, thereby accelerating repolarization.

In many cases, potassium conductance, g_K is still increased after the original resting potential has been restored (→ **A2**), and E_m temporarily approaches E_K (→ pp. 44 and 32 ff.), resulting in a hyperpolarizing **afterpotential** (→ **A1**). Increased Na^+-K^+-ATPase pumping rates (electrogenic; → p. 28) can contribute to this afterpotential.

Very long trains of action potentials can be generated (up to 1000/s in some nerves) since the quantity of ions penetrating the membrane is very small (only ca. 1/100 000 th the number of intracellular ions). Moreover, the Na^+-K^+-ATPase (→ p. 26) ensures the continuous restoration of original ion concentrations (→ p. 46).


During an action potential, the cell remains unresponsive to further stimuli; this is called the **refractory period**. In the *absolute refractory period*, no other action potential can be triggered, even by extremely strong stimuli, since Na^+ channels in depolarized membranes cannot be activated (→ **B3**). This is followed by a *relative refractory period* during which only action potentials of smaller amplitudes and rates of rise can be generated, even by strong stimuli. The refractory period ends once the membrane potential returns to its resting value (→ e.g. p. 59 A).

The extent to which Na^+ channels can be activated and, thus, the strength of the Na^+ current, I_{Na}, depends on the pre-excitatory resting potential, not the duration of depolarization. The activation of the Na^+ channels reaches a maximum at resting potentials of ca. – 100 mV and is around 40% lower at – 60 mV. In mammals, Na^+ channels can no longer be activated at potentials of – 50 mV and less negative values (→ **B3**). This is the reason for the absolute and relative refractory periods (see above) and the non-excitability of cells after the administration of continuously depolarizing substances such as suxamethonium (→ p. 56).


An increased extracellular Ca^{2+} concentration makes it more difficult to stimulate the cell because the threshold potential becomes less negative. On the other hand, excitability increases (lower threshold) in hypocalcemic states, as in muscle spasms in *tetany* (→ p. 292).

The special features of action potentials in cardiac and smooth muscle fibers are described on pages 59, 70, and 194.

A. Action potential (1) and ion conductivity (2) (nerve and skeletal muscle)



B. Voltage-gated Na^+ channel



Electrical current flows through a *cable* when voltage is applied to it. The metal wire inside the cable is well insulated and has very low-level resistance, reducing current loss to a minimum. As a result, it can conduct electricity over long distances. *Nerve fibers*, especially unmyelinated ones (→ p. 42), have a much greater internal longitudinal resistance (R_i) and are not well insulated from their surroundings. Therefore, the cable-like, **electrotonic transmission** of neural impulses dwindles very rapidly, so the conducted impulses must be continuously "refreshed" by generating new **action potentials** (→ p. 46).

Propagation of action potentials: The start of an action potential is accompanied by a brief influx of Na^+ into the nerve fiber (→ **A1a**). The cell membrane that previously was inside negative now becomes positive (+20 to +30 mV), thus creating a longitudinal potential difference with respect to the adjacent, still unstimulated nerve segments (internal –70 to –90 mV; → p. 44). This is followed by a passive *electrotonic withdrawal of charge* from the adjacent segment of the nerve fiber, causing its *depolarization*. If it exceeds threshold, another action potential is created in the adjacent segment and the action potential in the previous segment dissipates (→ **A1b**).


Because the membrane acts as a *capacitor*, the withdrawal of charge represents a capacitating (depolarizing) flow of charge that becomes smaller and rises less steeply as the spatial distance increases. Because of the relatively high R_i of nerve fiber, the outward loops of current cross the membrane relatively close to the site of excitation, and the longitudinal current decreases as it proceeds towards the periphery. At the same time, depolarization increases the driving force ($= E_m - E_K$; → p. 32) for K^+ outflow. K^+ fluxing out of the cell therefore accelerates repolarization. Hence, distal action potentials are restricted to distances from which the capacitative current suffices to depolarize the membrane quickly and strongly enough. Otherwise, the Na^+ channels will be deactivated before the threshold potential is reached (→ p. 46).

Action potentials normally run forward (orthodromic) because each segment of nerve fiber becomes refractory when an action potential passes (→ **A1b** and p. 46). If, however, the impulses are conducted backwards (antidromic) due, for example, to electrical stimulation of nerve fibers from an external source (→ p. 50), they will terminate at the next synapse (valve-like function, → p. 42).


Although the continuous generation of action potentials in the immediately adjacent fiber segment guarantees a refreshed signal, this process is rather time-consuming (→ **B1**). The **conduction velocity**, θ, in unmyelinated (type C) nerve fibers (→ **C**) is only around 1 m/s. Myelinated (types A and B) nerve fibers (→ **C**) conduct much faster (up to 80 m/s = 180 mph in humans). In the *internode regions*, a *myelin sheath* (→ p. 42) insulates the nerve fibers from the surroundings; thus, longitudinal currents strong enough to generate action potentials can travel further down the axon (ca. 1.5 mm) (→ **A2**). This results in more rapid conduction because the action potentials are generated only at the unmyelinated *nodes of Ranvier*, where there is a high density of Na^+ channels. This results in rapid, jump-like passage of the action potential from node to node (**saltatory propagation**). The saltatory length is limited since the longitudinal current (1 to 2 nA) grows weaker with increasing distance (→ **B2**). Before it drops below the threshold level, the signal must therefore be refreshed by a new action potential, with a time loss of 0.1 ms.

Since the internal resistance, R_i, of the nerve fiber limits the spread of depolarization, as described above, the **axon diameter** ($2r$) also affects the conduction velocity, θ (→ **C**). R_i is proportional to the cross-sectional area of the nerve fiber (πr^2), i.e., $R_i \sim 1/r^2$. Thick fibers therefore require fewer new APs per unit of length, which is beneficial for θ. However, increases in fiber diameter are accompanied by an increase in fiber circumference ($2\pi r$) and, therefore, in membrane capacity, K ($K \sim r$). Although θ decreases for this reason, the beneficial effect of the smaller R_i predominates because of the quadratic relationship.

A. Continuous (1a, 1b) and saltatory propagation (2) of action potentials



B. Pulse propagation (action currents) in myelinated and unmyelinated nerve fibers



C. Classification of nerve fibers (in humans)

Fiber type	Function according to fiber type (Lloyd and Hunt types I–IV)	Diameter (µm)	Conduction rate (m/s)
Aα	Skeletal muscle efferent, afferents in muscle spindles (Ib) and tendon organs (Ib)	11–16	60–80
Aβ	Mechanoafferents of skin (II)	6–11	30–60
Aγ	Muscle spindle efferents	1–6	2–30
Aδ	Skin afferents (temperature and "fast" pain) (III)		
B	Sympathetic preganglionic; visceral afferents	3	3–15
C	Skin afferents ("slow" pain); sympathetic postganglionic afferents (IV)	0.5–1.5 (unmyelinated)	0.25–1.5

(After Erlanger and Gasser)

When an electrical stimulus is applied to a nerve cell from an external source, current flows from the positive stimulating electrode (*anode*) into the neuron, and exits at the negative electrode (*cathode*). The nerve fiber below the cathode is depolarized and an action potential is generated there if the threshold potential is reached.

The **conduction velocity** of a nerve can be measured by placing two electrodes on the skin along the course of the nerve at a known distance from each other, then stimulating the nerve (containing multiple neurons) and recording the time it takes the summated action potential to travel the known distance. The conduction velocity in humans is normally 40 to 70 $m \cdot s^{-1}$. Values below 40 $m \cdot s^{-1}$ are considered to be pathological.

Accidental electrification. Exposure of the body to high-voltage electricity, especially low-frequency alternating current (e.g., in an electrical outlet) and low contact resistance (bare feet, bathtub accidents), primarily affects the conduction of impulses in the heart and can cause ventricular fibrillation (→ p. 202).

Direct current usually acts as a stimulus only when switched on or off: High-frequency alternating current (> 15 kHz), on the other hand, cannot cause depolarization but heats the body tissues. **Diathermy** works on this principle.

Synaptic Transmission


Synapses connect nerve cells to other nerve cells (also applies for certain muscle cells) as well as to sensory and effector cells (muscle and glandular cells).

Electrical synapses are direct, ion-conducting cell–cell junctions through channels (*connexons*) in the region of *gap junctions* (→ p. 16 f.). They are responsible for the conduction of impulses between neighboring smooth or cardiac muscle fibers (and sometimes between neurons in the retina and in the CNS) and ensure also communication between neighboring epithelial or glial cells.

Chemical synapses utilize **(neuro)transmitters** for the transmission of information and provide not only simple 1 : 1 connections, but also serve as switching elements for the nervous system. They can facilitate or inhibit the neuronal transmission of information or process them with other neuronal input. At the chemical synapse, the arrival of an action potential (AP) in the axon (→ **A1,2** and p. 48) triggers the release of the transmitter from the presynaptic axon terminals. The transmitter then diffuses across the narrow synaptic cleft (ca. 30 nm) to bind postsynaptically to **receptors** in the *subsynaptic membrane* of a neuron or of a glandular or muscle cell. Depending on the type of transmitter and receptor involved, the effect on the *postsynaptic membrane* may either be excitatory or inhibitory, as is described below.

Transmitters are **released** by regulated *exocytosis* of so-called *synaptic vesicles* (→ **A1**). Each vesicle contains a certain *quantum* of neurotransmitters. In the case of the motor end-plate (→ p. 56), around 7000 molecules of acetylcholine (ACh) are released. Some of the vesicles are already docked on the membrane (*active zone*), ready to exocytose their contents. An incoming action potential functions as the signal for transmitter release (→ **A1,2**). The higher the action potential *frequency* in the axon the more vesicles release their contents. An action potential increases the open probability of *voltage-gated Ca^{2+} channels* in the presynaptic membrane (sometimes oscillating), thereby leading to an increase in the cytosolic Ca^{2+} concentration, $[Ca^{2+}]_i$ (→ **A1, 3** and p. 36). Extracellular Mg^{2+} inhibits this process. Ca^{2+} binds to *synaptotagmin* (→ **A1**), which triggers the interaction of *syntaxin* and *SNAP-25* on the presynaptic membrane with *synaptobrevin* on the vesicle membrane, thereby triggering exocytosis of already docked vesicles (approximately 100 per AP) (→ **A1, 4**). On the other hand, Ca^{2+} activates calcium-calmodulin-dependent protein kinase-II (*CaM-kinase-II*; → **A5**, and p. 36), which activates the enzyme *synapsin* at the presynaptic terminal. As a result, vesicles dock anew on the active zone.

Synaptic facilitation (= **potentiation**). If an action potential should arrive at the presynaptic terminal immediately after another AP (AP frequency > approx. 30 Hz), the cytosolic Ca^{2+} concentration will not yet drop to the resting value, and residual Ca^{2+} will accumulate. As a result, the more recent rise in $[Ca^{2+}]_i$ builds on ▶


A. Chemical synapse
Na+
AP
1
Presynaptic action potential
2
0
mV
−80
Calmodulin
Presynaptic ending
Ca2+
Ca2+ influx
3
0
nA
−0.5
ICa
Vesicle
CaM-kinase II
Synapto-tagmin
Active zone
Transmitter
Transmitter release
4
Transmitter in cleft
mmol/L
1
0
Ionotropic receptor
or
Metabotropic receptor
Cation channel
Synaptic cleft
Postsynaptic cell
(Partly after Llinás)
5
Synapsin
CaM-kinase II
Vesicle preparation
Active zone
Docking
K+
Na+ (Ca2+)
or
Signal chain
K+
6
7
Ca2+ (Na+)
Transmitter binding to receptors
EPSP1 EPSP2 EPSP3
Summation
Postsynaptic action potential
mV
0
−90
(see plate B.)


▶ the former one. $[Ca^{2+}]_i$ rises to a higher level after the second stimulus than after the first, and also releases more transmitters. Hence, the first stimulus *facilitates* the response to the second stimulus. Muscle strength increases at high stimulus frequencies for similar reasons (→ p. 67 A).


Among the many substances that act as **excitatory transmitters** are acetylcholine (ACh) and glutamate (Glu). They are often released together with *co-transmitters* which modulate the transmission of a stimulus (e.g., ACh together with substance P, VIP or galanin; Glu with substance P or enkephalin). If the transmitter's receptor is an ion channel itself (*ionotropic receptor* or *ligand-gated ion channel*; → **A6** and **F**), e.g., at the N-cholinergic synapse (→ p. 82), the channels open more often and allow a larger number of cations to enter (Na^+, sometimes Ca^{2+}) and leave the cell (K^+). Other, so-called *metabotropic receptors* influence the channel via *G proteins* that control channels themselves or by means of "second messengers" (→ **A7** and **F**). Because of the high electrochemical Na^+ gradient (→ p. 32), the number of incoming Na^+ ions is much larger than the number of exiting K^+ ions. Ca^{2+} can also enter the cell, e.g., at the glutamate-NMDA receptor (→ **F**). The net influx of cations leads to depolarization: **excitatory postsynaptic potential (EPSP)** (maximum of ca. 20 mV; → **B**). The EPSP begins approx. 0.5 ms after the arrival of an action potential at the presynaptic terminal. This *synaptic delay* (latency) is caused by the relatively slow release and diffusion of the transmitter.


A single EPSP normally is not able to generate a postsynaptic (axonal) action potential (AP_A), but requires the triggering of a large number of local depolarizations in the dendrites. Their depolarizations are transmitted electrotonically across the soma (→ p. 48) and summed on the axon hillock (**spatial summation**; → **B**). Should the individual stimuli arrive at different times (within approx. 50 ms of each other), the prior depolarization will not have dissipated before the next one arrives, and summation will make it easier to reach threshold. This type of **temporal summation** therefore increases the excitability of the postsynaptic neuron (→ **C**).


Inhibitory transmitters include substances as glycine, GABA (γ-aminobutyric acid), and acetylcholine (at M2 and M3 receptors; → p. 82). They increase the conductance, g, of the subsynaptic membrane only to K^+ (e.g., the metabotropic $GABA_B$ receptor.) or Cl^- (e.g., the ionotropic glycine and $GABA_A$ receptors; → **F**). The membrane usually becomes hyperpolarized in the process (ca. 4 mV max.). Increases in g_K occur when E_m approaches E_K (→ p. 44). However, the main effect of this *inhibitory postsynaptic potential* IPSP (→ **D**) is not hyperpolarization – which works counter to EPSP-related depolarization (the IPSP is sometimes even slightly depolarizing). Instead, the IPSP-related increase in membrane conductance short circuits the electrotonic currents of the EPSP (high g_K or g_{Cl} levels). Since both E_K and E_{Cl} are close to the resting potential (→ p. 44), stabilization occurs, that is, the EPSP is cancelled out by the high K^+ and Cl^- short-circuit currents. As a result, EPSP-related depolarization is reduced and stimulation of postsynaptic neurons is inhibited (→ **D**).

Termination of synaptic transmission (→ **E**) can occur due to *inactivation* of the cation channels due to a conformational change in the channel similar to the one that occurs during an action potential (→ p. 46). This very rapid process called *desensitization* also functions in the presence of a transmitter. Other terminating pathways include the rapid *enzymatic decay* of the transmitter (e.g., acetylcholine) while still in the synaptic cleft, the *re-uptake* of the transmitter (e.g., noradrenaline = norepinephrine) into the presynaptic terminal or *uptake* into extraneuronal cells (e.g., in glial cells of the CNS), endocytotic *internalization* of the receptor (→ p. 28), and binding of the transmitter to a receptor on the presynaptic membrane (autoceptor). In the latter case, a rise in g_K and a drop in g_{Ca} can occur, thus inhibiting transmitter release, e.g., of GABA via $GABA_B$ receptors or of norepinephrine via α_2-adrenoceptors (→ **F** and p. 86).


B. Spatial summation of stimuli
AP1
AP2
AP3
Dendrite
Neuron (soma)
Axon hillock
APA
Axon
mV
−70
−90
ms
EPSP1
EPSP2
EPSP3
At the same time
Electrotonic currents (depolarizing)
mV
0
−10
−30
−50
−70
−90
0 2 4 6 8
ms
Action potential (APA)
Summed EPSP


C. Temporal summation of stimuli
AP1
Dendrite
Neuron (soma)
AP2
APA
mV
−70
−90
EPSP1
EPSP2
Elapsed time
Electrotonic currents (depolarizing)
mV
0
−10
−30
−50
−70
−90
0 2 4 6 8
ms
Action potential (APA)
Summed EPSP


D. Effect of IPSP on postsynaptic stimulation
Excitatory transmitter
AP_E
mV
−70
EPSP
−90
ms
K^+
Na^+
Depolarization
Electrotonic transmission
AP_I
Inhibitory transmitter
−70
IPSP
−90
"Short-circuit" via K^+- (and/or Cl^-) channels
K^+
Hyperpolarization
mV
−70
Summation EPSP + IPSP
−90
ms
Postsynaptic neuron
Electrotonic currents hyperpolarize axon hillock
To axon hillock



E. Termination of transmitter action
Extraneuronal uptake
Glial cell, etc.
Reuptake
Inhibition of exocytose
Presynaptic ending
Diffusion out of cleft
g_K↑ g_{Ca}↓
Autoceptor
Postsynaptic cell
Enzymatic breakdown of transmitter
Rapid inactivation of cation channel (desensitization)
Internalization of receptor


F. Neurotransmitters in the central nervous system

Transmitter	Receptor subtypes	Receptor types	Effect: Ion conductance Na^+	K^+	Ca^{2+}	Cl^-	Effect: Second messenger cAMP	IP_3/DAG
Acetylcholine	Nicotinic Muscarinic: M1, M2, M3	● ● ●	↑	↑ ↑	↑		↓	↑
ADH (= vasopressin)	V1 V2	● ●					↑	↑
CCK (= cholecystokinin)	CCK_{A-B}	●						↑
Dopamine	D1, D5 D2	● ●		↑	↓		↑ ↓	
GABA (= γ-aminobutyric acid)	$GABA_A$, $GABA_C$ $GABA_B$	● ●		↑	↓	↑	↓	
Glutamate (aspartate)	AMPA Kainat NMDA m-GLU	● ● ● ●	↑ ↑ ↑	↑ ↑ ↑	↑		↓	↑
Glycine	–	●				↑		
Histamine	H_1 H_2	● ●					↑	↑
Neurotensin	–	●					↓	↑
Norepinephrine, epinephrine	$\alpha_{1(A-D)}$ $\alpha_{2(A-C)}$ β_{1-3}	● ● ●		↑ ↑	↓		↓ ↑	↑
Neuropeptide Y (NPY)	Y1–2	●		↑	↓		↓	
Opioid peptides	μ, δ, κ	●		↑	↓		↓	
Oxytocin	–	●						↑
Purines	P_1: A_1 A_{2a} P_{2X} P_{2Y}	● ● ● ●	↑	↑ ↑	↓ ↑		↓ ↑	↑
Serotonin (5-hydroxytryptamine)	$5\text{-}HT_1$ $5\text{-}HT_2$ $5\text{-}HT_3$ $5\text{-}HT_{4-7}$	● ● ● ●	↑	↓ ↑			↓ ↑	↑
Somatostatin (= SIH)	SRIF	●		↑	↓		↓	
Tachykinin	NK 1–3	●						↑

Amino acids
Catecholamines
Peptides
Others







(Modified from F. E. Bloom)

The transmission of stimuli from a motor axon to a skeletal muscle fiber occurs at the motor end-plate, MEP (→ **A**), a type of chemical synapse (→ p. 50 ff.). The transmitter involved is **acetylcholine** (**ACh**, → cf. p. 82), which binds to the N(nicotinergic)-cholinoceptors of the subsynaptic muscle membrane (→ **A3**). **N-cholinoceptors** are ionotropic, that is, they also function as *ion channels* (→ **A4**). The N-cholinoceptor of the MEP (type N_M) has 5 subunits (2α, 1β, 1γ, 1δ), each of which contains 4 membrane-spanning α-helices (→ p. 14).

The channel opens briefly (→ **B1**) (for approx. 1 ms) when an ACh molecule binds to the two α-subunits of an N-cholinoceptor (→ **A4**). Unlike voltage-gated Na^+-channels, the open-probability p_o of the N_M-cholinoceptor is not increased by depolarization, but is determined by the *ACh concentration in the synaptic cleft* (→ p. 50 ff.).

The channel is *specific to cations* such as Na^+, K^+, and Ca^{2+}. Opening of the channel at a resting potential of ca. −90 mV leads mainly to an *influx of Na^+ ions* (and a much lower outflow of K^+; → pp. 32 ff. and 44). Depolarization of the subsynaptic membrane therefore occurs: **end-plate potential (EPP)**. *Single-channel currents* of 2.7 pA (→ **B1**) are summated to yield a *miniature end-plate current* of a few nA when spontaneous exocytosis occurs and a vesicle releases a quantum of ACh activating thousands of N_M-cholinoceptors (→ **B2**). Still, this is not enough for generation of a postsynaptic action potential unless an action potential transmitted by the motor neuron triggers exocytosis of around a hundred vesicles. This opens around 200,000 channels at the same time, yielding a *neurally induced end-plate current (I_{EP})* of ca. 400 nA (→ **B3**). **End-plate current, I_{EP},** is therefore dependent on:

- the number of open channels, which is equal to the total number of channels (n) times the open-probability (p_o) and p_o is determined by the concentration of ACh in the synaptic cleft (up to 1 mmol/L);
- the single-channel conductance γ (ca. 30 pS);
- and, to a slight extent, the membrane potential, E_m, since the electrical driving "force" ($= E_m - E_{Na,K}$; → p. 32 ff.) becomes smaller when E_m is less negative.

$E_{Na,K}$ is the common equilibrium potential for Na^+ and K^+ and amounts to approx. 0 mV. It is also called the **reversal potential** because the direction of I_{EP} ($= I_{Na} + I_K$), which enters the cell when E_m is negative (Na^+ influx > K^+ outflow), reverses when E_m is positive (K^+ outflow > Na^+ influx). As a result,


$$I_{EP} = n \cdot p_o \cdot \gamma \cdot (E_m - E_{Na,K})\ [A] \qquad [2.1]$$

Because **neurally induced EPPs** in skeletal muscle are much larger (depolarization by ca. 70 mV) than neuronal EPSPs (only a few mV; → p. 50 ff.), single motor axon action potentials are above threshold. The EPP is transmitted electrotonically to the adjacent sarcolemma, where muscle action potentials are generated by means of voltage-gated Na^+ channels, resulting in muscle contraction.

Termination of synaptic transmission in MEPs occurs (1) by rapid degradation of ACh in the synaptic cleft by *acetylcholinesterase* localized at the subsynaptic basal membrane, and (2) by diffusion of ACh out of the synaptic cleft (→ p. 82).


A motor end-plate can be blocked by certain **poisons** and **drugs**, resulting in muscular weakness and, in some cases, *paralysis*. *Botulinum neurotoxin*, for example, inhibits the discharge of neurotransmitters from the vesicles, and *α-bungarotoxin* in cobra venom blocks the opening of ion channels. Curare-like substances such as (+)-tubocurarine are used as **muscle relaxants** in surgical operations. They displace ACh from its binding site (*competitive inhibition*) but do not have a depolarizing effect of their own. Their inhibitory effect can be reversed by *cholinesterase inhibitors* such as neostigmine (decurarinization). These agents increase the concentration of ACh in the synaptic cleft, thereby displacing curare. Entry of anticholinesterase agents into intact synapses leads to an increase in the ACh concentration and, thus, to *paralysis due to permanent depolarization*. ACh-like substances such as suxamethonium have a similar depolarizing effect, but decay more slowly than ACh. In this case, paralysis occurs because permanent depolarization also permanently inactivates Na^+ channels near the motor end-plate on the sarcolemma (→ p. 46).

A. Motor end-plate



(Partly after Akert and Peper)

B. End-plate currents



1 Single-channel current

2 Miniature end-plate current

3 Nerve-induced end-plate current

(After Neher and Sakmann (1) and after Peper et al. (2))

Active motility (ability to move) is due to either the **interaction of** energy-consuming **motor proteins** (fueled by ATPase) such as myosin, kinesin and dynein with other proteins such as actin or the **polymerization** and depolymerization of actin and tubulin. Cell division (cytokinesis), cell migration (→ p. 30), intracellular vesicular transport and cytosis (→ p. 12f.), sperm motility (→ p. 308f.), axonal transport (→ p. 42), electromotility of outer hair cells (→ p. 372), and ciliary motility (→ p. 110) are examples of cell and organelle motility.

The muscles consist of cells (fibers) that contract when stimulated. **Skeletal muscle** is responsible for locomotion, positional change, and the convection of respiratory gases. **Cardiac muscle** (→ p. 192 ff.) is responsible for pumping the blood, and **smooth muscle** (→ p. 70) serves as the motor of internal organs and blood vessels. The different muscle types are distinguished by several functional characteristics (→ **A**).

Motor Unit of Skeletal Muscle

Unlike some types of smooth muscle (single-unit type; → p. 70) and cardiac muscle fibers, which pass electric stimuli to each other through gap junctions or nexus (→ **A**; p. 16f.), **skeletal muscle** fibers are not stimulated by adjacent muscle fibers, but by *motor neurons*. In fact, muscle paralysis occurs if the nerve is severed.

One motor neuron together with all muscle fibers innervated by it is called a **motor unit** (MU). Muscle fibers belonging to a single motor unit can be distributed over large portions (1 cm^2) of the muscle cross-sectional area. To supply its muscle fibers, a motor neuron splits into collaterals with terminal branches (→ p. 42). A given motor neuron may supply only 25 muscle fibers (mimetic muscle) or well over 1000 (temporal muscle).

Two **types of skeletal muscle fibers** can be distinguished: **S** – slow-twitch fibers (type 1) and **F** – fast-twitch fibers (type 2), including two subtypes, **FR** (2 A) and **FF** (2 B). Since each motor unit contains only one type of fiber, this classification also applies to the motor unit. **Slow-twitch fibers** are the least fatigable and are therefore equipped for *sustained performance*. They have high densities of capillaries and mitochondria and high concentrations of fat droplets (high-energy substrate reserves) and the red pigment myoglobin (short-term O_2 storage). They are also rich in oxidative enzymes (→ p. 72). **Fast-twitch fibers** are mainly responsible for brief and rapid contractions. They are quickly fatigued (FF > FR) and are rich in glycogen (FF > FR) but contain little myoglobin (FF≪FR).


The **fiber type distribution** of a muscle depends on the muscle type. Motor units of the *S type* predominate in "red" muscles such as the soleus muscle, which helps to maintain the body in an upright position, whereas the *F type* predominates in "white" muscles such as the gastrocnemius muscle, which is involved in running activity. Each fiber type can also be *converted* to the other type. If, for example, the prolonged activation of fast-twitch fibers leads to a chronic increase in the cytosolic Ca^{2+} concentration, fast-twitch fibers will be converted to slow-twitch fibers and vice versa.

Graded muscle activity is possible because a variable number of motor units can be recruited as needed. The more motor units a muscle has, the more finely graded its contractions. Contractions are much finer in the external eye muscles, for example, which have around 2000 motor units, than in the lumbrical muscles, which have only around 100 motor units. The larger the **number of motor units recruited**, the stronger the contraction. The number and type of motor units recruited depends on the type of movement involved (fine or coarse movement, intermittent or persistent contraction, reflex activity, voluntary or involuntary movement, etc.). In addition, the strength of each motor unit can be increased by increasing the **frequency of neuronal impulses**, as in the *tetanization* of skeletal muscle (→ p. 67 A).

A. Structure and function of heart, skeletal and smooth muscle

Structure and function	Smooth muscle	Cardiac muscle (striated)	Skeletal muscle (striated)
Motor end-plates	None	None	Yes
Fibers	Fusiform, short (≤ 0.2 mm)	Branched	Cylindrical, long (≤ 15 cm)
Mitochondria	Few	Many	Few (depending on muscle type)
Nucleus per fiber	1	1	Multiple
Sarcomeres	None	Yes, length ≤ 2.6 μm	Yes, length ≤ 3.65 μm
Electr. coupling	Some (single-unit type)	Yes (functional syncytium)	No
Sarcoplasmic reticulum	Little developed	Moderately developed	Highly developed
Ca^{2+} "switch"	Calmodulin/caldesmon	Troponin	Troponin
Pacemaker	Some spontaneous rhythmic activity ($1s^{-1}$ – $1h^{-1}$)	Yes (sinus nodes ca. $1s^{-1}$)	No (requires nerve stimulus)
Response to stimulus	Change in tone or rhythm frequency	All or none	Graded
Tetanizable	Yes	No	Yes
Work range	Length-force curve is variable	In rising length-force curve (see **2.15E**)	At peak of length-force curve (see **2.15E**)

Response to stimulus



The **muscle cell** is a fiber (→ **A2**) approximately 10 to 100 μm in diameter. Skeletal muscles fibers can be as long as 15 cm. Meat "fibers" visible with the naked eye are actually bundles of muscle fibers that are around 100 to 1000 μm in diameter (→ **A1**). Each striated muscle fiber is invested by a cell membrane called the *sarcolemma*, which surrounds the *sarcoplasm* (cytoplasm), several cell nuclei, mitochondria (*sarcosomes*), substances involved in supplying O_2 and energy (→ p. 72), and several hundreds of *myofibrils*.

So-called Z lines or, from a three-dimensional aspect, *Z plates* (plate-like proteins; → **B**) subdivide each **myofibril** (→ **A3**) into approx. 2 μm long, striated compartments called **sarcomeres** (→ **B**). When observed by (two-dimensional) microscopy, one can identify alternating light and dark bands and lines (hence the name "striated muscle") created by the thick **myosin II filaments** and thin **actin filaments** (→ **B**; for myosin I, see p. 30). Roughly 2000 actin filaments are bound medially to the Z plate. Thus, half of the actin filament projects into two adjacent sarcomeres (→ **B**). The region of the sarcomere proximal to the Z plate contains only actin filaments, which form a so-called *I band* (→ **B**). The region where the actin and myosin filaments overlap is called the *A band*. The *H zone* solely contains myosin filaments (ca. 1000 per sarcomere), which thicken towards the middle of the sarcomere to form the M line (*M plate*).

The (actin) filaments are anchored to the membrane of muscle cell by the protein *dystrophin*, which is connected to sarcoglycans of the sarcolemma. Merosin binds the sarcoglycans to the collagen fibrils of the extracellular matrix.

Mutation of these proteins leads to **muscular dystrophy** (Duchenne muscular dystrophy, limb-girdle dystrophy, congenital muscular dystrophy) implying the degeneration of muscle fibers with increasing muscular weakness.


Each myosin filament consists of a bundle of ca. 300 dimeric **myosin-II molecules** (→ **B**). Each molecule has two globular heads connected by flexible necks (head and neck = subfragment S1; formed after proteolysis) to the filamentous tail of the molecule (two intertwined α-helices = subfragment S2) (→ **C**). Each of the heads has a *motor domain* with a *nucleotide binding pocket* (for ATP or ADP + P_i) and an *actin binding site*. Two light protein chains are located on this heavy molecule (220 kDa): one is regulatory (20 kDa), the other so-called essential (17 kDa). Conformational changes in the head–neck segment allow the myosin head to "tilt" when interacting with actin (*sliding filaments*; → p. 62).

Actin is a globular protein molecule (G-actin). Four hundered such molecules join to form F-actin, a beaded polymer chain. Two of the twisted protein filaments combine to form an **actin filament** (→ **B**), which is positioned by the equally long protein *nebulin*.

Tropomyosin molecules joined end-to-end (40 nm each) lie adjacent to the actin filament, and a **troponin** (TN) molecule is attached every 40 nm or so (→ **B**). Each troponin molecule consists of three subunits: *TN-C*, which has two regulatory bindings sites for Ca^{2+} at the amino end, *TN-I*, which prevents the filaments from sliding when at rest (→ p. 62), and *TN-T*, which interacts with TN-C, TN-I, and actin.

The sarcomere also has another system of filaments (→ **B**) formed by the filamentous protein **titin** (connectin). Titin is more than 1000 nm in length and has some 30 000 amino acids ($M_r > 3000$ kDa). It is the longest known polypeptide chain and comprises 10% of the total muscle mass. Titin is anchored at its carboxyl end to the M plate and, at the amino end, to the Z plate (→ p. 66 for functional description).

The sarcolemma forms a T system with several **transverse tubules** (tube-like invaginations) that run perpendicular to the myofibrils (→ p. 63 A). The endoplasmic reticulum (→ p. 10 ff.) of muscle fibers has a characteristic shape and is called the **sarcoplasmic reticulum** (SR; → p. 63 A). It forms closed chambers without connections between the intra- or extracellular spaces. Most of the chambers run lengthwise to the myofibrils, and are therefore called *longitudinal tubules* (→ p. 63 A). The sarcoplasmic reticulum is more prominently developed in skeletal muscle than in the myocardium and serves as a **Ca^{2+} storage space**. Each T system separates the adjacent longitudinal tubules, forming *triads* (→ p. 63 A, B).



(After D. M. Warshaw)

Stimulation of muscle fibers. The release of *acetylcholine* at the motor end-plate of skeletal muscle leads to an *end-plate current* that spreads electrotonically and activates fast voltage-gated *Na^+ channels* in the sarcolemma (→ p. 56). This leads to the firing of an **action potential** (**AP**) that travels at a rate of 2 m/s along the sarcolemma of the entire muscle fiber, and penetrates rapidly into the depths of the fiber along the T system (→ **A**).

Genetic defects of these Na^+ channels slow down their deactivation (→ p. 46), which leads to hyperexcitability with extended contraction and delayed muscle relaxation (**myotonia**). The extended muscular activity is accompanied by a high number of K^+ ions exiting the muscle fibers. This results in hyperkalemia that reduces the muscular resting potential to the point where the Na^+ channels cannot be activated any longer and the muscle becomes temporarily paralyzed: **familial hyperkalemic periodic paralysis**.


The conversion of this excitation into a contraction is called **electromechanical coupling** (→ **B**). In the *skeletal muscle*, this process begins with the action potential exciting voltage-sensitive *dihydropyridine receptors* (DHPR) of the sarcolemma in the region of the triads. The DHPR are arranged in rows, and directly opposite them in the adjacent membrane of the sarcoplasmic reticulum (SR) are rows of *Ca^{2+} channels* called *ryanodine receptors* (type 1 in skeletal muscle: RYR1). Every other RYR1 is associated with a DHPR (→ **B2**). RYR1 open when they directly "sense" by mechanical means an AP-related conformational change in the DHPR. In the *myocardium*, on the other hand, each DHPR is part of a *voltage-gated Ca^{2+} channel* (L-type) of the sarcolemma that opens in response to an action potential. Small quantities of extracellular Ca^{2+} enter the cell through this channel, subsequently leading to the opening of myocardial RYR2 (so-called *trigger effect* of Ca^{2+} or *Ca^{2+} spark*; → **B3**). Ca^{2+} ions stored in the SR now flow through the opened RYR1 or RYR2 channels into the cytosol, increasing the cytosolic Ca^{2+} concentration $[Ca^{2+}]_i$ from a resting value of ca. 0.01 μmol/L to over 1 μmol/L (→ **B1**). In skeletal muscle, DHPR stimulation at a single site is enough to trigger the coordinated opening of an entire group of RYR1. This increases the reliability of impulse transmission. The increased cytosolic Ca^{2+} concentration saturates the Ca^{2+} binding sites on **troponin-C**. This cancels the troponin-mediated inhibitory effect of tropomyosin on filament sliding (→ **D1**), which now allows for a strong (high affinity) actin-myosin-II binding.

In patients with genetic defects of RYR1, general anesthesia may lead to the massive release of Ca^{2+}, which causes intense muscle contractions accompanied by a rapid and life threatening increase of body temperature: **malignant hyperthermia**.


ATP (→ p. 72) is essential for **filament sliding** and, hence, for muscle contraction. Due to their ATPase activity, the myosin heads (→ p. 60) act as the *motors* (motor proteins) of this process. The myosin-II and actin filaments of a sarcomere (→ p. 60) are arranged in such a way that they can slide past each other. The myosin heads connect with the actin filaments at a particular angle, forming so-called *cross-bridges*. Due to a *conformational change* in the region of the nucleotide binding site of myosin-II (→ p. 61 C), the spatial extent of which is increased by concerted movement of the neck region, the myosin head tilts down, drawing, in two separate steps, the thin filament a combined length of roughly 4 – 12 nm (power stroke). The second myosin head may also move an adjacent actin filament. The head then detaches and "tenses" in preparation for the next "oarstroke" when it binds to actin anew.

Kinesin, another motor protein (→ pp. 42 u. 58), independently advances on the microtubule by incremental movement of its two heads (8 nm increments), as in tug-of-war. In this case, fifty percent of the cycle time is "work time" (**duty ratio** = 0.5). Between two consecutive interactions with actin in *skeletal muscle*, on the other hand, myosin-II "jumps" 36 nm (or multiples of 36, e.g. 396 nm or more in rapid contractions) to reach the next (or the 11th) suitably located actin binding site (→ **C3**, jump from **a** to **b**). Meanwhile, the other myosin heads working on this particular actin filament must make at least another 10 to 100 oarstrokes of around 4 – 12 nm each. The duty ratio of a myosin-II head is therefore 0.1 to 0.01. This division of labor by the myosin heads ensures that a certain percentage of the heads ▶


A. The sarcotubular system of myocytes (muscle fibers)




B. Ca^{2+} as mediator between electrical stimulus and contraction



1 Ca^{2+} release




2 Skeletal muscle



3 Myocardium

C. Sliding filaments



1 Strong binding

2 Work phase (ca. 10 % of time)

3 Resting phase (ca. 90 % of time; other myosin heads are meanwhile active)

▶ will always be ready to generate rapid contractions.

When filament sliding occurs, the Z plates approach each other and the overlap region of thick and thin filaments becomes larger, but the length of the filaments remains unchanged. This results in shortening of the I band and H zone (→ p. 60). When the ends of the thick filaments ultimately bump against the Z plate, maximum muscle shortening occurs, and the ends of the thin filaments overlap (→ p. 67 C). Shortening of the sarcomere therefore occurs at both ends of the myosin bundle, but in opposite directions.

Contraction cycle (→ **C** and **D**). Each of the two myosin heads (M) of a myosin-II molecule bind (with the aid of Mg^{2+}) one ATP molecule in their nucleotide binding pocket. The resulting M-ATP complex lies at an approx. 45° angle to the rest of the myosin filament (→ **D4**). In this state, myosin has only a very weak affinity for actin binding. Now, due to the influence of the *increased cytosolic Ca^{2+} concentration* on the troponin–tropomyosin complex, *actin (A) activates myosin's ATPase*, resulting in hydrolysis of ATP (ATP → ADP + P_i) and the formation of an A-M-ADP-P_i complex (→ **D1**). This causes the myosin-II heads to lift again and as a result of this conformational change the actin-myosin association constant increases by four powers of ten (→ **C1**, **D1**). Now P_i (inorganic phosphate) detaches from the complex, which results in a 40° tilt of the myosin heads (→ **D2a**). This causes the actin and myosin filaments to slide past each other (first step of the *power stroke*). The following release of ADP initiates part two of the power stroke, which ultimately results in the final positioning of the myosin heads (→ **D2b**). The remaining A-M complex (*rigor complex*) is stable and can again be transformed into a much weaker bond when the myosin heads bind ATP anew (*"softening effect" of ATP*, → **D4**). The high flexibility of the muscle at rest is important for processes such as cardiac filling or the relaxing of the extensor muscles during rapid bending movement. If the cytosolic Ca^{2+} concentration remains $> 10^{-6}$ mol/L, the **D1** to **D4** cycle will begin anew. This depends mainly on whether subsequent action potentials arrive. Only a portion of the myosin heads that pull actin filaments are "on duty" (low duty ratio; see p. 62) to ensure the smoothness of contractions.


The **Ca^{2+} ions** released from the sarcoplasmic reticulum (SR) are continuously pumped back to the SR due to active transport by **Ca^{2+}-ATPase** (→ pp. 17 A and 26), also called SERCA (→ p. 16). Thus, if the RYR-mediated release of Ca^{2+} from the SR is interrupted, the cytosolic Ca^{2+} concentration rapidly drops below 10^{-6} mol/L and filament sliding ceases (*resting position*; → **D**, upper left corner).

Parvalbumin, a protein that occurs in the cytosol of fast-twitch muscle fibers (→ type F; p. 58), accelerates muscle relaxation after short contractions by binding cytosolic Ca^{2+} in exchange for Mg^{2+}. Parvalbumin's binding affinity for Ca^{2+} is higher than that of troponin, but lower than that of SR's Ca^{2+}-ATPase. It therefore functions as a "slow" Ca^{2+} buffer.

The course of the filament sliding cycle as described above mainly applies to **isotonic contractions**, that is, to contractions where muscle shortening occurs. During strictly **isometric contractions** where muscular tension increases but the muscle length remains unchanged, the tilting of the myosin heads and the filament sliding cannot take place. Instead, the isometric force is created through the deformation of the myosin heads.

The muscle fibers of a dead body do not produce any ATP. This means that, after death, Ca^{2+} is no longer pumped back into the SR, and the ATP reserves needed to break down stable A-M complexes are soon depleted. This results in stiffening of the dead body or **rigor mortis**, which passes only after the actin and myosin molecules in the muscle fibers decompose.

D. Work cycle of sliding filaments (isotonic contraction)



Action potentials generated in muscle fibers increase the cytosolic Ca^{2+} concentration $[Ca^{2+}]_i$, thereby triggering a contraction (skeletal muscle; → p. 36 B; myocardium; → p. 196). In skeletal muscles, **gradation of contraction force** is achieved by variable *recruitment* of motor units (→ p. 58) and by changing the *action potential frequency*. A single stimulus always leads to maximum Ca^{2+} release and, thus, to a maximum single twitch of skeletal muscle fiber if above threshold (**all-or-none response**). Nonetheless, a single stimulus does not induce maximum shortening of muscle fiber because it is too brief to keep the sliding filaments in motion long enough for the end position to be reached. Muscle shortening continues only if a second stimulus arrives before the muscle has completely relaxed after the first stimulus. This type of stimulus repetition leads to incremental **mechanical summation** or **superposition** of the individual contractions (→ **A**). Should the frequency of stimulation become so high that the muscle can no longer relax at all between stimuli, sustained maximum contraction of the motor units or **tetanus** will occur (→ **A**). This occurs, for example, at 20 Hz in slow-twitch muscles and at 60–100 Hz in fast-twitch muscles (→ p. 58). The muscle force during tetanus can be as much as four times larger than that of single twitches. The Ca^{2+} concentration, which decreases to some extent between superpositioned stimuli, remains high in tetanus.


Rigor (→ p. 64) as well as **contracture**, another state characterized by persistent muscle shortening, must be distinguished from tetanus. Contracture is not caused by action potentials, but by *persistent local depolarization* due, for example, to increased extracellular K^+ concentrations (K^+ contracture) or drug-induced intracellular Ca^{2+} release, e.g., in response to caffeine. The contraction of so-called **tonus fibers** (specific fibers in the external eye muscles and in muscle spindles; → p. 320) is also a form of contracture. Tonus fibers do not respond to stimuli according to the all-or-none law, but contract in proportion with the magnitude of depolarization. The magnitude of contraction of tonus fibers is regulated by *variation of the cytosolic Ca^{2+} concentration* (not by action potentials!)

In contrast, the general **muscle tone** (*reflex tone*), or the tension of skeletal muscle at rest, is attributable to the arrival of normal action potentials at the individual motor units. The individual contractions cannot be detected because the motor units are alternately (asynchronously) stimulated. When apparently at rest, muscles such as the postural muscles are in this involuntary state of tension. Resting muscle tone is regulated by reflexes (→ p. 320 ff.) and increases as the state of attentiveness increases.


Types of contractions (→ **B**). There are different types of muscle contractions. In **isometric contractions**, muscle force ("tension") varies while the length of the muscle remains constant. (In cardiac muscle, this also represents *isovolumetric contraction*, because the muscle length determines the atrial or ventricular volume.) In **isotonic contractions**, the length of the muscle changes while muscle force remains constant. (In cardiac muscle, this also represents *isobaric contraction*, because the muscle force determines the atrial or ventricular pressure.) In **auxotonic contractions**, muscle length and force both vary simultaneously. An isotonic or auxotonic contraction that builds on an isometric one is called an **afterloaded contraction.**

Muscle extensibility. A resting muscle containing ATP can be stretched like a rubber band. The force required to start the stretching action (→ **D**, **E**; extension force at rest) is very small, but increases exponentially when the muscle is under high elastic strain (see *resting tension curve*, → **D**). A muscle's *resistance to stretch*, which keeps the sliding filaments in the sarcomeres from separating, is influenced to a small extent by the fascia (fibrous tissue). The main factor, however, is the giant filamentous elastic molecule called **titin** (or *connectin*; 1000 nm long, M_r = 3 to 3.7 MDa) which is incorporated in the sarcomere (6 titin molecules per myosin filament). In the A band region of the sarcomere (→ p. 61 B), titin lies adjacent to a myosin filament and helps to keep it in the center of the sarcomere. Titin molecules in the I band region are flexible and function as "elastic bands" that counteract passive stretching of a muscle and influence its shortening velocity. ▶


A. Muscle strength at increasing and decreasing stimulus frequencies



B. Types of contractions



C. Isometric muscle force relative to sarcomere length



(After Gordon et al.)

▶ The **extensibility of titin molecules**, which can stretch to up to around ten times their normal length in skeletal muscle and somewhat less in cardiac muscle, is mainly due to frequent repetition of the *PEVK motif* (proline-glutamate-valine-lysine). In very strong muscle extension, which represents the steepest part of the resting extensibility curve (→ **D**), globular chain elements called immunoglobulin C2 domains also unfold. The quicker the muscle stretches, the more sudden and crude this type of "shock absorber" action will be.

The **length** (**L**) and **force** (**F**) or "tension" of a muscle are closely related (→ **C, E**). The total force of a muscle is the sum of its active force and its extension force at rest, as was explained above. Since the active force is determined by the magnitude of all potential actin-myosin interactions, it varies in accordance with the initial sarcomere length (→ **C, D**). Skeletal muscle can develop maximum active (isometric) force (F_0) from its resting length (L_{max}; sarcomere length ca. 2 to 2.2 μm; → **C**). When the sarcomeres shorten ($L < L_{max}$), part of the thin filaments overlap, allowing only forces smaller than F_0 to develop (→ **C**). When L is 70% of L_{max} (sarcomere length: 1.65 μm), the thick filaments make contact with the Z disks, and F becomes even smaller. In addition, a greatly pre-extended muscle ($L > L_{max}$) can develop only restricted force, because the number of potentially available actin–myosin bridges is reduced (→ **C**). When extended to 130% or more of the L_{max}, the extension force at rest becomes a major part of the total muscle force (→ **E**).

The length–force curve corresponds to the **cardiac pressure–volume diagram** in which ventricular filling volume corresponds to muscle length, and ventricular pressure corresponds to muscle force; → p. 204. Changes in the cytosolic Ca^{2+} concentration can modify the pressure–volume relationship by causing a change in *contractility* (→ p. 205 B2).

Other important functional **differences between cardiac muscle and skeletal muscle** are listed below (see also p. 59 A):

◆ Since skeletal muscle is more extensible than the cardiac muscle, the passive extension force of cardiac muscle at rest is greater than that of skeletal muscle (→ **E1, 2**).

◆ Skeletal muscle normally functions in the plateau region of its length–force curve, whereas cardiac muscle tends to operate in the ascending limb (below L_{max}) of its length–force curve without a plateau (→ **C, E1, 2**). Hence, the ventricle responds to increased diastolic filling loads by increasing its force development (**Frank–Starling mechanism**; → p. 206). In cardiac muscle, extension also affects troponin's sensitivity to Ca^{2+}, resulting in a steeper curve (→ **E2**).


◆ **Action potentials** in cardiac muscle are of much longer duration than those in skeletal muscle (→ p. 59 A) because g_K temporarily decreases and g_{Ca} increases for 200 to 500 ms after rapid inactivation of Na^+ channels. This allows the slow influx of Ca^{2+}, causing the action potential to reach a *plateau*. As a result, the refractory period does not end until a contraction has almost subsided (→ p. 59 A). Therefore, *tetanus cannot be evoked in cardiac muscle*.

◆ Unlike skeletal muscle, *cardiac muscle has no motor units*. Instead, the stimulus spreads across all myocardial fibers of the atria and subsequently of the ventricles generating an *all-or-none contraction* of both atria and, thereafter, both ventricles.


◆ In cardiac muscle but not in skeletal muscle, the duration of an action potential can change the force of contraction, which is controlled by the variable influx of Ca^{2+} into the cell.

The greater the force (load), the lower the **velocity** of an (isotonic) contraction (see velocity–force diagram, **F1**). Maximal force and a small amount of heat will develop if shortening does not occur. The maximal velocity (biceps: ca. 7 m/s) and a lot of heat will develop in muscle without a stress load. Light loads can therefore be picked up more quickly than heavy loads (→ **F2**). The total amount of energy consumed for work and heat is greater in isotonic contractions than in isometric ones. **Muscle power** is the product of force and the shortening velocity: $N \cdot m \cdot s^{-1} = W$ (→ **F1**, colored areas).


D. Active and passive components of muscle force (skeletal muscle)



E. Length-force curve for skeletal and cardiac muscle



F. Muscle force (or load) and shortening velocity



Smooth muscle (SmM) consists of multiple layers of spindle-shaped cells. It is involved in the function of many organs (stomach, intestine, gall bladder, urinary bladder, uterus, bronchi, eyes, etc.) and the blood vessels, where it plays an important role in circulatory control. SmM contains a special type of F-actin-tropomyosin and myosin II filaments (→ p. 60), but lacks troponin and myofibrils. Furthermore, it has no distinct tubular system and no sarcomeres (nonstriated). It is therefore called smooth muscle because of this lack of striation (see p. 59 A for further differences in the muscle types). SmM filaments form a loose contractile apparatus arranged approximately longitudinally within the cell and attached to discoid plaques (see **B** for model), which also provide a mechanical means for cell–cell binding of SmM. Smooth muscle can shorten much more than striated muscle.

The **membrane potential** of the SmM cells of many organs (e.g., the intestine) is not constant, but fluctuates rhythmically at a low frequency (3 to 15 min^{-1}) and amplitude (10 to 20 mV), producing *slow waves*. These waves trigger a burst of action potentials (spikes) when they exceed a certain threshold potential. The longer the slow wave remains above the threshold potential, the greater the number and frequency of the action potentials it produces. A relatively sluggish contraction occurs around 150 ms after a spike (→ p. 59 A, left panel). *Tetanus* occurs at relatively low spike frequencies (→ p. 66). Hence, SmM is constantly in a state of a more or less strong contraction (**tonus** or tone). The action potential of SmM cells of some organs has a plateau similar to that of the cardiac action potential (→ p. 59 A, middle panel).

There are two types of smooth muscles (→ **A**). The cells of **single-unit SmM** are electrically coupled with each other by *gap junctions* (→ pp. 18 and 50). Stimuli are passed along from cell to cell in organs such as the stomach, intestine, gallbladder, urinary bladder, ureter, uterus, and some types of blood vessels. Stimuli are generated autonomously from within the SmM, partly by pacemaker cells. In other words, the stimulus is innervation-independent and, in many cases, spontaneous (*myogenic tonus*). The second type, **multi-unit SmM,** contracts primarily due to stimuli from the autonomic nervous system (*neurogenic tonus*). This occurs in structures such as the arterioles, spermatic ducts, iris, ciliary body, and the muscles at the roots of the hair. Since these SmM cells generally are not connected by gap junctions, stimulation remains localized, as in the motor units of the skeletal muscle.


Smooth muscle tonus is regulated by the degree of depolarization (e.g., through stretch or pacemaker cells) as well as by transmitter substances (e.g., acetylcholine or noradrenaline) and numerous hormones (e.g., estrogens, progesterone and oxytocin in the uterus and histamine, angiotensin II, adiuretin, serotonin and bradykinin in vascular muscle). An increase in tonus will occur if any of these factors directly or indirectly increases the cytosolic Ca^{2+} concentration to more than 10^{-6} mol/L. The Ca^{2+} influx comes mainly from extracellular sources, but a small portion comes from intracellular stores (→ **B1**). Ca^{2+} ions bind to calmodulin (CM) (→ **B2**), and Ca^{2+}-CM promotes contraction in the following manner.

Regulation at **myosin II** (→ **B3**): The Ca^{2+}-CM complex activates myosin light chain kinase (MLCK), which phosphorylates myosin's regulatory light chain (RLC) in a certain position, thereby enabling the myosin head to interact with actin (→ **B6**).

Regulation at the **actin** *level* (→ **B4**). The Ca^{2+}-CM complex also binds with caldesmon (CDM), which then detaches from the actin–tropomyosin complex, thus making it available for filament sliding (→ **B6**). Phosphorylation of CDM by protein kinase C (PK-C) also seems to be able to induce filament sliding (→ **B5**).

Factors that lead to a **reduction of tonus** are: reduction of the cytosolic Ca^{2+} concentration to less than 10^{-6} mol/L (→ **B7**), phosphatase activity (→ **B8**), and PK-C if it phosphorylates another position on the RLC (→ **B9**).

When length–force curves are recorded for smooth muscle, the curve shows that muscle force decreases continuously while muscle length remains constant. This property of a muscle is called **plasticity**.


A. Smooth muscle fibers according to type of stimulation
1 Single-unit fibers
Electrical coupling (gap junctions)
Spontaneous stimulation
General contraction
Stomach, intestine, uterus, blood vessels, etc.
2 Multi-unit fibers
Stimulated by autonomic nerve
Local contraction
Arterioles, deferent duct, iris, etc.
B. Regulation of smooth muscle contraction
Depolarization, transmitter, hormones, stretch
Intermediate filaments
Adhesive plaques
Myocyte
Nucleus
Actin-myosin filaments
Thickening zones
Smooth ER (Ca2+ stores)
1
Ca2+
[Ca2+]i >10−6 mol/l
2
Ca2+ CM
Calmodulin binding
?
7
RLC
Myosin II
Caldesmon (CDM)
Actin-tropomyosin
[Ca2+]i <10−6 mol/l
Low muscle tone
9
ATP
P
PK-C
8
P
Phosphatase
MLCK
3
ATP
P
ADP
Phosphorylation of myosin II
4
CDM
Release of actin
or
5
PK-C
ATP
CDM
P
?
6
Filaments slide
Contraction: Increased tone

Adenosine triphosphate (ATP) is a direct source of chemical energy for muscle contraction (→ **A**, pp. 40 and 64). However, a muscle cell contains only a limited amount of ATP–only enough to take a sprinter some 10 to 20 m or so. Hence, spent ATP is continuously regenerated to keep the intracellular ATP concentration constant, even when large quantities of it are needed. The three routes of **ATP regeneration** are (→ **B**):

1. Dephosphorylation of creatine phosphate
2. Anaerobic glycolysis
3. Aerobic oxidation of glucose and fatty acids.

Routes 2 and 3 are relatively slow, so **creatine phosphate** (**CrP**) must provide the chemical energy needed for *rapid ATP regeneration*. ADP derived from metabolized ATP is immediately transformed to ATP and creatine (Cr) by mitochondrial creatine kinase (→ **B1** and p. 40). The CrP reserve of the muscle is sufficient for short-term high-performance bursts of 10 – 20 s (e.g., for a 100-m sprint).

Anaerobic glycolysis occurs later than CrP dephosphorylation (after a maximum of ca. 30 s). In anaerobic glycolysis, *muscle glycogen* is converted via glucose-6-phosphate to lactic acid (→ lactate + H^+), yielding 3 ATP molecules for each glucose residue (→ **B2**). During *light exercise*, lactate$^-$ is broken down in the heart and liver whereby H^+ ions are used up. **Aerobic oxidation** of glucose and fatty acids takes place approx. 1 min after this less productive anaerobic form of ATP regeneration. If aerobic oxidation does not produce a sufficient supply of ATP during *strenuous exercise*, anaerobic glycolysis must also be continued.


In this case, however, glucose must be imported from the liver where it is formed by glycogenolysis and gluconeogenesis (see also p. 284f.). Imported glucose yields only two ATP for each molecule of glucose, because one ATP is required for 6-phosphorylation of glucose.

Aerobic regeneration of ATP from glucose (about 32 ATP per glucose residue) or fatty acids is required for *sustained exercise* (→ **B3**). The cardiac output (= heart rate × stroke volume) and total ventilation must therefore be increased to meet the increased metabolic requirements of the muscle; the heart rate then becomes constant (→ p. 75 B). The several minutes that pass before this *steady state* is achieved are bridged by anaerobic energy production, *increased O_2 extraction* from the blood and depletion of short-term O_2 reserves in the muscle (*myoglobin*). The interim between the two phases is often perceived as the *"low point"* of physical performance.

The O_2 affinity of **myoglobin** is higher than that of hemoglobin, but lower than that of respiratory chain enzymes. Thus, myoglobin is normally saturated with O_2 and can pass on its oxygen to the mitochondria during brief arterial oxygen supply deficits.

The **endurance limit**, which is some 370 W (≈ 0.5 HP) in top athletes, is mainly dependent on the speed at which O_2 is supplied and on how fast aerobic oxidation takes place. When the endurance limit is exceeded, steady state cannot occur, the heart rate then rises continuously (→ p. 75 B). The muscles can temporarily compensate for the energy deficit (see above), but the H^+-consuming lactate metabolism cannot keep pace with the persistently high level of anaerobic ATP regeneration. An excess of lactate and H^+ ions, i.e. *lactacidosis*, therefore develops. If an individual exceeds his or her endurance limit by around 60%, which is about equivalent to maximum O_2 consumption (→ p. 74), the **plasma lactate** concentration will increase sharply, reaching the so-called *anaerobic threshold* at 4 mmol/L. No significant increase in performance can be expected after that point. The systemic drop in pH results in increasing inhibition of the chemical reactions needed for muscle contraction. This ultimately leads to an ATP deficit, rapid muscle **fatigue** and, finally, a stoppage of muscle work.

CrP metabolism and anaerobic glycolysis enable the body to achieve three times the performance possible with aerobic ATP regeneration, albeit for only about 40 s. However, these processes result in an **O_2 deficit** that must be compensated for in the post-exercise recovery phase (**O_2 debt**). The body "pays off" this debt by regenerating its energy reserves and breaking down the excess lactate in the liver and heart. The O_2 debt after strenuous exercise is much larger (up to 20 L) than the O_2 deficit for several reasons.


A. ATP as a direct energy source
Chemical energy
Reserve: ca. 5 µmol per g muscle
ATP
ΔG ≈ –50 kJ/mol ATP
ADP
Pi
Heat
+
Mechanical energy
Reserve enough for 10 contractions
Contraction
B. Regeneration of ATP
1 Cleavage of creatine phosphate
Reserve: ca. 25 µmol per g muscle
CrP
Cr
Creatine kinase
ADP
ATP
Short-term peak performance
2 Anaerobic glycolysis
Glycogen
Reserve: ca. 100 µmol/g muscle
Blood glucose
Liver
Glucose-6-P
1 ATP
1 ATP
anaerobic
Net gain: 2 mol ATP/mol glucose (3 mol ATP/mol glucose-6-P)
4 ATP
Long-term high performance
Increase in lactic acid → Drop in pH
2 pyruvic acid ⇌ 2 pyruvate⁻ + 2 H⁺
2 lactic acids ⇌ 2 H⁺ + 2 lactate⁻
Broken down in liver and heart
3 Oxidation of glucose
2 Acetyl-CoA
6 O2
H2O
Total net gain: ca. 32 mol ATP/mol glucose
aerobic
6 CO2
Krebs cycle
Respiratory chain
ca. 30 ATP
Endurance sport

There are three types of muscle work:

- *Positive dynamic work*, which requires to muscles involved to alternately contract and relax (e.g., going uphill).
- *Negative dynamic work*, which requires the muscles involved to alternately extend while braking (*braking work*) and contract without a load (e.g., going downhill).
- *Static postural work*, which requires continuous contraction (e.g., standing upright).

Many activities involve a combination of two or three types of muscle work. Outwardly directed mechanical work is produced in dynamic muscle activity, but not in purely postural work. In the latter case, force × distance = 0. However, chemical energy is still consumed and completely transformed into a form of heat called *maintenance heat* (= muscle force times the duration of postural work).

In *strenuous exercise*, the muscles require up to 500 times more **O_2** than when at rest. At the same time, the muscle must rid itself of metabolic products such as **H^+**, **CO_2**, and **lactate** (→ p. 72). Muscle work therefore requires drastic cardiovascular and respiratory changes.

In untrained subjects (UT), the cardiac output (CO; → p. 188) rises from 5–6 L/min at rest to a maximum of 15–20 L/min during exercise (→ p. 77 C). Work-related **activation of the sympathetic nervous system** increases the heart rate up to ca. 2.5 fold and the stroke volume up to ca. 1.2 fold (UT). In *light to moderate exercise*, the heart rate soon levels out at a new constant level, and no fatigue occurs. *Very strenuous exercise*, on the other hand, must soon be interrupted because the heart cannot achieve the required long-term performance (→ **B**). The increased CO provides more blood for the muscles (→ **A**) and the skin (*heat loss;* → p. 224). The blood flow in the kidney and intestine, on the other hand, is reduced by the sympathetic tone below the resting value (→ **A**). The systolic **blood pressure** (→ p. 208) rises while the diastolic pressure remains constant, yielding only a moderate increase in the mean pressure.

The smaller the muscle mass involved in the work, the higher the increase in blood pressure. Hence, the blood pressure increase in arm activity (cutting hedges) is higher than that in leg activity (cycling).

In patients with coronary artery disease or cerebrovascular sclerosis, arm activity is therefore more dangerous than leg activity due to the risk of myocardial infarction or brain hemorrhage.

Muscular blood flow. At the maximum work level, the blood flow in 1 kg of active muscle rises to as much as 2.5 L/min (→ p. 215 A), equivalent to 10% of the maximum cardiac output. Hence, no more than 10 kg of muscle (< 1/3 the total muscle mass) can be fully active at any one time. Vasodilatation, which is required for the higher blood flow, is mainly achieved through *local chemical influences* (P_{CO2} ↑, P_{O2} ↑, pH ↓) or NO release (→ p. 214). In purely postural work, the increase in blood flow is prevented in part by the fact that the continuously contracted muscle squeezes its own vessels. The muscle then *fatigues* faster than in rhythmic dynamic work.


During physical exercise (→ **C1**), the **ventilation** ($\dot{V}_E$) increases from a resting value of ca. 7.5 L/min to a maximum of 90 to 120 L/min (→ **C3**). Both the respiratory rate (40–60 min^{-1} max; → **C2**) and the tidal volume (ca. 2 L max.) contribute to this increase. Because of the high $\dot{V}_E$ and increased CO, oxygen consumption ($\dot{V}_{O_2}$) can increase from ca. 0.3 L/min at rest to a maximum ($\dot{V}_{O_2}$ max) of ca. 3 L/min in UT (→ **C4** and p. 76). Around 25 L of air has to be ventilated to take up 1 L of O_2 at rest, corresponding to a *respiratory equivalent* ($\dot{V}_E/\dot{V}_{O_2}$) of 25. During physical exercise, $\dot{V}_E/\dot{V}_{O_2}$ rises beyond the endurance limit to a value of 40–50.

Increased **O_2 consumption** in the tissues also contributes to the large increase in $\dot{V}_{O_2}$ during exercise. The decreasing pH and increasing temperature shift the O_2 binding curve towards the right (→ p. 129 B). O_2 consumption is calculated as the arteriovenous difference in O_2 concentration ($avDO_2$ in L/L blood) times the blood flow in L/min. The **maximum O_2 consumption** (**$\dot{V}_{O_2}$ max**) is therefore defined as:


$$\dot{V}_{O_2}\,\text{max} = \text{HRmax} \cdot \text{SVmax} \cdot \text{avD}_{O_2}\text{max}$$

where HR is the heart rate and SV is the stroke volume. $\dot{V}_{O_2}$ max per body weight is an ideal measure of *physical exercise capacity* (→ p. 76).


A. Blood supply in organs at rest and during physical work




B. Heart rate during physical work



C. Respiration during physical work





(After J. Stegemann)

The **physical exercise capacity** can be measured using simple yet standardized techniques of **ergometry**. This may be desirable in athletes, for example, to assess the results of training, or in patients undergoing rehabilitation therapy. Ergometry assesses the effects of exercise on physiological parameters such as O_2 consumption ($\dot{V}_{O_2}$), respiration rate, heart rate (→ p. 74), and the plasma lactate concentration (→ **A**). The measured physical power (performance) is expressed in watts (W) or W/kg body weight (BW).

In **bicycle ergometry**, a brake is used to adjust the watt level. In "uphill" ergometry on a *treadmill* set at an angle α, exercise performance in watts is calculated as a factor of body mass (kg) × gravitational acceleration g ($m \cdot s^{-2}$) × distance traveled (m) × sin α × 1/time required (s^{-1}). In the **Margaria step test**, the test subject is required to run up a staircase as fast as possible after a certain starting distance. Performance is then measured as body mass (kg) × g ($m \cdot s^{-2}$) × height/time ($m \cdot s^{-1}$).

Short-term performance tests (10–30 s) measure performance achieved through the rapidly available energy reserves (creatine phosphate, glycogen). *Medium-term performance tests* measure performance fueled by anaerobic glycolysis (→ p. 72). The **maximum O_2 consumption ($\dot{V}_{O_2}$ max)** is used to measure longer term aerobic exercise performance achieved through oxidation of glucose and free fatty acids (→ p. 74).

In strenuous exercise (roughly 2/3 the maximum physical capacity or more), the aerobic mechanisms do not produce enough energy, so anaerobic metabolism must continue as a parallel energy source. This results in lactacidosis and a sharp increase in the plasma lactate concentration (→ **A**). **Lactate concentrations** of up to 2 mmol/L (*aerobic threshold*) can be tolerated for prolonged periods of exercise. Lactate concentrations above 4 mmol/L (*anaerobic threshold*) indicate that the performance limit will soon be reached. Exercise must eventually be interrupted, not because of the increasing lactate concentration, but because of the increasing level of acidosis (→ p. 74).


Physical training raises and maintains the physical exercise capacity. There are three types of physical training strategies, and most training programs use a combination of them.

- *Motor learning*, which increases the rate and accuracy of motor skills (e.g., typewriting). These activities primarily involve the CNS.
- *Endurance training*, which improves submaximal long-term performance (e.g., running a marathon). The main objectives of endurance training are to increase the oxidative capacity of slow-twitch motor units (→ p. 58), e.g., by increasing the mitochondrial density, increase the cardiac output and, consequently, to increase $\dot{V}_{O_2}$ max (→ **B, C**). The resulting increase in heart weight allows higher stroke volumes (→ **C**) as well as higher tidal volumes, resulting in very low resting heart rates and respiratory rates. Trained athletes can therefore achieve larger increases in cardiac output and ventilation than untrained subjects (→ **C**). The $\dot{V}_{O_2}$ max of a healthy individual is limited by the cardiovascular capacity, not the respiratory capacity. In individuals who practice endurance training, the exercise-related rise in the lactate concentraton is also lower and occurs later than in untrained subjects (→ **A**).
- *Strength training* improves the maximum short-term performance level (e.g., in weight lifting). The main objectives are to increase the muscle mass by increasing the size of the muscle fibers (hypertrophy) and to increase the glycolytic capacity of type F motor units (→ p. 58).


Excessive physical exercise causes **muscle soreness and stiffness.** The underlying cause is not lactic acid accumulation, but sarcomere microtrauma, which leads to muscle swelling and pain. The muscle ache, is a sign of microinflammation (→ **D**).

Muscle fatigue may be peripheral or central. *Peripheral fatigue* ist caused by the exhaustion of energy reserves and the accumulation of metabolic products in the active muscle. This is particularly quick to occur during postural work (→ p. 66). *Central fatigue* is characterized by work-related pain in the involved muscles and joints that prevents the continuation of physical exercise or decreased the individual's motivation to continue the exercise.

A. Lactate concentration (phys. exercise)




B. Maximum O_2 uptake



C. Comparison of non-athletic individuals and endurance athletes

Physiological parameters
(2 men, age 25, 70 kg)








	Non-athletes			Endurance athletes		
	Resting		Maximum	Resting		Maximum
Heart weight (g)	300			500		
Blood volume (L)	5.6			5.9		
Heart rate (min^{-1})	80	→ →	**180**	40	→ →	**180**
Stroke volume (mL)	70	→ →	**100**	140	→ →	**190**
Cardiac output (L/min)	5.6	→ →	**18**	5.6	→ →	**35**
Total ventilation (L/min)	8.0	→ →	**100**	8.0	→ →	**200**
O_2 uptake (L/min)	0.3	→ →	**2.8**	0.3	→ →	**5.2**

(Data partly from H.-J. Ulmer)

D. Post-exercise muscle ache



In the *somatic nervous system*, nerve fibers extend to and from the skeletal muscles, skin and sense organs. They usually emit impulses in response to stimuli from the outside environment, as in the *withdrawal reflex* (→ p. 322). Much somatic nervous activity occurs *consciously* and under *voluntary control*. In contrast, the **autonomic** (= vegetative) **nervous system** (**ANS**) is mainly concerned with **regulation of circulation and internal organs**. It responds to changing outside conditions by triggering orthostatic responses, work start reactions, etc. to regulate the body's **internal environment** (→ p. 2). As the name implies, most activities of the ANS are not subject to voluntary control.

For the most part, the autonomic and somatic nervous systems are anatomically and functionally separate in the periphery (→ **A**), but closely connected in the central nervous system, CNS (→ p. 268). The *peripheral ANS is efferent*, but most of the nerves containing ANS fibers hold also afferent neurons. These are called *visceral afferents* because their signals originate from visceral organs, such as the esophagus, gastrointestinal (GI) tract, liver, lungs, heart, arteries, and urinary bladder. Some are also named after the nerve they accompany (e.g., vagal afferents).

Autonomic nervous activity is usually regulated by the **reflex arc**, which has an afferent limb (visceral and/or somatic afferents) and an efferent limb (autonomic and/or somatic efferents). The *afferent fibers* convey stimuli from the skin (e.g. nociceptive stimuli; → p. 318) and nocisensors, mechanosensors and chemosensors in organs such as the lungs, gastrointestinal tract, bladder, vascular system and genitals. The ANS provides the autonomic *efferent fibers* that convey the reflex response to such afferent information, thereby inducing smooth muscle contraction (→ p. 70) in organs such as the eye, lung, digestive tract and bladder, and influencing the function of the heart (→ p. 196) and glands. Examples of *somatic nervous system* involvement are afferent stimuli from the skin and sense organs (e.g., light stimuli) and efferent impulses to the skeletal muscles (e.g., coughing and vomiting).

Simple reflexes can take place *within an organ* (e.g., in the gut, → p. 246), but complex reflexes are controlled by **superordinate autonomic centers** in the CNS, primarily in the *spinal cord* (→ **A**). These centers are controlled by the *hypothalamus,* which incorporates the ANS in the execution of its programs (→ p. 332). The *cerebral cortex* is an even higher-ranking center that integrates the ANS with other systems.

The **peripheral ANS** consists of a *sympathetic division* and a *parasympathetic division* (→ **A**) which, for the most part, are separate entities (→ also p. 80 ff.). The autonomic centers of the sympathetic division lie in the *thoracic and lumbar segments of the spinal cord*, and those of the parasympathetic division lie in the *brain stem* (eyes, glands, and organs innervated by the vagus nerve) and *sacral part of the spinal cord* (bladder, lower parts of the large intestine, and genital organs). (→ **A**). *Preganglionic fibers* of both divisions of the ANS extend from their centers to the **ganglia**, where they terminate at the *postganglionic neurons*.


Preganglionic **sympathetic neurons** arising from the spinal cord terminate either in the *paravertebral ganglionic chain*, in the *cervical or abdominal ganglia* or in so-called terminal ganglia. Transmission of stimuli from preganglionic to postganglionic neurons is *cholinergic*, that is, mediated by release of the neurotransmitter *acetylcholine* (→ p. 82). Stimulation of all effector organs except sweat glands by the postganglionic sympathetic fibers is *adrenergic*, i.e., mediated by the release of *norepinephrine* (→ **A** and p. 84ff.).

Parasympathetic ganglia are situated near or within the effector organ. Synaptic transmissions in the parasympathetic ganglia and at the effector organ are *cholinergic* (→ **A**).


Most organs are innervated by sympathetic and parasympathetic nerve fibers. Nonetheless, the organ's response to the two systems can be either antagonistic (e.g., in the heart) or complementary (e.g., in the sex organs).


The **adrenal medulla** is a ganglion and hormone gland combined. Preganglionic sympathetic fibers in the adrenal medulla release acetylcholine, leading to the secretion of *epinephrine* (and some norepinephrine) *into the bloodstream* (→ p. 86).

A. Schematic view of autonomic nervous system (ANS)



A. Functions of the autonomic nervous system (ANS)




Sympathetic division
(Preganglionic cholinergic: N_N and M_1 receptors, postganglionic mainly adrenergic)
α receptors (α_1: IP_3 + DAG↑; α_2: cAMP↓) β receptors (cAMP↑)
Eye (α_1)
C Dilator pupillae
Eye (β_2)
Far accommodation of ciliary muscle
Cholinergic
S A Sweat glands
Postganglionic sympathetic
Submandibular gland
A Mucus secretion (viscous)
Heart (β_1 and β_2)
Faster stimulus conduction
Heart rate ↑
Myocardial contraction force ↑
Excitability ↑
S C Hair muscles of skin
D Bronchi (β_2)
Blood vessels
S D Sympathetic cholinergic vasodilatation (not confirmed in humans)
Stomach, intestine
C Sphincter (α_1)
Stomach, intestine
R Muscle
Ganglion coeliacum
R Gallbladder
Kidney
A Renin secretion (β_1)
Pancreas
I Insulin secretion (α_2)
I Exocrine secretion
Pancreas
A Insulin secretion (β_2)
Adrenal medulla
A Secretion
Ganglion mesentericum sup. et inf.
C Splenic capsule
Blood vessels
S D Skin, muscles, etc.
S
Blood vessels
C In skin
In muscles
Coronaries
General
S
Lipocytes
S Lipolysis
Liver (β_2 and α_1)
Gluconeogenesis
♂ Genitals (α_1)
Ejaculation
Urinary bladder
C Sphincter
Urinary bladder
R Detrusor (β_2)
C Uterus (α_1) (in pregnancy)
R Uterus (β_2) (Tocolysis)
Preganglionic cholinergic
Postganglionic adrenergic
S = Efferents from affiliated CNS segment

Acetylcholine (**ACh**) serves as a neurotransmitter not only at motor end plates (→ p. 56) and in the central nervous system, but also in the **autonomic nervous system**, **ANS** (→ p. 78ff.), where it is active

- in all preganglionic fibers of the ANS;
- in all parasympathetic postganglionic nerve endings;
- and in some sympathetic postganglionic nerve endings (sweat glands).

Acetylcholine synthesis. ACh is synthesized in the cytoplasm of nerve terminals, and acetyl coenzyme A (acetyl-CoA) is synthesized in mitochondria. The reaction acetyl-CoA + choline is catalyzed by *choline acetyltransferase*, which is synthesized in the soma and reaches the nerve terminals by axoplasmic transport (→ p. 42). Since choline must be taken up from extracellular fluid by way of a carrier, this is the rate-limiting step of ACh synthesis.

Acetylcholine release. Vesicles on presynaptic nerve terminals empty their contents into the synaptic cleft when the cytosolic Ca^{2+} concentration rises in response to incoming action potentials (AP) (→ **A**, p. 50ff.). Epinephrine and norepinephrine can *inhibit ACh release* by stimulating presynaptic α_2-adrenoceptors (→ p. 84). In postganglionic parasympathetic fibers, ACh blocks its own release by binding to presynaptic autoreceptors (M-receptors; see below), as shown in **B**.

ACh binds to postsynaptic **cholinergic receptors** or **cholinoceptors** in autonomic ganglia and organs innervated by parasympathetic fibers, as in the heart, smooth muscles (e.g., of the eye, bronchi, ureter, bladder, genitals, blood vessels, esophagus, and gastrointestinal tract), salivary glands, lacrimal glands, and (sympathetically innervated) sweat glands (→ p. 80ff.). Cholinoceptors are nicotinic (N) or muscarinic (M). **N-cholinoceptors** *(nicotinic)* can be stimulated by the alkaloid nicotine, whereas *M-cholinoceptors (muscarinic)* can be stimulated by the alkaloid mushroom poison muscarine.

Nerve-specific N_N-cholinoceptors on autonomic ganglia (→ **A**) differ from muscle-specific N_M-cholinoceptors on motor end plates (→ p. 56) in that they are formed by different subunits. They are similar in that they are both *ionotropic receptors*, i.e., they act as cholinoceptors and cation channels at the same time. ACh binding leads to rapid Na^+ and Ca^{2+} influx and in early (rapid) excitatory postsynaptic potentials (EPSP; → p. 50ff.), which trigger postsynaptic action potentials (AP) once they rise above threshold (→ **A**, **left panel**).

M-cholinoceptors (M_1–M_5) indirectly affect synaptic transmission through G-proteins (*metabotropic receptors*).


M_1-cholinoceptors occur mainly on *autonomic ganglia* (→ **A**), *CNS*, and *exocrine gland cells*. They activate phospholipase Cβ (PLCβ) via G_q protein in the postganglionic neuron. and inositol *tris*-phosphate (IP_3) and diacylglycerol (DAG) are released as second messengers (→ p. 278) that stimulate Ca^{2+} influx and a *late EPSP* (→ **A**, **middle panel**). Synaptic signal transmission is modulated by the late EPSP as well as by co-transmitting peptides that trigger *peptidergic EPSP or IPSP* (→ **A**, **right panel**).

M_2-cholinoceptors occur in the *heart* and function mainly via a G_i protein (→ p. 276 ff.). The G_i protein *opens specific K^+ channels* located mainly in the sinoatrial node, atrioventricular (AV) node, and atrial cells, thereby exerting negative chronotropic and dromotropic effects on the heart (→ **B**). The G_i protein also *inhibits adenylate cyclase*, thereby reducing Ca^{2+} influx (→ **B**).

M_3-cholinoceptors occur mainly in *smooth muscles*. Similar to M_1-cholinoceptors (→ **A**, middle panel), M_3-cholinoceptors trigger contractions by stimulating Ca^{2+} influx (→ p. 70). However, they can also induce relaxation by activating Ca^{2+}-dependent NO synthase, e.g., in *endothelial cells* (→ p. 280).

Termination of ACh action is achieved by *acetylcholinesterase*-mediated cleavage of ACh molecules in the synaptic cleft (→ p. 56). Approximately 50% of the liberated choline is reabsorbed by presynaptic nerve endings (→ **B**).

Antagonists. *Atropine* blocks all M-cholinoceptors, whereas *pirenzepine, methoctramine, hexahydrosiladifenidol,* and *tropicamide* selectively block M_1-, M_2-, M_3-, and M_4-cholinoceptors, respectively, *tubocurarine* blocks N_M-cholinoceptors (→ p. 56), and *trimetaphan* blocks N_N-cholinoceptors.


A. Neurotransmission in autonomic ganglia
Presynaptic AP
ACh
Preganglionic neuron
Ca2+
Cholinergic NN-receptor
Cholinergic M1-receptor
Peptide receptor
Peptide as a co-transmitter
Gq protein
PIP
Phospholipase Cβ
K+
Na+ (Ca2+)
IP3 DAG
[Ca]i
Postganglionic neuron
20 ms
Early EPSP
mV
2 s
Late EPSP
Peptidergic EPSP or IPSP
60 s
Postsynaptic action potentials
B. Cholinergic transmission in the heart
Presynaptic AP
ACh
Postganglionic parasympathetic neuron
Ca2+
Choline
Cholinergic M-autoreceptor
Acetate
Acetylcholine esterase
Cholinergic M2-receptor
K+ channel
Adenylyl cyclase
Gi protein
Gi protein
opens
Sinus node or AV node cell
ATP
K+
cAMP
Hyperpolarization
Protein kinase A
Sinus node
AV node
Ca2+ influx
0
mV
−50
Negative chronotropism
Negative dromotropism

Certain neurons can enzymatically produce *L-dopa* (L-**d**ihydr**o**xy**p**henyl**a**lanine) from the amino acid L-tyrosine. L-dopa is the parent substance of dopamine, norepinephrine (= noradrenaline), and epinephrine (=adrenaline)—the three natural **catecholamines**, which are enzymatically synthesized in this order. Dopamine (**DA**) is the final step of synthesis in neurons containing only the enzyme required for the first step (the *aromatic L-amino acid decarboxylase*). Dopamine is used as a transmitter by the dopaminergic neurons in the *CNS* and by autonomic neurons that innervate the *kidney*.

Norepinephrine (NE) is produced when a second enzyme (*dopamine-β-hydroxylase*) is also present. In most *sympathetic postganglionic nerve endings* and noradrenergic central neurons (→ **A**), NE serves as the neurotransmitter along with the *co-transmitters* adenosine triphosphate (ATP), somatostatin (SIH), or neuropeptide Y (NPY).

Within the adrenal medulla (see below) and adrenergic neurons of the medulla oblongata, *phenylethanolamine N-methyltransferase* transforms norepinephrine (NE) into **epinephrine (E)**.

The endings of unmyelinated sympathetic postganglionic neurons are knobby or *varicose* (→ **A**). These knobs establish synaptic contact, albeit not always very close, with the effector organ. They also serve as sites of **NE synthesis** and **storage**. L-tyrosine (→ **A1**) is actively taken up by the nerve endings and transformed into dopamine. In adrenergic stimulation, this step is accelerated by protein kinase A-mediated (PKA; → **A2**) phosphorylation of the responsible enzyme. This yields a larger dopamine supply. Dopamine is transferred to chromaffin vesicles, where it is transformed into NE (→ **A3**). Norepinephrine, the end product, inhibits further dopamine synthesis (negative feedback).

NE release. NE is exocytosed into the synaptic cleft (→ **A5**) after the arrival of action potentials at the nerve terminal and the initiation of Ca^{2+} influx (→ **A4** and p. 50).


Adrenergic receptors or **adrenoceptors** (→ **A, B**). Four main types of adrenoceptors (α_1, α_2, β_1 and β_2) can be distinguished according to their affinity to E and NE and to numerous agonists and antagonists. All adrenoceptors respond to E, but NE has little effect on β_2-adrenoceptors. Isoproterenol (isoprenaline) activates only β-adrenoceptors, and phentolamine only blocks α-adrenoceptors. The activities of all adrenoceptors are mediated by G proteins (→ p. 55).

Different subtypes (α_{1A}, α_{1B}, α_{1D}) of **α_1-adrenoceptors** can be distinguished (→ **B1**). Their location and function are as follows: CNS (sympathetic activity ↑), salivary glands, liver (glycogenolysis ↑), kidneys (alters threshold for renin release; → p. 186), and smooth muscles (trigger contractions in the arterioles, uterus, deferent duct, bronchioles, urinary bladder, gastrointestinal sphincters, and dilator pupillae).

Activation of α_1-adrenoceptors (→ **B1**), mediated by *G_q proteins* and *phospholipase Cβ* (PLCβ), leads to formation of the second messengers *inositol tris-phosphate* (IP_3), which increases the cytosolic Ca^{2+} concentration, and *diacylglycerol* (DAG), which activates protein kinase C (PKC; see also p. 278). G_q protein-mediated α_1-adrenoceptor activity also activates Ca^{2+}-dependent *K^+ channels*. The resulting K^+ outflow hyperpolarizes and relaxes target smooth muscles, e.g., in the gastrointestinal tract.

Three subtypes (α_{2A}, α_{2B}, α_{2C}) of **α_2-adrenoceptors** (→ **B2**) can be distinguished. Their location and action are as follows: CNS (sympathetic activity ↓, e.g., use of the α_2 agonist clonidine to lower blood pressure), salivary glands (salivation ↓), pancreatic islets (insulin secretion ↓), lipocytes (lipolysis ↓), platelets (aggregation ↑), and neurons (presynaptic autoreceptors, see below). Activated α_2-adrenoceptors (→ **B2**) link with *G_i protein* and inhibit (via α_i subunit of G_i) adenylate cyclase (*cAMP synthesis* ↓, → p. 274) and, at the same time, increase (via the $\beta\gamma$ subunit of G_i) the open-probability of voltage-gated K^+ channels (*hyperpolarization*). When coupled with G_0 proteins, activated α_2-adrenoceptors also inhibit voltage-gated Ca^{2+} channels ($[Ca^{2+}]_i$ ↓).

All **β-adrenoceptors** are coupled with a G_S protein, and its α_S subunit releases cAMP as a second messenger. cAMP then activates protein kinase A (PKA), which phosphorylates different proteins, depending on the target cell type (→ p. 274).



▶ NE and E work via **β_1-adrenoceptors** (→ **B3**) to open L-type Ca^{2+} channels through cAMP and PKA in *cardiac cell* membranes. This increases the $[Ca^{2+}]_i$ and therefore produces *positive chronotropic, dromotropic, and inotropic effects*. Activated G_s protein can also directly increase the open-probability of voltage-gated Ca^{2+} channels in the heart (→ **B3**). In the *kidney*, the basal renin secretion is increased via β_1-adrenoceptors.

Activation of **β_2-adrenoceptors** by epinephrine (→ **B4**) increases cAMP levels, thereby lowering the $[Ca^{2+}]_i$ (by a still unclear mechanism). This *dilates* the bronchioles and blood vessels of skeletal muscles and *relaxes* the muscles of the uterus, deferent duct, and gastrointestinal tract. Further effects of β_2-adrenoceptor activation are *increased insulin secretion* and *glycogenolysis* in liver and muscle and *decreased platelet aggregation*. ▶

▶ Epinephrine also enhances NE release in noradrenergic fibers by way of presynaptic β_2-adrenoceptors (→ **A2, A5**).

Heat production is increased via **β_3-adrenoceptors** on brown lipocytes (→ p. 224).

NE in the synaptic cleft **is deactivated by** (→ **A6 a – d**):

◆ *diffusion* of NE from the synaptic cleft *into the blood*;

◆ *extraneuronal NE uptake* (in the heart, glands, smooth muscles, glia, and liver), and subsequent intracellular degradation of NE by catecholamine-O-methyltransferase (COMT) and monoamine oxidase (MAO);

◆ *active re-uptake of NE* (70%) by the presynaptic nerve terminal. Some of the absorbed NE enters intracellular vesicles (→ **A3**) and is reused, and some is inactivated by MAO;

◆ stimulation of presynaptic α_2-adrenoceptors (*autoreceptors*; → **A 6d, 7**) by NE in the synaptic cleft, which inhibits the further release of NE.

Presynaptic α_2-adrenoceptors can also be found on cholinergic nerve endings, e.g., in the gastrointestinal tract (motility ↓) and cardiac atrium (negative dromotropic effect), whereas presynaptic M-cholinoceptors are present on noradrenergic nerve terminals. Their mutual interaction permits a certain degree of peripheral ANS regulation.

Adrenal Medulla

After stimulation of preganglionic sympathetic nerve fibers (cholinergic transmission; → p. 81), 95% of all cells in the adrenal medulla secrete the endocrine hormone **epinephrine (E)** into the blood by exocytosis, and another 5% release norepinephrine (NE). Compared to noradrenergic neurons (see above), *NE synthesis* in the adrenal medulla is similar, but most of the NE leaves the vesicle and is enzymatically metabolized into E in the cytoplasm. Special vesicles called *chromaffin bodies* then actively store E and get ready to release it and co-transmitters (enkephalin, neuropeptide Y) by exocytosis.


In **alarm reactions**, secretion of E (and some NE) from the adrenal medulla increases substantially in response to physical and mental or emotional stress. Therefore, cells not sympathetically innervated are also activated in such stress reactions. E also increases neuronal NE release via presynaptic β_2-adrenoceptors (→ **A2**). Epinephrine secretion from the adrenal medulla (mediated by increased sympathetic activity) is stimulated by certain **triggers**, e.g., *physical work*, cold, heat, anxiety, anger (stress), *pain, oxygen deficiency*, or a *drop in blood pressure*. In severe hypoglycemia (< 30 mg/dL), for example, the plasma epinephrine concentration can increase by as much as 20-fold, while the norepinephrine concentration increases by a factor of only 2.5, resulting in a corresponding rise in the E/NE ratio.

The **main task of epinephrine** is to mobilize stored chemical energy, e.g., through *lipolysis* and *glycogenolysis*. Epinephrine enhances the uptake of glucose into skeletal muscle (→ p. 285) and activates enzymes that accelerate glycolysis and lactate formation (→ p. 72ff.). To enhance the blood flow in the muscles involved, the body increases the cardiac output while curbing gastrointestinal blood flow and activity (→ p. 75 A). Adrenal epinephrine and neuronal NE begin to stimulate the secretion of hormones responsible for replenishing the depleted energy reserves (e.g., ACTH; → p. 299 A) while the alarm reaction is still in process.

Non-cholinergic, Non-adrenergic Transmitters

In humans, gastrin-releasing peptide (GRP) and vasoactive intestinal peptide (VIP) serve as co-transmitters in *preganglionic* **sympathetic fibers**; neuropeptide Y (NPY) and somatostatin (SIH) are the ones involved in *postganglionic* fibers. Postganglionic **parasympathetic fibers** utilize the peptides enkephalin, substance P (SP) and/or NPY as co-transmitters.

Modulation of postsynaptic neurons seems to be the primary goal of preganglionic peptide secretion. There is substantial evidence demonstrating that **ATP** (adenosine triphosphate), **NPY** and **VIP** also function as independent neurotransmitters in the autonomic nervous system. VIP and acetylcholine often occur jointly (but in separate vesicles) in the parasympathetic fibers of blood vessels, exocrine glands, ▶



▶ and sweat glands. Within the gastrointestinal tract, VIP (along with nitric oxide) induces the slackening of the circular muscle layer and sphincter muscles and (with the co-transmitters dynorphin and galanin) enhances intestinal secretion. **Nitric oxide (NO)** is liberated from nitrergic neurons (→ p. 280)

The **blood volume** of an adult correlates with his or her (fat-free) body mass (→ Table) and amounts to ca. 4–4.5 L in women (♀) and 4.5–5 L in men of 70 kg BW (♂). The **functions of blood** include the *transport* of various molecules (O_2, CO_2, nutrients, metabolites, vitamins, electrolytes, etc.), heat (regulation of body temperature) and *transmission of signals* (hormones) as well as *buffering* and immune *defense*. The blood consists of a fluid (*plasma*) and *formed elements* (→ Table): **Red blood cells** (RBCs) transport O_2 and play an important role in pH regulation. **White blood cells** (WBCs) can be divided into *neutrophilic, eosinophilic* and *basophilic granulocytes, monocytes*, and *lymphocytes*. Neutrophils play a role in nonspecific immune defense, whereas monocytes and lymphocytes participate in specific immune responses. **Platelets (thrombocytes**) are needed for hemostasis. *Hematocrit* (Hct) is the volume ratio of RBCs to whole blood (→ **C** and Table). **Plasma** is the fluid portion of the blood in which electrolytes, nutrients, metabolites, vitamins, hormones, gases, and proteins are dissolved.

Plasma proteins (→ Table) are involved in humoral immune defense and maintain oncotic pressure, which helps to keep the blood volume constant. By *binding to plasma proteins*, compounds insoluble in water can be transported in blood, and many substances (e.g., heme) can be protected from breakdown and renal excretion. The binding of small molecules to plasma proteins reduces their osmotic efficacy. Many plasma proteins are involved in blood clotting and fibrinolysis (→ p. 102 ff). **Serum** forms when fibrinogen separates from plasma in the process of blood clotting.

The **formation of blood cells** occurs in the red bone marrow of flat bone in adults and in the spleen and liver of the fetus. Hematopoietic tissues contain pluripotent **stem cells** which, with the aid of hematopoietic growth factors (see below), develop into myeloid, erythroid and lymphoid precursor cells. Since pluripotent stem cells are autoreproductive, their existence is ensured throughout life. In *lymphocyte development,* lymphocytes arising from lymphoid precursor cells first undergo special differentiation (in the thymus or bone marrow) and are later formed in the spleen and lymph nodes as well as in the bone marrow. All other precursor cells are produced by *myelocytopoiesis*, that is, the entire process of proliferation (reproduction), maturation, and release into the bloodstream occurs in the bone marrow. Two hormones, erythropoietin and thrombopoietin, are involved in myelopoiesis. *Thrombopoietin* (formed mainly in the liver) promotes the proliferation and maturation of mega karyocytes from which the platelets are split off. A number of other growth factors affect blood cell formation in bone marrow via paracrine mechanisms.

Erythropoietin promotes the **proliferation and maturation of red blood cells**. It is secreted by the liver in the fetus, and chiefly by the kidney (ca. 90%) in postnatal life. In response to an oxygen deficiency (due to high altitudes, hemolysis, etc.; → **A**), erythropoietin secretion increases, larger numbers of red blood cells are produced, and the fraction of reticulocytes (young erythrocytes) in the blood rises. The **life span** of a red blood cell is around 120 days. Red blood cells regularly exit from arterioles in the splenic pulp and travel through small pores to enter the splenic sinus (→ **B**), where old red blood cells are sorted out and destroyed (*hemolysis*). Macrophages in the spleen, liver, bone marrow, etc. engulf and break down the cell fragments. *Heme*, the iron-containing group of hemoglobin (Hb) released during hemolysis, is broken down into bilirubin (→ p. 252), and the iron is recycled (→ p. 90).

Blood volume in liters relative to body weight (BW)
♂ 0.041 × BW (kg) + 1.53, ♀ 0.047 × BW (kg) + 0.86

Hematocrit (cell volume/ blood volume):
♂ 0.40–0.54 ♀: 0.37–0.47

Erythrocytes (10^{12}/L of blood = 10^6/ μL of blood):
♂ 4.6–5.9 ♀ 4.2–5.4

Hemoglobin (g/L of blood):
♂ 140–180 ♀ 120–160

MCH, MCV, MCHC—**m**ean **c**orpuscular (MC) **h**emoglobin (Hb), MC **v**olume, MC **H**b **c**oncentration (→ **C**)


Leukocytes (10^9/L of blood = 10^3/ μL of blood):
3–11 (64% granulocytes, 31% lymphocytes, 6% monocytes)

Platelets (10^9/L of blood = 10^3/ μL of blood):
♂ 170–360 ♀ 180–400


Plasma proteins (g/L of serum):
66–85 (including 55–64% albumin)

A. Regulation of RBC production


1 Hypoxia




2 Hemolysis



B. Life cycle of red blood cells



C. Erythrocyte parameters MCH, MCV and MCHC



MCH (mean Hb mass/RBC)

$$= \frac{\text{Hb conc.}}{\text{red cell count}} \text{ (g/RBC)}$$

Normal: 27–32 pg

MCV (mean volume of one RBC)

$$= \frac{\text{Hct}}{\text{red cell count}} \text{ (L/RBC)}$$

Normal: 80–100 fl

MCHC (mean Hb conc. in RBCs)

$$= \frac{\text{Hb conc.}}{\text{Hct}} \text{ (g/L}_{RBC}\text{)}$$

Normal: 320–360 g/L

Roughly $^2/_3$ of the body's **iron pool** (ca. 2 g in women and 5 g in men) is bound to *hemoglobin* (Hb). About $^1/_4$ exists as *stored iron* (ferritin, hemosiderin), the rest as *functional iron* (myoglobin, iron-containing enzymes). **Iron losses** from the body amount to about 1 mg/day in men and up to 2 mg/day in women due to menstruation, birth, and pregnancy. **Iron absorption** occurs mainly in the duodenum and *varies according to need*. The absorption of iron usually amounts to about 3 to 15% of iron supplied by the diet in healthy individuals, but can increase to over 25% in individuals with iron deficiency (→ **A1**). A minimum daily **iron intake** of at least 10–20 mg/day is therefore recommended (women > children > men).

Iron absorption (→ **A2**). Fe supplied by the diet (hemoglobin, myoglobin found chiefly in meat and fish) is absorbed relatively efficiently as a **heme-Fe** by *HCP1* (heme carrier protein 1). Within mucosal cells, Fe^{3+} is released by *heme oxygenase* and reduced to Fe^{2+} which is transported across the cell by *mobilferrin*. It either enters the bloodstream or remains in the mucosa as a ferritin-Fe(III) complex and returns to the gut lumen during cell turnover. **Non-heme-Fe** can only be absorbed as Fe^{2+}. Therefore, non-heme Fe^{3+} must first be reduced to Fe^{2+} by ferrireductase (FR;→ **A2**) and ascorbate on the surface of the luminal mucosa (→ **A2**). Fe^{2+} is absorbed through secondary active transport via the Fe^{2+}-H^+ symport carrier *DCT1* (= divalent cation transporter = DMT1 = divalent metal transporter) where it competes with Mn^{2+}, Co^{2+}, Cd^{2+}, etc. A *low chymous pH* is important since it (a) increases the H^+ gradient that drives Fe^{2+} via DCT1 into the cell and (b) frees dietary iron from complexes. The uptake of iron into the bloodstream is *regulated by two mechanisms*: (1) When an iron deficiency exists, *aconitase* (an iron-regulating protein) in the cytosol binds with *ferritin-mRNA*, thereby inhibiting mucosal ferritin translation. As a result, larger quantities of absorbed Fe can enter the bloodstream. (2) On the baso-lateral cell side, Fe^{2+} is oxidized to Fe^{3+} by *hephaestin* (= membrane-bound homologue of the ferroxidase ceruloplasmin). Fe^{3+} leaves the cell via *ferroportin 1* (= IREG1). Its density in the plasma membrane of mucosal cells (as well as of hepatocytes and macrophages) is diminished by *hepcidin*. Secretion of this liver hormone decreases during iron deficiency. Thus, the IREG1 density increases and more Fe^{3+} enters the blood. There, it binds to *apotransferrin*, a protein responsible for **iron transport in plasma** (→ **A2**, **3**). *Transferrin* [= apotransferrin loaded with 2 Fe(III)], is taken up by endocytosis into erythroblasts and cells of the liver, placenta, etc. with the aid of *transferrin receptors*. Once Fe has been released to the target cells, apotransferrin again becomes available for uptake of Fe from the intestine and macrophages (see below).


Iron storage and recycling (→ **A3**). *Ferritin* occurs mainly in the intestinal mucosa, liver, bone marrow, red blood cells, and plasma. It contains binding pockets for up to 4500 Fe^{3+} ions and provides rapidly available stores of iron (ca. 600 mg), whereas iron mobilization from *hemosiderin* is much slower. Hb-Fe and heme-Fe released from malformed erythroblasts (so-called inefficient erythropoiesis) and hemolyzed red blood cells bind to haptoglobin and hemopexin, respectively. They are then engulfed by macrophages in the bone marrow or in the liver and spleen resulting in 97% iron recycling (→ **A3**).

An **iron deficiency** inhibits Hb synthesis, leading to hypochromic microcytic anemia: MCH < 26 pg, MCV < 70 fL, Hb < 110 g/L. The primary causes are: (1) blood loss (most common cause); 0.5 mg Fe are lost with each mL of blood; (2) insufficient Fe intake or absorption; (3) increased Fe requirement due to growth, pregnancy, breast-feeding, etc.; (4) decreased Fe recycling due to chronic infection. Inflammatory signals, e.g. IL6, increase secretion of hepcidin. Therefore, **IREG1** density decreases also in macrophages and Fe is retained there.


Iron overload (e.g. due to defects in hepcidin or IREG1) most commonly damages the liver, pancreas, and myocardium (*hemochromatosis*). If the Fe supply bypasses the intestinal tract (Fe injection), the transferrin capacity can be exceeded and the resulting quantities of free Fe can induce Fe poisoning.

B_{12} vitamins (cobalamins) and **folic acid** are also required for erythropoiesis (→ **B**). Deficiencies lead to *hyperchromic anemia* (decreased RCC, increased MCH). The main causes are lack of intrinsic factor (required for cobalamin resorption) and decreased folic acid absorption due to malabsorption (see also p. 262) or an extremely unbalanced diet. Because of the large stores available, decreased cobalamin absorption does not lead to symptoms of deficiency until many years later, whereas folic acid deficiency leads to symptoms within a few months.

A. Iron intake and metabolism



B. Folic acid and vitamin B_{12} (cobalamins)



The **viscosity** (η) of blood is higher than that of plasma due to its erythrocyte (RBC) content. Viscosity (η) = 1/fluidity = shearing force (τ)/shearing action (γ) [Pa·s]. The viscosity of blood rises with increasing *hematocrit* and decreasing *flow velocity*. Erythrocytes lack the major organelles and, therefore, are highly deformable. Because of the low viscosity of their contents, the liquid film-like characteristics of their membrane, and their high surface/volume ratio, the blood behaves more like an emulsion than a cell suspension, especially when it flows rapidly. The viscosity of *flowing* blood (η_{blood}) passing through small arteries ($\varnothing$ 20 μm) is about 4 relative units (RU). This is twice as high as the viscosity of plasma (η_{plasma} = 2 RU; water: 1 RU = 0.7 mPa·s at 37 °C).

Because they are *highly deformable*, normal RBCs usually have no problem passing through capillaries or pores of the splenic circulation (see p. 89 B), although their diameter ($\varnothing$ < 5 μm) is smaller than that of freely mobile RBCs (7 μm). Although the slowness of flow in small vessels causes the blood viscosity to increase, this is partially compensated for ($\eta_{blood}\downarrow$) by the passage of red cells in single file through the center of small vessels (diameter < 300 μm) due to the **Fåhraeus–Lindqvist effect** (→ **A**). Blood viscosity is only slightly higher than plasma viscosity in arterioles ($\varnothing \approx 7$ μm), but rises again in capillaries ($\varnothing \approx 4$ μm).

A *critical increase* in blood viscosity can occur a) if blood flow becomes too sluggish and/or b) if the fluidity of red cells decreases due to hyperosmolality (resulting in crenation), cell inclusion, hemoglobin malformation (e.g., sickle-cell anemia), changes in the cell membrane (e.g., in old red cells), and so forth. Under such circumstances, the RBCs undergo aggregation (*rouleaux formation*), increasing the blood viscosity tremendously (up to 1000 RU). This can quickly lead to the cessation of blood flow in small vessels (→ p. 220).


Plasma, Ion Distribution

Plasma is obtained by preventing the blood from clotting and extracting the formed elements by centrifugation (→ p. 89 C). High molecular weight proteins (→ **B, C**) as well as ions and non-charged substances with low molecular weights are dissolved in plasma. The sum of the concentrations of these particles yields a *plasma osmolality* of 290 mOsm/kgH_2O (→ pp. 164, 383). The most abundant cation in plasma is Na^+, and the most abundant anions are Cl^- and HCO_3^-. Although plasma proteins carry a number of anionic (i.e. negative) net charges (→ **C**), their osmotic efficacy is smaller because the number of particles, not the ionic valency, is the determining factor.


The fraction of proteins able to leave the blood vessels is small and varies from one organ to another. Capillaries in the liver, for example, are much more permeable to proteins than those in the brain. The composition of *interstitial fluid* therefore differs significantly from that of plasma, especially with respect to protein content (→ **C**). A completely different composition is found in the *cytosol*, where K^+ is the prevailing cation, and where phosphates, proteins and other organic anions comprise the major fraction of anions (→ **C**). These fractions vary depending on cell type.

Sixty percent of all **plasma protein** (→ **B**) is albumin (35–46 g/L). Albumin serves as a vehicle for a number of substances in the blood. They are the main cause of colloidal osmotic pressure or, rather, *oncotic pressure* (→ pp. 210, 384), and they provide a protein reserve in times of protein deficiency. The α_1, α_2 and β globulins (→ **B**) mainly serve to transport lipids (apolipoproteins), hemoglobin (haptoglobin), iron (apotransferrin), cortisol (transcortin), and cobalamins (transcobalamin). Most plasma factors for coagulation and fibrinolysis are also proteins. Most plasma *immunoglobulins* (*Ig*, → **D**) belong to the group of γ globulins and serve as defense proteins (antibodies). IgG, the most abundant immunoglobulin (7–15 g/L), can cross the placental barrier (maternofetal transmission; → **D**). Each Ig consists of two group-specific, heavy protein chains (IgG: γ chain, IgA: α chain, IgM: μ chain, IgD: δ chain, IgE: ε chain) and two light protein chains (λ or $\varkappa$ chain) linked by disulfide bonds to yield a characteristic Y-shaped configuration (see p. 95 A).


A. Fåhraeus–Lindqvist effect



B. Plasmaproteins



C. Ion composition of body fluids





mEq/L (mmol/L)

	Ion	Plasma	Serum	Interstitium	Cytosol
Cations	Na^+	142	153	145	ca. 12
	K^+	4.3	4.6	4.4	ca. 140
	Free Ca^{2+}	2.6 (1.3*)	2.8 (1.3)	2.5 (1.5)	<0,001
	Free Mg^{2+}	1.0 (0.5**)	1.0 (0.5)	0.9 (0.45)	1.6
	Sum	150	162	153	ca. 152
Anions	Cl^-	104	112	117	ca. 3
	HCO_3^-	24	26	27	10
	Inorganic phosphate	2	2.2	2.3	ca. 30
	Proteins	14	15	0.4	ca. 54
	Misc.	5.9	6.3	6.2	ca. 54
	Sum	150	162	153	ca. 152

*) Total plasma Ca: 2.5 mmol/L; **) Total plasma Mg: 0.9 mmol/L

D. Concentrations of immunglobulins in serum





Fundamental Principles

The body has *nonspecific* (*innate*) *immune defenses* linked with *specific (acquired) immune defenses* that counteract bacteria, viruses, fungi, parasites and foreign (non-self) macromolecules. They all function as **antigens**, i.e., substances that stimulate the specific immune system, resulting in the activation of antigen-specific **T lymphocytes** (**T cells**) and **B lymphocytes** (**B cells**). In the process, B lymphocytes differentiate into *plasma cells* that secrete antigen-specific **antibodies** (**immunoglobulins, Ig**) (→ **C** and p. 93 **D**). Ig function to neutralize and opsonize antigens and to activate the complement system (→ p. 96). These mechanisms ensure that the respective antigen is *specifically recognized*, then eliminated by relatively nonspecific means. Some of the T and B cells have an *immunologic memory*.

Precursor lymphocytes without an antigen-binding receptor are *preprocessed* within the *thymus* (*T*) or *bone marrow* (*B*). These organs produce a set of up to 10^8 monospecific T or B cells, each of which is directed against a specific antigen. *Naive* T and B cells which have not previously encountered antigen circulate through the body (blood → peripheral lymphatic tissue → lymph → blood) and undergo **clonal expansion and selection** after contact with its specific antigen (usually in lymphatic tissue). The lymphocyte then begins to divide rapidly, producing numerous monospecific daughter cells. The progeny differentiates into plasma cells or "armed" T cells that initiate the elimination of the antigen.

Clonal deletion is a mechanism for eliminating lymphocytes with receptors directed against autologous (self) tissue. After first contact with their specific self-antigen, these lymphocytes are eliminated during the early stages of development in the thymus or bone marrow. Clonal deletion results in **central immunologic tolerance**. The ability of the immune system to distinguish between endogenous and foreign antigens is called **self/nonself recognition**. This occurs around the time of birth. All substances encountered by that time are recognized as endogenous (self); others are identified as foreign (nonself).

The inability to distinguish self from nonself results in *autoimmune disease*.


At first contact with a virus (e.g., measles virus), the nonspecific immune system usually cannot prevent the viral proliferation and the development of the measles. The specific immune system, with its T-killer cells (→ **B2**) and Ig (first IgM, then IgG; → **C3**), responds slowly: **primary immune response** or **sensitization**. Once activated, it can eliminate the pathogen, i.e., the individual recovers from the measles. **Secondary immune response**: When infected a second time, specific IgG is produced much more rapidly. The virus is quickly eliminated, and the disease does not develop a second time. This type of protection against infectious disease is called **immunity**. It can be achieved by vaccinating the individual with a specific antigen (*active immunization*). *Passive immunization* can be achieved by administering ready-made Ig (immune serum).

Nonspecific Immunity

Lysozyme and *complement factors* dissolved in plasma (→ **A1**) as well as *natural killer cells* (*NK cells*) and phagocytes, especially *neutrophils* and *macrophages* that arise from *monocytes* that migrate into the tissues (→ **A2**) play an important role in nonspecific immunity. Neutrophils, monocytes, and eosinophils circulate throughout the body. They have chemokine receptors (e.g., CXCR1 and 2 for IL-8) and are attracted by various *chemokines* (e.g., IL-8) to the sites where microorganisms have invaded (*chemotaxis*). These cells are able to migrate. With the aid of selectins, they dock onto the endothelium (*margination*), penetrate the endothelium (*diapedesis*), and engulf and damage the microorganism with the aid of *lysozyme*, *oxidants* such as H_2O_2, oxygen radicals (O_2^-, OH·, $^1O_2$), and *nitric oxide* (NO). This is followed by digestion (*lysis*) of the microorganism with the aid of lysosomal enzymes. If the antigen (parasitic worm, etc.) is too large for digestion, other substances involved in nonspecific immunity (e.g., proteases and cytotoxic proteins) are also exocytosed by these cells.

Reducing enzymes such as catalase and superoxide dismutase usually keep the oxidant concentration low. This is often discontinued, especially when macrophages are activated (→ below and **B3**), to fully exploit the bactericidal effect of the oxidants. However, ▶

A. Nonspecific immune defenses enhanced by specific antibodies



▶ the resulting *inflammation* (→ **A2, 4**) also damages cells involved in nonspecific defense and, in some cases, even other endogenous cells.

Opsonization (→ **A1, 2**) involves the binding of *opsonins*, e.g., IgG or complement factor C3b, to specific domains of an antigen, thereby enhancing phagocytosis. It is the only way to make bacteria with a polysaccharide capsule phagocytable. The phagocytes have **receptors** on their surface for the (antigen-independent) Fc segment of IgG as well as for C3b. Thus, the antigen-bound IgG and C3b bind to their respective receptors, thereby linking the rather unspecific process of phagocytosis with the specific immune defense system. Carbohydrate-binding proteins (lectins) of plasma, called *collectins* (e.g. mannose-*binding protein*), which dock onto microbial cell walls, also acts as unspecific opsonins.

The **complement cascade** is activated by antigens opsonized by Ig (classical pathway) as well as by non-opsonophilic antigens (alternative pathway) (→ **A1**). Complement components C3a, C4a and C5a activate basophils and eosinophils (→ **A4**). Complement components C5 –C9 generate the *membrane-attack complex* (MAC), which perforates and kills (Gram-negative) bacteria by **cytolysis** (→ **A3**). This form of defense is assisted by **lysozyme** (= muramidase), an enzyme that breaks down murein-containing bacterial cell walls. It occurs in granulocytes, plasma, lymph, and secretions.

Natural killer (NK) cells are large, granular lymphocytes specialized in nonspecific defense against viruses, mycobacteria, tumor cells etc. They recognize infected cells and tumor cells on "foreign surfaces" and dock via their Fc receptors on IgG-opsonized surface antigens (*antibody-dependent cell-mediated cytotoxicity,* **ADCC**; → **A3**). *Perforins* exocytosed by NK cells form pores in target cell walls, thereby allowing their subsequent lysis (*cytolysis*). This not only makes the virus unable to proliferate (enzyme apparatus of the cell), but also makes it (and other intracellular pathogens) subject to attack from other defense mechanisms.


Various **interferons (IFNs)** stimulate NK cell activity: IFN-α, IFN-β and, to a lesser degree, IFN-γ. IFN-α and IFN-β are released mainly from leukocytes and fibroblasts, while IFN-γ is liberated from activated T cells and NK cells. Virus-infected cells release large quantities of IFNs, resulting in heightened viral resistance in non-virus-infected cells. **Defensins** are cytotoxic peptides released by phagocytes. They can exert unspecific cytotoxic effects on pathogens resistant to NK cells (e.g., by forming ion channels in the target cell membrane).

Macrophages arise from monocytes that migrate into the tissues. Some macrophages are freely mobile (*free macrophages*), whereas others (*fixed macrophages*) remain restricted to a certain area, such as the hepatic sinus (Kupffer cells), the pulmonary alveoli, the intestinal serosa, the splenic sinus, the lymph nodes, the skin (Langerhans cells), the synovia (synovial A cells), the brain (microglia), or the endothelium (e.g., in the renal glomeruli). The **mononuclear phagocytic system (MPS)** is the collective term for the circulating monocytes in the blood and macrophages in the tissues. Macrophages recognize relatively unspecific carbohydrate components on the surface of bacteria and ingest them by phagocytosis. The macrophages have to be activated if the pathogens survive within the phagosomes (→ below and **B3**).

Specific Immunity: Cell-Mediated Immune Responses

Since specific cell-mediated immune responses through "armed" T effector cells need a few days to become effective, this is called *delayed-type immune* response. It requires the participation of **professional antigen-presenting cells (APCs)**: dendritic cells, macrophages and B cells. APCs process and present antigenic peptides to the T cells in association with *MHC-I or MHC-II proteins*, thereby delivering the co-stimulatory signal required for activation of naive T cells. (The gene loci for these proteins are the class I (MHC-I) and class II (MHC-II) major histocompatibility complexes (MHC)), **HLA** *(human leukocyte antigen)* is the term for MHC proteins in humans. Virus-infected dendritic cells, which are mainly located in lymphatic tissue, most commonly serve as APCs. Such HLA-restricted antigen presentation (→ **B1**) involves the insertion of an antigen in the binding pocket of an HLA protein. An *ICAM* (intercellular adhesion molecule) on the surface of the APC then binds to ▶

B. Specific immunity: T-cell activation



▶ *LFA1* (lymphocyte function-associated antigen 1) on the T cell membrane. When a T cell specific for the antigen in question docks onto the complex, the bond is strengthened and the *APC dual signal* stimulates the activation and clonal selection of the T cell (→ **B1**).

The **APC dual signal** consists of **1) recognition of the antigen** (class I or class II HLA-restricted antigen) by the *T cell receptor* and its *co-receptor* and **2) a co-stimulatory signal**, that is, the binding of the B7 protein (on the APC) with the CD28 protein on the T cell (→ **B1**). CD8 molecules on T cytotoxic cells (T_C cells = T-killer cells) and CD4 molecules on T helper cells (T_H cells) function as the co-receptors. When antigen binding occurs without co-stimulation (e.g., in the liver, where there are no APCs), the lymphocyte is inactivated, i.e., it becomes **anergic**, and *peripheral immunologic tolerance* develops.

The T cell can receive APC dual signals from infected macrophages or B cells, provided their receptors have bound the antigen in question (e.g., insect or snake venom or allergens). The APC dual signal induces the T cell to express *interleukin-2* (**IL-2**) and to bind the respective *IL-2 receptor* (→ **B1**). IL-2 is the actual *signal for clonal expansion* of these monospecific T cells. It functions through autocrine and paracrine mechanisms.

Potent *immunosuppression,* e.g., for organ transplantation, can be achieved with IL-2 inhibitors like *cyclosporin A*.

During clonal expansion, the T cells differentiate into three "armed" subtypes, i.e., *T cytotoxic cells* (**T_c cells** or **T killer cells**) and *T helper cells type 1* (**T_{H1} cells**) and type 2 (**T_{H2} cells**). These cells no longer require costimulation and express a different type of adhesion molecule (VLA-4 instead of L-selectins) by which they now dock onto the endothelium of inflamed tissues (rather than to lymphatic tissue like their naïve precursors).


T killer cells develop from naive CD8-containing ($CD8^+$) T cells after HLA-I-restricted antigen presentation (→ **B2**). **Endogenous antigen presentation** occurs when the HLA-I protein takes up the antigen (virus, cytosolic protein) from the cytosol of the APC, which is usually the case. With its CD8-associated T-cell receptor, the T killer cell is able to recognize HLA-I-restricted antigens on (virus) infected endogenous cells and tumor cells as well as on cells of transplanted organs. It subsequently drives the cells into **apoptosis** (programmed cell death) or **necrosis**. Binding of the *Fas ligand* to CD95 (= Fas) plays a role, as does granzyme B (protease), which enters the cell through pores created by exocytosed *perforins* (→ **B2**).

Once **HLA-II-restricted presentation** (→ **B1**) of antigens from intracellular vesicles (e.g., phagocytosed bacteria or viral envelope proteins = **exogenous antigen presentation**) has occurred, naive $CD4^+$ T cells transform into immature T helper cells (T_{H0}), which differentiate into *T_{H1} or T_{H2} cells*. **T_{H1} cells** induce *inflammatory responses* and promote the activation of macrophages with the aid of IFN-γ (→ **B3**), while **T_{H2} cells** are required for *B-cell activation* (→ **C2**). T_{H1} and T_{H2} cells mutually *suppress* each other, so only one of the two types will predominate in any given cell-mediated immune response (→ **B3**).

Specific Immunity: Humoral Immune Responses

Humoral immunity arise from **B cells** (→ **C1**). Numerous *IgD* and *IgM monomers* anchored onto the B-cell surface bind with the respective antigen (dissolved IgM occurs in pentameric form). A resulting network of antigen-bound Ig leads to *internalization* and *processing of the antigen-antibody complex* in B cells. However, **B-cell activation** requires a second signal, which can come directly from a thymus-independent (TI) antigen (e.g., bacterial polysaccharide) or indirectly from a **T_{H2} cell** in the case of a thymus-dependent (TD) antigen. In the latter case, the B cell presents the HLA-II-restricted TD antigen to the T_{H2} cell (→ **C2**). If the *CD4-associated T-cell receptor* (TCR) of the T_{H2} cell recognizes the antigen, *CD40 ligands* are expressed on the T_{H2} surface (CD40 ligands bind with CD40 proteins on B cells) and **IL-4** is secreted. The CD40 ligand and IL-4 (later also IL-5 and IL-6) stimulate the B cell to undergo *clonal selection*, IgM secretion, and differentiation into **plasma cells** (→ **C3**). Before differentiation, **class switching** can occur, i.e., a different type of Ig heavy chain (→ p. 92) can be expressed by altered DNA splicing (→ p. 8f.). In this manner, IgM is converted into IgA, IgG or IgE (→ p. 92). All Ig types arising from a given B-cell clone remain monospecific for the same antigen. The plasma cells formed after class switching produce only a single type of Ig.

C. Specific immunity: B-cell activation



Allergy is a specific, exaggerated immune response to a (usually harmless) foreign substance or antigen (→ p. 94ff.). **Allergens** are antigens that induce allergies. Small molecules conjugated to endogenous proteins can also have antigenic effects. In this case, they are referred to as incomplete antigens or **haptens**. The heightened immune response to secondary antigen contact (→ p. 94ff.) normally has a protective effect. In allergies, however, the first contact with an antigen induces sensitization (allergization), and subsequent exposure leads to the destruction of healthy cells and intact tissue. This can also result in damage to endogenous proteins and *autoantibody* production. *Inflammatory reactions* are the main causes of damage.

Types of hypersensitivity reactions: **Type I** reactions are common. On first contact, the allergen internalized by B cells is presented to T_{H2} cells. The B cell then proliferates and differentiates into plasma cells (see p. 98), which release *immunoglobulin E* (**IgE**). The Fc fragment of IgE binds to *mast cells* and *basophils*. On subsequent contact, the antigens bind to the already available IgE-linked mast cells (→ **A**). Due to the rapid release of mostly vasoactive mediators of inflammation such as histamine, leukotrienes and platelet-activating factor (PAF) from these cell types, an immediate reaction (*anaphylaxis*) occurs within seconds or minutes: **immediate type hypersensitivity**. This is the mechanism by which allergens breathed into the lungs trigger hay fever and asthma attacks. The vasodilatory effect of a generalized type I reaction can lead to *anaphylactic shock* (see p. 220).

In **type II** reactions, the immune system mainly attacks *cells* with antigenic properties. This can be attributable to the transfusion of the erythrocytes of the wrong blood group or the binding of *haptens* (e.g., medications) to endogenous cells. The binding of haptens to platelets can, for example, result in thrombocytopenia.

Type III reactions are caused by antigen-antibody complexes. If more antigen than antibody is available, *soluble antigen-antibody complexes* circulate in blood for a long time (→ **B**) and settle mainly in the capillaries, making the capillary wall subject to attack by the complement system. This leads to the development of **serum sickness** (→ **B**), the main symptoms of which are joint pain and fever.

Type IV reactions are mainly mediated by T_{H1} cells, T_C cells, and macrophages. Since symptoms peak 2 to 4 days after antigen contact, this is called **delayed type hypersensitivity**. The main triggers are mycobacteria (e.g. Tbc), other foreign proteins, and haptens, such as medications and plant substances, such as poison ivy. Primary *transplant rejection* is also a type IV hypersensitivity reaction. *Contact dermatitis* is also a type IV reaction caused by various haptens (e.g., nickel in jewelry).

Blood Groups

A person's blood group is determined by the type of antigen (certain glycolipids) present on the red blood cells (RBCs). In the **AB0 system**, the antigens are A and B (→ **C**). In blood type A, antigen A (on RBC) and anti-B antibody (in serum) are present; in type B, B and anti-A are present; in type AB, A and B are present, no antibody; in type 0 (zero), no antigen but anti-A and anti-B are present.


When giving a **blood transfusion**, it is important that the blood groups of donor and recipient match, i.e. that the RBCs of the donor (e.g. A) do not come in contact with the respective antibodies (e.g. anti-A) in the recipient. If the donor's blood is the wrong type, *agglutination* (cross-linking by IgM) and *hemolysis* (bursting) of the donor's RBCs will occur (→ **C1**). Donor and recipient blood types must therefore be determined and *cross-matched* (→ **C2**) prior to a blood transfusion.

Since AB0 antibodies belong to the IgM class, they usually do not cross the placenta.


In the **Rh system**, antibodies against rhesus antigens (C, D, E) on RBCs do not develop unless *prior sensitization* has occurred. D is by far the most antigenic. A person is Rh-positive (Rh^+) when D is present on their RBCs (most people), and Rh-negative (Rh^-) when D is absent. Anti-D antibodies belong to the IgG class of immunoglobulins, which are capable of crossing the placenta (→ p. 93 D).

Rh^- individuals can form anti-Rh^+ (= anti-D) antibodies, e.g., after sensitization by a mismatched blood transfusion or of an Rh^- mother by an Rh^+ fetus. Subsequent exposure to the mismatched blood leads to a severe antigen-antibody reaction characterized by intravascular agglutination and hemolysis (→ **D**).


A. Anaphylaxis




B. Serum sickness



C. AB0 blood group incompatibility



D. Rh sensitization of mother by child or by Rh-mismatched transfusion



The hemostatic system stops bleeding. *Thrombocytes (platelets), coagulation* (or *clotting*) *factors in plasma* and *vessel walls* interact to seal leaks in blood vessels. The damaged vessel constricts (release of endothelin), and platelets aggregate at the site of puncture (and attract more platelets) to seal the leak by a *platelet plug*. The time required for sealing (ca. 2 to 4 min) is called the *bleeding time*. Subsequently, the coagulation system produces a fibrin meshwork. Due to covalent cross-linking of fibrin, it turns to a *fibrin clot* or *thrombus* that retracts afterwards, thus reinforcing the seal. Later recanalization of the vessel can be achieved by fibrinolysis.


Platelets ($170–400 \cdot 10^3$ per μL of blood; half-life ≈ 10 days) are small non-nucleated bodies that are pinched off from megakaryocytes in the bone marrow. When an endothelial injury occurs, platelets adhere to subendothelial collagen fibers (→ **A1**) bridged by **von Willebrand's factor** (vWF), which is formed by endothelial cells and circulates in the plasma complexed with factor VIII. Glycoprotein complex GP Ib/IX on the platelets are vWF receptors. This *adhesion* activates **platelets** (→ **A2**). They begin to release substances (→ **A3**), some of which promote platelet adhesiveness (vWF). Others like serotonin, platelet-derived growth factor (PDGF) and thromboxane A_2 (TXA_2) promote vasoconstriction. Vasoconstriction and platelet *contraction* slow the blood flow. Mediators released by platelets enhance platelet activation and attract and activate more platelets: ADP, TXA_2, platelet-activating factor (PAF). The shape of activated platelets change drastically (→ **A4**). Discoid platelets become spherical and exhibit pseudopodia that intertwine with those of other platelets. This *platelet aggregation* (→ **A5**) is further enhanced by thrombin and stabilized by GP IIb/IIIa. Once a platelet changes its shape, GP IIb/IIIa is expressed on the platelet surface, leading to fibrinogen binding and platelet aggregation. GP IIb/IIIa also increases the adhesiveness of platelets, which makes it easier for them to stick to subendothelial fibronectin.


Several **coagulation factors** are involved in the clotting process. Except for Ca^{2+}, they are proteins formed in the *liver* (→ **B** and Table). Factors labeled with a "K" in the table (as well

I	Fibrinogen	Half-life (h): 96
II ^{K}	Prothrombin	72
III	Tissue thromboplastin	
IV	Ionized calcium (Ca^{2+})	
V	Proaccelerin	20
VII ^{K}	Proconvertin	5
VIII	Antihemophilic factor A	12
IX ^{K}	Antihemophilic factor B; plasma thromboplastin component (PTC); Christmas factor	24
X ^{K}	Stuart–Prower factor	30
XI	Plasma thromboplastin antecedent (PTA)	48
XII	Hageman factor	50
XIII	Fibrin-stabilizing factor (FSF)	250
–	Prekallikrein (PKK); Fletcher factor	
–	High-molecular-weight kininogen (HMK); Fitzgerald factor	

duced with **vitamin K**, an essential cofactor in posttranslational γ-carboxylation of glutamate residues of the factors. These γ-carboxyglutamyl groups are chelators of Ca^{2+}. They are required for Ca^{2+}-mediated complex formation of factors on the surface of phospholipid layers (PL), particularly on the platelet membrane (platelet factor 3). Vitamin K is oxidized in the reaction and has to be re-reduced by liver epoxide reductase (*vitamin K recycling*). **Ca^{2+} ions** are required for several steps in the clotting process (→ **B**). When added to blood samples in vitro, citrate, oxalate, and EDTA bind with Ca^{2+} ions, thereby preventing the blood from clotting. This effect is desirable when performing various blood tests.

Activation of blood clotting (→ **B**). Most coagulation factors normally are not active, or *zymogenic*. Their activation takes place as a cascade of events (An "a" added to the factor number means "activated") that enhance one another. Thus, even small amounts of a trigger factor lead to rapid blood clotting. The trigger can be endogenous (within a vessel) or exogenous (external). In the case of exogenous (extravascular) activation, following injuries to the blood vessels (→ **B** top left), the *tissue factor* (TF = extrinsic thromboplastin, an integral membrane protein) forms a complex with VIIa and Ca^{2+}, already contained in the blood, on phospholipid surfaces (**PL**). This complex acti- ▶


A. Platelet-mediated hemostasis
vWF
Platelet (PLT)
Blood
1
Endothelial damage
Collagen
PLT adhesion
2
4
Change in shape
PLT activation
Slowing of blood flow
Vasoconstriction
Secretion
3
Fibrinogen
vWF
Serotonin, PDGF
TXA2
ADP, PAF
5
PLT aggregation: Clot formation


B. Blood clotting
Exogenous activation
(tissue injury)
Tissue
Blood
TF
Ca2+
VIIa
VII
TF – PL – Ca2+ – VIIa
Complex
Activates
Converts to
Inhibits
Endogenous activation
(on foreign surfaces)
HMK
KK
PKK
XII
XIIa
XIa
XI
IXa
IX
X
PL – Ca2+ – IXa – VIIIa
VIII
Xa
V
PL – Ca2+ – Xa – Va
3
Prothrombin (II)
Thrombin (IIa)
PLT aggregation
Positive feedback loop
TFPI
XIII
XIIIa
Red clot
Clot formation
Fibrinogen (I)
Fibrin monomer
Fibrin mesh-work

▶ vates VII, IX, and X, which in turn leads to the formation of small amounts of thrombin (**initiating reaction**, → **B**, narrow arrows). This amount of thrombin is sufficient to activate V, IIIV, XI, IX, and X (→ **B**, bold arrows) and then, by way of positive feedback, release the amount of thrombin that allows clot formation (see below). The effects of the TF-PL-Ca^{2+}-VIIa-complex are now inhibited by TFPI (tissue factor pathway inhibitor) (→ **B**, left). The "endogenous" activation (→ **B**, top right) starts through contact activation of XII. Because patients with a genetic defect of XII do not display hemorrhagic diatheses, it is now believed that this activation type only plays a part on external (test tube) or internal (vascular prosthesis) foreign surfaces.

Fibrin formation (→ **B3**). Xa and Va form an additional complex with PL and Ca^{2+}. This complex activates prothrombin (II) to **thrombin** (IIa). In the process, Ca^{2+} binds with phospholipids, and the N-terminal end of prothrombin splits off. The thrombin liberated in the process now activates not only V, VIII, IX, X, and XI (see above) but also fibrinogen to **fibrin**, as well as fibrin-stabilizing factor (XIII). The single (monomeric) fibrin threads form a soluble meshwork (*$fibrin_s$*: "s" for soluble) which XIIIa ultimately stabilizes to insoluble fibrin (*$fibrin_i$*). XIIIa links the side chains of the fibrin threads via covalent bonds. Thrombin also supports the PLT aggregation, resulting in a very stable tight seal (red clot) formed by PLT aggregate (white clot) and the fibrin meshwork.

Fibrinolysis and Thromboprotection

To prevent excessive clotting and occlusion of major blood vessels (*thrombosis*) and *embolisms* due to clot migration, $fibrin_s$ is re-dissolved (fibrinolysis) and inhibitory factors are activated as soon as vessel repair is initiated.

Fibrinolysis is mediated by **plasmin** (→ **C**). Various factors in blood (plasma kallikrein, factor XIIa), tissues (tissue plasminogen activator, tPA, at endothelial cells etc.), and urine (urokinase) activate *plasminogen* to plasmin.

Streptokinase, urokinase and tPA are used therapeutically to activate plasminogen. This is useful for dissolving a fresh thrombus located, e.g., in a coronary artery.


Fibrin is split into fibrinopeptides which inhibit thrombin formation and polymerization of fibrin to prevent further clot formation. *$Alpha_2$-antiplasmin* is an endogenous inhibitor of fibrinolysis. *Tranexamic acid* is administered therapeutically for the same purpose.


Thromboprotection. **Antithrombin III**, a serpin, is the most important thromboprotective plasma protein (→ **D**). It inactivates the protease activity of thrombin and factors IXa, Xa, XIa and XIIa by forming complexes with them. This is enhanced by **heparin** and heparin-like endothelial glucosaminoglycans. Heparin is produced naturally by mast cells and granulocytes, and synthetic heparin is injected for therapeutic purposes.

The binding of thrombin with endothelial **thrombomodulin** provides further thromboprotection. Only in this form does thrombin have anticoagulant effects (→ **D**, negative feedback). Thrombomodulin activates protein C to Ca which, after binding to protein S, deactivates coagulation factors Va and VIIIa. The synthesis of proteins C and S is vitamin K-dependent. Other plasma proteins that inhibit thrombin are **α_2-macroglobulin** and **α_1-antitrypsin** (→ **D**). Endothelial cells secrete **tissue thromboplastin inhibitor**, a substance that inhibits exogenous activation of coagulation, and **prostacyclin** (= prostaglandin I_2), which inhibits platelet adhesion to the normal endothelium.

Anticoagulants are administered for thromboprotection in patients at risk of blood clotting. Injected **heparin** has immediate action. Oral coumarin derivatives (phenprocoumon, warfarin, acenocoumarol) are **vitamin K antagonists** that work by inhibiting epoxide reductase, which is necessary for vitamin K recycling. Therefore, these drugs do not take effect until the serum concentration of vitamin K-dependent coagulation factors has decreased. **Cyclooxygenase inhibitors**, such as aspirin (acetylsalicylic acid), inhibit platelet aggregation by blocking thromboxane A_2 (TXA2) synthesis (→ p. 271).

Hemorrhagic diatheses can have the following causes: a) Congenital deficiency of certain coagulation factors. Lack of VIII or IX, for example, leads to *hemophilia A* or *B*, respectively. b) Acquired deficiency of coagulation factors. The main causes are liver damage as well as vitamin K deficiency due to the destruction of vitamin K-producing intestinal flora or intestinal malabsorption. c) Increased consumption of coagulation factors, by *disseminated intravascular coagulation*. d) Platelet deficiency (thrombocytopenia) or platelet defect (thrombocytopathy). e) Certain vascular diseases, and f) excessive fibrinolysis.


C. Fibrinolysis
Plasminogen
Fibrin mesh-work
Streptokinase
Urokinase
Plasma kallikrein (PKK)
Plasmin
XIIa
tPA
Aprotinin, etc.
Kallikrein
Tranexamic acid
Urokinase
α2-Antiplasmin
Activates
Converts to
Inhibits
Medication
Soluble fibrinopeptides


D. Suppression of coagulation
Heparin
Exogenous activation
TF–PL–Ca2+–VIIa
Endogenous activation
XIIa
XIa
XI
IXa
IX
X
PL–Ca2+–IXa–VIIIa
Protein S
Protein Ca
Antithrombin III
V
PL–Ca2+–Xa–Va
Negative feedback
Prothrombin
Thrombin
Binding to endothelial thrombomodulin
Protein C
Fibrin
α2-Macroglobulin
α1-Antitrypsin
Activates
Converts to
Inhibits
Fibrinopeptides

The lung is mainly responsible for respiration, but it also has *metabolic functions*, e.g. conversion of angiotensin I to angiotensin II (→ p. 186). In addition, the pulmonary circulation *buffers the blood volume* (→ p. 206) and *filters* out small blood clots from the venous circulation before they obstruct the arterial circulation (heart, brain!).

External **respiration** is the **exchange of gases** between the body and the environment. (*Internal* or *tissue respiration* involves nutrient oxidation, → p. 230). **Convection (bulk flow)** is the means by which the body transports gases over long distances (→ p. 24) along with the flow of air and blood. Both flows are driven by a pressure difference. **Diffusion** is used to transport gases over short distances of a few μm—e.g., through cell membranes and other physiological barriers (→ p. 20ff.). The exchange of gas between the atmosphere and alveoli is called **ventilation**. Oxygen (O_2) in the inspired air is convected to the alveoli before diffusing across the alveolar membrane into the bloodstream. It is then transported via the bloodstream to the tissues, where it diffuses from the blood into the cells and, ultimately, to the intracellular mitochondria. *Carbon dioxide* (CO_2) produced in the mitochondria returns to the lung by the same route.

The **total ventilation per unit time, $\dot{V}_T$,** is the volume (V) of air inspired or expired per time. As the expiratory volume is usually measured, it is also abbreviated **$\dot{V}_E$**. (The dot means "per unit time"). At rest, the body maintains a **$\dot{V}_E$** of about *8 L/min,* with a corresponding **oxygen consumption rate** (**$\dot{V}_{O_2}$**) of about 0.3 L/min and a **CO_2 elimination rate** (**$\dot{V}_{CO_2}$**) of about 0.25 L/min. Thus, about 26 L of air have to be inspired and expired to supply 1 L of O_2 (*respiratory equivalent* = 26). The **tidal volume** (V_T) is the volume of air moved in and out during one respiratory cycle. $\dot{V}_E$ is the product of V_T (ca. 0.5 L at rest) and **respiration rate** *f* (about 16/min at rest) (see p. 74 for values during physical work). Only around 5.6 L/min (at $f = 16\ min^{-1}$) of the $\dot{V}_E$ of 8 L/min reaches the alveoli; this is known as **alveolar ventilation** (**$\dot{V}_A$**). The rest fills airways space not contributing to gas exchange (**dead space ventilation, $\dot{V}_D$**; → pp. 114 and 120).

The human body contains around 300 million **alveoli**, or thin-walled air sacs (ca. 0.3 mm in diameter) located on the terminal branches of the bronchial tree. They are surrounded by a dense network of **pulmonary capillaries** and have a total surface area of about 100 m^2. Because of this and the small air/blood diffusion distances of only a few μm (→ p. 22, Eq. 1.7), sufficient quantities of O_2 can **diffuse** across the alveolar wall into the blood and CO_2 towards the alveolar space (→ p. 120ff.), even at a tenfold increased O_2 demand (→ p. 74). The oxygen-deficient "venous" blood of the pulmonary artery is thus oxygenated ("arterialized") and pumped back by the left heart to the periphery.

The **cardiac output (CO)** is the volume of blood pumped through the pulmonary and systemic circulation per unit time (5–6 L/min at rest). CO times the *arterial–venous O_2 difference ($avDO_2$)*—i.e., the difference between the arterial O_2 fraction in the aorta and in mixed venous blood of the right atrium (ca. 0.05 L of O_2 per L of blood)—gives the *O_2 volume transported per unit time from the lungs to the periphery*. At rest, it amounts to ($6 \times 0.05 =$) 0.3 L/min, a value matching that of $\dot{V}_{O_2}$ (see above). Inversely, if $\dot{V}_{O_2}$ and $avDO_2$ have been measured, CO can be calculated (**Fick's principle**):


$$CO = \dot{V}_{O_2} / avD_{O_2} \qquad [5.1]$$

The *stroke volume* **(SV)** is obtained by dividing CO by the heart rate (pulse rate).

According to *Dalton's law*, the total pressure (P_{total}) of a **mixture of gases** is the sum of the **partial pressures (P)** of the individual gases. The volume **fraction** (F, in L/L; → p. 382) of the individual gas relative to the total volume times P_{total} gives the partial pressure—in the case of O_2, for example, P_{O_2} **= $F_{O_2} \times P_{total}$.** The atmospheric partial pressures in *dry* ambient air at sea level (P_{total} = 101.3 kPa = 760 mmHg) are: $F_{O_2} = 0.209$, $F_{CO_2} = 0.0004$, and $F_{N_2 + \text{noble gases}} = 0.79$ (→ **A**, top right).

If the mixture of gases is "wet", the **partial pressure of water, P_{H_2O}** has to be subtracted from P_{total} (usually = atmospheric pressure). The other partial pressures will then be lower, since Px = Fx ($P_{total} - P_{H_2O}$). When passing through the respiratory tract (37 °C), inspired air is fully saturated with water. As a result, P_{H_2O} rises to 6.27 kPa (47 mmHg), and P_{O_2} drops 1.32 kPa lower than the dry atmospheric air (→ p. 112). The partial pressures in the inspiratory air, alveoli, arteries, veins (mixed venous blood), tissues, and expiratory air (all "wet") are listed in **A**.

A. Gas transport



Pressure differences between the alveoli and the environment are the *driving "forces"* for the exchange of gases that occurs during ventilation. **Alveolar pressure** (P_A = intrapulmonary pressure; → **B**) must be lower than the barometric pressure (P_B) during **inspiration** (breathing in), and higher during **expiration** (breathing out). If the barometric pressure P_B *is defined as zero*, the alveolar pressure is negative during inspiration and positive during expiration (→ **B**). These pressure differences are created through coordinated movement of the diaphragm and chest (thorax), resulting in an increase in lung volume (V_{pulm}) during inspiration and a decrease during expiration (→ **A1,2**).

The **inspiratory muscles** consist of the *diaphragm*, *scalene muscles*, and external intercostal muscles. Their contraction lowers (flattens) the diaphragm and raises and expands the chest, thus expanding the lungs. Inspiration is therefore *active*. The external intercostal muscles and accessory respiratory muscles are activated for deep breathing. During **expiration**, the diaphragm and other inspiratory muscles *relax*, thereby raising the diaphragm and lowering and reducing the volume of the chest and lungs. Since this action occurs primarily due to the intrinsic elastic recoil of the lungs (→ p. 116), expiration is *passive* at rest. In deeper breathing, active mechanisms can also play a role in expiration: the *internal intercostal muscles* contract, and the diaphragm is pushed upward by *abdominal pressure* created by the muscles of the abdominal wall.

Two adjacent ribs are bound by internal and external intercostal muscle. Counteractivity of the muscles is due to variable leverage of the upper and lower rib (→ **A3**). The distance separating the insertion of the external intercostal muscle on the upper rib (Y) from the axis of rotation of the upper rib (X) is smaller than the distance separating the insertion of the muscles on the lower rib (Z′) and the axis of rotation of the lower rib (X′). Therefore, X′–Z′ is longer and a more powerful lever than X–Y. The chest generally rises when the external intercostal muscles contract, and lowers when the opposing internal intercostal muscles contract (X–Y′ > X′–Z).

To exploit the motion of the diaphragm and chest for ventilation, the lungs must be able to follow this motion without being completely attached to the diaphragm and chest. This is achieved with the aid of the **pleura**, a thin fluid-covered sheet of cells that invests each lung (*visceral pleura*), thereby separating it from the adjacent organs, which are covered by the pleura as well (*parietal pleura*).


The lung has a tendency to shrink due to its *intrinsic elasticity* and *alveolar surface tension* (→ p. 118). Since the fluid in the pleural space cannot expand, the lung sticks to the inner surface of the chest, resulting in suction (which still allows tangential movement of the two pleural sheets). **Pleural pressure (P_{pl})** is then negative with respect to atmospheric pressure. P_{pl}, also called *intrapleural* (P_{ip}) or *intrathoracic* pressure, can be measured during breathing (dynamically) using an esophageal probe ($\approx P_{pl}$). The intensity of suction (negative pressure) increases when the chest expands during inspiration, and decreases during expiration (→ **B**). P_{pl} usually does not become positive unless there is very forceful expiration requiring the use of expiratory muscles.


The **transmural pressures (P_{tm}) of the respiratory system** (internal pressure less external pressure) are calculated using P_A, P_{pl} (→ **B**) and the environmental pressure (P_{bar}= 0, see above):


- P_{tm} of Lungs: P_A–P_{pl}= transpulmonary pressure (→ **B**, bottom right)
- P_{tm} of Thorax (with diaphragm): $P_{pl} - 0 = P_{pl}$= transthoracic pressure
- P_{tm} of Lungs plus Thorax: $P_A - 0 = P_A$= transmural pressure of the whole respiratory system. Plotting the latter pressure (P_A) against lung volume gives the resting pressure–volume curve of the respiratory system (→ p. 117 A).

Characterization of breathing activity. The terms *hyperpnea* and *hypopnea* are used to describe abnormal increases or decreases in the depth and rate of respiratory movements. *Tachypnea* (too fast), *bradypnea* (too slow), and *apnea* (cessation of breathing) describe abnormal changes in the respiratory rate. The terms *hyperventilation* and *hypoventilation* imply that the volume of exhaled CO_2 is larger or smaller, respectively, than the rate of CO_2 production, and the arterial partial pressure of CO_2 ($Paco_2$) decreases or rises accordingly (→ p. 142). *Dyspnea* is used to describe difficult or labored breathing, and *orthopnea* occurs when breathing is difficult except in an upright position.


A. Respiratory muscles








B. Alveolar pressure P_A and pleural pressure P_{pl} during respiration





Inhaled foreign particles are trapped by **mucus** in the nose, throat, trachea, and bronchial tree. The entrapped particles are engulfed by *macrophages* and are driven back to the trachea by the *cilia* lining the bronchial epithelium. **Cilial escalator:** The cilia move at a rate of 5–10 s^{-1} and propel the mucus towards the mouth at a rate of 1 cm/min on a film of fluid secreted by the epithelium. Heavy smoking, cystic fibrosis (mucoviscidosis) can impair cilial transport. A volume of 10–100 mL of mucus is produced each day, depending on the type and frequency of local irritation (e.g., smoke inhalation) and vagal stimulation. Mucus is usually swallowed, and the fluid fraction is absorbed in the gastrointestinal tract.

Artificial Respiration

Mouth-to-mouth resuscitation is an emergency measure performed when someone stops breathing. The patient is placed flat on the back. While pinching the patient's nostrils shut, the aid-giver places his or her mouth on the patient's mouth and blows forcefully into the patient's lungs (→ **A3**). This raises the alveolar pressure (→ p. 108) in the patient's lungs relative to the atmospheric pressure outside the chest and causes the lungs and chest to expand (inspiration). The rescuer then removes his or her mouth to allow the patient to exhale. Expulsion of the air blown into the lungs (expiration) occurs due to the intrinsic elastic recoil of the lungs and chest (→ p. 109 A2). This process can be accelerated by pressing down on the chest. The rescuer should ventilate the patient at a rate of about 16 min^{-1}. The exspiratory O_2 fraction (→ p. 107 A) of the the rescuer is high enough to adequately oxygenate the patient's blood. The color change in the patient's skin from blue (cyanosis; → p. 130) to pink indicates that a resuscitation attempt was successful.


Mechanical ventilation. Mechanical *intermittent positive pressure ventilation* (**IPPV**) works on the same principle. This technique is used when the respiratory muscles are paralyzed due to disease, anesthesia, etc. The pump of the respirator drives air into the patient's lung during inspiration (→ **A1**). The external inspiratory and expiratory pathways are separated by a valve (close to the patient's mouth as possible) to prevent enlargement of dead space (→ p. 114). Ventilation frequency, tidal volume, inspiratory flow, as well as duration of inspiration and expiration can be preselected at the respirator. The drawback of this type of ventilation is that venous return to the heart is impaired to some extent (→ p. 206). Today, the standard technique of mechanical respiration is *continuous positive pressure ventilation* (**CPPV**). In contrast to IPPV, the *endexpiratory pressure* is kept *positive* (PEEP) in CPPV. In any case, all ventilated patients should be continuously monitored (expiratory gas fraction; blood gas composition, etc.).

The **iron lung** (Drinker respirator) makes use of *negative-pressure respiration* (→ **A2**). The patient's body is enclosed from the neck down in a metal tank. To achieve inhalation, pressure in the tank is decreased to a level below normal ambient pressure and, thus, below alveolar pressure. This pressure difference causes the chest to expand (inspiratory phase), and the cessation of negative pressure in the tank allows the patient to breathe out (expiratory phase). This type of respirator is used to ventilate patients who require long-term mechanical ventilation due to paralytic diseases, such as polio.

Pneumothorax

Pneumothorax occurs when air enters the pleural space and P_{pl} falls to zero (→ p. 108), which can lead to collapse of the affected lung due to elastic recoil and respiratory failure (→ **B**). The contralateral lung is also impaired because a portion of the inspired air travels back and forth between the healthy and collapsed lung and is not available for gas exchange. *Closed pneumothorax*, i.e., the leakage of air from the alveolar space into the pleural space, can occur spontaneously (e.g., lung rupture due to bullous emphysema) or due to lung injury (e.g., during mechanical ventilation = barotrauma; → p. 134). **Open pneumothorax** (→ **B2**) can be caused by an open chest wound or blunt chest trauma (e.g., penetration of the pleura by a broken rib). **Valvular pneumothorax** (→ **B3**) is a life-threatening form of pneumothorax that occurs when air enters the pleural space with every breath and can no longer be expelled. A flap of skin or similar at the trauma site acts like a valve. Positive pressure develops in the pleural space on the affected side, as well as in the rest of the thoracic cavity. Since the tidal volume increases due to hypoxia, high pressure levels (4 kPa = 30 mmHg) quickly develop. This leads to increasing impairment of cardiac filling and compression of the healthy contralateral lung. Treatment of valvular pneumothorax consists of slow drainage of excess pressure and measures to prevent further valvular action.

A. Artificial respiration




1 Positive-pressure respiration

2 Negative-pressure respiration

3 Mouth-to-mouth resuscitation

B. Pneumothorax



1 Normal

2 Open pneumothorax

3 Valvular pneumothorax

At the end of normal quiet expiration, the lung–chest system returns to its intrinsic **resting position**. About 0.5 L of air is taken in with each breath during normal quiet respiration; this is called the **resting tidal volume** (V_T). Inspiration can be increased by another 3 L or so on forced (maximum) inspiration; this is called the **inspiratory reserve volume** (**IRV**). Likewise, expiration can be increased by about 1.7 L more on forced (maximum) expiration. This is called the **expiratory reserve volume** (**ERV**). These reserve volumes are used during strenuous physical exercise (→ p. 74) and in other situations where normal tidal volumes are insufficient. Even after forced expiration, about 1.3 L of air remains in the lungs; this is called the **residual volume** (**RV**). Lung capacities are sums of the individual lung volumes. The **vital capacity** (**VC**) is the maximum volume of air that can be moved in and out in a single breath. Therefore, VC = V_T + IRV + ERV. The average 20-year-old male with a height of 1.80 m has a VC of about 5.3 L. Vital capacity decreases and residual volume increases with age (1.5 ⇒ 3 L). The **total lung capacity** is the sum of VC and RV—normally 6 to 7 L. The **functional residual capacity** is the sum of ERV and RV (→ **A** and p. 114). The *inspiratory* capacity is the sum of V_T and IRV. All numerical values of these volumes apply under body temperature–pressure saturation (BTPS) conditions (see below).

Spirometry. These lung volumes and capacities (except FRC, RV) can be measured by routine spirometry. The *spirometer* (→ **A**) consists usually of a water-filled tank with a bell-shaped floating device. A tube connects the air space within the spirometer (→ **A**) with the airways of the test subject. A counterweight is placed on the bell. The position of the bell indicates how much air is in the spirometer and is calibrated in volume units (L_{ATPS}; see below). The bell on the spirometer rises when the test subject blows into the device (expiration), and falls during inspiration (→ **A**).

If the spirometer is equipped with a recording device (*spirograph*), it can be also used for graphic measurement of the total ventilation per unit time ($\dot{V}_E$; → pp. 106 and 118), compliance (→ p. 116), O_2 consumption ($\dot{V}O_2$), and in dynamic lung function tests (→ p. 118).

Range of normal variation. Lung volumes and capacities vary greatly according to age, height, physical constitution, sex, and degree of physical fitness. The range of normal variation of VC, for example, is 2.5 to 7 L. Empirical formulas were therefore developed to create normative values for better interpretation of lung function tests. For instance, the following formulas are used to calculate the range of normal values for VC in Caucasians:

Men: VC = 5.2 h – 0.022 a – 3.6 (± 0.58)

Women: VC = 5.2 h – 0.018 a – 4.36 (± 0.42),

where h = height (in meters) and a = age (in years); the standard deviation is given in parentheses. Because of the broad range of normal variation, patients with mild pulmonary disease may go undetected. Patients with lung disease should ideally be monitored by recording baseline values and observing *changes* over the course of time.

Conversion of respiratory volumes. The volume, V, of a gas (in L or m^3; 1 m^3 = 1000 L) can be obtained from the amount, M, of the gas (in mol), absolute temperature, T (in K), and total pressure, P (in Pa), using the *ideal gas equation*:

$$V = M \cdot R \cdot T/P, \qquad [5.2]$$

where P is barometric pressure (P_B) minus water partial pressure (P_{H_2O}; → p. 106) and R is the universal gas constant = 8.31 $J \cdot K^{-1} \cdot mol^{-1}$.

Volume conditions

STPD:	Standard temperature pressure dry (273 K, 101 kPa, P_{H_2O} = 0)
ATPS:	Ambient temperature pressure H_2O-saturated (T_{amb}, P_B, P_{H_2O} at T_{Amb})
BTPS:	Body temperature pressure-saturated (310 K, P_B, P_{H_2O} = 6.25 kPa)

It follows that:


$V_{STPD} = M \cdot R \cdot 273/101\,000$ [m^3]

$V_{ATPS} = M \cdot R \cdot T_{Amb}/(P_B - P_{H_2O})$ [m^3]

$V_{BTPS} = M \cdot R \cdot 310/(P_B - 6250)$ [m^3].

Conversion factors are derived from the respective quotients (M · R is a reducing factor). Example: V_{BTPS}/V_{STPD} = 1.17. If V_{ATPS} is measured by spirometry at room temperature (T_{Amb} = 20 °C; $P_{H_2O_{sat}}$ = 2.3 kPa) and P_B = 101 kPa, $V_{BTPS} \approx 1.1\ V_{ATPS}$ and $V_{STPD} \approx 0.9\ V_{ATPS}$.

A. Lung volumes and their measurement



The exchange of gases in the respiratory tract occurs in the alveoli. Only a portion of the tidal volume (V_T) reaches the alveoli; this is known as the **alveolar part** (**V_A**). The rest goes to dead space (not involved in gas exchange) and is therefore called **dead space** volume (**V_D**). The oral, nasal, and pharyngeal cavities plus the trachea and bronchi are jointly known as *physiological dead space* or *conducting zone of the airways*. The physiological dead space (ca. 0.15 L) is approximately equal to the *functional* dead space, which becomes larger than physiological dead space when the exchange of gases fails to take place in a portion of the alveoli (→ p. 120). The **functions of dead space** are to conduct incoming air to the alveoli and to purify (→ p. 110), humidify, and warm inspired ambient air. Dead space is also an element of the vocal organ (→ p. 370).

The **Bohr equation** (→ **A**) can be used to **estimate** the dead space.

Derivation: The expired tidal volume V_T is equal to the sum of its alveolar part V_A plus dead space V_D (→ **A, top**). Each of these three variables has a characteristic CO_2 fraction (→ p. 382): $F_{E_{CO_2}}$ in V_T, $F_{A_{CO_2}}$ in V_A, and $F_{I_{CO_2}}$ in V_D. $F_{I_{CO_2}}$ is extremely small and therefore negligible. The product of each of the three volumes and its corresponding CO_2 fraction gives the volume of CO_2 for each. The CO_2 volume in the expired air ($V_T \cdot F_{E_{CO_2}}$) equals the sum of the CO_2 volumes in its two components, i.e. in V_A and V_D (→ **A**).

Thus, V_T, $F_{E_{CO_2}}$ and $F_{A_{CO_2}}$ must be known to **determine the dead space**. V_T can be measured using a spirometer, and $F_{E_{CO_2}}$ and $F_{A_{CO_2}}$ can be measured using a Bunte glass burette or an infrared absorption spectrometer. $F_{A_{CO_2}}$ is present in the last expired portion of V_T—i.e., in *alveolar gas*. This value can be measured using a Rahn valve or similar device.

The **functional residual capacity** (FRC) is the amount of air remaining in the lungs at the end of normal quiet expiration, and the **residual volume** (RV) is the amount present after forced maximum expiration (→ p. 112). About 0.35 L of air (V_A) reaches the alveolar space with each breath during normal quiet respiration. Therefore, only about 12% of the 3 L total FRC is renewed at rest. The composition of gases in the alveolar space therefore remains relatively constant.


Measurement of FRC and RV cannot be performed by spirometry. This must be done using indirect techniques such as **helium dilution** (→ **B**). Helium (He) is a poorly soluble inert gas. The test subject is instructed to repeatedly inhale and exhale a known volume (V_{Sp}) of a helium-containing gas mixture (e.g., $F_{He_0} = 0.1$) out of and into a spirometer. The helium distributes evenly in the lungs (V_L) and spirometer (→ **B**) and is thereby diluted ($F_{He_x} < F_{He_0}$). Since the total helium volume does not change, the known initial helium volume ($V_{Sp} \cdot F_{He_0}$) is equal to the final helium volume ($V_{Sp} + V_L) \cdot F_{He_x}$. V_L can be determined once F_{He_x} in the spirometer has been measured at the end of the test (→ **B**). V_L will be equivalent to RV if the test was started after a forced expiration, and will be equivalent to FRC if the test was started after normal expiration, i.e. from the resting position of lung and chest. The helium dilution method measures gases in *ventilated* airways only.

Body plethysmography can also detect gases in encapsulated spaces (e.g., cysts) in the lung. The test subject is placed in an airtight chamber and instructed to breathe through a *pneumotachygraph* (instrument for recording the flow rate of respired air). At the same time, respiration-dependent changes in air pressure in the subject's mouth and in the chamber are continuously recorded. FRC and RV can be derived from these measurements.

Such measurements can also be used to determine **airway resistance**, **R_L**, which is defined as the *driving pressure gradient* between the alveoli and the atmosphere *divided by the air flow per unit time*. Airway resistance is very low under normal conditions, especially during inspiration when (a) the lungs become more expanded (*lateral traction* of the airways), and (b) the *transpulmonary pressure* (P_A-P_{pl}) *rises* (→ p. 108). P_A-P_{pl} represents the transmural pressure of the airways and widens them more and more as it increases. Airway resistance may become too high when the airway is narrowed by mucus—e.g., in chronic obstructive pulmonary disease, or when its smooth muscle contracts, e.g. in asthma (→ p.118).

The RV *fraction of the total lung capacity* (TLC) is clinically significant (→ p. 112). It normally is ≤ 0.25 and somewhat higher in old age. It can rise to > 0.55 when pathological enlargement of the alveoli has occurred (e.g. in *emphysema*). The RV/TLC fraction is therefore a rough measure of the severity of such diseases.

A. Measurement of dead space


Alveolar part of tidal volume V_A
Dead space volume V_D
Mixing
Tidal volume V_T
$F_{A_{CO_2}}$
$F_{I_{CO_2}}$
$F_{E_{CO_2}}$
Alveolar CO_2 volume + Dead space CO_2 volume = CO_2 volume in expired air
$V_A \cdot F_{A_{CO_2}} + V_D \cdot F_{I_{CO_2}} = V_T \cdot F_{E_{CO_2}}$
$V_A = V_T - V_D$ $F_{I_{CO_2}} = 0$ Insert values

Bohr equation


$$\text{Dead space } V_D = \frac{V_T (F_{A_{CO_2}} - F_{E_{CO_2}})}{F_{A_{CO_2}}}$$

Using normal values:

$$V_D = \frac{0.5\,(0.056 - 0.040)}{0.056}$$

Dead space V_D = 143 mL

B. Measurement of residual volume and functional residual capacity



Helium volume (in spirometer only) = Helium volumen (in lung and spirometer)

$V_{Sp} \cdot FHe_0 = (V_{Sp} + V_L) \cdot FHe_X$

$$V_L = V_{Sp} \cdot \frac{FHe_0 - FHe_X}{FHe_X}$$

V_{Sp} and FHe_0 are known
FHe_X: Measurement

Respiratory resting position (RRP) is the position to which the lung–chest system returns at the end of normal quiet expiration; this lung volume equals the functional residual capacity (FRC, → p. 114). Its value is set at zero ($V_{pulm} = 0$) in **A–C**. RRP (→ **A1**) is a stable central position characterized by the reciprocal cancellation of two passive forces: chest expansion force (CEF) and lung contraction force (LCF). As we breathe in and out, the lung–chest system makes excursions from RRP; thus, LCF > CEF during inspiration, and CEF > LCF during expiration. The difference between LCF and CEF, i.e. the net force (→ blue arrows in **A2, 3, 5, 6**), is equal to the **alveolar pressure** (P_A → p. 108) if the airway is closed (e.g., by turning a stopcock, as in **A1–3, 6**) after a known air volume has been inhaled ($V_{pulm} > 0$, → **A2**) from a spirometer or expelled into it ($V_{pulm} < 0$, → **A3**). (In the RRP, CEF = LCF, and $P_A = 0$). Therefore, the relationship between V_{pulm} and P_A in the lung–chest system can be determined as illustrated by the **static resting pressure–volume (PV) curve** (→ **blue curve** in **A–C**; see also p. 108) ("static" = measured while holding the breath; "resting" = with the respiratory muscles relaxed).

(Compression and expansion of V_{pulm} by a positive or negative P_A during measurement has to be taken into account; → **A**, dark-gray areas).

The **slope** of the static resting PV curve, $\Delta V_{pulm}/\Delta P_A$, represents the (static) **compliance** *of the lung–chest system* (→ **B**). The steepest part of the curve (range of greatest compliance; ca. 1 L/kPa in an adult) lies between RRP and V_{pulm} = 1 L. This is in the normal respiratory range. The curve loses its steepness, i.e. compliance decreases, in old age or in the presence of lung disease. As a result, greater effort is needed to breathe the same tidal volume.

The above statements apply to lung-and-chest compliance. It is also possible to calculate compliance for the *chest wall alone* ($\Delta V_A/\Delta P_{pl}$ = 2 L/kPa) or for the *lung alone* ($\Delta V_A/\Delta[P_A - P_{pl}]$ = 2 L/kPa) when the pleural pressure (P_{pl}) is known (→ p. 108).


PV relationships can also be plotted during maximum expiratory and inspiratory effort to determine the **peak expiratory** and **inspiratory pressures** (→ **A**, red and green curves). Only a very small pressure can be generated from a position of near-maximum expiration ($V_{pulm} \ll 0$; → **A7**) compared to a peak pressure of about 15 kPa (≈ 110 mmHg) at $V_{pulm} \gg 0$ (Valsalva's maneuver; → **A5**). Likewise, the greatest negative pressure (suction) (ca. – 10 kPa = 75 mmHg) can be generated from a position of maximum expiration (Müller's maneuver; → **A6**), but not from an inspiratory position (→ **A4**).

A **dynamic PV curve** is obtained *during* respiration (→ **C**). The result is a loop consisting of the opposing inspiratory (red) and expiratory (green) curves transected by the resting curve (blue) because airway flow resistance (R_L) must be overcome (mainly in the upper and middle airways) while inhaling in the one direction and exhaling in the other. The *driving pressure gradients (⊿P)* also oppose each other (inspiratory $P_A < 0$; expiratory $P_A > 0$; → p. 109 B). As in Ohm's law, $\Delta P = R_L \cdot$ respiratory flow rate ($\dot{V}$). Therefore, ΔP must increase if the bronchial tubes narrow and/or if the respiratory flow rate increases (→ **C**).


In **asthma**, the airway radius (r) decreases and a very high ΔP is needed for normal ventilation ($R_L \sim 1/r^4$!). During exspiration, a high ΔP decreases the *transpulmonary pressure* ($= P_A - P_{pl}$) and thereby squeezes the airways ($R_L \uparrow$). The high R_L results in a pressure decrease along the expiratory airway ($P_{airway} \downarrow$) until $P_{airway} - P_{pl} < 0$. At this point, the airway will collapse. This is called **dynamic airway compression**, which often results in a life-threatening vicious cycle: r↓ ➪ $\Delta P \uparrow$ ➪ r ↓↓ ➪ $\Delta P \uparrow\uparrow$ ….

Respiratory work. The colored areas within the loop ($A_{R_{insp}}$ and $A_{R_{exp}}$; → **C**) represent the inspiratory and expiratory PV work (→ p. 380) exerted to overcome flow resistance. The cross-hatched area (→ **C**) is the work required to overcome the intrinsic elastic force of the lungs and chest (A_{elast}). *Inspiratory work* is defined as $A_{R_{insp}} + A_{elast}$. The inspiratory muscles (→ p. 108) must overcome the elastic force, whereas the same elastic force provides the (passive) driving force for expiration at rest (sign reverses for A_{elast}). Thus, *expiratory work* is $A_{R_{exp}} - A_{elast}$. Expiration can also require muscle energy if $A_{R_{exp}}$ becomes larger than A_{elast}—e.g., during forced respiration or if R_L is elevated.

A. Pressure–volume relationships of the lung–chest system




B. Static compliance



$$\frac{\Delta V_{pulm}}{\Delta P_A} = \text{Compliance of lung–chest system}$$

C. Dynamic pressure–volume curve



Respiratory work	Inspiration:	$AR_{insp} + A_{elast}$
	Expiration:	$AR_{exp} - A_{elast}$

Surface tension is the main factor that determines the *compliance* of the lung-chest system (→ p. 116) and develops at gas-liquid interfaces or, in the case of the lungs, on the *gas exchange surface of the alveoli* (ca. 100 m^2).

The effectiveness of these forces can be demonstrated by filling an isolated and completely collapsed lung with (a) air or (b) liquid. In example (a), the lung exerts a much higher resistance, especially at the beginning of the filling phase. This represents the **opening pressure**, which raises the alveolar pressure (P_A) to about 2 kPa or 15 mmHg when the total lung capacity is reached (→ p. 113 A). In example (b), the resistance and therefore P_A is only one-fourth as large. Accordingly, the larger pressure requirement in example (a) is required to overcome surface tension.

If a *gas bubble* with radius r is surrounded by liquid, the surface tension γ ($N \cdot m^{-1}$) raises the pressure inside the bubble relative to the outside pressure (transmural pressure $\Delta P > 0$). According *to Laplace's law* (cf. p. 190):

$$\Delta P = 2\gamma/r \text{ (Pa)}. \qquad [5.3]$$

Since γ normally remains constant for the respective liquid (e.g., plasma: 10^{-3} $N \cdot m^{-1}$), ΔP becomes larger and larger as r decreases.

Soap bubble model. If a flat soap bubble is positioned on the opening of a cylinder, r will be relatively large (→ **A1**) and ΔP small. (Since two air-liquid interfaces have to be considered in this case, Eq. 5.3 yields $\Delta P = 4\gamma/r$). For the bubble volume to expand, r must initially decrease and ΔP must increase (→ **A2**). Hence, a relatively high "opening pressure" is required. As the bubble further expands, r increases again (→ **A3**) and the pressure requirement/volume expansion ratio decreases. The alveoli work in a similar fashion. This model demonstrates that, in the case of two alveoli connected with each other (→ **A4**), the smaller one (ΔP_2 high) would normally become even smaller while the larger one (ΔP_1 low) becomes larger due to pressure equalization.

Surfactant (***surf***ace-***act***ive ***a***ge***nt***) lining the inner alveolar surface prevents this problem by lowering γ in smaller alveoli more potently than in larger alveoli. Surfactant is a mixture of proteins and phospholipids (chiefly dipalmitoyl lecithin) secreted by alveolar type II cells.

Respiratory distress syndrome of the newborn, a serious pulmonary gas exchange disorder, is caused by failure of the immature lung to produce sufficient quantities of surfactant. Lung damage related to O_2 toxicity (→ p. 136) is also partly due to oxidative destruction of surfactant, leading to reduced compliance. This can ultimately result in alveolar collapse (*atelectasis*) and pulmonary edema.

Dynamic Lung Function Tests


The **maximum breathing capacity** (MBC) is the greatest volume of gas that can be breathed (for 10 s) by voluntarily increasing the tidal volume and respiratory rate (→ **B**). The MBC normally ranges from 120 to 170 L/min. This capacity can be useful for monitoring diseases affecting the respiratory muscles, e.g., myasthenia gravis.

The **forced expiratory volume** (FEV or Tiffeneau test) is the maximum volume of gas that can be expelled from the lungs. In clinical medicine, FEV in the first second (FEV_1) is routinely measured. When its absolute value is related to the *forced vital capacity* (FVC), the *relative* FEV_1 (normally > 0.7) is obtained. (FVC is the maximum volume of gas that can be expelled from the lungs as quickly and as forcefully as possible from a position of full inspiration; → **C**). It is often slightly lower than the vital capacity VC (→ p. 112). **Maximum expiratory flow**, which is measured using a pneumotachygraph during FVC measurement, is around 10 L/s.


Dynamic lung function tests are useful for distinguishing *restrictive lung disease* (RLD) from *obstructive lung disease* (OLD). RLD is characterized by a functional reduction of lung volume, as in pulmonary edema, pneumonia and impaired lung inflation due to spinal curvature, whereas OLD is characterized by physical narrowing of the airways, as in asthma, bronchitis, emphysema, and vocal cord paralysis (→ **C2**).

As with VC (→ p. 112), empirical formulas are also used to standardize FVC for age, height and sex.


A. Surface tension (soap bubble model)




B. Maximum breathing capacity (MBC)



C. Forced expired volume in first second (FEV_1)



1 Measurement



2 Clinical significance

Alveolar ventilation. Only the alveolar part (V_A) of the tidal volume (V_T) reaches the alveoli. The rest stays in the dead space (V_D). It follows that $V_A = V_T - V_D$ (L) (→ p. 114). Multiplying these volumes by the *respiratory rate* (**f** in min^{-1}) results in the respective ventilation, i.e., $\dot{V}_A$, $\dot{V}_E$ (or $\dot{V}_T$), and $\dot{V}_D$. Thus, $\dot{V}_A = \dot{V}_E - \dot{V}_D$ ($L \cdot min^{-1}$). Since V_D is anatomically determined, $\dot{V}_D$ ($= V_D \cdot f$) rises with f. If, at a given total ventilation ($\dot{V}_E = V_T \cdot f$), the breathing becomes more frequent (f ↑) yet more shallow (V_T ↓), $\dot{V}_A$ will decrease because $\dot{V}_D$ increases.

Example: At a $\dot{V}_E$ of 8 $L \cdot min^{-1}$, a V_D of 0.15 L and a normal respiratory rate f of 16 min^{-1} $\dot{V}_A = 5.6\ L \cdot min^{-1}$ or 70% of $\dot{V}_E$. When f is doubled and V_T drops to one-half, $\dot{V}_A$ drops to 3.2 $L \cdot min^{-1}$ or 40% of V_T, although $\dot{V}_E$ (8 $L \cdot min^{-1}$) remains unchanged.

Alveolar gas exchange can therefore decrease due to flat breathing and panting (e.g., due to a painful rib fracture) or due to pathologic (→ **C2**, **3**) or artificial enlargement of V_D (→ p. 134).

O_2 consumption ($\dot{V}_{O_2}$) is calculated as the *difference between* the *inspired* O_2 volume/time ($= \dot{V}_E \cdot F_{I O_2}$, and the *expired* O_2 volume/time ($= \dot{V}_E \cdot F_{E O_2}$. Therefore, $\dot{V}_{O_2} = \dot{V}_E$ **$(F_{I O_2} - F_{E O_2})$**. At rest, $\dot{V}_{O_2} \approx 8\ (0.21 - 0.17) = 0.32\ L \cdot min^{-1}$.

The **eliminated CO_2 volume** ($\dot{V}_{CO_2}$) is calculated as $\dot{V}_E \cdot F_{E CO_2}$ ($\approx 0.26\ L \cdot min^{-1}$ at rest; $F_{I CO_2} \approx 0$). $\dot{V}_{O_2}$ and $\dot{V}_{CO_2}$ increase about tenfold during strenuous physical work (→ p. 74). The $\dot{V}_{CO_2}$ to $\dot{V}_{O_2}$ ratio is called the **respiratory quotient** (**RQ**), which depends on a person's nutritional state. RQ ranges from 0.7 to 1.0 (→ p. 230).


The **exchange of gases** between the alveoli and the blood occurs by **diffusion**, as described by Fick's law of diffusion (→ Eq. 1.7, p. 22,). The driving "force" for this diffusion is provided by the *partial pressure differences* between alveolar space and erythrocytes in pulmonary capillary blood (→ **A**). The mean alveolar partial pressure of O_2 ($P_{A O_2}$) is about 13.3 kPa (100 mmHg) and that of CO_2 ($P_{A CO_2}$) is about 5.3 kPa (40 mmHg). The mean partial pressures in the "venous" blood of the pulmonary artery are approx. 5.3 kPa (40 mmHg) for O_2 ($P\bar{v}_{O_2}$) and approx. 6.1 kPa (46 mmHg) for CO_2 ($P\bar{v}_{CO_2}$). Hence, the mean **partial pressure difference** between alveolus and capillary is about 8 kPa (60 mmHg) for O_2 and about 0.8 kPa (6 mmHg) for CO_2, although regional variation occurs (→ p. 122). $P_{A O_2}$ will rise when $P_{A CO_2}$ falls (e.g., due to hyperventilation) and vice versa (→ alveolar gas equation, p. 136).

O_2 diffuses about 1–2 μm from alveolus to bloodstream (**diffusion distance**). Under normal resting conditions, the blood in the pulmonary capillary is in contact with the alveolus for about 0.75 s. This **contact time** (→ **A**) is long enough for the blood to equilibrate with the partial pressure of alveolar gases. The capillary blood is then *arterialized*. P_{O_2} and P_{CO_2} in **a**rterialized blood (Pa_{O_2} and Pa_{CO_2}) are about the same as the corresponding mean alveolar pressures ($P_{A O_2}$ and $P_{A CO_2}$). However, venous blood enters the arterialized blood through arteriovenous shunts in the lung and from bronchial and thebesian veins (→ **B**). This *extra-alveolar shunt* as well as *ventilation–perfusion inequality* (→ p. 122) make the Pa_{O_2} decrease from 13.3 kPa (after alveolar passage) to about 12.0 kPa (90 mmHg) in the aorta (Pa_{CO_2} increases slightly; → **A** and p. 107).


The small pressure difference of about 0.8 kPa is large enough for alveolar CO_2 exchange, since Krogh's diffusion coefficient K for CO_2 ($K_{CO_2} \approx 2.5 \cdot 10^{-16}\ m^2 \cdot s^{-1} \cdot Pa^{-1}$ in tissue) is 23 times larger than that for O_2 (→ p. 22). Thus, CO_2 diffuses much more rapidly than O_2. During physical work (high cardiac output), the contact time falls to a third of the resting value. If diffusion is impaired (see below), alveolar equilibration of O_2 partial pressure is less likely to occur during physical exercise than at rest.

Impairment of alveolar gas exchange can occur for several reasons: (a) when the blood flow rate along the alveolar capillaries decreases (e.g., due to *pulmonary infarction*; → **B2**), (b) if a *diffusion barrier exists* (e.g., due to a thickened alveolar wall, as in pulmonary edema; → **B3**), and (c) *if alveolar ventilation is reduced* (e.g., due to bronchial obstruction; → **B4**). Cases **B2** and **B3** lead to an *increase in functional dead space* (→ p. 114); cases **B3** and **B4** lead to inadequate arterialization of the blood (*alveolar shunt*, i.e. non-arterialized blood mixing towards arterial blood). Gradual impairments of type **B2** and **B4** can occur even in healthy individuals (→ p. 122).

A. Alveolar gas exchange



B. Impairment of alveolar gas exchange



Neglecting the slight amount of blood that reaches the lungs via the bronchial arteries, the mean **pulmonary perfusion ($\dot{Q}$)**, or blood flow to the lungs, is equal to the cardiac output (CO = 5–6 L/min). The **pulmonary arterial pressure** is about 25 mmHg in systole and 8 mmHg in diastole, with a mean ($\bar{P}$) of about 15 mmHg. $\bar{P}$ decreases to about 12 mmHg (P_{precap}) in the precapillary region (up to the origin of the pulmonary capillaries) and about 8 mmHg in the postcapillary region ($P_{postcap}$). These values apply to the areas of the lung located at the level of the pulmonary valve.

Uneven distribution of blood flow within the lung (→ A). Due to the additive effect of hydrostatic pressure (up to 12 mmHg), P_{precap} increases in blood vessels below the pulmonary valves (near the base of the lung) when the chest is positioned upright. Near the apex of the lung, P_{precap} decreases in vessels above the pulmonary valve (→ **A,** zone 1). Under these conditions, P_{precap} can even drop to subatmospheric levels, and the mean alveolar pressure (P_A) is atmospheric and can therefore cause extensive capillary compression ($P_A > P_{precap} > P_{postcap}$; → **A**). $\dot{Q}$ per unit of lung volume is therefore very small. In the central parts of the lung (→ **A**, zone 2), luminal narrowing of capillaries can occur at their venous end, at least temporarily ($P_{precap} > P_A > P_{postcap}$), while the area near the base of the lung (→ **A**, zone 3) is continuously supplied with blood ($P_{precap} > P_{postcap} > P_A$). $\dot{Q}$ per unit of lung volume therefore decreases from the apex of the lung to the base (→ **A, B**, red line).

Uneven distribution of alveolar ventilation. Alveolar ventilation ($\dot{V}_A$) per unit of lung volume also increases from the apex to the base of the lungs due to the effects of gravity (→ **B** , orange line), although not as much as $\dot{Q}$. Therefore, the **$\dot{V}_A/\dot{Q}$ ratio** decreases from the apex to the base of the lung (→ **B**, green curve and top scale).


$\dot{V}_A/\dot{Q}$ imbalance. The mean $\dot{V}_A/\dot{Q}$ for the entire lung is 0.93 (→ **C2**). This value is calculated from the mean alveolar ventilation $\dot{V}_A$ (ca. 5.6 L/min) and total perfusion $\dot{Q}$ (ca. 6 L/min), which is equal to the cardiac output (CO). Under extreme conditions in which one part of the lung is not ventilated at all, $\dot{V}_A/\dot{Q} = 0$ (→ **C1**). In the other extreme in which blood flow is absent ($\dot{V}_A/\dot{Q}$ approaches infinity; → **C3**), fresh air conditions will prevail in the alveoli (functional dead space; → p. 120). Therefore, $\dot{V}_A/\dot{Q}$ can vary tremendously—theoretically, from 0 to ∞. In this range, the $P_{A_{O_2}}$ will fluctuate between mixed venous $P\bar{v}_{O_2}$ and $P_{I_{O_2}}$ of (humidified) fresh air (→ **D**). In a healthy upright lung, $\dot{V}_A/\dot{Q}$ decreases greatly (from 3.3 to 0.63) from apex to base at rest (→ **B**, green line); $P_{A_{O_2}}$ ($P_{A_{CO_2}}$) is therefore 17.6 (3.7) kPa in the "hyperventilated" lung apex, 13.3 (5.3) kPa in the normally ventilated central zone, and 11.9 (5.6) kPa in the "hypoventilated" lung base. These changes are less pronounced during physical exercise because $\dot{Q}$ also increases in zone 1 due to the corresponding increase in P_{precap}.

$\dot{V}_A/\dot{Q}$ imbalance *decreases the efficiency of the lungs for gas exchange*. In spite of the high $P_{A_{O_2}}$ at the apex of the lung (ca. 17.6 kPa; → **D**, right panel) and the fairly normal mean $P_{A_{O_2}}$ value, the relatively small $\dot{Q}$ fraction of zone 1 contributes little to the total $\dot{Q}$ of the pulmonary veins. In this case, $Pa_{O_2} < P_{A_{O_2}}$ and an *alveolar–arterial* O_2 *difference* (AaD_{O_2}) exists (normally about 1.3 kPa). When a total arteriovenous shunt is present ($\dot{V}_A/\dot{Q} = 0$), even oxygen treatment will not help the patient, because it would not reach the pulmonary capillary bed (→ **C1**).


Hypoxic vasoconstriction regulates alveolar perfusion and prevents the development of extreme $\dot{V}_A/\dot{Q}$ ratios. When the $P_{A_{O_2}}$ decreases sharply, receptors in the alveoli emit local signals that trigger constriction of the supplying blood vessels. This throttles shunts in poorly ventilated or non-ventilated regions of the lung, thereby routing larger quantities of blood for gas exchange to more productive regions.

$\dot{V}_A/\dot{Q}$ imbalance can cause severe complications in many lung diseases. In *shock lung*, for example, shunts can comprise 50% of $\dot{Q}$. Life-threatening lung failure can quickly develop if a concomitant pulmonary edema, alveolar diffusion barrier, or surfactant disorder exists (→ p. 118).


A. Regional blood flow in the lung (upright chest position)




B. Regional perfusion and ventilation of lung



C. Effect of ventilation-perfusion ratio ($\dot{V}_A/\dot{Q}$) on partial pressures in lung



D. Regional parameters of lung function



(A, B, C, D after West et al.)

Carbon dioxide (CO_2) is an end-product of energy metabolism (→ p. 230). CO_2 produced by cells of the body undergoes **physical dissolution** and diffuses into adjacent blood capillaries. A small portion of CO_2 in the blood remains dissolved, while the rest is **chemically bound** in form of HCO_3^- and carbamate residues of hemoglobin (→ **A** , lower panel, blue arrows; → arteriovenous CO_2 difference given in the table). Circulating CO_2-loaded blood reaches the pulmonary capillaries via the right heart. CO_2 entering the pulmonary capillaries is released from the compounds (→ **A**, red arrows), diffuses into the alveoli, and is expired into the atmosphere (→ **A** and p. 106).

The enzyme **carbonic anhydrase** (carbonate dehydratase) catalyzes the reaction

$$HCO_3^- + H^+ \rightleftharpoons CO_2 + H_2O$$

in erythrocytes (→ **A5, 7**). Because it accelerates the establishment of equilibrium, the short contact time (< 1 s) between red blood cells and alveolus or peripheral tissue is sufficient for the transformation $CO_2 \rightleftharpoons HCO_3^-$.

CO_2 diffusing from the **peripheral cells** (→ **A**, bottom panel: "*Tissue*") increases P_{CO_2} (approx. 5.3 kPa = 40 mmHg in arterial blood) to a mean venous P_{CO_2} of about 6.3 kPa = 47 mmHg. It also increases the concentration of CO_2 dissolved in plasma. However, the major portion of the CO_2 diffuses into red blood cells, thereby increasing their content of dissolved CO_2. CO_2 (+ H_2O) within the cells is converted to **HCO_3^-** (→ **A5, 2**) and **hemoglobin carbamate** (→ **A3**). The HCO_3^- concentration in erythrocytes therefore becomes higher than in plasma. As a result, about three-quarters of the HCO_3^- ions exit the erythrocytes by way of an HCO_3^-/Cl^- antiporter. This **anion exchange** is also called *Hamburger shift* (→ **A4**).

H^+ ions are liberated when CO_2 in red cells circulating in the periphery is converted to HCO_3^- and hemoglobin (Hb) carbamate.

Bicarbonate formation:

$$CO_2 + H_2O \rightleftharpoons HCO_3^- + \mathbf{H^+}, \qquad [5.4]$$

Hemoglobin carbamate formation:

$$Hb\text{–}NH_2 + CO_2 \rightleftharpoons Hb\text{–}NH\text{–}COO^- + \mathbf{H^+}. \qquad [5.5]$$


Hemoglobin (Hb) is a key **buffer for H^+** ions in the red cells (→ **A6**; see also p. 140, "Non-bicarbonate buffers"). Since the removal of H^+ ions in reactions 5.4 and 5.5 prevents the rapid establishment of equilibrium, large quantities of CO_2 can be incorporated in HCO_3^- and Hb carbamate. Deoxygenated hemoglobin (Hb) can take up more H^+ ions than oxygenated hemoglobin (Oxy-Hb) because Hb is a weaker acid (→ **A**). This promotes CO_2 uptake in the peripheral circulation (*Haldane effect*) because of the simultaneous liberation of O_2 from erythrocytes, i.e. deoxygenation of Oxy-Hb to Hb.

In the **pulmonary capillaries**, these reactions proceed in the opposite direction (→ **A**, top panel, red and black arrows). Since the P_{CO_2} in alveoli is lower than in venous blood, CO_2 diffuses into the alveoli, and reactions 5.4 and 5.5 proceed to the left. CO_2 is released from HCO_3^- and Hb carbamate whereby H^+ ions (released from Hb) are bound in both reactions (→ **A7, A8**), and the direction of HCO_3^-/Cl^- exchange reverses (→ **A9**). Reoxygenation of Hb to Oxy-Hb in the lung promotes this process by increasing the supply of H^+ ions (*Haldane effect*).

CO_2 distribution in blood (mmol/L blood, 1 mmol = 22.26 mL CO_2)

	Dissolved CO_2	HCO_3^-	Carbamate	Total
Arterial blood:				
Plasma*	0.7	13.2	0.1	14.0
Erythrocytes**	0.5	6.5	1.1	8.1
Blood	1.2	19.7	1.2	22.1
Mixed venous blood:				
Plasma*	0.8	14.3	ca. 0.1	15.2
Erythrocytes**	0.6	7.2	1.4	9.2
Blood	1.4	21.5	1.5	24.4
Arteriovenous CO_2 difference in blood	0.2	1.8	0.3	2.3
Percentage of total arteriovenous difference	9%	78%	13%	100%

* Approx 0.55 L plasma/L blood; ** ca. 0.45 L erythrocytes/L blood


A. CO_2 transport in blood
Expelled from lung
CO_2
Alveolus
Oxy-Hb
NH_2
8
Hb
NH— COO^-
CO_2
O_2
H^+
Hb
H
H
Oxy-Hb
In lung
H_2O
H^+
7
CO_2
Carbonic anhydrase
HCO_3^-
9
HCO_3^-
Cl^-
Erythrocyte
In plasma
In periphery
5
Carbonic anhydrase
CO_2
HCO_3^-
HCO_3^-
Bicarbonate formation
2
4
Cl^-
H_2O
H^+
6
Hb
H
H
Oxy-Hb
Hemoglobin as buffer
O_2
H^+
Hemoglobin carbamate formation
Oxy-Hb
Hb
3
NH_2
NH— COO^-
Hemoglobin carbamate
CO_2
CO_2
1
Tissue
Metabolism

The **total carbon dioxide** concentration (= chemically bound "CO_2" + dissolved CO_2) of mixed venous blood is about 24–25 mmol/L; that of arterial blood is roughly 22–23 mmol/L. Nearly 90% of this is present as HCO_3^- (→ **A**, right panel, and table on p. 124). The partial pressure of CO_2 (P_{CO_2}) is the chief factor that determines the CO_2 content of blood. The **CO_2 dissociation curve** illustrates how the total CO_2 concentration depends on P_{CO_2} (→ **A**).

The concentration of **dissolved CO_2**, **[CO_2]**, in plasma is directly proportional to the P_{CO_2} in plasma and can be calculated as follows:

$$[CO_2] = \alpha_{CO_2} \cdot P_{CO_2} \text{ (mmol/L plasma or mL/L plasma)}, \quad [5.6]$$

where α_{CO_2} is the (Bunsen) *solubility coefficient* for CO_2. At 37 °C,

$\alpha_{CO_2} = 0.225 \text{ mmol} \cdot L^{-1} \cdot kPa^{-1}$,

After converting the amount of CO_2 into volume CO_2 (mL = mmol · 22.26), this yields

$\alpha_{CO_2} = 5 \text{ mL} \cdot L^{-1} \cdot kPa^{-1}$.

The *curve for dissolved* CO_2 is therefore linear (→ **A**, green line).

Since the buffering and carbamate formation capacities of hemoglobin are limited, the relation between **bound CO_2** and P_{CO_2} is curvilinear. The *dissociation curve for total* CO_2 is calculated from the sum of dissolved and bound CO_2 (→ **A**, red and violet lines).

CO_2 binding with hemoglobin depends on the degree of **oxygen saturation** (S_{O_2}) of hemoglobin. Blood completely saturated with O_2 is not able to bind as much CO_2 as O_2-free blood at equal P_{CO_2} levels (→ **A**, red and violet lines). When venous blood in the lungs is loaded with O_2, the buffer capacity of hemoglobin and, consequently, the levels of chemical CO_2 binding decrease due to the Haldane effect (→ p. 124). Venous blood is never completely void of O_2, but is always O_2-saturated to a certain degree, depending on the degree of O_2 extraction (→ p. 130) of the organ in question. The S_{O_2} of mixed venous blood is about 0.75. The CO_2 dissociation curve for S_{O_2} = 0.75 therefore lies between those for S_{O_2} = 0.00 and 1.00 (→ **A**, dotted line). In arterial blood, $P_{CO_2} \approx 5.33$ kPa and $S_{O_2} \approx 0.97$ (→ **A**, point a). In mixed venous blood, $P_{CO_2} \approx 6.27$ kPa and $S_{O_2} \approx 0.75$ (→ **A**, point ▽). The normal range of CO_2 dissociation is determined by connecting these two points by a line called *"physiologic CO_2 dissociation curve."*


The concentration ratio of HCO_3^- to dissolved CO_2 in plasma and red blood cells differs (about 20 : 1 and 12 : 1, respectively). This reflects the difference in the pH of plasma (7.4) and erythrocytes (ca. 7.2) (→ p. 138ff.).

CO_2 in Cerebrospinal Fluid


Unlike HCO_3^- and H^+, CO_2 can cross the blood-cerebrospinal fluid (CSF) barrier with relative ease (→ **B1** and p. 312). The P_{CO_2} in CSF therefore adapts quickly to **acute changes in the P_{CO_2} in blood**. CO_2-related (respiratory) pH changes in the body can be buffered by *non-bicarbonate buffers* (NBBs) only (→ p. 144). Since the concentration of non-bicarbonate buffers in CSF is very low, an acute rise in P_{CO_2} (respiratory acidosis; → p. 144) leads to a relatively sharp decrease in the pH of CSF (→ **B1**, pH ↓↓). This decrease is registered by central chemosensors (or chemoreceptors) that adjust respiratory activity accordingly (→ p. 132). (In this book, sensory receptors are called sensors in order to distinguish them from hormone and transmitter receptors.)

The concentration of non-bicarbonate buffers in blood (hemoglobin, plasma proteins) is high. When the CO_2 concentration increases, the liberated H^+ ions are therefore effectively buffered in the blood. The actual HCO_3^- concentration in blood then rises relatively slowly, to ultimately become higher than in the CSF. As a result, HCO_3^- diffuses (relatively slowly) into the CSF (→ **B2**), resulting in a renewed increase in the pH of the CSF because the HCO_3^-/CO_2 ratio increases (→ p. 140). This, in turn, leads to a reduction in respiratory activity (via central chemosensors), a process enhanced by renal compensation, i.e., a pH increase through HCO_3^- retention (→ p. 144). By this mechanism, the body ultimately adapts to **chronic elevation in P_{CO_2}**—i.e., a chronically elevated P_{CO_2} will no longer represent a respiratory drive (cf. p. 132).

A. CO_2 dissociation curve



B. Effect of CO_2 on pH of CSF



Hemoglobin (Hb) is the O_2-*carrying protein* of red blood cells (RBCs) (mol. mass: 64 500 Da). Hb is also involved in *CO_2 transport* and is an important blood *pH buffer* (→ pp. 124 and 138ff.). Hb is a tetramer with 4 subunits (adults: 98%: $2\alpha + 2\beta$ = **HbA**; 2% $2\alpha + 2\delta$ = HbA_2), each with its own heme group. **Heme** consists of porphyrin and **Fe(II)**. Each of the four Fe(II) atoms (each linked with one histidine residue of Hb) binds reversibly with an O_2 molecule. This is referred to as **oxygenation** (not oxidation) of Hb to oxyhemoglobin (Oxy-Hb). The amount of O_2 which combines with Hb depends on the partial pressure of O_2 (P_{O_2}): **oxygen dissociation curve** (→ **A**, red line). The curve has a sigmoid shape, because initially bound O_2 molecules change the conformation of the Hb tetramer (positive cooperativity) and thereby increase *hemoglobin-O_2 affinity*.

When fully saturated with O_2, 1 mol of tetrameric Hb combines with 4 mol O_2, i.e., 64 500 g of Hb combine with 4×22.4 L of O_2. Thus, 1 g Hb can theoretically transport 1.39 mL O_2, or 1.35 mL in vivo (Hüfner number). The total Hb concentration of the blood ($[Hb]_{total}$) is a mean 150 g/L (→ p. 88), corresponding to a maximum O_2 concentration of 9.1 mmol/L or an O_2 fraction of 0.203 L O_2/L blood. This **oxygen-carrying capacity** is a function of $[Hb]_{total}$ (→ **A**, yellow and purple curves as compared to the red curve).


The O_2 content of blood is virtually equivalent to the amount of O_2 bound by Hb since only 1.4% of O_2 in blood is dissolved at a P_{O_2} of 13.3 kPa (→ **A**, orange line). The solubility coefficient (α_{O_2}), which is $10\,\mu mol \cdot [L\ of\ plasma]^{-1} \cdot kPa^{-1}$, is 22 times smaller than α_{CO_2} (→ p. 126).

Oxygen saturation (S_{O_2}) is the fraction of Oxy-Hb relative to $[Hb]_{total}$, or the ratio of *actual* O_2 *concentration*/ O_2-*carrying capacity*. At normal P_{O_2} in arterial blood (e.g., Pa_{O_2} = 12.6 kPa or 95 mmHg), S_{O_2} will reach a *saturation plateau* at approx. 0.97, while S_{O_2} will still amount to 0.73 in mixed venous blood ($P\bar{v}_{O_2}$ = 5.33 kPa or 40 mmHg). The venous S_{O_2} values in different organs can, however, vary greatly (→ p. 130).


O_2 dissociation is independent of total Hb if plotted as a function of S_{O_2} (→ **B**). Changes in O_2 affinity to Hb can then be easily identified as **shifting of the O_2 dissociation curve**. A shift to the right signifies an affinity decrease, and a shift to the left signifies an affinity increase, resulting in flattening and steepening, respectively, of the initial part of the curve. **Shifts to the left** are caused by increases in pH (with or without a P_{CO_2} decrease) and/or decreases in P_{CO_2}, temperature and 2,3-bisphosphoglycerate (BPG; normally 1 mol/mol Hb tetramer). **Shifts to the right** occur due to decreases in pH and/or increases in P_{CO_2}, temperature and 2,3-BPG (→ **B**). The **half-saturation pressure** ($P_{0.5}$ or P_{50}) of O_2 (→ **B**, dotted lines) is the P_{O_2} at which S_{O_2} is 0.5 or 50%. The $P_{0.5}$, which is normally 3.6 kPa or 27 mmHg, is a measure of shifting to the right ($P_{0.5}$ ↑) or left ($P_{0.5}$ ↓). Displacement of the O_2 dissociation curve due to changes in pH and P_{CO_2} is called the **Bohr effect**. A shift to the right means that, in the periphery (pH ↓, P_{CO_2} ↑), larger quantities of O_2 can be taken up from the blood without decreasing the P_{O_2}, which is the driving force for O_2 diffusion (→ **B**, broken lines). A higher affinity for O_2 is then re-established in the pulmonary capillaries (pH ↑, P_{CO_2} ↓). A shift to the left is useful when the $P_{A_{O_2}}$ is decreased (e.g., in altitude hypoxia), a situation where arterial Pa_{O_2} lies to the left of the S_{O_2} plateau.

Myoglobin is an Fe(II)-containing muscle protein that serves as a short-term storage molecule for O_2 (→ p. 72). As it is monomeric (no positive cooperativity), its O_2 dissociation curve at low P_{O_2} is much steeper than that of HbA (→ **C**). Since the O_2 dissociation curve of **fetal Hb** ($2\alpha + 2\gamma$ = HbF) is also steeper, S_{O_2} values of 45 to 70% can be reached in the fetal umbilical vein despite the low P_{O_2} (3–4 kPa or 22–30 mmHg) of maternal placental blood. This is sufficient, because the fetal $[Hb]_{total}$ is 180 g/L. The **carbon monoxide (CO) dissociation curve** is extremely steep. Therefore, even tiny amounts of CO in the respiratory air will dissociate O_2 from Hb. This can result in *carbon monoxide poisoning* (→ **C**). **Methemoglobin**, Met-Hb (normally 1% of Hb), is formed from Hb by oxidation of Fe(II) to Fe(III) either spontaneously or via exogenous oxidants. Met-Hb cannot combine with O_2 (→ **C**). *Methemoglobin reductase* reduces Fe(III) of Met-Hb back to Fe(II); deficiencies of this enzyme can cause methemoglobinemia, resulting in neonatal anoxia.


A. O_2 dissociation curve: O_2-carrying capacity



B. O_2 dissociation curve: O_2 saturation



C. O_2 and carbon monoxide (CO) dissociation curves



O_2 **diffuses** from peripheral blood to adjacent tissues and CO_2 in the opposite direction (→ pp. 20ff. and 106). Since CO_2 diffuses much faster (→ p. 120), O_2 diffusion is the limiting factor. Sufficient O_2 delivery is ensured by a dense capillary network with a gas *exchange area* of about 1000 m^2. The *diffusion distance* (→ R in **A**) is only 10–25 μm. The *driving force* for diffusion is the difference in partial pressures of oxygen (ΔP_{O_2}) in capillary blood and mitochondria, where the P_{O_2} must not fall below 0.1 kPa ≈ 1 mmHg. Since P_{O_2} decreases with distance parallel and perpendicular to the course of capillaries, the O_2 supply to cells at the venous end far away from the capillaries (large R) is lowest, as shown using *Krogh's cylinder model* (→ **A1**). Since these cells are also the first to be affected by oxygen deficiency (*hypoxia*), this is sometimes called the "lethal corner" (→ **A2**).

Using *Fick's principle* (→ p. 106), **oxygen consumption** of a given organ, $\dot{V}_{O_2}$ (in L/min), is calculated as the difference between the ***a***rterial supply ($\dot{Q} \cdot [O_2]_a$) and non-utilized ***v***enous O_2 volume/time ($\dot{Q} \cdot [O_2]_v$), where $\dot{Q}$ is rate of blood flow in the organ (L/min) and $[O_2]$ is the oxygen fraction (L O_2/L blood):

$$\dot{V}_{O_2} = \dot{Q}\,([O_2]_a - [O_2]_v) \qquad [5.7]$$

To meet **increased O_2 demands**, $\dot{Q}$ *can therefore be increased* by **vasodilatation** in the organ in question and/or by **raising the oxygen extraction (E_{O_2})**. E_{O_2} describes the O_2 consumption in the organ (= $\dot{Q}$ ([O_2]a – [O_2]v); see Eq. 5.7) relative to the arterial O_2 supply ($\dot{Q} \cdot [O_2]a$). Since $\dot{Q}$ can be simplified,

$$E_{O_2} = ([O_2]_a - [O_2]_v)/\,[O_2]_a \qquad [5.8]$$

E_{O_2} varies according to the type and function of the organ under resting conditions: skin 0.04 (4%), kidney 0.07; brain, liver and resting skeletal muscle ca. 0.3, myocardium 0.6. The E_{O_2} of muscle during strenuous exercise can rise to 0.9. Skeletal muscle can therefore meet **increased O_2 demands** by raising the E_{O_2} (0.3 ⇒ 0.9), whereas in myocardial tissue, and in the three types of hypoxia listed below (→ **B 1–3**) only a limited compensation is possible (→ p. 212).

Hypoxia. An abnormally reduced O_2 supply to tissue is classified as follows:

1. *Hypoxic hypoxia* (→ **A2, B1**): an insufficient O_2 supply reaches the blood due, for example, to decreased atmospheric P_{O_2} at high altitudes (→ p. 136), reduced alveolar ventilation, or impaired alveolar gas exchange.

2. *Anemic hypoxia* (→ **B2**): reduced O_2-carrying capacity of blood (→ p. 128), e.g., due to decreased total Hb in iron deficiency anemia (→ p. 90).

3. *Stagnant* or *ischemic hypoxia* (→ **B3**): insufficient O_2 reaches the tissue due to reduced blood flow ($\dot{Q}\downarrow$). The cause can be systemic (e.g., heart failure) or local (e.g., obstructed artery). The reduction of blood flow must be compensated for by a rise in ($[O_2]_a - [O_2]_v$) to maintain an adequate O_2 delivery (see Eq. 5.7). This is not the case in hypoxic and anemic hypoxia. The influx and efflux of substrates and metabolites is also impaired in stagnant hypoxia. Anaerobic glycolysis (→ p. 72) is therefore of little help.


4. Hypoxia can also occur when the *diffusion distance* is increased due to tissue thickening without a corresponding increase in the number of blood capillaries. This results in an insufficient blood supply to cells lying outside the O_2 supply radius (R) of the Krogh cylinder (→ **A**).

5. *Histotoxic* or *cytotoxic hypoxia* occurs due to impaired utilization of O_2 by the tissues despite a sufficient supply of O_2 in the mitochondria, as observed in *cyanide poisoning*. Cyanide (HCN) blocks oxidative cellular metabolism by inhibiting cytochromoxidase.


Brain tissue is extremely susceptible to hypoxia, which can cause critical damage since dead nerve cells usually cannot be replaced. **Anoxia**, or a total lack of oxygen, can occur due to heart or respiratory failure. The cerebral survival time is thus the limiting factor for overall survival. Unconsciousness occurs after only 15 s of anoxia, and irreparable brain damage occurs if anoxia lasts for more than 3 min or so.

Cyanosis is a bluish discoloration of the skin, lips, nails, etc. due to excessive arterial deoxyhemoglobin (> 50 g/L). Cyanosis is a sign of hypoxia in individuals with normal or only moderately reduced total Hb levels. When total Hb is extremely low, O_2 deficiencies (anemic hypoxia) can be life-threatening, even in the absence of cyanosis. Cyanosis can occur in absence of significant hypoxia when the Hb level is elevated.

A. O_2 supply: Krogh's cylinder model



B. Hypoxia



The respiratory muscles (→ p. 108) are innervated by nerve fibers extending from the cervical and thoracic medulla (C4 –C8 and T1 –T7). The most important **control centers** are located in the *medulla oblongata* and cervical *medulla* (C1–C2), where interactive *inspiratory and expiratory neurons* exist on different levels (→ **A1,** red and green areas). The network of these spatially separate neuron groups form a **rhythm generator (respiratory "center")** where respiratory rhythm originates (→ **A1**). The neuron groups are triggered alternately, resulting in rhythmic inspiration and expiration. They are activated in a tonic (non-rhythm-dependent) manner by the *formatio reticularis*, which receives signals from *respiratory stimulants* in the periphery and higher centers of the brain.

Respiratory sensors or receptors are involved in respiratory control circuits (→ p. 4). *Central* and *peripheral chemosensors* on the medulla oblongata and in the arterial circulation continuously register gas partial pressures in cerebrospinal fluid (CSF) and blood, respectively, and *mechanosensors* in the chest wall respond to stretch of intercostal muscles to modulate the depth of breathing (→ **A2**). *Pulmonary stretch sensors* in the tracheal and bronchial walls respond to marked increases in lung volume, thereby limiting the depth of respiration in humans (*Hering–Breuer reflex*). *Muscle spindles* (→ p. 320) in the respiratory muscles also respond to changes in airway resistance in the lung and chest wall.

Chemical respiratory stimulants. The extent of involuntary ventilation is mainly determined by the partial pressures of O_2 and CO_2 and the pH of blood and CSF. Chemosensors respond to any changes in these variables. **Peripheral chemosensors** in the glomera aortica and carotica (→ **A3**) register changes in the arterial P_{O_2}. If it falls, they stimulate an increase in ventilation via the vagus (X) and glossopharyngeal nerves (IX) until the arterial P_{O_2} rises again. This occurs, for example, at high altitudes (→ p. 136). The impulse frequency of the sensors increases sharply when the P_{O_2} drops below 13 kPa or 97 mmHg (**peripheral ventilatory drive**). These changes are even stronger when P_{CO_2} and/or the H^+ concentration in blood also increase.

The central chemosensors, in particular, in the medulla react to CO_2 and H^+ increases (= pH decrease) in the CSF (→ **A4** and p. 126). Ventilation is then increased until P_{CO_2} and the H^+ concentration in blood and CSF decrease to normal values. This mostly **central respiratory drive** is very effective in responding to acute changes. An increase in arterial P_{CO_2} from, say, 5 to 9 kPa increases the total ventilation $\dot{V}_E$ by a factor of ten, as shown in the *CO_2 response curve* (→ **A6**).


When a **chronic rise in P_{CO_2}** occurs, the previously increased central respiratory drive decreases (→ p. 126). If O_2 supplied by artificial respiration tricks the peripheral chemosensors into believing that there is adequate ventilation, the residual peripheral respiratory drive will also be in jeopardy.

During **physical work** (→ **A5**), the total ventilation increases due to (a) co-innervation of the respiratory centers (by collaterals of cortical efferent motor fibers) and (b) through impulses transmitted by proprioceptive fibers from the muscles.

Non-feedback sensors and stimulants also play an important role in modulating the basic rhythm of respiration. They include

- *Irritant sensors* in the bronchial mucosa, which quickly respond to lung volume decreases by increasing the respiratory rate (deflation reflex or Head's reflex), and to dust particles or irritating gases by triggering the cough reflex.
- *J sensors* of free C fiber endings on alveolar and bronchial walls; these are stimulated in pulmonary edema, triggering symptoms such as apnea and lowering the blood pressure.
- *Higher central nervous centers* such as the cortex, limbic system, hypothalamus or pons. They are involved in the expression of emotions like fear, pain and joy; in reflexes such as sneezing, coughing, yawning and swallowing; and in voluntary control of respiration while speaking, singing, etc.
- *Pressosensors* (→ p. 216), which are responsible for increasing respiration when the blood pressure decreases.
- *Heat and cold sensors* in the skin and thermoregulatory center. Increases (fever) and decreases in body temperature lead to increased respiration.
- *Certain hormones* also help to regulate respiration. Progesterone, for example, increases respiration in the second half of the menstrual cycle and during pregnancy.

A. Respiratory control and stimulation



Diving creates a problem for respiration due to the lack of normal ambient air supply and to higher the outside pressures exerted on the body. The total pressure on the body underwater is equal to the water pressure (98 kPa or 735 mmHg for each 10 m of water) plus the atmospheric pressure at the water surface.

A **snorkel** can be used when diving just below the water surface (→ **A**), but it increases dead space (→ pp. 114 and 120), making it harder to breathe. The additional pressure load from the water on chest and abdomen must also be overcome with each breath.

The depth at which a snorkel can be used is limited 1) because an intolerable increase in dead space or airway resistance will occur when using an extremely long or narrow snorkel, respectively, and 2) because the water pressure in deeper waters will prevent inhalation. The maximum suction produced on inspiration is about 11 kPa, equivalent to 112 cm H_2O (peak inspiratory pressure, → p. 116). Inspiration therefore is no longer possible at aquatic depths of about 112 cm or more due to the risk of hypoxic anoxia (→ **A**).

Scuba diving equipment (scuba = ***s***elf-***c***ontained ***u***nderwater ***b***reathing ***a***pparatus) is needed to breathe at lower depths (up to about 70 m). The inspiratory air pressure (from pressurized air cylinders) is automatically adjusted to the water pressure, thereby permitting the diver to breathe with normal effort.

However, the additional water pressure increases the partial pressure of **nitrogen** P_{N_2} (→ **B**), resulting in higher concentrations of dissolved N_2 in the blood. The pressure at a depth of 60 meters is about seven times higher than at the water surface. The pressure decreases as the diver returns to the water surface, but the additional N_2 does not remain dissolved. The diver must therefore ascend slowly, in gradual stages so that the excess N_2 can return to and be expelled from the lungs. Resurfacing too quickly would lead to the development of N_2 bubbles in tissue (pain!) and blood, where they can cause obstruction and embolism of small blood vessels. This is called **decompression sickness** or **caisson disease** (→ **B**). Euphoria (N_2 narcosis?), also called *rapture of the deep*, can occur when diving at depths of over 40 to 60 meters. Oxygen toxicity can occur at depths of 75 m or more (→ p. 136).

When **diving unassisted**, i.e., simply by holding one's breath, P_{CO_2} in the blood rises, since the CO_2 produced by the body is not exhaled. Once a certain P_{CO_2} has been reached, chemosensors (→ p. 132) trigger a sensation of shortness of breath, signaling that it is time to resurface.


To delay the time to resurface, it is possible to lower the P_{CO_2} in blood by **hyperventilating before diving**. Experienced divers use this trick to stay under water longer. The course of alveolar partial pressures over time and the direction of alveolar gas exchange while diving (depth: 10 m; duration 40 s) is shown in **C**: Hyperventilating before a dive reduces the P_{CO_2} (solid green line) and slightly increases the P_{O_2} (red line) in the alveoli (and in blood). Diving at a depth of 10 m doubles the pressure on the chest and abdominal wall. As a result, the partial pressures of gases in the alveoli (P_{CO_2}, P_{O_2}, P_{N_2}) increase sharply. Increased quantities of O_2 and CO_2 therefore diffuse from the alveoli into the blood. Once the P_{CO_2} in blood rises to a certain level, the body signals that it is time to resurface. If the diver resurfaces at this time, the P_{O_2} in the alveoli and blood drops rapidly (O_2 consumption + pressure decrease) and the alveolar O_2 exchange stops.

Back at the water surface, the P_{O_2} reaches a level that is just tolerable. If the diver excessively hyperventilates before the dive, the signal to resurface will come too late, and the P_{O_2} will drop to zero (**anoxia**) before the person reaches the water surface, which can result in unconsciousness and drowning (→ **C**, dotted lines).

Barotrauma. The increased pressure associated with diving leads to compression of air-filled organs, such as the lung and middle ear. Their gas volumes are compressed to $^1/_2$ their normal size at water depths of 10 m, and to $^1/_4$ at depths of 30 m.

The missing volume of air in the lungs is automatically replaced by the scuba, but not that of the middle ear. The middle ear and throat are connected by the Eustachian tube, which is open only at certain times (e.g., when swallowing) or not at all (e.g., in pharyngitis). If volume loss in the ear is not compensated for during a dive, the increasing water pressure in the outer auditory canal distends the eardrum, causing pain or even eardrum rupture. As a result, cold water can enter the middle ear and impair the organ of equilibrium, leading to nausea, dizziness, and disorientation. This can be prevented by pressing air from the lungs into the middle ear by holding the nose and blowing with the mouth closed.

The air in air-filled organs expand when the diver ascends to the water surface. Resurfacing too quickly, i.e., without expelling air at regular intervals, can lead to complications such as lung laceration and pneumothorax (→ p. 110) as well as potentially fatal hemorrhage and air embolism.


A. Snorkeling
Normal
Too deep
<40 cm
Depth >100 cm
Excessive dead space or resistance
Anoxia
Water pressure prevents inhalation
B. Diving with equipment
Gas embolism
N2
N2 bubbles
Blood
Baro-trauma
Resurfacing too rapidly
N2
Depth ca. 70 m
C. Diving unassisted
0
Depth (m)
(Water pressure 98 kPa at depth of 10 m)
10
0
20
40
Diving time (s)
Alveolar partial pressures
Signal to resurface
Hyper-ventilation
PO2 (kPa)
19.3
15
6.6
6.6
PCO2 (kPa)
148
Too late!
13.3
5.2
3.5
4.2
Anoxia
PN2 (kPa)
76.5
76.5
76.5
0.0
Alveolar gas exchange
Lung
Blood
O2
N2
CO2
Water pressure
O2
N2
CO2
O2
N2
CO2
(after Hong et al.)

At sea level, the average barometric pressure (P_B) ≈ 101 kPa (760 mmHg), the O_2 fraction in ambient air (F_{IO_2}) is 0.209, and the inspiratory partial pressure of O_2 (P_{IO_2}) ≈ 21 kPa (→ p. 106). However, P_B decreases with increasing altitude (h, in km):

$$P_B \text{ (at h)} = P_B \text{ (at sea level)} \cdot e^{-0.127 \cdot h} \quad [5.9]$$

This results in a drop in P_{IO_2} (→ **A**, column 1), alveolar P_{O_2} (P_{AO_2}) and arterial P_{O_2} (Pa_{O_2}). The P_{AO_2} at sea level is about 13 kPa (→ **A**, column 2). P_{AO_2} is an important measure of oxygen supply. If the P_{AO_2} falls below a critical level (ca. 4.7 kPa = 35 mmHg), hypoxia (→ p. 130) and impairment of cerebral function will occur. The *critical* P_{AO_2} would be reached at heights of about 4000 m above sea level during normal ventilation (→ **A**, dotted line in column 2). However, the low Pa_{O_2} triggers chemosensors (→ p. 132) that stimulate an increase in total ventilation ($\dot{V}_E$); this is called **O_2 deficiency ventilation** (→ **A**, column 4). As a result, larger volumes of CO_2 are exhaled, and the P_{ACO_2} and Pa_{CO_2} decrease (see below). As described by the *alveolar gas equation*,

$$P_{AO_2} = P_{IO_2} - \frac{P_{ACO_2}}{RQ} \quad [5.10]$$

where RQ is the respiratory quotient (→ pp. 120 and 230), any fall in P_{ACO_2} will lead to a rise in the P_{AO_2}. O_2 deficiency ventilation stops the P_{AO_2} from becoming critical up to altitudes of about 7000 m (*altitude gain*, → **A**).

The maximal increase in ventilation (≈ 3 × resting rate) during acute O_2 deficiency is relatively small compared to the increase (≈ 10 times the resting rate) during strenuous physical exercise at normal altitudes (→ p. 74, C3) because increased ventilation at high altitudes reduces the Pa_{CO_2} (= **hyperventilation**, → p. 108), resulting in the development of **respiratory alkalosis** (→ p. 144). Central chemosensors (→ p. 132) then emit signals to lower the respiratory drive, thereby counteracting the signals from O_2 chemosensors to increase the respiratory drive. As the mountain climber adapts, respiratory alkalosis is compensated for by increased renal excretion of HCO_3^- (→ p. 144). This helps return the pH of the blood toward normal, and the O_2 deficiency-related increase in respiratory drive can now prevail. Stimulation of O_2 chemosensors at high altitudes also leads to an increase in the heart rate and a corresponding *increase in cardiac output*, thereby increasing the O_2 supply to the tissues.

High altitude also stimulates **erythropoiesis** (→ p. 88ff.). Prolonged exposure to high altitudes increases the hematocrit levels, although this is limited by the corresponding rise in blood viscosity (→ pp. 92, 188).

Breathing oxygen from pressurized O_2 cylinders is necessary for survival at altitudes above 7000 m, where P_{IO_2} is almost as high as the barometric pressure P_B (→ **A**, column 3). The critical P_{AO_2} level now occurs at an altitude of about 12 km with normal ventilation, and at about 14 km with increased ventilation. Modern long-distance planes fly slightly below this altitude to ensure that the passengers can survive with an oxygen mask in case the cabin pressure drops unexpectedly.


Survival at altitudes above 14 km is not possible without pressurized chambers or pressurized suits like those used in space travel. Otherwise, the body fluids would begin to boil at altitudes of 20 km or so (→ **A**), where P_B is lower than water vapor pressure at body temperature (37 °C).

Oxygen Toxicity

Hyperoxia occurs when P_{IO_2} is above normal (> 22 kPa or 165 mmHg) due to an increased O_2 fraction (*oxygen therapy*) or to an overall pressure increase with a normal O_2 fraction (e.g. in diving, → p. 134). The degree of O_2 toxicity depends on the P_{IO_2} level (critical: ca. 40 kPa or 300 mmHg) and duration of hyperoxia. Lung dysfunction (→ p. 118, *surfactant deficiency*) occurs when a P_{IO_2} of about 70 kPa (525 mmHg) persists for several days or 200 kPa (1500 mmHg) for 3–6 hours. Lung dysfunction initially manifests as *coughing* and *painful breathing*. *Seizures* and *unconsciousness* occur at P_{IO_2} levels above 220 kPa (1650 mmHg), e.g., when diving at a depth of about 100 m using pressurized air.

Newborns will go blind if exposed to P_{IO2} levels much greater than 40 kPa (300 mmHg) for long periods of time (e.g., in an incubator), because the vitreous body then opacifies.

A. Respiration at high altitudes (without acclimatization)



The **pH** indicates the hydrogen ion activity or the "effective" H^+ concentration of a solution (H^+ activity = $f_H \cdot [H^+]$, where square brackets mean concentration; → p. 384), where

$$pH = -\log (f_H \cdot [\mathbf{H^+}]) \quad [6.1]$$

In healthy individuals, the **pH of the blood** is usually a mean pH **7.4** (see p. 142 for normal range), corresponding to H^+ activity of about 40 nmol/L. The maintenance of a constant pH is important for human survival. Large deviations from the norm can have detrimental effects on metabolism, membrane permeability, and electrolyte distribution. Blood pH values below 7.0 and above 7.8 are not compatible with life.

Various **pH buffers** are responsible for maintaining the body at a constant pH (→ p. 385). One important buffer for blood and other body fluids is the **bicarbonate/carbon dioxide (HCO_3^-/CO_2) buffer system**:

$$CO_2 + H_2O \rightleftharpoons HCO_3^- + H^+. \quad [6.2]$$

The *pK_a value* (→ p. 378f.) determines the prevailing *concentration ratio of the buffer base and buffer acid* ($[HCO_3^-]$ and $[CO_2]$, respectively in Eq. 6.2) at a given pH (*Henderson–Hasselbalch equation*; → **A**).

The primary **function of the HCO_3^-/CO_2 buffer system** in blood is to buffer H^+ ions. However, this system is especially important because the concentrations of the two buffer components can be modified largely independent of each other: $[CO_2]$ by respiration and $[HCO_3^-]$ by the liver and kidney (→ **A**; see also p. 176). It is therefore classified as an **open buffer system** (→ p. 140).

Hemoglobin in red blood cells (320 g Hb/L erythrocytes! → MCHC, p. 89 C), the second most important buffer in blood, is a **non-bicarbonate buffer**.

$$HbH \rightleftharpoons Hb^- + H^+ \quad [6.3]$$

$$Oxy\text{-}HbH \rightleftharpoons Oxy\text{-}Hb^- + H^+ \quad [6.4]$$

The relatively acidic oxyhemoglobin anion ($Oxy\text{-}Hb^-$) combines with fewer H^+ ions than deoxygenated Hb^-, which is less acidic (see also p. 124). H^+ ions are therefore liberated upon oxygenation of Hb to Oxy-Hb in the lung. Reaction 6.2 therefore proceeds to the left, thereby promoting the release of CO_2 from its bound forms (→ p. 124). This, in turn, increases the pulmonary elimination of CO_2.


Other non-bicarbonate buffers of the blood include *plasma proteins* and inorganic *phosphate* ($H_2PO_4^- \rightleftharpoons H^+ + HPO_4^{2-}$) as well as organic phosphates (in red blood cells). Intracellular organic and inorganic substances in various tissues also function as buffers.

The **buffer capacity** is a measure of the buffering power of a buffer system ($mol \cdot L^{-1} \cdot [\Delta pH]^{-1}$). It corresponds to the number of added H^+ or OH^- ions per unit volume that change the pH by one unit. The buffer capacity therefore corresponds to the slope of the titration curve for a given buffer (→ p. 386, B). The buffer capacity is dependent on (a) the buffer concentration and (b) the pH. The farther the pH is from the pK_a of a buffer system, the smaller the buffer capacity (→ p. 386). The buffer capacity of the blood is about $75\ mmol \cdot L^{-1} \cdot (\Delta pH)^{-1}$ at pH 7.4 and constant P_{CO_2}. Since the buffer capacity is dependent on the prevailing P_{CO_2}, the **buffer base concentration** of the blood (normally about 48 mEq/L) is normally used as the measure of buffering power of the blood in clinical medicine (→ pp. 142 and 146). The buffer base concentration is the sum of the concentrations of all buffer components that accept hydrogen ions, i.e., HCO_3^-, Hb^-, $Oxy\text{-}Hb^-$, diphosphoglycerate anions, plasma protein anions, HPO_4^{2-}, etc.

Changes in the pH of the blood are chiefly due to changes in the following factors (→ **A** and p. 142ff.):

- *H^+ ions*: Direct uptake in foodstuffs (e.g., vinegar) or by metabolism, or removal from the blood (e.g., by the kidney; → p. 176 ff.).
- *OH^- ions*: Uptake in foodstuffs containing (basic) salts of weak acids, especially in primarily vegetarian diet.
- *CO_2*: Its concentration, $[CO_2]$, can change due to alterations in metabolic production or pulmonary elimination of CO_2. A drop in $[CO_2]$ leads to a rise in pH and vice versa (→ **A**: $[CO_2]$ is the denominator in the equation).
- HCO_3^-: It can be eliminated directly from the blood by the kidney or gut (in diarrhea) (→ pp. 178, 142). A rise or fall in $[HCO_3^-]$ will lead to a corresponding rise or fall in pH (→ **A**: $[HCO_3^-]$ is the numerator in the equation).

A. Factors that affect the blood pH



The pH of any buffer system is determined by the concentration *ratio* of the buffer pairs and the pK_a of the system (→ p. 384). The pH of a bicarbonate solution is the concentration ratio of bicarbonate and dissolved carbon dioxide (**$[HCO_3^-]/[CO_2]$**), as defined in the Henderson-Hasselbalch equation (→ **A1**). Given $[HCO_3^-]$ = 24 mmol/L and $[CO_2]$ = 1.2 mmol/l, $[HCO_3^-]/[CO_2]$ = 24/1.2 = 20. Given log20 = 1.3 and pK_a = 6.1, a pH of 7.4 is derived when these values are set into the equation (→ **A2**). If $[HCO_3^-]$ drops to 10 and $[CO_2]$ decreases to 0.5 mmol/L, the *ratio* of the two variables will not change, and the pH will remain constant.

When added to a buffered solution, H^+ ions combine with the buffer base (HCO_3^- in this case), resulting in the formation of buffer acid ($HCO_3^- + H^+ \rightarrow CO_2 + H_2O$). In a **closed system** from which CO_2 cannot escape (→ **A3**), the amount of buffer acid formed (CO_2) equals the amount of buffer base consumed (HCO_3^-). The inverse holds true for the addition of hydroxide ions ($OH^- + CO_2 \rightarrow HCO_3^-$). After **addition of** 2 mmol/L of **H^+**, the aforementioned baseline ratio $[HCO_3^-]/[CO_2]$ of 24/1.2 (→ **A2**) changes to 22/3.2, making the pH fall to 6.93 (→ **A3**). Thus, the buffer capacity of the HCO_3^-/CO_2 buffer at pH 7.4 is very low in a *closed system*, for which the pK_a of 6.1 is too far from the target pH of 7.4 (→ pp. 138, 386 ff).

If, however, the additionally produced CO_2 is eliminated from the system (**open system**; → **A4**), only the $[HCO_3^-]$ will change when the same amount of **H^+ is added** (2 mmol/L). The corresponding decrease in the $[HCO_3^-]/[CO_2]$ ratio (22/1.2) and pH (7.36) is much less than in a closed system. In the body, bicarbonate buffering occurs in an open system in which the partial pressure (P_{CO_2}) and hence the concentration of carbon dioxide in plasma ($[CO_2] = \alpha \cdot P_{CO_2}$; → p. 126) are regulated by respiration (→ **B**). The lungs normally eliminate as much CO_2 as produced by metabolism (15 000–20 000 mmol/day), while the alveolar P_{CO_2} remains constant (→ p. 120ff.). Since the plasma P_{CO_2} adapts to the alveolar P_{CO_2} during each respiratory cycle, the arterial P_{CO_2} (Pa_{CO_2}) also remains constant. An increased supply of H^+ in the periphery leads to an increase in the P_{CO_2} of venous blood ($H^+ + HCO_3^- \rightarrow CO_2 + H_2O$) (→ **B1**). The lungs eliminate the additional CO_2 so quickly that the arterial P_{CO_2} remains practically unchanged despite the addition of H^+ (open system!).


The following example demonstrates the quantitatively small impact of increased **pulmonary CO_2 elimination**. A two-fold increase in the amount of H^+ ions produced within the body on a given day (normally 60 mmol/day) will result in the added production of 60 mmol more of CO_2 per day (disregarding non-bicarbonate buffers). This corresponds to only about 0.3% of the normal daily CO_2 elimination rate.

An increased supply of OH^- ions in the periphery has basically similar effects. Since $OH^- + CO_2 \rightarrow HCO_3^-$, $[HCO_3^-]$ increases and the venous P_{CO_2} becomes smaller than normal. Because the rate of CO_2 elimination is also reduced, the arterial P_{CO_2} also does not change in the illustrated example (→ **B2**).

At a pH of 7.4, the open HCO_3^-/CO_2 buffer system makes up about two-thirds of the buffer capacity of the blood when the P_{CO_2} remains constant at 5.33 kPa (→ p. 138). Mainly intracellular non-bicarbonate buffers provide the remaining buffer capacity.

Since **non-bicarbonate buffers** (NBBs) function in *closed systems*, their total concentration ([NBB base] + [NBB acid]) remains constant, even after buffering. The total concentration changes in response to changes in the hemoglobin concentration, however, since hemoglobin is the main constituent of NBBs (→ pp. 138, 146). NBBs supplement the HCO_3^-/CO_2 buffer in non-respiratory (metabolic) acid–base disturbances (→ p. 142), but are the *only* effective buffers in respiratory acid–base disturbances (→ p. 144).


A. Bicarbonate buffers in closed and open systems



Closed system: pH 6.93

Open system: pH 7.36

B. Bicarbonate buffers in blood (open system)



The main objective of acid–base regulation is to keep the pH of blood, and thus of the body, constant. The normal ranges for parameters relevant to acid–base homeostasis, as measured in plasma (arterialized capillary blood) are listed in the table (see table on p. 124 for erythrocyte P_{CO_2} and $[HCO_3^-]$ values).

Normal range of acid–base parameters in plasma

	Women	Men
$[H^+]$ (nmol/L)	39.8 ± 1.4	40.7 ± 1.4
pH	7.40 ± 0.015	7.39 ± 0.015
P_{CO_2} (kPa)	5.07 ± 0.3	5.47 ± 0.3
(mmHg)	38.9 ± 2.3	41.0 ± 2.3
$[HCO_3^-]$ (mmol/L)	24 ± 2.5	24 ± 2.5

Acid–base homeostasis exists when the following balances are maintained:

1. (H^+ addition + production) – (HCO_3^- addition + production) = (H^+ excretion) – (HCO_3^- excretion) ≈ 60 mmol/day (diet-dependent).
2. (CO_2 production) = (CO_2 excretion) ≈ 15 000–20 000 mmol/day.

H^+ production (HCl, H_2SO_4, lactic acid, H_3PO_4, etc.) and adequate renal H^+ excretion (→ p. 176 ff.) are the main factors that influence the first balance. A vegetarian diet can lead to a considerable addition of HCO_3^- (metabolism: $OH^- + CO_2 \rightarrow HCO_3^-$; → p. 138). HCO_3^- is excreted in the urine to compensate for the added supply (the urine of vegetarians therefore tends to be alkaline).

Acid–base disturbances. *Alkalosis* occurs when the pH of the blood rises above the normal range (see table), and *acidosis* occurs when it falls below the lower limits of normal. *Respiratory* acid–base disturbances occur due to primary changes in P_{CO_2} (→ p. 144), whereas non-*respiratory (metabolic)* disturbances occur due to a primary change in $[HCO_3^-]$. Acid–base disturbances can be partially or almost completely compensated.


Nonrespiratory (Metabolic) Acid–Base Disturbances

Nonrespiratory acidosis is most commonly caused by (1) *renal failure* or isolated renal tubular H^+ secretion defect resulting in inability to eliminate normal quantities of H^+ ions (*renal acidosis*); (2) *hyperkalemia* (→ p. 182); (3) increased β-hydroxybutyric acid and acetoacetic acid production (*diabetes mellitus, starvation*); (4) increased anaerobic conversion of glucose to lactic acid (→ $lactate^- + H^+$), e.g., due to *strenuous physical work* (→ p. 74) or hypoxia; (5) increased metabolic production of HCl and H_2SO_4 in individuals with a *high intake of dietary proteins*; and (6) *loss of* HCO_3^- through renal excretion (proximal renal tubular acidosis, use of carbonic anhydrase inhibitors) or *diarrhea*.

Buffering (→ **A1**) of excess hydrogen ions occurs in the first stage of non-respiratory acidosis (every HCO_3^- lost results in an H^+ gained). Two-thirds and one-third of the buffering is achieved by HCO_3^- and non-bicarbonate buffer bases (NBB^-), respectively, and the CO_2 arising from HCO_3^- buffering is eliminated from the body by the lungs (open system; → p. 140). The standard bicarbonate concentration $[HCO_3^-]_{St}$, the actual bicarbonate concentration $[HCO_3^-]_{Act}$ and the buffer base concentration [BB] *decrease* (negative base excess; → p. 146).

Respiratory compensation of non-respiratory acidosis (→ **A2**) occurs in the second stage. The total ventilation rises in response to the reduced pH levels (via central chemosensors), leading to a decrease in the alveolar and arterial P_{CO_2} (hyperventilation; → **A2a**). This not only helps to return the $[HCO_3^-]/[CO_2]$ ratio towards normal (20:1), but also converts NBB-H back to NBB^- (due to the increasing pH) (→ **A2b**). The latter process also requires HCO_3^- and, thus, further compensatory pulmonary elimination of CO_2 (→ **A2c**). If the cause of acidosis persists, respiratory compensation will eventually become insufficient, and increased renal excretion of H^+ ions will occur (→ p. 176 ff.), provided that the acidosis is not of renal origin (see above, cause 1).

Nonrespiratory (metabolic) alkalosis is caused by (1) the administration of bases (e.g., *HCO_3^- infusion*); (2) increased breakdown of *organic anions* (e.g., $lactate^-$, α-ketoglutarate^{2-}); (3) loss of H^+ ions due to *vomiting* (→ p. 240) or *hypokalemia;* and (4) *volume depletion*. **Buffering** in metabolic alkalosis is similar to that of non-respiratory acidosis (rise in $[HCO_3^-]_{St}$, positive base excess). Nonetheless, the capacity for **respiratory compensa-** ▶


A. Metabolic acidosis
Bicarbonate buffer
Non-bicarbonate buffer (NBB)
HCO3−
CO2
8.0
7.4
7.0
NBB−
NBB-H
7.4
Normal: pH 7.4
Addition of H+
H+
CO2
H+
1 Buffering
HCO3− + H+ → CO2 + H2O
NBB− + H+ → NBB–H
Buffering by HCO3−
Buffering by NBB−
Non-respiratory (metabolic) acidosis: pH ↓
Stimulation of chemosensors
Total ventilation increases
Increased pulmonary elimination of CO2
CO2
2 Respiratory compensation
a
pH rises
b
H+
NBB− is regenerated
CO2
Additional HCO3− consumption
c
HCO3− + H+ → CO2 + H2O
Respiratory compensation of acidosis is achieved: pH ↑
But: [HCO3−]act und PCO2 are decreased
Increased renal excretion of H+ and NH4+
HCO3− replenished

tion through hypoventilation is very limited because of the resulting O_2 deficit.

Respiratory Acid–Base Disturbances


Respiratory alkalosis (→ **B**) occurs when the lungs eliminate more CO_2 than is produced by metabolism (*hyperventilation*), resulting in a decrease in plasma P_{CO_2} (hypocapnia). Inversely, respiratory acidosis occurs (→ **B**) when less CO_2 is eliminated than produced (*hypoventilation*), resulting in an increase in plasma P_{CO_2} (hypercapnia). Whereas bicarbonate and non-bicarbonate buffer bases (NBB^-) jointly buffer the pH decrease in non-respiratory acidosis (→ p. 142), the two buffer systems behave very differently in respiratory alkalosis (→ **B1**). In the latter case, the HCO_3^-/CO_2 system is not effective because the change in P_{CO_2} is the primary *cause*, not the result of respiratory alkalosis.

Respiratory acidosis can occur as the result of lung tissue damage (e.g., tuberculosis), impairment of alveolar gas exchange (e.g., pulmonary edema), paralysis of respiratory muscles (e.g., polio), insufficient respiratory drive (e.g., narcotic overdose), reduced chest motility (e.g., extreme spinal curvature), and many other conditions. The resulting increase in plasma CO_2 concentration ($[CO_2] = \alpha \cdot P_{CO_2}$) is followed by increased HCO_3^- and H^+ production (→ **B1**, left panel). The H^+ ions are buffered by NBB bases ($NBB^- + H^+ \rightarrow$ NBB-H; → **B1**, right panel) while $[HCO_3^-]_{Act}$ increases. Unlike non-respiratory acidosis, $[HCO_3^-]_{St}$ remains unchanged (at least initially since it is defined for normal P_{CO_2}; → p. 146) and [BB] remains unchanged because the *[NBB^-] decrease equals the $[HCO_3^-]_{Act}$ increase*. Since the percentage increase in $[HCO_3^-]_{Act}$ is much lower than the rise in $[CO_2]$, the $[HCO_3^-]/[CO_2]$ ratio and pH are lower than normal (acidosis).

If the increased P_{CO_2} persists, **renal compensation** (→ **B2**) of the respiratory disturbance will occur. The kidneys begin to excrete increased quantities of H^+ in form of titratable acidity (→ p. 176 ff.) and, after a latency period of 1 to 2 days, of NH_4^+ as well. Each NH_4^+ ion excreted results in the sparing of one HCO_3^- ion in the liver, and each H^+ ion excreted results in the tubular cellular release of one HCO_3^- ion into the blood (→ p. 176 ff.). This process continues until the pH has been reasonably normalized despite the P_{CO_2} increase. A portion of the HCO_3^- is used to buffer the H^+ ions liberated during the reaction $NBB\text{-}H \rightarrow NBB^- + H^+$ (→ **B2, right** panel). Because of the relatively long latency for renal compensation, the drop in pH is more pronounced in acute respiratory acidosis than in chronic respiratory acidosis. In the chronic form, $[HCO_3^-]_{Act}$ can rise by about 1 mmol per 1.34 kPa (10 mmHg) increase in P_{CO_2}.

Respiratory alkalosis is usually *caused* by hyperventilation due to anxiety or high altitude (oxygen deficit ventilation; → p. 136), resulting in a fall in plasma P_{CO_2}. This leads to a slight decrease in $[HCO_3^-]_{Act}$ since a small portion of the HCO_3^- is converted to CO_2 ($H^+ + HCO_3^- \rightarrow CO_2 + H_2O$); the HCO_3^- required for this reaction is supplied by H^+ ions from NBB's (**buffering**: $NBB\text{-}H \rightarrow NBB^- + H^+$). This is also the reason for the additional drop in $[HCO_3^-]_{Act}$ when respiratory compensation of non-respiratory acidosis occurs (→ p. 143 **A**, **bottom** panel, and p. 146). Further reduction of $[HCO_3^-]_{Act}$ is required for adequate pH normalization (compensation). This is achieved through reduced renal tubular secretion of H^+. As a consequence, increased renal excretion of HCO_3^- will occur (renal compensation).

In acute respiratory acidosis or alkalosis, CO_2 diffuses more rapidly than HCO_3^- and H^+ from the blood into the cerebrospinal fluid (CSF). The low NBB concentrations there causes relatively strong fluctuations in the pH of the CSF (→ p. 126), providing an adequate stimulus for central chemosensors (→ p. 132).


B. Respiratory acidosis
Bicarbonate buffer
Non-bicarbonate buffer (NBB)
HCO3−
CO2
NBB−
NBB-H
8.0
7.5
7.0
normal: pH 7.4
Decreased pulmonary elimination of CO2
CO2
HCO3− + H+ ← CO2 + H2O
H+
1
Buffering
NBB− + H+ → NBB-H
Buffering by NBB− only
Respiratory acidosis: pH ↓
2HCO3− + 2NH4+ → Urea
Liver
H2O
CO2
H+ + OH−
Kidney
HCO3−
2
Renal compensation
Increased excretion
NH4+
H+
Increased production (kidney) and sparing (liver)
HCO3−
CO2
Increased pulmonary elimination of CO2
HCO3−
HCO3− + H+ → CO2 + H2O
NBB is regenerated
Renal compensation of acidosis is achieved: pH ↑
But: [HCO3−]act and PCO2 are increased

The *Henderson–Hasselbalch equation* for the HCO_3^-/CO_2 buffer system states:

$$pH = pK_a + \log([HCO_3^-]/[CO_2]). \quad [6.5]$$

Since $[CO_2] = \alpha \cdot P_{CO_2}$ (→ p. 126), Equation 6.5 contains two constants (pK_a and α) and three variables (pH, $[HCO_3^-]$, and P_{CO_2}). At 37 °C in plasma, $pK_a = 6.1$ and $\alpha = 0.225\ mmol \cdot L^{-1} \cdot kPa^{-1}$ (cf. p. 126). When one of the variables remains constant (e.g., $[HCO_3^-]$), the other two (e.g., P_{CO_2} and pH) are interdependent. In a graphic representation, this dependency is reflected as a straight line when the logarithm of P_{CO_2} is plotted against the pH (→ **A–C** and p. 388).

When the P_{CO_2} varies in a **bicarbonate solution** (without other buffers), the pH changes but $[HCO_3^-]$ remains constant (→ **A**, solid line). One can also plot the lines for different HCO_3^- concentrations, all of which are parallel (→ **A**, **B**, dotted orange lines). Figures **A** through **C** use a scale that ensures that the bicarbonate lines intersect the coordinates at 45° angles. The **Siggaard–Andersen nomogram** (→ **C**) does not use the lines, but only the points of intersection of the $[HCO_3^-]$ lines with the normal P_{CO_2} of 5.33 kPa (40 mmHg).

The **blood** contains not only the HCO_3^-/CO_2 buffer but also **non-bicarbonate buffers**, **NBB** (→ p. 138). Thus, a change in the P_{CO_2} does not alter the pH as much as in a solution containing the HCO_3^-/CO_2 buffer alone (→ p. 144). In the P_{CO_2}/pH nomogram, the slope is therefore steeper than 45° (→ **B**, green and red lines). Hence, the **actual bicarbonate** concentration, **$[HCO_3^-]_{Act}$**, in blood changes and shifts in the same direction as the P_{CO_2} if the pH varies (→ p. 144). Therefore, both the $[HCO_3^-]_{Act}$ and the **standard bicarbonate** concentration, **$[HCO_3^-]_{St}$**, can be determined in clinical blood tests. By definition, $[HCO_3^-]_{St}$ represents the $[HCO_3^-]$ at a normal P_{CO_2} of 5.33 kPa (40 mmHg). $[HCO_3^-]_{St}$ therefore permits an assessment of $[HCO_3^-]$ independent of P_{CO_2} changes.


$[HCO_3^-]_{St}$ and **$[HCO_3^-]_{Act}$** are **determined** using measured P_{CO_2} and pH values obtained with a blood gas analyzer. When plotted on the *Siggaard–Andersen nomogram*, $[HCO_3^-]_{St}$ is read from the line as indicated by the points of intersect of the $[HCO_3^-]$ line (→ **B**, orange lines) and the P_{CO_2}/pH line (**B** and **C**, green and red lines) *at normal* P_{CO_2} = 5.33 (→ **B** and **C**, points *D* and *d*). $[HCO_3^-]_{Act}$ is read from the $[HCO_3^-]$ line intersected by the P_{CO_2}/pH line at the level of the *actually measured* P_{CO_2}. Since the normal and measured P_{CO_2} values agree in normals, their $[HCO_3^-]_{Act}$ is usually equal to $[HCO_3^-]_{St}$. If P_{CO_2} deviates from normal (→ **B**, **C**, point *c*), $[HCO_3^-]_{Act}$ is read at point *e* on the HCO_3^- line (→ **B, C**, interrupted 45° line) on which the actually measured P_{CO_2} lies (→ **B**, **C**, point *c*).

Blood P_{CO_2} and pH measurement. When using the equilibration method (*Astrup method*), three pH measurements are taken: (1) in the unchanged blood sample; (2) after equilibration with a high P_{CO_2} (e.g., 10 kPa [75 mmHg]; → **C**, points *A* and *a*), and (3) after equilibration with a low P_{CO_2} (e.g., 2.7 kPa [20 mmHg]; → **C**, points *B* and *b*). The P_{CO_2} of the original blood sample can then be read from lines *A–B* and *a–b* using the pH value obtained in measurement 1. In normals (→ **C**, upper case letters, green), $[HCO_3^-]_{Act} = [HCO_3^-]_{St} = 24$ mmol/L (→ **C**, points *E* and *D*). Example 2 (→ **C**, lower case letters, red) shows an acid–base disturbance: The pH is too low (7.2) and $[HCO_3^-]_{St}$ (→ **C**, point *d*) has dropped to 13 mmol/L (metabolic acidosis). This has been partially compensated (→ p. 142) by a reduction in P_{CO_2} to 4 kPa, which led to a consequent reduction in $[HCO_3^-]_{Act}$ to 11 mmol/L (→ **C**, point *e*).


Total **buffer bases** (BB) and **base excess** (BE) (→ p. 142) can also be read from the Siggaard–Andersen nomogram (→ **C**). The base excess (points F and f on the curve) is the difference between the measured buffer base value (points *G* or *g*) and the normal buffer base value (point *G*). Point *G* is dependent on the hemoglobin concentration of the blood (→ **C**; [Hb]/BB comparison). Like $[HCO_3^-]_{St}$, deviation of BB from the norm (0 ± 2.5 mEq/L) is diagnostic of primary non-respiratory acid–base disturbances.

The P_{CO_2}/pH line of the blood sample in plate **C** can also be determined if (1) the P_{CO_2} (without equilibration), (2) the pH, and (3) the hemoglobin concentration are known. One point (→ **C**, point *c*) on the unknown line can be drawn using (1) and (2). The line must be drawn through the point in such a way that BB (point *g*) – BB_{normal} (dependent on Hb value) = BE (point *f*).


A. P_{CO_2}/pH nomogram (without NBB)



B. P_{CO_2}/pH nomogram (with NBB)



C. Siggaard-Andersen nomogram



Three fundamental mechanisms characterize kidney function: (1) large quantities of water and solutes are **filtered** from the blood. (2) This *primary urine* enters the tubule, where most of it is **reabsorbed**, i.e., it exits the tubule and passes back into the blood. (3) Certain substances (e.g., toxins) are not only not reabsorbed but actively **secreted** into the tubule lumen. The non-reabsorbed residual filtrate is **excreted** together with the secreted substances in the *final urine*.

Functions: The kidneys (1) adjust salt and water excretion to maintain a constant *extracellular fluid volume* and *osmolality*; (2) they help to maintain *acid-base homeostasis*; (3) they *eliminate end-products* of metabolism and foreign substances while (4) preserving useful compounds (e.g., glucose) by reabsorption; (5) they produce *hormones* (e.g., erythropoietin) and hormone activators (renin), and (6) have *metabolic functions* (protein and peptide catabolism, gluconeogenesis, etc.).

Nephron Structure

Each kidney contains about 10^6 **nephrons**, each consisting of the malpighian body and the tubule. The **malpighian body** is located in the renal cortex (→ **A**) and consists of a tuft of capillaries (**glomerulus**) surrounded by a double-walled capsule (**Bowman's capsule**). The *primary urine* accumulates in the capsular space between its two layers (→ **B**). Blood enters the glomerulus by an afferent arteriole (*vas afferens*) and exits via an efferent arteriole (*vas efferens*) from which the peritubular capillary network arises (→ p. 150). The **glomerular filter** (→ **B**) separates the blood side from the Bowman's capsular space.

The **glomerular filter** comprises the partially fenestrated, partially perforated endothelium of the glomerular capillaries (50–100 nm pore size) followed by the basal membrane as the second layer and the visceral membrane of Bowman's capsule on the urine side. The latter is formed by *podocytes* with numerous interdigitating footlike processes (*pedicels*). The slit-like spaces between them are covered by the *slit membrane*, the *pores* of which are about 5 nm in diameter. They are shaped by the protein *nephrine*, which is anchored to the cytoskeleton of the podocytes.

◆ The **proximal tubule** (→ **A**, dark green) is the longest part of a nephron (ca. 10 mm). Its twisted initial segment (*proximal convoluted tubule, PCT*; → **A3**) merges into a straight part, PST (*pars recta*; → **A4**).

◆ The **loop of Henle** consists of a *thick descending limb* that extends into the renal medulla (→ **A4** = PST), a *thin descending limb* (→ **A5**), a *thin ascending limb* (only in juxtamedullary nephrons which have long loops), and a *thick ascending limb, TAL* (→ **A6**). It contains the **macula densa** (→ p. 186), a group of specialized cells that closely communicate with the glomerulus of the respective nephron. Only about 20% of all Henle's loops (those of the deep juxtamedullary nephrons) are long enough to penetrate into the inner medulla. Cortical nephrons have shorter loops (→ **A** and p. 150).


◆ The **distal tubule** (→ **A**, grayish green) has an initially straight part (= TAL of Henle's loop; → **A6**) that merges with a convoluted part (*distal convoluted tubule, DCT*; → **A7**).

The DCT merges with a connecting tubule (→ **A8**). Many of them lead into a **collecting duct, CD** (→ **A9**) which extends through the renal cortex (cortical CD) and medulla (medullary CD). At the *renal papilla* the collecting ducts opens in the *renal pelvis*. From there, the urine (propelled by peristaltic contractions) passes via the *ureter* into the *urinary bladder* and, finally, into the *urethra*, through which the urine exits the body.


Micturition

Voiding of the bladder is controlled by reflexes. Filling of the bladder activates the smooth detrusor muscle of the bladder wall via stretch sensors and parasympathetic neurons (S_2–S_4, → p. 78 ff.). At low filling volumes, the wall relaxes via sympathetic neurons (L_1–L_2) controlled by supraspinal centers (pons). At higher filling volumes (> 0.3 L), the threshold pressure (about 1 kPa) that triggers the *micturition reflex* via a positive feedback loop is reached: The detrusor muscle contracts → pressure ↑ → contraction ↑↑ and so on until the *internal* (smooth m.) and *external sphincter* (striated m.) open so the urine can exit the body.

A. Anatomy of the kidney (schematic diagram)



B. Glomerulus and Bowman's capsule



The *arcuate arteries* (→ **A1**) pass between the renal cortex and medulla. They branch towards the cortex into the *interlobular arteries* (→ **A2**) from which the *afferent arterioles* (or vasa afferentia) arise (→ **A3**). Unlike other organs, the kidney has *two successive capillary networks* that are connected with each other by an *efferent arteriole* (or vas efferens) (→ **A, B**). *Pressure* in the first network of **glomerular capillaries** (→ p. 148) is a relatively *high* (→ **B** and p. 152) and is regulated by adjusting the width of interlobular artery, the afferent and/or efferent arterioles (→ **A 3,4**). The second network of **peritubular capillaries** (→ **A**) winds around the cortical tubules. It supplies the tubule cells with blood, but it is also involved in the exchange of substances with the tubule lumen (reabsorption, secretion; → p. 154 ff.).

The **renal blood flow** (**RBF**) is relatively high, ca. 1.2 L/min, equivalent to 20–25% of the cardiac output. This is required to maintain a high glomerular filtration rate (GFR; → p. 152) and results in a very low arteriovenous O_2 difference (ca. 15 mL/L of blood). In the *renal cortex*, **O_2 is consumed** (ca. 18 mL/min) for oxidative **metabolism** of fatty acids, etc. Most of the ATP produced in the process is used to fuel active transport. In the renal medulla, metabolism is mainly anaerobic (→ p. 72).

Around 90% of the renal blood supply goes to the cortex. Per gram of tissue, approximately 5, 1.75 and 0.5 mL/min of blood pass through the cortex, outer medulla, and inner medulla, respectively. The latter value is still higher than in most organs (→ p. 215 A).

The kidney contains **two types of nephrons** that differ with respect to the features of their second network of capillaries (→ **A**).

- **Cortical nephrons** are supplied by peritubular capillaries (see above) and have short loops of Henle.
- **Juxtamedullary nephrons** are located near the cortex-medulla junction. Their efferent arterioles give rise to relatively long (≤ 40 mm), straight arterioles (**vasa recta**) that descend into the renal medulla. The vasa recta supply the renal medulla and can accompany long loops of Henle of juxtamedullary nephrons as far as the tip of the renal papilla (→ p. 148). Their hairpin shape is important for the concentration of urine (→ p. 164 ff.).

Any **change in blood distribution** to these two types of nephrons affects NaCl excretion. Antidiuretic hormone (ADH) increases the GFR of the juxtamedullary nephrons.

Due to **autoregulation of renal blood flow**, only slight changes in *renal plasma flow* (**RPF**) and glomerular filtration rate (GFR) occur (even in a denervated kidney) when the systemic blood pressure fluctuates between 80 and about 180 mmHg (→ **C**). Resistance in the *interlobular arteries* and *afferent arterioles* located upstream to the cortical glomeruli is automatically adjusted when the mean blood pressure changes (→ **B, C**). If the blood pressure falls below about 80 mmHg, however, renal circulation and filtration will ultimately fail (→ **C**). RBF and GFR can also be regulated independently by making isolated changes in the (serial) resistances of the afferent and efferent arterioles (→ p. 152).

Non-invasive **determination of RBF** is possible if the **RPF** is known (approx. **0.6 L/min**). RPF is obtained by measuring the amount balance (Fick's principle) of an intravenously injected test substance (e.g., *p*-aminohippurate, **PAH**) that is almost completely eliminated in the urine during one renal pass (PAH is filtered and highly secreted, → p. 156 ff.). The eliminated amount of PAH is calculated as the arterial inflow of PAH into the kidney minus the venous flow of PAH out of the kidney per unit time. Since

$$\text{Amount/time} = (\text{volume/time}) \cdot \text{concentration} \quad [7.1]$$

$$(RPF \cdot Pa_{PAH}) - (RPF \cdot Prv_{PAH}) = \dot{V}_U \cdot U_{PAH} \quad [7.2]$$

or

$$RPF = \dot{V}_U \cdot U_{PAH}/(Pa_{PAH} - Prv_{PAH}). \quad [7.3]$$

where Pa_{PAH} is the arterial PAH conc., Prv_{PAH} is the renal venous PAH conc., U_{PAH} is the urinary PAH conc., and $\dot{V}_U$ is the urine output/time. Prv_{PAH} makes up only about 10% of the Pa_{PAH} and normally is not measured directly, but is estimated by dividing **PAH clearance** (= $\dot{V}_U \cdot U_{PAH}/Pa_{PAH}$; → p. 152) by a factor of 0.9. Therefore,


$$\mathbf{RPF = \dot{V}_U \cdot U_{PAH}/(0{,}9 \cdot Pa_{PAH})}. \quad [7.4]$$

This equation is only valid when the Pa_{PAH} is not too high. Otherwise, PAH secretion will be saturated and PAH clearance will be much smaller than RPF (→ p. 161 A).


RBF is derived by inserting the known hematocrit (Hct) value (→ p. 88) into the following equation:

$$\mathbf{RBF = RPF/(1 - Hct)} \quad [7.5]$$


A. Renal blood vessel system



B. Renal blood pressure



C. Autoregulation of renal blood flow (RBF) and glomerular filtration rate (GFR)



The **glomerular filtration rate (GFR)** is the total volume of fluid filtered by the glomeruli of both kidneys per unit time. It is normally about **120 mL/min** per 1.73 m^2 of body surface area, equivalent to around 180 L/day. Accordingly, the volume of exchangeable extracellular fluid of the whole body (ca. 17 L) enters the renal tubules about 10 times a day. About 99% of the GFR returns to the extracellular compartment by tubular reabsorption. The mean *fractional excretion of H_2O* is therefore about 1% of the GFR, and absolute H_2O excretion (= **urine output/time** = $\dot{V}_U$) is about 1 to 2 L per day. (The filtration of dissolved substances is described on p. 154).

The GFR makes up about 20% of renal plasma flow, RPF (→ p. 150). The **filtration fraction** (**FF**) is defined as the ratio of GFR/RPF. The filtration fraction is increased by *atriopeptin*, a peptide hormone that increases efferent arteriolar resistance (R_e) while lowering afferent arteriolar resistance (R_a). This raises the effective filtration pressure in the glomerular capillaries without significantly changing the overall resistance in the renal circulation.

The effective filtration pressure (P_{eff}) is the driving "force" for filtration. P_{eff} is the glomerular capillary pressure ($P_{cap} \approx 48$ mmHg) minus the pressure in Bowman's capsule ($P_{Bow} \approx 13$ mmHg) and the oncotic pressure in plasma (π_{cap} = 25 to 35 mmHg):

$$P_{eff} = P_{cap} - P_{Bow} - \pi_{cap} \qquad [7.6]$$

P_{eff} at the arterial end of the capillaries equals 48–13–25 = 10 mmHg. Because of the high filtration fraction, the plasma protein concentration and, therefore, π_{cap} values along the glomerular capillaries increase (→ p. 384) and P_{eff} decreases. (The mean effective filtration pressure, $\overline{P}_{eff}$, is therefore used in Eq. 7.7.) Thus, filtration ceases (near distal end of capillary) when π_{cap} rises to about 35 mmHg, decreasing P_{eff} to zero (*filtration equilibrium*).

GFR is the product of $\overline{P}_{eff}$ (mean for all glomeruli), the glomerular filtration area A (dependent on the number of intact glomeruli), and the water permeability k of the glomerular filter. The *ultrafiltration coefficient K_f* is used to represent A · k. This yields

$$\mathbf{GFR} = \overline{\mathbf{P}}_{\mathbf{eff}} \cdot \mathbf{K_f}. \qquad [7.7]$$

Indicators present in the plasma are used to **measure GFR.** They must have the following properties:

- They must be freely filterable
- Their filtered amount must not change due to resorption or secretion in the tubule
- They must not be metabolized in the kidney
- They must not alter renal function

Inulin, which must be infused intravenously, fulfills these requirements. **Endogenous creatinine** (normally present in blood) can also be used with certain limitations.

The amount of indicator filtered over time (→ **A**) is calculated as the plasma concentration of the indicator (P_{In}, in g/L or mol/L) times the GFR in L/min. The same amount of indicator/time appears in the urine (conditions 2 and 3; see above) and is calculated as $\dot{V}_U$ (in L/min), times the indicator conc. in urine (U_{In}, in g/L or mol/L, resp.), i.e. $P_{In} \cdot GFR = \dot{V}_U \cdot U_{In}$, or:


$$\mathbf{GFR} = \frac{\dot{\mathbf{V}}_\mathbf{U} \cdot \mathbf{U_{In}}}{\mathbf{P_{In}}} \text{ [L/min] } (\rightarrow \mathbf{A}). \qquad [7.8]$$

The expression on the right of Eq. 7.8 represents **clearance**, regardless of which substance is being investigated. Therefore, the *inulin or creatinine clearance represents the GFR.* (Although the plasma concentration of creatinine, P_{cr}, rises as the GFR falls, P_{cr} alone is a quite unreliable measure of GFR.)

Clearance can also be regarded as the completely indicator-free (or cleared) plasma volume flowing through the kidney per unit time. **Fractional excretion** (**FE**) is the ratio of clearance of a given substance X to inulin clearance (C_X/C_{In}) and defines which fraction of the filtered quantity of X was excreted (cf. p. 154). FE < 1 if the substance is removed from the tubule by reabsorption (e.g. Na^+, Cl^-, amino acids, glucose, etc.; → **B1**), and FE > 1 if the substance is subject to filtration plus tubular secretion (→ **B2**). For PAH (→ p. 150), tubular secretion is so effective that $FE_{PAH} \approx 5$ (500%).

The **absolute rate of reabsorption or secretion** by the kidneys of a freely filterable substance X (mol/min) is calculated as the difference between the filtered amount/time ($GFR \cdot P_X$) and the excreted amount/time ($\dot{V}_U \cdot U_X$), where a positive result means net reabsorption and a negative net secretion. (For inulin, the result would be zero.)

A. Inulin clearance = glomerular filtration rate (GFR)



Amount excreted/time = Urinary inulin concentration · (urine volume/time)

=


Amount filtered/time = Plasma inulin concentration · (filtered volume/time)


U_{In} (g/L) · $\dot{V}_U$ (mL/min) = P_{In} (g/L) · GFR (mL/min)

$$GFR = \frac{U_{In}}{P_{In}} \cdot \dot{V}_U \text{ (mL/min)}$$

GFR ≈ ca. 120 mL/min per 1.73 m^2 body surface area

B. Clearance levels (1) lower or (2) higher than inulin clearance





$$\frac{C_X}{C_{In}} = \frac{C_X}{GFR} = \text{Fractional excretion} = FE < 1.0$$

$$\frac{C_X}{C_{In}} = \frac{C_X}{GFR} = \text{Fractional excretion} = FE > 1.0$$

Filtration of solutes. The glomerular filtrate also contains small dissolved molecules of plasma (*ultrafiltrate*) (→ p. 152). The *glomerular sieving coefficient GSC* of a substance (= concentration in filtrate/concentration in plasma water) is a measure of the permeability of the glomerular filter for this substance (→ p. 148). Molecules with a radius of $r < 1.8$ nm (molecular mass < ca. 10 000 Da) can freely pass through the filter (GSC ≈ 1.0), while those with a radius of $r > 4.4$ nm (molecular mass > 80 000 DA, e.g., globulins) normally cannot pass through it (GSC = 0). Only a portion of molecules where $1.8 \text{ nm} < r < 4.4 \text{ nm}$ applies are able to pass through the filter (GSC ranges between 1 and 0). Negatively charged particles (e.g., albumin: r = 3.4 nm; GSC ≈ 0.0003) are less permeable than neutral substances of equal radius because negative charges on the wall of the glomerular filter repel the ions. When small molecules are bound to plasma proteins (**protein binding**), the bound fraction is practically non-filterable (→ p. 24).

Molecules entrapped in the glomerular filter are believed to be eliminated by phagocytic mesangial macrophages (→ p. 94ff.) and glomerular podocytes.

Tubular epithelium. The epithelial cells lining the renal tubule and collecting duct are *polar cells.* As such, their luminal (or apical) membrane on the urine side differs significantly from that of the basolateral membrane on the blood side. The luminal membrane of the proximal tubule has a high *brush border* consisting of *microvilli* that greatly increase the surface area (especially in the convoluted proximal tubule). The basolateral membrane of this tubule segment has deep folds (*basal labyrinth*) that are in close contact with the intracellular mitochondria (→ p. 9 B), which produce the ATP needed for Na^+-K^+-ATPase (→ p. 26) located in the basolateral membrane (of all epithelial cells). The large surface areas (about 100 m^2) of the proximal tubule cells of both kidneys are needed to reabsorb the lion's share of filtered solutes within the contact time of a couple of seconds. Postproximal tubule cells do not need a brush border since the amount of substances reabsorbed decreases sharply from the proximal to the distal segments of the tubules.

Whereas permeability of the two membranes in series is decisive for **transcellular transport** (reabsorption, secretion), the tightness of *tight junctions* (→ p. 18) determines the paracellular permeability of the epithelium for water and solutes that cross the epithelium by **paracellular transport**. The tight junctions in the proximal tubule are relatively permeable to water and small ions which, together with the large surface area of the cell membranes, makes the epithelium well equipped for para- and transcellular mass transport (→ **D**, column 2). The thin limbs of Henle's loop are relatively "leaky", while the thick ascending limb and the rest of the tubule and collecting duct are "moderately tight" epithelia. The tighter epithelia can develop much higher *transepithelial chemical and electrical gradients* than "leaky" epithelia.


Measurement of reabsorption, secretion and excretion. Whether and to which degree a substance filtered by the glomerulus is reabsorbed or secreted at the tubule and collecting duct cannot be determined based on its urinary concentration alone as concentrations rise due to the reabsorption of water (→ p. 164). The urinary/plasma inulin (or creatinine) concentration ratio, U_{in}/P_{in} *is a measure of the degree of water reabsorption*. These substances can be used as indicators because they are neither reabsorbed nor secreted (→ p. 152). Thus, changes in indicator concentration along the length of the tubule occur due to the **H_2O reabsorption** alone (→ **A**). If $U_{in}/P_{in} = 200$, the inulin concentration in the final urine is 200 times higher than in the original filtrate. This implies that *fractional excretion of H_2O (FE_{H_2O})* is 1/200 or 0.005 or 0.5% of the GFR. Determination of the concentration of a (freely filterable and perhaps additionally secreted) substance X in the same plasma and urine samples for which U_{in}/P_{in} was measured will yield U_x/P_x. Considering U_{in}/P_{in}, the fractional excretion of X, FE_X can be calculated as follows (→ **A** and **D**, in % in column 5):

$$\mathbf{FE_X = (U_X/P_X)/(U_{In}/P_{In})} \quad [7.9]$$

Eq. 7.9 can also be derived from C_x/C_{in} (→ p. 152) when simplified for $\dot{V}_U$. The **fractional reabsorption** of X ($\mathbf{FR_X}$) is calculated as

$$\mathbf{FR_X = 1 - FE_X} \quad [7.10]$$

▶


A. Fractional excretion (FE)
Inulin
Substance X
P_{In}, P_X
TF_{In}, TF_X
H_2O
X
Reabsorption or secretion of X
X
H_2O
Concentrations of inulin and X rise due to H_2O reabsorption
U_{In}, U_X
$FE_X = \frac{(U_X/P_X)}{(U_{In}/P_{In})}$
Final urine
B. Tubular transport
Filtration
Active reabsorption
Passive reabsorption
Active transcellular secretion
Passive cellular secretion
Active
C. Overview of important transport processes along the nephron
Primary active and passive
Secondary active
Na^+ Ca^{2+} K^+
NH_3
H^+
Na^+: Primary active
Cl^- : Secondary active
NaCl
K^+
Na^+
Cl^- H_2O
Glucose, amino acids, phosphate, lactate, sulfate
Secondary active
Cl^- H_2O
Urea
Ca^{2+}
Metabolites, drugs, PAH
Ca^{2+} Mg^+
H^+
Cl⁻
Urea
Transport processes: see **B.1–6**

▶ **Reabsorption in different segments of the tubule**. The concentration of a substance X (TF_X) and inulin (TF_{in}) in tubular fluid can be measured via micropuncture (→ **A**). The values can be used to calculate the non-reabsorbed fraction (*fractional delivery*, FD) of a freely filtered substance X as follows:

$FD = (TF_X/P_X)/(TF_{in}/P_{in})$,

where P_X and P_{in} are the respective concentrations in plasma (more precisely: in plasma water).

Fractional reabsorption (FR) up to the sampling site can then be derived from 1 – FD (→ **D**, columns 2 and 3, in %).

Reabsorption and secretion of various substances (see pp. 16–30, transport mechanisms). Apart from H_2O, many inorganic ions (e.g., Na^+, Cl^-, K^+, Ca^{2+}, and Mg^{2+}) and organic substances (e.g., HCO_3^-, D-glucose, L-amino acids, urate, lactate, vitamin C, peptides and proteins; → **C, D**, p. 158ff.) are also subject to tubular **reabsorption** (→ **B1–3**). Endogenous products of metabolism (e.g., urate, glucuronides, hippurates, and sulfates) and foreign substances (e.g., penicillin, diuretics, and PAH; → p. 150) enter the tubular urine by way of **transcellular secretion** (→ **B4, C**). Many substances, such as ammonia (NH_3) and H^+ are first produced by tubule cells before they enter the tubule by **cellular secretion**. NH_3 enters the tubule lumen by passive transport (→ **B5**), while H^+ ions are secreted by active transport (→ **B6** and p. 176ff.).

Na^+/K^+ transport by **Na^+-K^+-ATPase** (→ p. 26) in the basolateral membrane of the tubule and collecting duct serves as the **"motor"** for most of these transport processes. By *primary active transport* (fueled directly by ATP consumption), Na^+-K^+-ATPase pumps Na^+ out of the cell into the blood while pumping K^+ in the opposite direction (subscript "i" = intracellular and "o" = extracellular). This creates two driving "forces" essential for the transport of numerous substances (including Na^+ and K^+): first, a **chemical Na^+ gradient** ($[Na^+]_o > [Na^+]_i$ and (because $[K^+]_i > [K^+]_o$), second, a **membrane potential** (inside the cell is negative relative to the outside) which represents an **electrical gradient** and can drive ion transport (→ pp. 32ff. and 44).

Transcellular transport implies that two membranes must be crossed, usually by two different mechanisms. If a given substance (D-glucose, PAH, etc.) is actively transported across an epithelial barrier (i.e., against an electrochemical gradient; → see p. 26ff.), at least one of the two serial membrane transport steps must also be active.

Interaction of transporters. Active and passive transport processes are usually closely interrelated. The active absorption of a solute such as Na^+ or D-glucose, for example, results in the development of an *osmotic gradient* (→ p. 24), leading to the passive absorption of water. When water is absorbed, certain solutes are carried along with it (*solvent drag*; → p. 24), while other substrates within the tubule become more *concentrated*. The latter solutes (e.g., Cl^- and urea) then return to the blood along their concentration gradients by passive reabsorption. Electrogenic ion transport and ion-coupled transport (→ p. 28) can depolarize or hyperpolarize only the luminal or only the basolateral membrane of the tubule cells. This causes a *transepithelial potential* which serves as the driving "force" for paracellular ion transport in some cases.

Since non-ionized forms of weak electrolytes are more lipid-soluble than ionized forms, they are better able to penetrate the membrane (**non-ionic diffusion**; → **B2**). Thus, the pH of the urine has a greater influence on passive reabsorption by non-ionic diffusion. *Molecular size* also influences diffusion: the smaller a molecule, the larger its diffusion coefficient (→ p. 20ff.).

D. Reabsorption, secretion and fractional excretion

	1	2	3	4	5	6
Substance	Concentration in plasma water (P) [mmol/L]	Fractional reabsorption (FR) [%]: % in proximal tubule (TF/P)	Fractional reabsorption (FR) [%]: % in loop of Henle (TF/P)	Fractional reabsorption (FR) [%]: Total %	Fractional excretion (FE) [% of filtered amount]	P = Plasma concentration; TF = Concentration in tubular urine; Effects: ↑ raises FE, ↓ lowers FE
H_2O	---	65%	10%	93%–99.5%	0.5%–7%	ADH: ↓
Na^+	153	65% (1.0)	25% (0.4)	95%–99.5%	0.5%–5%	Aldosterone: ↓ ADH: ↓ ANP: ↑
K^+	4,6	65% (1.0)	10%–20%	Secretion possible	2%–150%	Aldosterone: ↑
Ca^{2+}	Free: 1.6	60% (1.1)	30%	95%–99%	1%–5%	PTH: ↓ Acidosis: ↑
Mg^{2+}	Free: 0.6	15% (2.5)	ca. 70%	80%–95%	5%–20%	P rise: ↑
Cl^-	112	55% (1.3)	ca. 20%	95%–99.5%	0.5%–5%	---
HCO_3^-	24	93% (0.2)		98%–99%	1%–2%	Alkalosis: ↑
Phosphate	2.2	65% (1.0)	15%	80%–97%	3%–20%	P rise: ↑ PTH: ↑ Ca^{2+} falls: ↑ Acidosis: ↑
D-Glucose	5	96% (0.1)	4%	≈100%	≈0%	Sharp P rise: ↑
Urea	5	50% (1.4)	Secretion	ca. 60%	ca. 40%	Diuresis: ↑
Creatinine	0.1	0% (2.9)	0%	0%	100%	---
PAH (I. V.)	C_{test}	Secretion	Secretion	Secretion	≈500%	Sharp P rise: ↓

The **filtered load of a substance** is the product of its plasma concentration and glomerular filtration rate (GFR). Since the GFR is high (ca. 180 L/day), enormous quantities of substances enter the primary urine each day (e.g., 160 g/day of D-glucose).

Fractional excretion (FE, → p. 154) of **D-glucose** is very low (FE ≈ 0.4%). This virtually complete reabsorption is achieved by secondary active transport (*Na^+-glucose symport*) at the luminal cell membrane (→ **B** and p. 29 B1). About 95% of this activity occurs in the proximal tubule.

If the plasma glucose conc. exceeds 10–15 mmol/L, as in diabetes mellitus (normally 5 mmol/L), *glucosuria* develops, and urinary glucose conc. rises (→ **A**). Glucose reabsorption therefore exhibits *saturation kinetics* (Michaelis-Menten kinetics; → p. 28). The above example illustrates *prerenal glucosuria*. *Renal glucosuria* can also occur when one of the tubular glucose carriers is defective.

Low-affinity **carriers** in the luminal cell membrane of the pars convoluta (sodium-glucose transporter type 2 = SGLT2) and high-affinity carriers (SGLT1) in the pars recta are responsible for D-glucose reabsorption. The co-transport of D-glucose and Na^+ occurs in each case, namely at a ratio of 1 : 1 with SGLT2 and 1 : 2 with SGLT1. The energy required for this form of *secondary active* glucose transport is supplied by the electrochemical Na^+ gradient directed towards the cell interior. Because of the co-transport of two Na^+ ions, the gradient for SGLT1 is twice as large as that for SGLT2. A *uniporter* (GLUT2 = glucose transporter type 2) on the blood side facilitates the passive transport of accumulated intracellular glucose out of the cell (*facilitated diffusion*, → p. 22). **D-galactose** also makes use of the SGLT1 carrier, while **D-fructose** is passively absorbed by tubule cells (GLUT5).

The plasma contains over 25 **amino acids**, and about 70 g of amino acids are filtered each day. Like D-glucose, most L-amino acids are reabsorbed at proximal tubule cells by Na^+-coupled secondary active transport (→ **B** and p. 29 B3). At least 7 different amino acid transporters are in the proximal tubule, and the specificities of some overlap. J_{max} and K_M (→ p. 28) and, therefore, saturability and reabsorption capacities vary according to the type of amino acid and carrier involved. Fractional excretion of most amino acids ≈ to 1% (ranging from 0.1% for L-valine to 6% for L-histidine).

Increased urinary excretion of amino acids (**hyperaminoaciduria**) can occur. *Prerenal* hyperaminoaciduria occurs when plasma amino acid concentrations are elevated (and reabsorption becomes saturated, as in **A**), whereas *renal* hyperaminoaciduria occurs due to deficient transport. Such a dysfunction may be *specific* (e.g., in cystinuria, where only L-cystine, L-arginine and L-lysine are hyperexcreted) or *unspecific* (e.g., in Fanconi's syndrome, where not only amino acids but also glucose, phosphate, bicarbonate etc. are hyperexcreted).

Certain substances (lactate, sulfate, phosphate, dicarboxylates, etc.) are also reabsorbed at the proximal tubule by way of Na^+ symport, whereas urea is subject to passive back diffusion (→ p. 166).


Urate and **oxalate** are both reabsorbed and secreted (→ p. 160), with the predominant process being reabsorption for urate (FE ≈ 0.1) and secretion for oxalate (FE > 1). If the urinary conc. of these poorly soluble substances rises above normal, they will start to precipitate (increasing the risk of **urinary calculus formation**). Likewise, the excessive urinary excretion of **cystine** can lead to cystine calculi.

Oligopeptides such as glutathione and angiotensin II are broken down so quickly by *luminal peptidases* in the brush border that they can be reabsorbed as free amino acids (→ **C1**). **Dipeptides** resistant to luminal hydrolysis (e.g., carnosine) must be reabsorbed as intact molecules. A symport carrier (*PepT2*) driven by the inwardly directed H^+ gradient (→ p. 176) transports the molecules into the cells *tertiary active* H^+ symport; → p. 26, 29 B4). The dipeptides are then hydrolyzed within the cell (→ **C2**). The PepT2 carrier is also used by certain drugs and toxins.


Proteins. Although *albumin* has a low sieving coefficient of 0.0003 (→ p. 154), 2400 mg/day are filtered at a plasma conc. of 45 g/L (180 L/day · 45 g/L · 0.0003 = 2400 mg/day). Only 2 to 35 mg of albumin are excreted each day (FE ≈ 1%). In the proximal tubule, albumin, lysozyme, α_1-microglobulin, β_2-microglobulin and other proteins are reabsorbed by *receptor-mediated endocytosis* (→ p. 28) and are "digested" by lysosomes (→ **D**). Since this type of reabsorption is nearly saturated at normal filtered loads of proteins, an elevated plasma protein conc. or increased protein sieving coefficient will lead to *proteinuria*.

25-OH-cholecalciferol, which is bound to **DBP** (vitamin D-binding protein) in plasma and glomerular filtrate, is reabsorbed in combination with DBP by receptor-mediated endocytosis (→ p. 294).


A. Reabsorption of glucose and amino acids




B. Reabsorption of organic substances



C. Reabsorption of oligopeptides



D. Reabsorption of proteins by endocytosis



Food provides necessary nutrients, but also contains inert and harmful substances. The body can usually sort out these substances already at the time of **intake**, either based on their smell or taste or, if already eaten, with the help of specific digestive enzymes and intestinal absorptive mechanisms (e.g., D-glucose and L-amino acids are absorbed, but L-glucose and D-amino acids are not). Similar distinctions are made in **hepatic excretion** (⇒ bile ⇒ stools): useful bile salts are almost completely reabsorbed from the gut by way of specific carriers, while waste products such as bilirubin are mainly eliminated in the feces. Likewise, the **kidney** reabsorbs hardly any useless or harmful substances (including end-products such as creatinine). Valuable substances (e.g., D-glucose and L-amino acids), on the other hand, are reabsorbed via specific transporters and thus spared from excretion (→ p. 158).

The liver and kidney are also able to modify endogenous waste products and foreign compounds (xenobiotics) so that they are "**detoxified**" if toxic and made ready for rapid elimination. In unchanged form or after the enzymatic addition of an OH or COOH group, the substances then combine with glucuronic acid, sulfate, acetate or glutathione to form **conjugates**. The conjugated substances are then secreted into the bile and proximal tubule lumen (with or without further metabolic processing).

Tubular Secretion

The proximal tubule utilizes **active transport mechanisms** to secrete numerous waste products and xenobiotics. This is done by way of carriers for organic anions (OA^-) and organic cations (OC^+). The secretion of these substances makes it possible to raise their clearance level above that of inulin and, therefore, to raise their fractional excretion (FE) above 1.0 = 100% (→ p. 152) in order to eliminate them more effectively (→ **A**; compare red and blue curves). Secretion is carrier-mediated and is therefore subject to saturation kinetics. Unlike reabsorbed substances such as D-glucose (→ p. 159 A), the fractional excretion (FE) of organic anions and cations decreases when their plasma concentrations rise (→ **A**; PAH secretion curve reaches plateau, and slope of PAH excretion curve decreases). Some organic anions (e.g., urate and oxalate) and cations (e.g., choline) are both secreted and reabsorbed (bidirectional transport), which results in net reabsorption (urate, choline) or net secretion (oxalate).


The secreted **organic anions** (**OA^-**) include indicators such as PAH (p-aminohippurate; → p. 150) and phenol red; endogenous substances such as oxalate, urate, hippurate; drugs such as penicillin G, barbiturates, and numerous diuretics (→ p. 174); and conjugated substances (see above) containing glucuronate, sulfate or glutathione. Because of its high affinity for the transport system, *probenecid* is a potent inhibitor of OA^- secretion.

The *active step of* **OA^- secretion** (→ **B**) occurs across the *basolateral membrane* of proximal tubule cells and accumulates organic anions in the cell whereby the inside-negative membrane potential has to be overcome. The membrane has a broad specificity carrier (OAT1 = *organic anion transporter* type 1) that transports OA^- from the blood into the tubule cells in exchange for a dicarboxylate, such as succinate^{2-} or α-ketoglutarate^{2-}; → **B1**). The latter substance arises from the glutamine metabolism of the cell (→ p. 179 D2); the human Na^+-dicarboxylate transporter hNaDC-1 also conveys dicarboxylates (in combination with 3 Na^+) into the cell by secondary active transport (→ **B2**). The transport of OA^- is therefore called *tertiary active transport*. The efflux of OA^- into the lumen is passive (facilitated diffusion; → **B3**). An ATP-dependent *conjugate pump* (MRP2 = multi-drug resistance protein type 2) in the luminal membrane is also used for secretion of amphiphilic conjugates, such as glutathione-linked lipophilic toxins (→ **B4**).


The **organic cations** (**OC^+**) secreted include endogenous substances (epinephrine, choline, histamine, serotonin, etc.) and drugs (atropine, quinidine, morphine, etc.).

In contrast to OA^- secretion, the *active step* of **OC^+ secretion** occurs across the *luminal* membrane of proximal tubule cells (luminal accumulation occurs after overcoming the negative membrane potential inside the cell). The membrane contains (a) direct ATP-driven carriers for organic cations (mdr1; primary active OC^+ transport; → **C1**) and (b) a multispecific OC^+/H^+ antiporter (tertiary active transport; → **C2**). The OC^+ diffuse passively from the blood into the cell by way of a polyspecific organic cation transporter (OCT; → **C3**).


A. Secretion and excretion of p-aminohippurate (PAH)



B. Secretion of organic anions (OA^-)



C. Secretion of organic cations (OC^+)



About 99% of the *filtered load of* Na^+ is reabsorbed (ca. 27 000 mmol/day), i.e., the fractional excretion of Na^+ (FE_{Na}) is about 1%. The precise value of FE_{Na} needed (range 0.5 to 5%) is regulated by aldosterone, atriopeptin (ANF) and other hormones (→ **B9** and p. 170).

Sites of Na^+ reabsorption. The reabsorption of Na^+ occurs in all parts of the renal tubule and collecting duct. About 65% of the filtered Na^+ is reabsorbed in the proximal tubule, while the luminal Na^+ conc. remains constant (→ p. 166). Another 25% is reabsorbed in the loop of Henle, where luminal Na^+ conc. drops sharply; → p. 157 D, columns 2 and 3). The distal convoluted tubule and collecting duct also reabsorb Na^+. The latter serves as the site of hormonal *fine adjustment* of Na^+ excretion.

Mechanisms of Na^+ reabsorption. Na^+-K^+-ATPase pumps Na^+ ions out of the cell while conveying K^+ ions into the cell (→ **A** and p. 156), thereby producing a chemical Na^+ gradient (→ **A2**). Back diffusion of K^+ (→ **A3**) also leads to the development of a membrane potential (→ **A4**). Both combined result in a high electrochemical Na^+ gradient that provides the driving "force" for passive Na^+ influx, the features of which vary in the individual nephron segments (→ **B**).

◆ In the **proximal tubule**, Na^+ ions diffuse passively from the tubule lumen into the cells via (a) the electroneutral Na^+/H^+ exchanger type 3 (NHE3), an *Na^+/H^+-antiport* carrier for electroneutral exchange of Na^+ for H^+ (→ **B1**, p. 29 B4 and p. 176) and (b) various *Na^+ symport carriers* for reabsorption of D-glucose etc. (→ **B1** and p. 158). Since most of these symport carriers are electrogenic, the luminal cell membrane is depolarized, and an early proximal *lumen-negative transepithelial potential* (L**N**TP) develops.

◆ In the thick ascending limb (**TAL**) of the **loop of Henle** (→ **B6**), Na^+ is reabsorbed via the bumetanide-sensitive co-transporter BSC, a *Na^+-K^+-2 Cl^- symport carrier* (→ p. 172). Although BSC is primarily electroneutral, the absorbed K^+ recirculates back to the lumen through K^+ channels. This hyperpolarizes the luminal membrane, resulting in the development of a lumen-positive transepithelial potential (L**P**TP).

◆ In the **distal convoluted tubule, DCT** (→ **B8**), Na^+ is reabsorbed via the thiazide-sensitive co-transporter TSC, an electroneutral Na^+-Cl^- symport carrier (→ p. 174).


◆ In *principal cells* of the connecting tubule and collecting duct (→ **B9**), Na^+ exits the lumen via *Na^+ channels* (ENaC) activated by aldosterone and antidiuretic hormone (ADH) and inhibited by prostaglandins and ANF (→ p. 170).

Since these four passive Na^+ transport steps in the luminal membrane are serially connected to active Na^+ transport in the basolateral membrane (Na^+-K^+-ATPase), the associated **transepithelial Na^+ reabsorption** is also *active*. This makes up about $^1/_3$ of the Na^+ reabsorption in the proximal tubule, and 1 ATP molecule is consumed for each 3 Na^+ ions absorbed (→ p. 26). The other $^2/_3$ of proximal sodium reabsorption is passive and **paracellular**.

Two **driving "forces"** are responsible for this: (1) the L**P**TP in the mid and late proximal tubule (→ **B5**) and in the loop of Henle (→ **B7**) drives Na^+ and other cations onto the blood side of the epithelium. (2) **Solvent drag** (→ p. 24): When water is reabsorbed, solutes for which the reflection coefficient < 1 (including Na^+) are "dragged along" due to friction forces (like a piece of wood drifts with flowing water). Since driving forces (1) and (2) are indirect products of Na^+-K^+-ATPase, the **energy balance** rises to about 9 Na^+ per ATP molecule in the proximal tubule (and to about 5 Na^+ per ATP molecule in the rest of the kidney).

On the basolateral side, Na^+ ions exit the proximal tubule cell via Na^+-K^+-ATPase and an Na^+-3 HCO_3^- symport carrier (→ p. 176). In the latter case, Na^+ exits the cell via tertiary active transport as secondary active secretion of H^+ (on the opposite cell side) results in intracellular accumulation of HCO_3^-.

The **fractional Cl^- excretion** (FE_{Cl}) ranges from 0.5% to 5%. About 50% of all **Cl^- reabsorption** occurs in the *proximal tubule*. The early proximal L**N**TP drives Cl^- through paracellular spaces out of the lumen (→ **B3**). The reabsorption of Cl^- lags behind that of Na^+ and H_2O, so the luminal Cl^- conc. rises. As a result, Cl^- starts to diffuse down its chemical gradient paracellularly along the mid and late proximal tubule (→ **B4**), thereby producing a L**P**TP (reversal of potential, → **B5**). At the TAL and the DCT, Cl^- enters the cells by secondary active transport and exits passively through ADH-activated basolateral Cl^- channels (→ **B6, 8**).


A. Electrochemical Na+ gradient
Lumen
Blood
K+
Na+
ATP
Na+-K+-ATPase
1
Primary active Na+ and K+ transport
Na+
145 mmol/L
15 mmol/L
2
Δ[Na+] = Chemical driving force for Na+
K+
–70 mV
3
Back diffusion of K+ creates membrane potential
4
Membrane potential = electrical driving force for Na+
B. Na+ and Cl– reabsorption
Early proximal
1
Electroneutral Na+/H+ exchanger
H+
Glucose0 etc.
2
Electrogenic Na+ symport
LNTP
Cl–
3
Cl– reabsorption
Thick ascending limb of Henle's loop
6
Na+-2Cl–-K+ symport
2Cl–
BSC
Recirculation of K+
LPTP
7
Reabsorption of cations
Ca2+
Mg2+
Distal convoluted tubule
8
Na+-Cl– symport
TSC
Mid/late proximal
H2O
Δ[Cl–]
4
Cl– reabsorption
LPTP
5
Reabsorption of cations
Na+
Filtrate: 100%
Late proximal: 35%
Early distal: 10%
Final urine: 0.5–5%
Collecting duct (principal cells)
9
Na+ transported via channels
Aldosterone, ADH
Prostaglandins, ANP

The glomeruli filter around 180 L of plasma water each day (= GFR; → p. 152). By comparison, the normal **urine output** ($\dot{V}_U$) is relatively small (**0.5 to 2 L/day**). Normal fluctuations are called *antidiuresis* (low $\dot{V}_U$) and *diuresis* (high $\dot{V}_U$; → p. 174). Urine output above the range of normal is called *polyuria*. Below normal output is defined as *oliguria* (< 0.5 L/day) or *anuria* (< 0.1 L/day). The **osmolality** (→ p. 383) of plasma and glomerular filtrate is about 290 mOsm/kg H_2O (= P_{osm}); that of the final urine (U_{osm}) ranges from 50 (hypotonic urine in extreme water diuresis) to about 1200 mOsm/kg H_2O (hypertonic urine in maximally concentrated urine). Since *water diuresis* permits the excretion of large volumes of H_2O without the simultaneous loss of NaCl and other solutes, this is known as "free water excretion", or "free water clearance" (C_{H_2O}). This allows the kidneys to normalize decreases in plasma osmolality, for example (→ p. 170). The C_{H_2O} represents the volume of water that could be theoretically extracted in order for the urine to reach the same osmolality as the plasma:

$$C_{H_2O} = \dot{V}_U\,(1 - [U_{osm}/P_{osm}]). \qquad [7.11]$$

Countercurrent Systems

A **simple exchange** system (→ **A1**) can consist of two tubes in which *parallel streams* of water flow, one cold (0 °C) and one hot (100 °C). Due to the exchange of heat between them, the water leaving the ends of both tubes will be about 50 °C, that is, the initially steep temperature gradient of 100 °C will be offset.

In **countercurrent exchange** of heat (→ **A2**), the fluid within the tubes flows in *opposite directions*. Since a temperature gradient is present in all parts of the tube, heat is exchanged along the entire length. Molecules can also be exchanged, provided the wall of the tube is permeable to them and that a concentration gradient exists for the substance.

If the countercurrent exchange of heat occurs in a **hairpin-shaped loop**, the bend of which is in contact with an environment with a temperature different from that inside the tube (ice, → **A3**), the fluid exiting the loop will be only slightly colder than that entering it, because heat always passes from the warmer limb of the loop to the colder limb.


Countercurrent exchange of **water** in the **vasa recta** of the *renal medulla* (→ **A6** and p. 150) occurs if the medulla becomes increasingly hypertonic towards the papillae (see below) and if the vasa recta are permeable to water. Part of the water diffuses by osmosis from the descending vasa recta to the ascending ones, thereby "bypassing" the inner medulla (→ **A4**). Due to the extraction of water, the concentration of all other blood components increases as the blood approaches the papilla. The plasma osmolality in the vasa recta is therefore continuously adjusted to the osmolality of the surrounding interstitium, which rises towards the papilla. The hematocrit in the vasa recta also rises. Conversely, substances entering the blood in the renal medulla diffuse from the ascending to the descending vasa recta, provided the walls of both vessels are permeable to them (e.g., urea; → **C**). The countercurrent exchange in the vasa recta permits the necessary supply of blood to the renal medulla without significantly altering the high osmolality of the renal medulla and hence impairing the urine concentration capacity of the kidney.

In a **countercurrent multiplier** such as the **loop of Henle**, a concentration gradient between the two limbs is maintained by the expenditure of energy (→ **A5**). The countercurrent flow amplifies the relatively small gradient at all points between the limbs (*local gradient* of about 200 mOsm/kg H_2O) to a relatively large gradient along the limb of the loop (about 1000 mOsm/kg H_2O). The longer the loop and the higher the one-step gradient, the steeper the multiplied gradient. In addition, it is inversely proportional to (the square of) the flow rate in the loop.


Reabsorption of Water

Approximately 65% of the GFR is reabsorbed at the **proximal convoluted tubule, PCT** (→ **B** and p. 157 D). The driving "force" for this is the reabsorption of solutes, especially Na^+ and Cl^-. This slightly dilutes the urine in the tubule, but H_2O immediately follows this small osmotic gradient because the PCT is "leaky" (→ p. 154). The reabsorption of water can occur by a *paracellular* route (through leaky tight junctions) or *transcellular* route, i.e., through *water channels* (aquaporin type 1 = *AQP1*) in the two cell membranes. The urine in PCT therefore remains (virtually) isotonic. *Oncotic pressure* (→ p. 384) in the peritubular capillaries provides an additional driving force for water reabsorption. The more water filtered at the glomerulus, the higher this oncotic pressure. ▶


A. Countercurrent systems




1 Simple exchange system




2 Countercurrent exchange




3 Countercurrent exchange (heat) in loop



4 Countercurrent exchange (water) in loop (e.g. vasa recta)



5 Countercurrent multiplier (Henle's loop)



6 Countercurrent systems in renal medulla

▶ Thus, the reabsorption of water at the proximal tubule is, to a certain extent, adjusted in accordance with the GFR (**glomerulotubular balance**).

Because the *descending limb* of the **loop of Henle** has aquaporins (AQP1) that make it permeable to water, the urine in it is largely in osmotic balance with the hypertonic interstitium, the content of which becomes increasingly hypertonic as it approaches the papillae (→ **A5**). The urine therefore becomes increasingly concentrated as it flows in this direction. In the *thin* descending limb, which is only sparingly permeable to salt, this increases the conc. of Na^+ and Cl^-. Most water drawn into the interstitium is carried off by the vasa recta (→ **B**). Since the *thin* and *thick ascending limbs* of the loop of Henle are largely impermeable to water, Na^+ and Cl^- passively diffuses (thin limb) and is actively transported (thick limb) out into the interstitium (→ **B**). Since water cannot escape, the urine leaving the loop of Henle is *hypotonic*.


Active reabsorption of Na^+ and Cl^- from the thick ascending limb of the loop of Henle (TAL; → p. 162) creates a **local gradient** (ca. 200 mOsm/kg H_2O; → **A5**) at all points between the TAL on the one side and the descending limb and the medullary interstitium on the other. Since the high osmolality of fluid in the medullary interstice is the reason why water is extracted from the collecting duct (see below), active NaCl transport is the ATP-consuming *"motor" for the kidney's urine-concentrating mechanism* and is up-regulated by sustained stimulation of ADH secretion.


Along the course of the **distal convoluted tubule** and, at the latest, at the **connecting tubule**, which contains aquaporins and ADH receptors of type V_2 (explained below), the fluid in the tubule will again become isotonic (in osmotic balance with the isotonic interstice of the renal cortex) if *ADH* is present (→ p. 168), i.e., when *antidiuresis* occurs. Although Na^+ and Cl^- are still reabsorbed here (→ p. 162), the osmolality does not change significantly because H_2O is reabsorbed (ca. 5% of the GFR) into the interstitial space due to osmotic forces and *urea* increasingly determines the osmolality of the tubular fluid.

Final adjustment of the excreted urine volume occurs in the **collecting duct**. In the presence of antidiuretic hormone, **ADH** (which binds to basolateral V_2 receptors, named after vasopressin, the synonym for ADH), *aquaporins* (**AQP2**) in the (otherwise water-impermeable) luminal membrane of principal cells are used to extract enough water from the urine passing through the increasingly hypertonic renal medulla. Thereby, the U_{osm} rises about four times higher than the P_{osm} ($U_{osm}/P_{osm} \approx 4$), corresponding to *maximum antidiuresis*. The *absence of ADH* results in *water diuresis*, where U_{osm}/P_{osm} can drop to < 0.3. The U_{osm} can even fall below the osmolality at the end of TAL, since reabsorption of Na^+ and Cl^- is continued in the distal convoluted tubule and collecting duct (→ p. 162) but water can hardly follow.

Urea also plays an important role in the formation of concentrated urine. A protein-rich diet leads to increased urea production, thus increased the urine-concentrating capacity of the kidney. About 50% of the filtered urea leaves the proximal tubule by diffusion (→ **C**). Since the ascending limb of the loop of Henle, the distal convoluted tubule, and the cortical and outer medullary sections of the collecting duct are only sparingly permeable to urea, its conc. increases downstream in these parts of the nephron (→ **C**). **ADH** can (via V_2 receptors) introduce *urea carriers* (urea transporter type 1, UT1) in the luminal membrane, thereby making the inner medullary collecting duct permeable to urea. Urea now diffuses back into the interstitium (where urea is responsible for half of the high osmolality there) via UT1 and is then transported by UT2 carriers back into the descending limb of the loop of Henle, comprising the **recirculation of urea** (→ **C**). The non-reabsorbed fraction of urea is excreted: $FE_{urea} \approx 40\%$. Urea excretion increases in water diuresis and decreases in antidiuresis, presumably due to up-regulation of the UT2 carrier.

Urine concentration disorders primarily occur due to (a) excessive medullary blood flow (washing out Na^+, Cl^- and urea); (b) osmotic diuresis; (c) loop diuretics (→ p. 174); (d) deficient secretion or effectiveness of ADH, as seen in *central* or *peripheral diabetes insipidus*, respectively.


B. Water reabsorption and excretion
GFR = 100%
Plasma water
Water follows NaCl
H2O follows NaCl, etc.
65%
Cortex
290 mosm/kg H2O
220
Rest: 25%
NaCl
ADH
H2O permeability subject to ADH control
Rest: 35%
Outer medulla
600
Watertight
High H2O permeability in antidiuresis
0.5%
Maximum antidiuresis
High osmolality of interstitium: H2O outflow
FEH2O
Inner medulla
1200
10%
5% and more
Maximum water diuresis


C. Urea in the kidney
100%
Urea
100%
Urea concentration (mmol/L)
5
Impermeable to urea
Passive reabsorption
Rest: 50%
Circulates via countercurrent exchange in vasa recta
Recirculation of urea
500
Urea permeability subject to ADH control
40%
FEurea

Water is the initial and final product of countless biochemical reactions. It serves as a solvent, transport vehicle, heat buffer, and coolant, and has a variety of other functions. Water is present in cells as *intracellular fluid* (→ p. 2).

The volume of fluid circulating in the body remains relatively constant when the **water balance** (→ **A**) is properly regulated. The average **fluid intake** of ca. 2.5 L per day is supplied by *beverages, solid foods*, and *metabolic oxidation* (→ p. 231 C). The fluid intake must be high enough to counteract **water losses** due to *urination, respiration, perspiration* (→ p. 225 B3), and *defecation* (→ p. 267 C). The mean daily H_2O turnover is 2.5 L/70 kg (1/30 th the body weight [BW]) in adults and 0.7 liters/7 kg (1/10th the BW) in infants. The water balance of infants is therefore more susceptible to disturbance.

Significant **rises in the H_2O turnover** can occur, but must be adequately compensated for if the body is to function properly (regulation, → p. 170). Respiratory H_2O losses occur, for example, due to *hyperventilation* at high altitudes (→ pp. 106 and 136), and *perspiration losses* (→ p. 224) occur due to exertion at high temperatures (e.g., hiking in the sun or hot work environment as in an ironworks). Both can lead to the loss of several liters of water per hour, which must be compensated for by increasing the intake of fluids (and salt) accordingly. Conversely, an increased intake of fluids will lead to an increased volume of urine being excreted (→ p. 170).

Body water content (→ **B**). The fraction of total body water (TBW) to body weight (BW = 1.0) ranges from **0.46** (46%) **to 0.75** depending on a person's age and sex (→ **B**). The TBW content in *infants* is 0.75 compared to only 0.64 (0.53) in young men (women) and 0.53 (0.46) in elderly men (women). Gender-related differences (and interindividual differences) are mainly due to differences in a person's total *body fat content*. The average fraction of water in most body tissues (in young adults) is 0.73 compared to a fraction of only about 0.2 in fat.


Fluid compartments (→ **C**). In a person with an average TBW of ca. 0.6, about 3/5 (0.35 BW) of the TBW is intracellular fluid (**ICF**), and the other 2/5 (0.25 BW) is extracellular (**ECF**). ICF and ECF are therefore separated by the plasma membrane of the cells. Extracellular fluid is located between cells (*interstice*, 0.19 BW), in blood (*plasma water* (0.045 BW) and in *"transcellular"* compartments (0.015 BW) such as the pleural, peritoneal and pericardial spaces, CSF space, chambers of the eye as well as intestinal lumen, renal tubules and glandular ducts (→ **C**). Blood plasma is separated from the interstice by the *endothelium*, while the epithelium divides the interstice from the transcellular compartments. The *protein concentration* of the plasma is significantly different from that of the interstitial fluid. Moreover, there are fundamental differences in the *ionic composition* of the ECF and the ICF (→ p. 93 C). Since most of the body's supply of Na^+ ions are located in extracellular compartments, the total Na^+ content of the body determines its ECF volume (→ p. 170).

Measurement of fluid compartments. In clinical medicine, the body's fluid compartments are usually measured by *indicator dilution techniques*. Provided the indicator substance, S, injected into the bloodstream spreads to the target compartment only (→ **C**), its volume V can be calculated from:


$$\mathbf{V[L] = \text{injected amount of indicator S [mol]}/C_S\,[\text{mol/L}]} \qquad [7.12]$$

where C_S is the concentration of S after it spreads throughout the target compartment (measured in collected blood specimens). The ECF volume is generally measured using *inulin* or sodium bromide as the indicator (does not enter cells), and the TBW volume is determined using *antipyrine*, heavy water (D_2O) or radiolabeled H_2O. The ICF volume is approximately equal to the antipyrine distribution volume minus the inulin distribution volume. Radiolabeled albumin or *Evans blue*, a substance entirely bound by plasma proteins, can be used to measure the plasma volume. The interstitial volume can be calculated as the ECF volume minus the plasma volume, and the blood volume as the plasma volume divided by [1 – hematocrit] (→ p. 88). (Since $^1/_{10}$ of the plasma remains interspersed with the erythrocytes after centrifuging, replacing 1 with 0.91 in this formula gives a more precise result.) The blood volume can also be determined by injection of ^{51}Cr-marked erythrocytes, so that the plasma volume is then calculated as blood volume times (0.91 – Hct).


A. Water balance



B. Total body water (TBW) content



C. Fluid compartments of the body



Osmoregulation. The osmolality of most body fluids is about 290 mOsm/kg H_2O (→ p. 383), so that the intracellular fluid (ICF) and extracellular fluid (ECF) are generally in osmotic balance. Any increase in the osmolality of ECF due, for example, to NaCl absorption or water loss, results in an outflow of water from the intracellular space (**Cell shrinkage**, → **A1** and p. 175 A2 and 6). A fall in extracellular osmolality due to drinking or infusion of large volumes of water or to sodium loss (e.g. in aldosterone deficit) results in an inflow of water to the cells from the ECF (**cell expansion**, →**A2** and p. 175 A3 and 5). Both volume fluctuations endanger the cell's functioning, but the cell can protect against them.

The cell's plasma membrane contains **mechanosensors** that stimulate balancing ion flow accompanied by water, for example K^+ and Cl^- outflow in cell volume expansion and Na^+, K^+, and Cl^- inflow in cell shrinkage. Such mechanisms also balance a volume expansion resulting from increased absorption of Na^+ and glucose in intestinal mucous cells or from a momentary hypoxy of a cell (with decreasing Na^+-K^+-ATPase activity).

Cells which are physiologically exposed to large osmolality fluctuations (e.g. in the kidney), are further able to regulate their intracellular osmolality through formation/absorbtion, or release/resorption of small molecular substances known as **organic osmolytes** (e.g. betaine, taurine, *myo*-inositol, sorbitol).


The osmolality of the ECF as a whole must be tightly regulated to protect cells from large volume fluctuations. Osmoregulation is controlled by *central osmosensors* (or *osmoreceptors*) located in circumventricular organs (SFO and OVLT, see below). H_2O fluctuations in the gastrointestinal tract are monitored by peripheral osmosensors in the portal vein region and communicated to the hypothalamus by vagal afferent neurons.

Water deficit (→ **B1**). Net water losses (hypovolemia) due, for example, to sweating make the ECF hypertonic. Osmolality rises of only 1–2% (= 3–6 mOsm/kg H_2O) are sufficient to increase the secretion of **ADH** (antidiuretic hormone = vasopressin; → p. 282), from the posterior lobe of the pituitary (→ **C1**). ADH decreases urinary H_2O excretion (→ p. 166). Fluid intake from outside the body is also required, however. The likewise hypertonic cerebrospinal fluid (CSF), via osmosensors in the OVLT (organum vasculosum laminae terminalis) and SFO (subfornical organ) stimulates the secretion of (central) angiotensin II (**AT II**) which trigger *hyperosmotic* **thirst** (→ C). **Isotonic hypovolemia**, for example following blood loss or secondarily following hyponatremia (**D1**), also stimulates thirst (hypovolemic thirst, → **C**), but the procentual deficit of the ECF in this case must be greater (> 10%) than the procentual increase in osmolality for hyperosmotic thirst (1–2%). The sensors for hypovolemia are primarily the atrial volume sensors (→ p. 216 ff). Via their afferent pathways and the nucleus tractus solitarii (NTS) secretion of central AT II is triggered in the SFO (→ **C**, **D1**) and via the sympathetic nervous system and β_1-adrenoceptors in the kidney the peripheral renin-AT-II system (**RAS**) is activated (→ **A4** and p. 186). A drop in mean blood pressure below approx. 85 mm Hg triggers very high renin secretion directly in the kidney. Like central AT II, peripheral AT II can also contribute to thirst and to increased Na^+ appetite, because the SFO and OVLT are located outside the blood–brain barrier.


Relaxin, a peptide hormone produced by the corpus luteum in pregnant women, binds to receptors in the SFO and OVLT. It causes thirst and stimulates ADH secretion. Despite the reduced plasma osmolality during pregnancy, which would suppress thirst and ADH secretion, relaxin evidently provides for normal or even increased fluid intake during pregnancy.

Thirst is a subjective perception and motivation to search for fluids and drink. The thirst that is a homeostatic response to hyperosmolality or hypovolemia (> 0.5% of body weight: thirst threshold) triggers *primary drinking*. Drinking quenches the thirst before osmolality has completely normalized. This pre-resorptive thirst quenching is astonishingly accurate as regards the estimate of volume, due to afferent signals from volume sensors and osmosensors in the throat, gastrointestinal tract, and liver. Primary drinking, however, is actually the exception under normal conditions where adequate fluids are available for drinking. A person usually drinks because she has a dry mouth or while eating a meal, but also out of habit, because it is cus- ▶

A. Water output and intake from the cell



B. Regulation of salt and water balance



▶ tomary or part of social ritual. This everyday form of drinking is called *secondary drinking*.

In older age thirst decreases, and 30% of 65–74-year-olds and 50% of the over 80s drink too little fluids. Since in older age the urine concentration capacity and ADH and aldosterone secretion also decrease, a substantial fluid deficit is common. This is a cause of confusion and forgetfulness, so that in turn the fluid intake drops further and sets off a vicious circle. Some older people also try to combat nocturia and pollakisuria by drinking less, which further dehydrates the body.

Water excess (→ **B2**). The absorption of hypotonic fluid including for example stomach flushes or the infusion of glucose solutions (where the glucose is quickly metabolized into CO_2 and water) reduces the osmolality of ECF. This signal inhibits the secretion of ADH, resulting in water diuresis (→ p. 166) and normalization of plasma osmolality within less than 1 hour.

Water intoxication occurs when excessive volumes of water are absorbed too quickly, leading to symptoms of nausea, vomiting and shock. The condition is caused by an undue drop in the plasma osmolality before adequate inhibition of ADH secretion has occurred.

Volume regulation. Around 8–15 g of NaCl are absorbed each day. The kidneys have to excrete the same amount over time to maintain Na^+ and ECF homeostasis (→ p. 168). Since Na^+ is the major extracellular ion (Cl^- balance is maintained secondarily), *changes in total body Na^+ content lead to changes in ECF volume*. It is regulated mainly by the following **factors**:

◆ *Renin–angiotensin system (**RAS**)* AT II not only induces *thirst* and *salt* appetite, but also reduces the GFR and promotes the secretion of ADH and **aldosterone**, which inhibits Na^+ excretion (→ **D2** and p. 163 B9) and, despite recent water intake, maintains a stable salt appetite.

◆ Oxytocin, a neurotransmitter produced in the hypothalamus, inhibits the neurons which uphold the continued salt appetite and via neuronal pathways causes increased NaCl excretion.

◆ *Atriopeptin* (*atrial natriuretic peptide; **ANP***) is a peptide hormone secreted by specific cells of the cardiac atrium in response to rises in ECF volume and hence atrial pressure. ANP inhibits thirst and reduces ADH secretion. It also promotes the renal excretion of Na^+ by raising the filtration fraction (→ p. 152) and inhibiting Na^+ reabsorption from the collecting duct (→ p. 163 B9). ANP is therefore effectively an antagonist to RAS.


◆ ***ADH.*** ADH secretion is stimulated by (a) *increased plasma* and *CSF osmolality*; (b) the *Gauer-Henry reflex,* which occurs when a decrease (> 10%) in ECF volume (~ atrial pressure) is communicated to the hypothalamus. AT II is the key agent for this.

◆ **Pressure diuresis** (→ p. 174) results in increased excretion of Na^+ and water. It is caused by an elevated blood pressure in the renal medulla, e.g. due to an elevated ECF volume (→ p. 218).


Salt deficit (→ **D1**). When hyponatremia (e.g. in aldosterone deficit) occurs in the presence of a primarily normal H_2O content of the body, blood osmolality and therefore ADH secretion decrease, thereby increasing transiently the excretion of H_2O. Although the hypoosmolality is elevated the ECF volume, plasma volume, and blood pressure consequently decrease (→ **D1**). This, in turn, activates the RAS, which triggers *hypovolemic thirst* by secreting AT II and induces Na^+ retention by secreting aldosterone. The retention of Na^+ increases plasma osmolality leading to secretion of ADH and, ultimately, to the retention of water. The additional intake of fluids in response to *thirst* also helps to normalize the ECF volume.

Salt excess (→ **D2**). An abnormally high NaCl content of the body e.g. after drinking salt water leads to increased plasma osmolality (thirst → drinking) as well as ADH secretion (retention of H_2O). Thus, the ECF volume rises and RAS activity is curbed. The additional secretion of ANP, perhaps together with a natriuretic hormone with a longer half-life than ANP (ouabain?), leads to increased excretion of NaCl and H_2O.

C. Thirst: activation and inhibition



D. Regulation of salt balance



▶ When *osmolality* remains normal, disturbances of salt and water homeostasis only affect the ECF volume (→ **E1**, **4**). When the osmolality of the ECF increases (hyperosmolality) or decreases (hypoosmolality), water in the extra- and intracellular compartments is redistributed (→ **E2**, **3**, **5**, **6**). The main **causes** of these disturbances are listed in **E** (orange background). The **effects** of these disturbances are *hypovolemia* in cases 1, 2 and 3, *intracellular edema* (e.g. swelling of the brain) in disturbances 3 and 5, and *extracellular edema* (pulmonary edema) in disturbances 4, 5, and 6.

Diuresis and Diuretics

Increases in urine excretion above 1 mL/min (**diuresis**) can have the following **causes**:

◆ **Water diuresis**: Decreases in plasma osmolality and/or an increased blood volume lead to the reduction of ADH levels and, thus, to the excretion of "free water" (→ p. 164).

◆ **Osmotic diuresis** results from the presence of non-reabsorbable, osmotically active substances (e.g., mannitol) in the renal tubules. These substances retain H_2O in the tubule lumen, which is subsequently excreted. Osmotic diuresis can also occur when the concentration of a reabsorbable substance (e.g., glucose) exceeds its tubular reabsorption capacity resulting from hyperglycemia (→ p. 158). The glucosuria occurring in diabetes mellitus is therefore accompanied by diuresis and a secondary increase in thirst. Hyperbicarbonaturia can lead to osmotic diuresis to the same reason (→ p. 178).

◆ **Pressure diuresis** occurs when osmolality in the renal medulla decreases in the presence of increased renal medullary blood flow due, in most cases, to hypertension (→ p. 170).

◆ **Diuretics** (→ **F**) are drugs that induce diuresis. Most of them (except osmotic diuretics like mannitol) work primarily by inhibiting NaCl reabsorption (*saluretics*) and, secondarily, by decreasing water reabsorption. The goal of therapeutic diuresis, e.g., in treating edema and hypertension, is to reduce the ECF volume.

Although diuretics basically inhibit NaCl transport throughout the entire body, they have a large degree of **renal "specificity"** because they act from the tubular lumen, where they become highly concentrated due to **tubular secretion** (→ p. 160) and tubular water reabsorption. Therefore, dosages that do not induce unwanted systemic effects are therapeutically effective in the tubule lumen.

Diuretics of the **carbonic anhydrase inhibitor type** (e.g., acetazolamide, benzolamide) decrease Na^+/H^+ exchange and HCO_3^- reabsorption in the *proximal tubule* (→ p. 176 ff.). The overall extent of diuresis achieved is small because more distal segments of the tubule reabsorb the NaCl not reabsorbed upstream and because the GFR decreases due to tubuloglomerular feedback, TGF (→ p. 186). In addition, increased HCO_3^- excretion also leads to non-respiratory (metabolic) acidosis. Therefore, this type of diuretic is used only in patients with concomitant alkalosis.


Loop diuretics (e.g., furosemide and bumetanide) are highly effective. They inhibit the *bumetanide-sensitive co-transporter BSC* (→ p. 162 B6), a Na^+-$2Cl^-$-K^+ symport carrier, in the thick ascending limb (TAL) of the loop of Henle. This not only decreases NaCl reabsorption there, but also stalls the "motor" on the concentration mechanism (→ p. 166). Since the lumen-positive transepithelial potential (**L**PTP) in the TAL also falls (→ p. 162 B7), paracellular reabsorption of Na^+, Ca^{2+} and Mg^{2+} is also inhibited. Because increasing amounts of non-reabsorbed Na^+ now arrive at the collecting duct (→ p. 183 B3), K^+ secretion increases and the simultaneous loss of H^+ leads to *hypokalemia* and hypokalemic *alkalosis*.

Loop diuretics inhibit BSC at the **macula densa**, thereby "tricking" the juxtaglomerular apparatus (JGA) into believing that no more NaCl is present in the tubular lumen. The GFR then rises as a result of the corresponding tubuloglomerular feedback (→ p. 186), which further promotes diuresis.


Thiazide diuretics inhibit NaCl resorption in the distal tubule (TSC, → p. 162 B8). Like loop diuretics, they increase Na^+ reabsorption downstream, resulting in losses of K^+ and H^+.

Potassium-sparing diuretics. *Amiloride* blocks Na^+ channels in the principal cells of the connecting tubule and collecting duct, leading to a *reduction of K^+ excretion*. *Aldosterone antagonists* (e.g., spironolactone), which block the cytoplasmic aldosterone receptor, also have a potassium-sparing effect.

E. Disturbances of salt and water homeostasis



F. Site of action of diuretics



Main functions of renal **H^+ secretion** (→ **A**):
— reabsorption of filtered bicarbonate (→ **B**),
— excretion of H^+ ions measurable as titratable acidity (→ **C**), and
— nonionic transport of NH_4^+, i.e. in the form of NH_3 (→ **D1, 2**).

1. Very large quantities of H^+ ions are secreted into the lumen of the **proximal tubule** (→ **A1**) by (a) primary active transport via *H^+-ATPase* and (b) by secondary active transport via an electroneutral *Na^+/H^+-antiporter* (NHE3 = SLC 9 A3, → p. 162). The *luminal pH* then decreases from 7.4 (filtrate) to about 6.6. One OH^- ion remains in the cell for each H^+ ion secreted; OH^- reacts with CO_2 to form HCO_3^- (accelerated by carbonic anhydrase-II, see below). HCO_3^- leaves the cell for the blood, where it binds one H^+ ion. Thus, each H^+ ion secreted into the lumen (and excreted) results in the elimination of one H^+ ion from the body, except the secreted H^+ is accompanied by a secreted NH_3.

2. In the **connecting tubule** and **collecting duct** (→ **A2**) *type A intercalated cells* secrete H^+ ions via H^+/K^+-ATPase and H^+-ATPase, allowing the luminal pH to drop as far as 4.5. The remaining OH^- in the cell reacts with CO_2 to HCO_3^-, released basolaterally via the *anion exchanger* AE1 (= SLC 4 A1) (→ **A2**). In metabolic alkalosis, *type B intercalated cells* can secrete HCO_3^- via pendrin (= SLC 26 A4) (→ **A3**).

Carbonic anhydrase (**CA**) is important in all cases where H^+ ions exit from one side of a cell and/or HCO_3^- exits from the other, e.g., in renal tubule cells, which contain CA^{II} in the cytosol and CA^{IV} on the outside of the luminal membrane; → **A, B, D**), as well as in the stomach, small intestine, pancreatic duct and erythrocytes, etc. CA catalyzes the gross reaction

$$\mathbf{H_2O + CO_2 \rightleftharpoons H^+ + HCO_3^-.} \qquad [7.13]$$

Underlying the aforementioned gross reaction are the reactions $H_2O \rightleftharpoons OH^- + H^+$ and $OH^- + CO_2 \rightleftharpoons HCO_3^-$.


Reabsorption of HCO_3^- (→ **B**). The amount of HCO_3^- filtered each day is 40 times the quantity present in the blood. HCO_3^- must therefore be reabsorbed to maintain acid–base balance (→ p. 183ff.). The H^+ ions secreted into the lumen of the proximal convoluted tubule react with about 90% of the filtered HCO_3^- to form CO_2 and H_2O (→ **B**). CA^{IV} anchored in the membrane catalyzes this reaction. CO_2 readily diffuses into the cell via water channels (aquaporin 1 → B and p. 166). CA^{II} then catalyzes the transformation of $CO_2 + H_2O$ to $H^+ + HCO_3^-$ within the cell (→ **B**). The H^+ ions are again secreted, while HCO_3^- exits through the basolateral membrane of the cell via an electrogenic Na^+- bicarbonate cotransporter (NBC1 = NBCe1 = SLC4 A4; → **B**) co-transports 1 Na^+ with 3 HCO_3^- (and/or with 1 $HCO_3^- + 1\ CO_3^{2-}$?) Thus, HCO_3^- is transported through the luminal membrane in the form of CO_2 (driving force: ΔP_{CO_2}), and exits the cell across the basolateral membrane as HCO_3^- (main driving force: membrane potential).

Hypokalemia leads to a rise in membrane potential (Nernst equation, → p. 32) and thus to a rise in basolateral HCO_3^- transport. This results in increased H^+ secretion and, ultimately, in **hypokalemic alkalosis.**

Urinary acid excretion. If the dietary protein intake is 70 g/day (→ p. 228), a daily load of about 190 mmol of H^+ occurs after the amino acids of the protein have been metabolized. HCl (from arginine, lysine and histidine), H_2SO_4 (from methionine and cystine), H_3PO_4, and lactic acid are the main sources of H^+ ions. They are "fixed" acids which, unlike CO_2, are not eliminated by respiration. Since about 130 mmol H^+/day are used to break down organic anions ($glutamate^-$, $aspartate^-$, $lactate^-$, etc.), the **net H^+ production** is about **60** (40–80) **mmol/day**. Although the H^+ ions are buffered at their production site, they must be excreted to regenerate the buffers.

In extreme cases, the **urinary pH** can rise to about pH 8 (high HCO_3^- excretion) or fall to about pH 4.5 (maximum H^+ conc. is 0.03 mmol/L). At a daily urine output of 1.5 L, the kidneys will excrete < 1% of the produced H^+ ions in their free form.

Titratable acids (80% phosphate, 20% uric acid, citric acid, etc.) comprise a significant fraction (10–30 mmol/day) of H^+ excretion (→ **C1**). This amount of H^+ ions can be determined by titrating the urine with NaOH back to the plasma pH value, which is normally pH 7.4 (→ **C2**). Around 80% of **phosphate** ($pK_a = 6.8$) in the blood occurs in the form of HPO_4^{2-}, whereas about all phosphate in acidic urine occurs as $H_2PO_4^-$ (→ p. 386), i.e., the secreted H^+ ions are buffered by filtered HPO_4^{2-}. Non-reabsorbed phosphate (5–20% of the filtered ▶


A. H+ secretion
Lumen
Blood
H+-ATPase
H2O
H+
Na+
NHE3 carrier
OH− + CO2
CAII
HCO3−
NBC1
1 Proximal tubule cell
H+-K+-ATPase
K+
NBC3
AE1
Cl−
2 Type A intercalated cell
Pendrin
3 Type B intercalated cell
pH
Filtrate: 7.4
Late proximal: 6.6
Urine, min.: 4.5
Urine, max.: 8.2
B. HCO3− reabsorption
CAIV
Aquaporin
CO2 + OH−
hNBC
Proximal tubule cell
HCO3−
Filtrate: 100%
Late proximal: 10%
Urine: < 1%

▶ quantity, → p. 180) is therefore loaded with H^+ ions, about half of it in the proximal tubule (pH 7.4 ⇒ ca. 6.6), and the rest in the collecting duct (pH 6.6 ⇒ 4.5) (→ **C1**). When *acidosis* occurs, increased quantities of phosphate are mobilized from the bone and excreted. The resulting increase in H^+ excretion precedes the increased NH_4^+ production associated with acidosis (see below).

Excretion of ammonium ions ($NH_4^+ \rightleftharpoons NH_3 + H^+$), about 25–50 mmol/day on average diet, is *equivalent* to H^+ disposal and is therefore an *indirect* form of H^+ excretion (see below, → **D**). NH_4^+ is *not* a titratable form of acidity. Unlike $HPO_4^{2-} + H^+ \rightleftharpoons H_2PO_4^-$, the reaction $NH_3 + H^+ \rightleftharpoons NH_4^+$ does not function in the body as a buffer because of its high pK_a value of ca. 9.2. Nevertheless, for every NH_4^+ excreted by the kidney, one HCO_3^- is spared by the liver. This is equivalent to one H^+ disposed since the spared HCO_3^- ion can buffer a H^+ ion (hence "indirect H^+ excretion"). With an average dietary intake of protein, the amino acid metabolism produces roughly equimolar amounts of HCO_3^- and NH_4^+ (ca. 700–1000 mmol/day). The liver utilizes about 95% of these two products to produce **urea** (→ **D1**):

$$2\,HCO_3^- + 2\,NH_4^+ \rightleftharpoons H_2N\text{-}\overset{\overset{O}{\|}}{C}\text{-}NH_2 + CO_2 + 3\,H_2O \qquad [7.14]$$


Thus, one HCO_3^- less is consumed for each NH_4^+ that passes from the liver to the kidney and is eliminated in the urine. Before exporting NH_4^+ to the kidney, the **liver** incorporates it into **glutamate** yielding **glutamine**; only a small portion reaches the kidney as free NH_4^+. High levels of $NH_4^+ \rightleftharpoons NH_3$ are toxic.

In the **kidney**, *glutamine* enters proximal tubule cells by Na^+ symport and is cleaved by mitochondrial *glutaminase*, yielding NH_4^+ and glutamate$^-$ (Glu^-). Glu^- is further metabolized by *glutamate dehydrogenase* to yield α-ketoglutarate^{2-}, producing a second NH_4^+ ion (→ **D2**). The NH_4^+ can reach the tubule lumen on two ways: (1) it dissociates within the cell to yield NH_3 and H^+, allowing NH_3 to diffuse (non-ionically, → p. 22) into the lumen, where it re-joins the separately secreted H^+ ions; (2) the NHE3 carrier secretes NH_4^+ (instead of H^+). Once NH_4^+ has arrived at *the thick ascending limb* of the loop of Henle (→ **D4**), the BSC carrier (→ p. 162) reabsorbs NH_4^+ (instead of K^+) so that it remains in the *renal medulla*. Recirculation of NH_4^+ through the loop of Henle yields a very high conc. of $NH_4^+ \rightleftharpoons NH_3 + H^+$ towards the papilla (→ **D3**). While the H^+ ions are then actively pumped into the lumen of the collecting duct (→ **A2, D4**), the NH_3 molecules arrive there by non-ionic diffusion and possibly by NH_3 transporter (RhB and RhC glycoproteins) (→ **D4**). The NH_3 gradient required to drive this diffusion can develop because the especially low luminal pH value (about 4.5) leads to a much smaller NH_3 conc. in the lumen than in the medullary interstitium where the pH is about two pH units higher and the NH_3 conc. is consequently about 100-times higher than in the lumen.


Disturbances of acid–base metabolism (see also p. 142ff.). When **chronic non-respiratory acidosis** of non-renal origin occurs, *NH_4^+ excretion rises* to about 3 times the normal level within 1 to 2 days due to a parallel increase in hepatic glutamine production (at the expense of urea formation) and renal glutaminase activity. **Non-respiratory alkalosis** only decreases the renal NH_4^+ production and H^+ secretion. This occurs in conjunction with an increase in filtered HCO_3^- (increased plasma concentration, → p. 144), resulting in a sharp rise in HCO_3^- excretion and, consequently, in osmotic diuresis (→ p. 174). To **compensate for respiratory disturbances** (→ p. 144), it is important that increased (or decreased) plasma P_{CO_2} levels result in increased (or decreased) H^+ secretion and, thus, in increased (or decreased) HCO_3^- resorption. CO_2 and HCO_3^- sensors on the basolateral side of the cell regulate this process.

The kidney can also be the primary site of an acid–base disturbance (**renal acidosis**), with the defect being either generalized or isolated. In a generalized defect, as observed in *renal failure*, acidosis occurs because of reduced H^+ excretion. In an isolated defect with disturbance of proximal H^+ secretion (e.g. a defect of the NBC1 gene), large portions of filtered HCO_3^- are not reabsorbed, leading to *proximal renal tubular acidosis*. When impaired renal H^+ secretion occurs in the collecting duct (e.g. a defect of the AE1 gene function), the urine can no longer be acidified (pH > 6 despite acidosis) and the excretion of titratable acids and NH_4^+ is consequently impaired (*distal renal tubular acidosis*).

C. Excretion of titratable acids



D. Secretion and excretion of $NH_4^+ \rightleftharpoons NH_3$



Phosphate metabolism. The plasma phosphate conc. normally ranges from 0.8–1.4 mmol/L, and a corresponding amount of ca. 150–250 mmol/day of inorganic phosphate P_i ($HPO_4^{2-} + H^+ \rightleftharpoons H_2PO_4^-$) is filtered each day, a large part of which is reabsorbed. The fractional excretion (→ **A1**), which ranges between 5 and 20%, functions to balance P_i, H^+, and Ca^{2+}. P_i excretion rises in the presence of a *P_i excess* (elevated P_i levels in plasma) and falls during a *P_i deficit*. *Acidosis* also results in phosphaturia and increased H^+ excretion (titratable acidity, → p. 176 ff.). This also occurs in phosphaturia of other causes. *Hypocalcemia* and *parathyrin* also induce a rise in P_i excretion (→ **A3** and p. 292 f).

P_i is reabsorbed at the proximal tubule (→ **A2,3**). Its luminal membrane contains the type 3 *Na^+-P_i symport carrier* (NaPi-3). The carrier accepts $H_2PO_4^-$ and HPO_4^{2-} and cotransports it with Na^+ by secondary active transport (→ p. 26 ff.).

Regulation of P_i reabsorption. P_i deficits, alkalosis, hypercalcemia, and low PTH levels result in the increased incorporation of NaPi-3 transporters into the luminal membrane, whereas P_i excesses, acidosis, hypocalcemia and increased PTH secretion results in internalization (down-regulation) and subsequent lysosomal degradation of NaPi-3 (→ **A3**).

Calcium metabolism (see also p. 36). Unlike the Na^+ metabolism, the calcium metabolism is regulated mainly by absorption of Ca^{2+} in the gut (→ p. 292 ff.) and, secondarily, by renal excretory function. *Total plasma calcium* (bound calcium + ionized Ca^{2+}) is a mean 2.5 mmol/L. About 1.3 mmol/L of this is present as *free, ionized Ca^{2+}*, 0.2 mmol/L forms *complexes* with phosphate, citrate, etc., and the rest of 1 mmol/L is *bound to plasma proteins* and, thus, not subject to glomerular filtration (→ p. 154). *Fractional excretion of Ca^{2+}* (FE_{Ca}) in the urine is 0.5%—3% (→ **A1**).


Ca^{2+} reabsorption occurs practically throughout the entire nephron (→ **A1,2**). The reabsorption of filtered Ca^{2+} occurs to about 60% in the proximal tubule and about 30% in the thick ascending limb (TAL) of the loop of Henle and is paracellular, i.e., passive (→ **A4a** and p. 163 B5, B7). The lumen-positive transepithelial potential (L**P**TP) provides most of the driving force for this activity. Since Ca^{2+} reabsorption in TAL depends on NaCl reabsorption, *loop diuretics* (→ p. 174) inhibit Ca^{2+} reabsorption there. **PTH** *promotes Ca^{2+} reabsorption* in TAL as well as in the distal convoluted tubule, where Ca^{2+} is reabsorbed by transcellular active transport (→ **A4b**). Thereby, Ca^{2+} influx into the cell is passive and occurs via *luminal Ca^{2+} channels*, and Ca^{2+} efflux is active and occurs via *Ca^{2+}-ATPase* (primary active Ca^{2+} transport) and via the *3 Na^+/1 Ca^{2+} antiporter* (secondary active Ca^{2+} transport). Acidosis inhibits Ca^{2+} reabsorption via unclear mechanisms.

Urinary calculi usually consist of *calcium phosphate* or *calcium oxalate*. When Ca^{2+}, P_i or oxalate levels are increased, the solubility product will be exceeded but calcium complex formers (e.g., citrate) and inhibitors of crystallization (e.g., nephrocalcin) normally permit a certain degree of supersaturation. Stone formation can occur if there is a deficit of these substances or if extremely high urinary concentrations of Ca^{2+}, P_i and oxalate are present (applies to all three in pronounced antidiuresis).

Magnesium metabolism and **reabsorption.** Since part of the magnesium in plasma (0.7–1.2 mmol/L) is protein-bound, the Mg^{2+} conc. in the filtrate is only 80% of the plasma magnesium conc. Fractional excretion of Mg^{2+}, FE_{Mg}, is 3–8% (→ **A1,2**). Unlike Ca^{2+}, however, only about 15% of the filtered Mg^{2+} ions leave the proximal tubule. About 70% of the Mg^{2+} is subject to paracellular reabsorption in the TAL (→ **A4** and p. 163 B5, B7). Another 10% of the Mg^{2+} is subject to transcellular reabsorption in the distal tubule (→ **A4b**), probably like Ca^{2+} (see above).

Mg^{2+} excretion is stimulated by hypermagnesemia, hypercalcemia, hypervolemia and loop diuretics, and is inhibited by Mg^{2+} deficit, Ca^{2+} deficit, volume deficit, PTH and other hormones that mainly act in the TAL.

The kidney has **sensors** for divalent cations like Ca^{2+} and Mg^{2+} (→ p. 36). When activated, the sensors inhibit NaCl reabsorption in the TAL which, like loop diuretics, reduces the driving force for paracellular cation resorption, thereby diminishing the normally pronounced Mg^{2+} reabsorption there.


A. Reabsorption of phosphate, Ca2+ and Mg2+
1
100
80
60
40
20
0
% of filtered amount
Filtrate
Mg2+
Ca2+
Phosphate
Control range
Late proximal
Early distal
Final urine
5–20%
3–8%
0.5–3%
3 Phosphate transport
Lumen
Proximal tubule cell
Blood
Na+
Pi
?
PTH
Down regulation
Pi
Insertion
Pi deficit
Alkalosis
Hypercalcemia
2
Phosphate
Ca2+
Mg2+
4 Ca2+ and Mg2+ transport
Lumen
Blood
Ca2+
Mg2+
a
Proximal tubule and thick ascending limb of Henle's loop
3Na+
Ca2+
Mg2+
b
Distal tubule

The dietary intake of K^+ is about 100 mmol/day (minimum requirement: 25 mmol/day). About 90% of intake is excreted in the urine, and 10% is excreted in the feces. The plasma K^+ conc. normally ranges from 3.5 to 4.8 mmol/L, while intracellular K^+ conc. can be more than 30 times as high (due to the activity of Na^+-K^+-ATPase; → **A**). Therefore, about 98% of the ca. 3000 mmol of K^+ ions in the body are present in the cells. Although the extracellular K^+ conc. comprises only about 2% of total body K^+, it is still very important because (a) it is needed for regulation of K^+ homeostasis and (b) relatively small changes in cellular K^+ (influx or efflux) can lead to tremendous changes in the plasma K^+ conc. (with an associated risk of cardiac arrhythmias). Regulation of K^+ homeostasis therefore implies *distribution of K^+* through intracellular and extracellular compartments and *adjustment of K^+ excretion according to K^+ intake*.


Acute regulation of the extracellular K^+ conc. is achieved by internal **shifting of K^+** between the extracellular fluid and intracellular fluid (→ **A**). This relatively rapid process prevents or mitigates dangerous rises in extracellular K^+ (hyperkalemia) in cases where large quantities of K^+ are present due to high dietary intake or internal K^+ liberation (e.g., in sudden hemolysis). The associated K^+ shifting is mainly subject to *hormonal control*. The **insulin** secreted after a meal stimulates Na^+-K^+-ATPase and distributes the K^+ supplied in the animal and vegetable cells of the food to the cells of the body. This is also the case in diet-independent hyperkalemia, which stimulates insulin secretion per se. **Epinephrine** likewise increases cellular K^+ uptake, which is particularly important in muscle work and trauma—two situations that lead to a rise in plasma K^+. In both cases, the increased epinephrine levels allow the re-uptake of K^+ in this and other cells. *Aldosterone* also increases the intracellular K^+ conc. (see below).

Changes in pH affect the intra- and extracellular distribution of K^+ (→ **A**). This is mainly because the ubiquitous Na^+/H^+ antiporter works faster in alkalosis and more slowly in acidosis (→ **A**). In acidosis, Na^+ influx therefore decreases, Na^+-K^+-ATPase slows down, and the extracellular K^+ concentration rises (especially in non-respiratory acidosis, i.e., by 0.6 mmol/L per 0.1 unit change in pH). Alkalosis results in hypokalemia.


Chronic regulation of K^+ homeostasis is mainly achieved by the **kidney** (→ **B**). K^+ is subject to free glomerular filtration, and most of the filtered K^+ is normally reabsorbed (net *reabsorption*). The excreted amount can, in some cases, exceed the filtered amount (net *secretion*, see below). About 65% of the filtered K^+ is reabsorbed before reaching the end of the *proximal tubule*, regardless of the K^+ supply. This is comparable to the percentage of Na^+ and H_2O reabsorbed (→ **B1** and p. 157, column 2). This type of K^+ transport is mainly paracellular and therefore passive. Solvent drag (→ p. 24) and the lumen-positive transepithelial potential, LPTP (→ **B1** and p. 162), in the mid and late proximal segments of the tubule provide the driving forces for it. In the *loop of Henle*, another 15% of the filtered K^+ is reabsorbed by trans- and paracellular routes (→ **B2**). The amount of K^+ excreted is determined in the *connecting tubule and collecting duct*. Larger or smaller quantities of K^+ are then either reabsorbed or secreted according to need. In extreme cases, the fractional excretion of K^+ (FE_K) can rise to more than 100% in response to a high K^+ intake, or drop to about 3–5% when there is a K^+ deficit (→ **B**).

Cellular mechanisms of renal K^+ transport. The connecting tubule and collecting duct contain **principal cells** (→ **B3**) that reabsorb Na^+ and secrete K^+. Accumulated intracellular K^+ can exit the cell through *K^+ channels* on either side of the cell. The electrochemical K^+ gradient across the membrane in question is decisive for the efflux of K^+. The luminal membrane of principal cells also contains *Na^+ channels* through which Na^+ enters the cell (→ p. 162). This depolarizes the luminal membrane, which reaches a potential of about –20 mV, while the basolateral membrane maintains its normal potential of ca. –70 mV (→ **B3**). The driving force for K^+ efflux ($E_m - E_K$, → p. 32) is therefore higher on the luminal side than on the opposite side. Hence, K^+ preferentially exits the cell toward the lumen (*secretion*). This is mainly why K^+ secretion is coupled with Na^+ reabsorption, i.e., the more Na^+ reabsorbed by the principle cell, the more K^+ secreted. ▶

A. Regulation of extracellular K^+ concentration



B. Resorption and secretion of K^+ in the kidney



▶ Another apparent reason is that the reabsorption-related increase in intracellular Na^+ concentration decreases the driving force for the $3\,Na^+/Ca^{2+}$ exchange at the basolateral cell membrane, resulting in a rise in the **cytosolic Ca^{2+}** concentration. This rise acts as a signal for more frequent opening of luminal K^+ channels.

Type A **intercalated cells** (→ **B4**) can active reabsorb K^+ in addition to secreting H^+ ions. Like the parietal cells of the stomach, their luminal membrane contains a *H^+/K^+-ATPase* for this purpose.

Factors that affect K^+ excretion (→ **C**):

1. An **increased K^+ intake** raises the intracellular and plasma K^+ concentrations, which thereby increases the chemical driving force for K^+ secretion.

2. Blood pH: The intracellular K^+ conc. in renal cells *rises in alkalosis* and *falls in acute acidosis*. This leads to a simultaneous fall in K^+ excretion, which again rises in chronic acidosis. The reasons for this are that (a) acidosis-related inhibition of Na^+-K^+-ATPase reduces proximal Na^+ reabsorption, resulting in increased distal urinary flow (see no. 3), and (b) the resulting hyperkalemia stimulates aldosterone secretion (see no. 4).

3. If there is **increased urinary flow** in the connecting tubule and collecting duct (e.g., due to a high Na^+ intake, osmotic diuresis, or other factors that inhibit Na^+ reabsorption upstream), larger quantities of K^+ will be excreted. This explains the *potassium-losing effect of certain diuretics* (→ p. 175). The reason for this is, presumably, that K^+ secretion is limited at a certain luminal K^+ concentration. Hence, the larger the volume/time, the more K^+ taken away over time.

4. Aldosterone leads to retention of Na^+, an increase in extracellular volume (→ p. 186), a moderate increase in H^+ secretion (cellular pH rises), and *increased K^+ excretion*. It also increases the number of Na^+-K^+-ATPase molecules in the target cells and leads to a chronic increase in mitochondrial density in K^+ adaptation, for example (see below).


Cellular mechanisms of aldosterone effects. The increase in Na^+ reabsorption is achieved by increased production of transport proteins, called aldosterone-induced proteins (AIPs). This is a genome-mediated effect that begins approx. 30 min to 1 hour after aldosterone administration or secretion. The maximum effects are observed after several hours. Aldosterone increases Na^+ reabsorption, thereby depolarizing the luminal cell membrane (→ **B3**). Consequently, it increases the driving force for K^+ secretion and increases K^+ conductance by increasing the pH of the cell. Both effects lead to increased K^+ secretion. Aldosterone also has a very rapid (few seconds to minutes) non-genomic effect on the cell membrane, the physiological significance of which has yet to be explained.


The capacity of the K^+ excretory mechanism increases in response to long-term increases in the K^+ supply (**K^+ adaptation**). Even when renal function is impaired, this largely maintains the K^+ balance in the remaining, intact parts of the tubular apparatus. The colon can then take over more than $^1/_3$ of the K^+ excretion.

Mineralocortico(stero)**ids.** Aldosterone is the main mineralocorticoid hormone synthesized and secreted by the *zona glomerulosa of the adrenal cortex* (→ **D** and p. 296ff.). As with other steroid hormones, aldosterone is not stored, but is synthesized as needed. The principal function of aldosterone is to regulate Na^+ and K^+ transport in the kidney, gut, and other organs (→ **D**). **Aldosterone secretion** increases in response to (a) drops in blood volume and blood pressure (mediated by angiotensin II; → p. 186) and (b) hyperkalemia (→ **D**). Aldosterone synthesis is inhibited by atriopeptin (→ p. 173 D2).

Normal **cortisol** concentrations are *not* effective at the aldosterone receptor only because cortisol is converted to cortisone by an 11β-hydroxysteroid oxidoreductase in aldosterone's target cells.

Hyperaldosteronism can be either *primary* (aldosterone-secreting tumors of adrenal cortex, as observed in *Conn's syndrome*) or *secondary* (in volume depletion, → p. 186). *Na^+ retention* resulting in high ECF volumes and *hypertension* as well as a simultaneous *K^+ losses* and hypokalemic *alkalosis* are the consequences. When more than about 90% of the adrenal cortex is destroyed, e.g. by autoimmune adrenalitis, metastatic cancer or tuberculosis, primary chronic **adrenocortical insufficiency** develops (*Addison's disease*). The *aldosterone deficit* leads to a sharp increase in Na^+ excretion, resulting in hypovolemia, hypotension and K^+ retention (hyperkalemia). As glucocorticoid deficiency also develops, complications can be life-threatening, especially under severe stress (infections, trauma). If only one gland is destroyed, *ACTH* causes hypertrophy of the other (→ p. 299 A).


C. Factors that affect K+ secretion and excretion
K+
K+ uptake
Acidosis
[K+] in plasma and cells
Na+ uptake
ECF volume
Aldosterone
Diuretics
Spirono-lactone
Furosemide, thiazides
Na+ reabsorption in Henle's loop and distal tubule, resp.
Na+ supply and flow rate in collecting duct
Na+ reabsorption in collecting duct
K+ secretion


D. Secretion, effect and degradation of aldosterone
Blood pressure
Hyperkalemia
ACTH
Renin
See next plate
Angiotensin II
Atriopeptin
Zona glomerulosa
Secretion
Aldosterone
Adrenal cortex
Physical activity, stress
Epinephrine
Adrenal medulla
Na+ retention and K+ excretion in:
Salivary glands
Sweat glands
Gallbladder
Degradation
Glucuronation in the liver
Excretion
Bile
Feces
Kidney
Colon

The **juxtaglomerular apparatus** (**JGA**) consists of (a) juxtaglomerular cells of the *afferent arteriole* (including renin-containing and sympathetically innervated granulated cells) and *efferent arteriole*, (b) *macula densa cells* of the thick ascending limb of the loop of Henle and (c) juxtaglomerular mesangial cells (*polkissen*, → **A**) of a given nephron (→ **A**).

JGA functions: (1) local transmission of tubuloglomerular feedback (**TGF**) at its own nephron via angiotensin II (ATII) and (2) systemic production of angiotensin II as part of the renin–angiotensin system (**RAS**).

Tubuloglomerular feedback (TGF). Since the daily GFR is 10 times larger than the total ECF volume (→ p. 168), the excretion of salt and water must be precisely adjusted according to uptake. **Acute changes in the GFR** of the single nephron (SNGFR) and the amount of NaCl filtered per unit time can occur for several reasons. An excessive SNGFR is associated with the risk that the distal mechanisms for NaCl reabsorption will be overloaded and that too much NaCl and H_2O will be lost in the urine. A too low SNGFR means that too much NaCl and H_2O will be retained. The extent of NaCl and H_2O reabsorption in the proximal tubule determines how quickly the tubular urine will flow through the loop of Henle. When less is absorbed upstream, the urine flows more quickly through the thick ascending limb of the loop, resulting in a lower extent of urine dilution (→ p. 162) and a higher NaCl concentration at the macula densa, $[NaCl]_{MD}$. If the $[NaCl]_{MD}$ becomes too high, the afferent arteriole will constrict to curb the GFR of the affected nephron within 10 s or vice versa (*negative feedback*). It is unclear how the $[NaCl]_{MD}$ results in the signal to constrict, but type 1 A angiotensin II (AT_{1A}) receptors play a key role.

If, however, the $[NaCl]_{MD}$ changes due to **chronic shifts in total body NaCl** and an associated change in ECF volume, rigid coupling of the SNGFR with the $[NaCl]_{MD}$ through TGF would be fatal. Since long-term increases in the ECF volume reduce proximal NaCl reabsorption, the $[NaCl]_{MD}$ would increase, resulting in a decrease in the GFR and a further increase in the ECF volume. The reverse occurs in ECF volume deficit. To prevent these effects, the *$[NaCl]_{MD}$/SNGFR response curve* is shifted in the appropriate direction by certain substances. Nitric oxide (NO) shifts the curve when there is an ECF excess (increased SNGFR at same $[NaCl]_{MD}$), and (only locally effective) angiotensin II shifts it in the other direction when there is an ECF deficit.

Renin–angiotensin system (RAS). If the mean renal blood pressure acutely drops below 90 mmHg or so, renal baroreceptors will trigger the release of **renin**, thereby increasing the systemic plasma renin conc. Renin is a peptidase that catalyzes the cleavage of *angiotensin I* from the renin substrate *angiotensinogen* (released from the liver). Angiotensin-converting enzyme (*ACE*) produced in the lung, etc. cleaves two amino acids from angiotensin I to produce **angiotensin II** approx. 30–60 minutes after the drop in blood pressure (→ **B**).


Control of the RAS (→ **B**). The blood pressure *threshold* for renin release is raised by α_1-adrenoceptors, and *basal renin secretion* is increased by β_1-adrenoceptors. *Angiotensin II* and *aldosterone* are the most important effectors of the RAS. Angiotensin II stimulates the release of aldosterone by adrenal cortex (see below). Both hormones directly (fast action) or indirectly (delayed action) lead to a renewed increase in arterial blood pressure (→ **B**), and renin release therefore decreases to normal levels. Moreover, both hormones *inhibit renin release* (negative feedback).


If the mean blood pressure is decreased in only one kidney (e.g., due to stenosis of the affected renal artery), the affected kidney will also start to release more renin which, in this case, will lead to **renal hypertension** in the rest of the circulation.

Angiotensin II effects: Beside altering the structure of the myocardium and blood vessels (mainly via AT_2 receptors), angiotensin II has the following fast or delayed effects mediated by AT_1 receptors (→ **A**).


- *Vessels*: Angiotensin II has potent vasoconstrictive and hypertensive action, which (via endothelin) takes effect in the arterioles (fast action).
- *CNS*: Angiotensin II takes effect in the hypothalamus, resulting in vasoconstriction through the circulatory "center" (rapid action). It also increases ADH secretion in the hypothalamus, which stimulates thirst and a craving for salt (delayed action).
- *Kidney*: Angiotensin II plays a major role in regulating renal circulation and GFR by constricting of the afferent and/or efferent arteriole (delayed action; cf. autoregulation, → p. 150). It directly stimulates Na^+ reabsorption in the proximal tubule (delayed action).
- *Adrenal gland*: Angiotensin II stimulates aldosterone synthesis in the adrenal cortex (delayed action; → p. 184) and leads to the release of epinephrine in the adrenal medulla (fast action).

A. Juxtaglomerular apparatus





B. Renin-Angiotensin-System


Acute drop in: Plasma volume and blood pressure
Renin secretion
Normalization of plasma volume and blood pressure
Renin
1 2 3 4 5 6 7 8 9 10 11 12 13 14
Angiotensinogen
1 Asp 2 Arg 3 Val 4 Tyr 5 Ile 6 His 7 Pro 8 Phe 9 His 10 Leu
Angiotensin I
Converting enzyme
1 Asp 2 Arg 3 Val 4 Tyr 5 Ile 6 His 7 Pro 8 Phe
Angiotensin II
Craving for salt
Thirst
Adrenal cortex
GFR and RBF
Aldosterone
General vasoconstriction
Reduced salt and water excretion
Increased fluid and salt intake

Blood is pumped from the left ventricle of the heart to capillaries in the periphery via the arterial vessels of the *systemic* (or greater) *circulation* and returns via the veins to the right heart. It is then expelled from the right ventricle to the lungs via the *pulmonary* (or lesser) *circulation* and returns to the left heart (→ **A**).

The total **Blood volume** is roughly 4–5 L (≈ 7% of the fat-free body mass; → table on p. 88). Around 80% of the blood circulates through the veins, right heart and pulmonary vessels, which are jointly referred to as the *low pressure system* (→ **A**, left). These highly distensible *capacitance vessels* function as a *blood reservoir* in which blood is stored and released as needed via venous vasoconstriction (→ e.g., p. 220). When the blood volume increases—due, for example, to a blood transfusion—over 99% of the transfused volume remains in the low-pressure system (*high capacitance*), while only < 1% circulates in the arterial *high-pressure system* (*low capacitance*). Conversely, a decrease will be reflected almost entirely by a decrease in the blood stores in the low-pressure system. **Central venous pressure** (measured in or near to the right atrium; normally 4–12 cm H_2O) is therefore a good indicator of blood volume (and ECF volume) in individuals with normally functioning heart and lungs.


Cardiac output (CO). The cardiac output is calculated as heart rate (HR) times stroke volume (SV). Under normal resting conditions, the CO is approx. 70 [min^{-1}] × 0.08 [L] = 5.6 L/min or, more precisely (cardiac index), a mean 3.4 L/min per m^2 body surface area. An increase in HR (up to about 180 min^{-1}) and/or SV can increase the CO to 15–20 L/min.

The **distribution of blood** to the organs arranged in *parallel* in the **systemic circulation** (→ **A**, $\dot{Q}$ values) is determined by their *functional priority* (vital organs) and by the *current needs* of the body (see also p. 215 A). Maintaining adequate cerebral perfusion (approx. 13% of the resting CO) is the top priority, not only because the *brain* is a major vital organ, but also because it is very susceptible to hypoxic damage (→ p. 130). *Myocardial* perfusion via coronary arteries (approx. 4% of the CO at rest) must also be maintained, because any disruption of cardiac pumping function will endanger the entire circulation. About 20 to 25% of the CO is distributed to the *kidneys*. This fraction is very large relative to the kidney weight (only 0.5% of body mass). Renal blood flow is primarily used to maintain renal *excretory and control functions*. Thus, renal blood flow may be reduced transiently in favor of cardiac and cerebral perfusion, e.g., to ward off impending shock (→ p. 220). During strenuous physical *exercise*, the CO increases and is alloted mainly to the *skeletal muscle*. During digestion, the *gastrointestinal tract* also receives a relatively high fraction of the CO. Naturally, both of these organ groups cannot receive the maximum blood supply at the same time (→ p. 75 A). Blood flow to the *skin* (approx. 10% of the resting CO) mainly serves the purpose of *heat disposal* (→ p. 224ff.). The cutaneous blood flow rises in response to increased heat production (physical work) and/or high external temperatures and decreases (pallor) in favor of vital organs in certain situations (e.g., shock; → p. 220).

The total CO flows through the **pulmonary circulation** as it and the systemic circulation are arranged in series (→ **A**). Oxygen-depleted (venous) blood is carried via the pulmonary arteries to the lungs, where it is *oxygenated* or "*arterialized.*" A relatively small quantity of additional oxygenated blood from the systemic circulation reaches the lung tissue via the bronchial arteries. All blood in the pulmonary circulation drains via the pulmonary veins.

Peripheral resistance. Flow resistance in the pulmonary circulation is only about 10% of the *total peripheral resistance (TPR)* in the systemic circulation. Consequently, the mean pressure in the right ventricle (approx. 15 mmHg = 2 kPa) is considerably lower than in the left ventricle (100 mmHg = 13.3 kPa). Since the resistance in the lesser arteries and arterioles amounts to nearly 50% of TPR (→ **A**, top right), they are called *resistance vessels*.

A. Cardiovascular system



In the systemic circulation, blood is ejected from the left ventricle to the aorta and returns to the right atrium via the venae cavae (→ **A**). As a result, the **mean blood pressure** (→ p. 208) drops from around 100 mmHg in the aorta to 2–4 mmHg in the venae cavae (→ **A2**), resulting in a pressure difference (ΔP) of about 97 mmHg (pulmonary circulation; → p. 122). According to **Ohm's Law**,

$$\mathbf{\Delta P = \dot{Q} \cdot R}\ (\text{mmHg}) \qquad [8.1]$$

where $\dot{Q}$ is the blood flow ($L \cdot min^{-1}$) and R is the flow resistance ($mmHg \cdot min \cdot L^{-1}$). Equation 8.1 can be used to calculate blood flow in a given organ (R = organ resistance) as well as in the entire cardiovascular system, where $\dot{Q}$ is the cardiac output (CO; → p. 188) and R is the total peripheral flow resistance (TPR). The TPR at rest is about $18\ mmHg \cdot min \cdot L^{-1}$.

The **aorta** and **greater arteries** distribute the blood to the periphery. In doing so, they act as a *hydraulic filter* because (due to their high *compliance*, $\Delta V/\Delta P_{tm}$) they convert the intermittent flow at the aortic root to a nearly steady flow through the capillaries. The high systolic pressures generated during the ejection phase cause the walls of these blood vessels to stretch, and part of the ejected blood is "stored" in the dilated lumen (*windkessel*). Elastic recoil of the vessel walls after aortic valve closure maintains blood flow during diastole. Arterial vessel compliance decreases with age.

Flow velocity ($\dot{V}$) and **flow rate** ($\dot{Q}$) of the blood. Assuming an aortic cross-sectional area (CSA) of 5.3 cm^2 and a total CSA of 20 cm^2 of all downstream arteries (→ **A5**), the **mean $\dot{V}$** (during systole and diastole) at rest can be calculated from a resting CO of 5.6 L/min: It equals 18 cm/s in the aorta and 5 cm/s in the arteries (→ **A3**). As the aorta receives blood only during the ejection phase (→ p. 192), the maximum resting values for $\dot{V}$ and $\dot{Q}$ in the aortic root are much higher during this phase ($\dot{V}$ = 95 cm/s, $\dot{Q}$ = 500 mL/s).

In the **Hagen–Poiseuille equation**,

$$\mathbf{R = 8 \cdot l \cdot \eta / (\pi \cdot r^4)} \qquad [8.2]$$

the flow resistance (R) in a tube of known length (l) is dependent on the viscosity (η) of the fluid in the tube (→ p. 92) and the fourth power of the inner radius of the tube (r^4). Decreasing the radius by only about 16% will therefore suffice to double the resistance.

The **lesser arteries** and **arterioles** account for nearly 50% of the TPR (*resistance vessels*; → **A1** and p. 189 A) since their small radii have a much stronger effect on total TPR ($R \sim 1/r^4$) than their large total CSA ($R \sim r^2$). Thus, the blood pressure in these vessels drops significantly. Any change in the radius of the small arteries or arterioles therefore has a radical effect on the TPR (→ p. 214ff.). Their width and that of the **precapillary sphincter** determines the amount of blood distributed to the capillary beds (exchange area).

Although the **capillaries** have even smaller radii (and thus much higher individual resistances than the arterioles), their total contribution to the TPR is only about 27% because their total CSA is so large (→ **A1** and p. 189 A). The *exchange of fluid and solutes* takes place across the walls of capillaries and **postcapillary venules**. Both vessel types are particularly suitable for the task because (a) their $\dot{V}$ is very small (0.02–0.1 cm/s; → **A3**) (due to the large total CSA), (b) their total surface area is very large (approx. 1000 m^2), (3) and their walls can be very thin as their inner radius (4.5 μm) is extremely small (*Laplace's law*, see below).

Transmural pressure P_{tm} [N/m^2], that is, the pressure difference across the wall of a hollow organ (= internal pressure minus external pressure), causes the wall to stretch. Its materials must therefore be able to withstand this stretch. The resulting tangential *mural tension* T [N/m] is a function of the inner radius r [m] of the organ. According to **Laplace's law** for cylindrical (or spherical) hollow bodies,


$$\mathbf{P_{tm} = T/r}\ (\text{or } \mathbf{P_{tm} = 2\,T/r},\ \text{resp.}) \qquad [8.3a/b]$$

Here, T is the total mural tension, regardless how thick the wall is. A thick wall can naturally withstand a given P_{tm} more easily than a thin one. In order to determine the **tension** exerted **per unit CSA of the wall** (i.e., the stress requirements of the wall material in N/m^2), the thickness of the wall (w) must be considered. Equation 8.3 a/b is therefore transformed to

$$P_{tm} = T \cdot w/r\ (\text{or } P_{tm} = 2\,T \cdot w/r,\ \text{resp.}) \qquad [8.4a/b]$$

The blood collects in the **veins**, which can accommodate large volumes of fluid (→ **A6**). These *capacitance vessels* serve as a *blood reservoir* (→ p. 188).

A. Characteristics of the vessel segments



1 Fraction of TPR

19% | 47% | 27% | 7%


2 Mean blood pressure $\bar{P}$ (mmHg)

100 | 40 | 25 | 20 | 2–4


3 Mean blood flow velocity $\bar{V}$ ($cm \cdot s^{-1}$)

18 | 5 | 1.5 | 0.02–0.1 | 1.0 | 6


4 Individual vessel diameter (cm)



5 Joint cross-sectional area (cm^2)



6 Joint holding capacity (cm^3)



The resting heart rate is 60–80 beats per minute. A **cardiac cycle** (→ **A**) therefore takes roughly 1 s. It can be divided into four distinct phases: (I) contraction phase and (II) ejection phase, both occurring in *systole*; (III) relaxation phase and filling phase (IV), both occurring in *diastole*. At the end of phase IV, the atria contract (phase IVc). Electrical excitation of the atria and ventricles precedes their contraction.

The **cardiac valves** determine the direction of blood flow within the heart, e.g., from the atria to the ventricles (phase IV) or from the ventricles to the aorta or pulmonary artery (phase II). All cardiac valves are closed during phases I and III (→ **A**, top). Opening and closing of the valves is controlled by the pressures exerted on the two sides of the valves.

Cardiac cycle. Near the end of ventricular diastole, the sinoatrial (SA) node emits an **electrical impulse**, marking to the beginning of the P wave of the ECG (phase IVc, → **A1** and p. 198ff.). This results in *atrial contraction* (→ **A4**) and is followed by *ventricular excitation* (QRS complex of the ECG). The ventricular pressure then starts to rise (→ **A2**, blue line) until it exceeds the atrial pressure, causing the atrioventricular valves (mitral and tricuspid valves) to close one immediately after the other producing part of the first heart sound. This marks the *end of diastole*. The mean *end-diastolic volume* (**EDV**) in the ventricle is now about 120 mL (→ **A4**) or, more precisely, 70 mL/m^2 body surface area.

The **isovolumetric contraction** phase now begins (phase I, ca. 50 ms). With all valves are closed, the ventricles now contract (→ **A6**), and the ventricular pressure increases rapidly. The slope of this ascending pressure curve indicates the maximum rate of pressure developed (**maximum dP/dt**). The semilunar valves (aortic and pulmonary valves) now open because the pressure in the left ventricle (→ **A2**, blue line) exceeds that in the aorta (→ **A2**, black broken curve) at about 80 mmHg, and the pressure in the right ventricle exceeds that in the pulmonary artery at about 10 mmHg.


The **ejection** phase (now begins phase II; ca. 210 ms at rest). During this period, the pressure in the left ventricle and aorta reaches a maximum of ca. 120 mmHg (systolic pressure). In the early phase of ejection (IIa or *rapid ejection phase*), a large portion of the stroke volume (SV) is rapidly expelled (→ **A4**) and the blood flow rate reaches a maximum (→ **A5**). Myocardial excitation subsequently decreases (T wave of the ECG, → **A1**) and ventricular pressure decreases (the remaining SV fraction is *slowly ejected*, phase IIb) until it falls below that of the aorta or pulmonary artery, respectively. This leads to closing of the semilunar valves, producing the **second heart sound** (→ **A6**). The mean SV at rest is about 80 mL or, more precisely, 47 mL/m^2 body surface area. The corresponding mean **ejection fraction** (**SV/EDV**) at rest is about 0.67. The *end-systolic volume* (**ESV**) remaining in the ventricles at this point is about 40 mL (→ **A4**).

The first phase of ventricular diastole or **isovolumetric relaxation** now begins (phase III; ca. 60 ms). The atria have meanwhile refilled, mainly due to the suction effect created by the lowering of the valve plane during ejection. As a result, the central venous pressure (CVP) decreases (→ **A3**, falls from c to x). The ventricular pressure now drops rapidly, causing the atrioventricular valves to open again when it falls short of atrial pressure.

The **filling phase** now begins (phase IV; ca. 500 ms at rest). The blood passes rapidly from the atria into the ventricles, resulting in a drop in CVP (→ **A3**, point y). Since the ventricles are 80% full by the first quarter of diastole, this is referred to as *rapid ventricular filling* (phase IVa; → **A4**). *Ventricular filling slows down* (phase IVb), and the *atrial systole* (phase IVc) and the *a* wave of CVP follows (→ **A2,3**). At a normal heart rate, the atrial contraction contributes about 15% to ventricular filling. When the heart rate increases, the duration of the cardiac cycle decreases mainly at the expense of diastole, and the contribution of atrial contraction to ventricular filling increases.

The heart beats produce a **pulse wave** (pressure wave) that travels through the arteries at a specific *pulse wave velocity* (PWV): the PWV of the aorta is 3–5 m/s, and that of the radial artery is 5–12 m/s. PWV is much higher than the blood flow velocity ($\dot{V}$), which peaks at 1 m/s in the aorta and increases proportionally to (a) decreases in the compliance of aortic and arterial walls and (b) increases in blood pressure.

A. Action phases of the heart (cardiac cycle)



The heart contains muscle cells that generate (*pacemaker system*), conduct (*conduction system*) and respond to electrical impulses (*working myocardium*). Cardiac impulses are generated within the heart (**automaticity**). The frequency and regularity of pacemaking activity are also intrinsic to the heart (**rhythmicity**). Myocardial tissue comprises a *functional* (not truly anatomical) *syncytium* because the cells are connected by *gap junctions* (→ p. 16ff.). This also includes the atrioventricular junction (→ p. 195 A). Thus, an impulse arising in any part of the heart leads to complete contraction of both atria and ventricles or to none at all (**all-or-none response**).

Cardiac contraction is normally stimulated by impulses from the **sinoatrial node** (SA node), which is therefore called the *primary pacemaker*. The impulses are conducted (→ **A**) through the atria to the *atrioventricular node* (**AV node**). The *bundle of His* is the beginning of the **specialized conduction system**, including also the left and right (Tawara's) *bundle branches* and the *Purkinje fibers*, which further transmit the impulses to the ventricular myocardium, where they travel from inside to outside and from apex to base of the heart. This electrical activity can be tracked in vivo (→ **C**) by electrocardiography (→ p. 198ff.).

Pacemaker potential (→ **B1**, top). The cell potential in the SA node is a *pacemaker potential*. These cells do not have a constant resting potential. Instead, they slowly depolarize immediately after each repolarization, the most negative value of which is the *maximum diastolic potential* (MDP, ca. –70 mV). The slow *diastolic depolarization* or *prepotential* (PP) prevails until the *threshold potential* (TP) has again been reached. Thus triggering another action potential (AP).

The pacemaker potential (→ **B1**, bottom) is subject to various underlying **changes in ion conductance** (g) and **ionic flow** (I) through the plasma membrane (→ p. 32 ff.). Starting at the MDP, a hyperpolarization-triggered increase in non-selective conductance and influx (I_f, = "funny") of cations into the cells lead to slow depolarization (PP). When the TP is reached, g_{Ca} increases quickly, and the slope of the pacemaker potential rises. This upslope is caused by increased influx of Ca^{2+} (I_{Ca}). When the potential rises to the positive range, g_K increases sharply, resulting in the efflux of K^+ (I_K), and the pacemaker cells repolarize to the MDP.

Each action potential in the SA node normally generates one heart beat. The **heart rate** is therefore determined by the rate of impulse generation by the pacemaker. The impulse generation frequency *decreases* (→ **B3,** broken curves) when (a) the PP slope decreases (→ **B3a**), (b) the TP becomes less negative (→ **B3b**), (c) the MDP becomes more negative, resulting in the start of spontaneous depolarization at lower levels (→ **B3c**), or (d) repolarization after an action potential occurs more slowly (slope flatter).


The first three conditions extend the time required to reach the threshold potential.

All components of the conduction system can depolarize spontaneously, but the SA node is the natural or *nomotopic pacemaker* in cardiac excitation (sinus rhythm normally has a rate of 60 to 100 min^{-1}). The intrinsic rhythms of the other pacemakers are slower than the sinus rhythm (→ **C**, table) because the slope of their PPs and repolarizations are "flatter" (see above). APs arising in the SA node therefore arrive at subordinate ("lower") levels of the conduction system before spontaneous depolarization has reached the intrinsic TP there. The intrinsic rhythm of the lower components come into play (*ectopic pacemakers*) when (a) their own frequency is enhanced, (b) faster pacemakers are depressed, or (c) the conduction from the SA node is interrupted (→ p. 202). The heart beats at the AV rhythm (40 to 55 min^{-1}) or even slower (25 to 40 min^{-1}) when controlled by tertiary (ventricular) pacemakers.

Overdrive suppression. The automaticity of lower pacemaker cells (e.g., AV node or Purkinje cells) is suppressed temporarily after they have been driven by a high frequency. This leads to increased Na^+ influx and therefore to increased activity of the Na^+-K^+-ATPase. Because it is electrogenic (→ p. 28), the cells become hyperpolarized and it takes longer to reach threshold than without prior high-frequency overdrive (→ **B3c**).

The cells of the **working myocardium** contain voltage-gated *fast Na^+ channels* that permit the brief but rapid influx of Na^+ at the beginning of an AP. The slope of their APs therefore rises more sharply than that of a pacemaker potential (→ **A**). A **resting potential** prevails between ▶


A. Cardiac excitation



B. Pacemaker potential and rate of impulse generation


1 Pacemaker potential and ionic currents

(after Di Francesco)




2 Duration of myocardial action potential is dependent on heart rate (f)


(after Trautwein et al.)



3 Changes in heart rate due to changes in pacemaker potential



4 Factors that affect the conduction of action potentials (AV node)



▶ APs, i.e. spontaneous depolarization normally does not occur in the working myocardium. The long-lasting myocardial AP has a characteristic **plateau** (→ p. 59 A). Thus, the first-stimulated parts of the myocardium are still in a refractory state when the AP reaches the last-stimulated parts of the myocardium. This prevents the cyclic re-entry of APs in the myocardium. This holds true, regardless of whether the heart rate is very fast or very slow since the duration of an AP varies according to heart rate (→ **B2**).

Role of Ca^{2+}. The incoming AP opens *voltage-gated Ca^{2+} channels* (associated with *dihydropyridine receptors*) on the sarcolemma of myocardial cells, starting an influx of Ca^{2+} from the ECF (→ p. 63/B3). This produces a local increase in cytosolic Ca^{2+} (*Ca^{2+} "spark"*) which, in turn, triggers the opening of *ligand-gated*, *ryanodine-sensitive Ca^{2+} channels* in the sarcoplasmic reticulum (Ca^{2+} store). The influx of Ca^{2+} into the cytosol results in electromechanical coupling (→ p. 62) and myocardial contraction. The cytosolic Ca^{2+} is also determined by active transport of Ca^{2+} ions back (a) into the Ca^{2+} stores via a Ca^{2+}-ATPase, called *SERCA*, which is stimulated by *phospholamban*, and (b) to the ECF. This is achieved with the aid of a *Ca^{2+}-ATPase* and a *3 Na^+/Ca^{2+} exchange* carrier that is driven by the electrochemical Na^+ gradient established by Na^+-K^+-ATPase.

Although the heart beats autonomously, efferent **cardiac nerves** are mainly responsible for **modulating heart action** according to changing needs. The *autonomic nervous system* (and epinephrine in plasma) can alter the following aspects of heart action: (a) *rate of impulse generation* by the pacemaker and, thus, the heart rate (chronotropism); (b) *velocity of impulse conduction*, especially in the AV node (dromotropism); and (c) *contractility* of the heart, i.e., the force of cardiac muscle contraction at a given initial fiber length (inotropism).


These changes in heart action are induced by **acetylcholine (ACh**; → p. 82) released by parasympathetic fibers of the vagus nerve (binds with M_2 cholinoceptors on pacemaker cells), by **norepinephrine (NE)** released by sympathetic nerve fibers, and by plasma **epinephrine (E)**. NE and E bind with β_1-adrenoceptors (→ p. 84ff.). The firing frequency of the SA node is increased by NE and E (positive chronotropism) and decreased by ACh (negative chronotropism) because these substances alter the slopes of the PP and the MDP in the SA cells (→ **B3a** and **c**). Under the influence of ACh, the slope of the PP becomes flatter and the MDP becomes more negative as g_K rises. In versely, slope and amplitude of PP rises under the influence of E or sympathetic stimuli (higher I_f) due to a rise in cation (Na^+) conductance and, under certain conditions, a decrease in the g_K. Only NE and E have chronotropic effects in the lesser components of the impulse conduction system. This is decisive when the AV node or tertiary pacemakers take over.

ACh (left branch of vagus nerve) decreases the velocity of **impulse conduction in the AV node**, whereas NE and E increase it due to their negative and positive dromotropic effects, respectively. This is mainly achieved through changes in the amplitude and slope of the upstroke of the AP (→ **B3c** and **B4**), caused by changes of g_K and g_{Ca}.

In positive inotropism, NE and E have a direct effect on the working myocardium. The resulting increase in **contractility** is based on an *increased influx of Ca^{2+}* ions from the ECF triggered by β_1-adrenoceptors, resulting in an increased cytosolic Ca^{2+}. This Ca^{2+} influx can be inhibited by administering Ca^{2+} channel blockers (*Ca^{2+} antagonists*). Other factors that increase cardiac contractility are an *increase in AP duration*, resulting in a longer duration of Ca^{2+} influx, and *inhibition of Na^+-K^+-ATPase* (e.g., by the cardiac glycosides digitalis and strophanthin). The consequences are: flatter Na^+ gradient across the cell membrane ⇒ decreased driving force for 3 Na^+/Ca^{2+} exchange carriers ⇒ decreased Ca^{2+} efflux ⇒ increased cytosolic Ca^{2+} conc.

When the heart rate is low, Ca^{2+} influx over time is also low (fewer APs per unit time), allowing plenty of time for the efflux of Ca^{2+} between APs. The mean cytosolic Ca^{2+} conc. is therefore reduced and contractility is low. Only by this indirect mechanism are parasympathetic neurons able to elicit a negative inotropic effect (*frequency inotropism*). NE and E can exert their positive inotropic effects either indirectly by increasing the high heart or directly via β_1-adrenoceptors of the working myocardium.

C. Cardiac impulse spreading



Normal activation sequence		Time (ms)	ECG	Conduction velocity ($m \cdot s^{-1}$)	Intrinsic rate (min^{-1})
SA node					60–100
Impulse generation		**0**	P wave	0.05	
Arrival of impulse in distal parts of atrium	Right atrium	**50**		0.8–1.0 in atrium	
	Left atrium	**85**			
AV node			P-Q segment (delayed conduction)		40–55
Arrival of impulse		**50**		0.05	
Relaying of impulse		**125**			
His bundle activated		**130**		1.0–1.5	25–40
End of bundle branches activated		**145**		1.0–1.5	
Purkinje fibers activated		**150**		3.0–3.5	
Inner myocardium completely activated	Right ventricle	**175**	QRS complex	1.0 in myocardium	None
	Left ventricle	**190**			
Outer myocardium completely activated	Right ventricle	**205**			
	Left ventricle	**225**			

The ECG records **potential differences** (few **m/V**) caused by cardiac excitation. This provides information on heart position, relative chamber size, heart rhythm, impulse origin/propagation and rhythm/conduction disturbances, extent and location of myocardial ischemia, changes in electrolyte concentrations, and drug effects on the heart. However, it does *not* provide data on cardiac contraction or pumping function.

ECG potential differences arise at the interface between stimulated and non-stimulated myocardium. Totally stimulated or unstimulated myocardial tissue does not generate any visible potentials The **migration of the excitatory front** through the heart muscle gives rise to numerous potentials that vary in magnitude and direction.

These *vectors* can be depicted as arrows, where the length of the arrow represents the magnitude of the potential and the direction of the arrow indicates the direction of the potential (arrowhead is +). As in a force parallelogram, the **integral vector** (summation vector) is the sum of the numerous individual vectors at that moment (→ **A**, red arrow).


The magnitude and direction of the integral vector change during the cardiac cycle, producing the typical *vector loop* seen on a **vectorcardiogram**. (In **A**, the maximum or chief vector is depicted by the arrow, called the "electrical axis" of the heart, see below).

Limb and chest leads of the ECG make it possible to visualize the course of the integral vector over time, projected at the plane determined by the leads (scalar ECG). Leads parallel to the integral vector show full deflection (R wave ≈ 1–2 mV), while those perpendicular to it show no deflection. *Einthoven leads I, II, and III* are *bipolar* limb leads positioned in the frontal plane. Lead I records potentials between the left and right arm, lead II those between the right arm and left leg, and lead III those between the left arm and left leg (→ **C1**). *Goldberger leads* are *unipolar* **a**ugmented limb leads in the frontal plane. One lead (right arm, **a**VR, left arm **a**VL, or left leg, **a**VF; → **D2**) acts as the *different electrode*, while the other two limbs are connected and serve as the *indifferent* (reference) *electrode* (→ **D1**). *Wilson leads* (V_1–V_6) are *unipolar chest leads* positioned on the left side of the thorax in a nearly *horizontal plane* (→ **F**). When used in combination with the aforementioned leads in the frontal plane, they provide a *three-dimensional view* of the integral vector. To make recordings with the chest leads (*different electrode*), the three limb leads are connected to form an *indifferent electrode* with high resistances (5 kΩ). The chest leads mainly detect potential vectors directed towards the back. These vectors are hardly detectable in the frontal plane. Since the mean QRS vector (see below) is usually directed downwards and towards the left back region, the QRS vectors recorded by leads V_1–V_3 are usually negative, while those detected by V_5 and V_6 are positive.


Intraesophageal leads and additional leads positioned in the region of the *right chest* (V_{r3}–V_{r6}) and *left back* (V_7–V_9) are useful in certain cases (→ **F2**).

An ECG depicts electrical activity as waves, segments, and intervals (→ **B** and p. 197 C). By convention, upward deflection of the waves is defined as positive (+), and downward deflection as negative (−). The electrical activity associated with *atrial depolarization* is defined as the **P wave** (< 0.3 mV, < 0.1 s). Repolarization of the atria normally cannot be visualized on the ECG since it tends to be masked by the QRS complex. The **QRS complex** (< 0.1 s) consists of one, two or three components: **Q wave** (mV < 1/4 of R, < 0.04 s), **R wave** and/or **S wave** (R+S > 0.6 mV). The potential of the **mean QRS vector** is the sum of the amplitudes of the Q, R and S waves (taking their positive and negative polarities into account). The voltage of the mean QRS vector is higher (in most leads) than that of the P wave because the muscle mass of the ventricles is much larger than that of the atria. The R wave is defined as the first positive deflection of the QRS complex, which means that R waves from different leads may not be synchronous. The QRS complex represents the *depolarization of the ventricles*, and the **T wave** represents their *repolarization*. Although opposing processes, the T wave usually points in the same direction as the R wave (+ in most leads). This means that depolarization and repolarization do not travel in the same direction (→ p. 197 C, **Q**R**S** and **T**: vector arrows point in the same direction despite reversed polarity during repolarization). The **PQ** (or PR) **segment** (complete atrial excitation) and the **ST segment** (complete ventricular excitation) lie ap- ▶


A. Vector loops of cardiac excitation




B. ECG curve




C. Einthoven leads I, II and III (bipolar)



D. Goldberger limb leads (unipolar)



E. Cabrera circle



▶ prox. on the **isoelectric line** (0 mV). The **PQ** (or PR) **interval** (< 0.2 s) is measured from the beginning of the P wave to the beginning of the Q wave (or to the R wave if Q wave is absent) and corresponds to the time required for *atrioventricular conduction* (→ **B**). The **QT interval** is measured from the start of the Q wave to the end of the T wave. It represents the overall time required for depolarization and repolarization of the ventricles and is dependent on the heart rate (0.35 to 0.40 s at a heart rate of 75 min^{-1}).

Figure **E** illustrates the six frontal leads (Einthoven and Goldberger leads) on the *Cabrera circle*. Synchronous measurement of the amplitude of Q, R and S from two or more leads can be used to determine any integral vector in the frontal plane (→ **G**). The direction of the largest mean QRS vector is called the **QRS axis** (→ **C3** and **G**, red arrows). If the excitation spreads normally, the QRS axis roughly corresponds to the anatomic longitudinal axis of the heart.

The mean QRS axis (**"electrical axis"**) of the heart, which normally lies between +90 degrees to –30 degrees in adults (→ **G, H**). *Right type* (α = +120° to +90°) is not unusual in children, but is often a sign of abnormality in adults. Mean QRS axes ranging from +90 degrees to +60 degrees are described as the *vertical type* (→ **G1**), and those ranging from +60 degrees to +30 degrees are classified as the *intermediate type* (→ **G2**). *Left type* occurs when α = +30 degrees to –30 degrees (→ **G3**).

Abnormal deviation: *Right axis deviation* (> +120°) can develop due right ventricular hypertrophy, while *left axis deviation* (more negative than –30°) can occur due to left ventricular hypertrophy.

An extensive **myocardial infarction** (**MI**) can shift the electrical axis of the heart. Marked *Q wave abnormality* (→ **I1**) is typical in *transmural myocardial infarction* (involving entire thickness of ventricular wall): Q wave duration > 0.04 s and Q wave amplitude > 25% of total amplitude of the QRS complex. These changes appear within 24 hours of MI and are caused by failure of the dead myocardium to conduct electrical impulses. Preponderance of the excitatory vector in the healthy contralateral side of the heart therefore occurs while the affected part of the myocardium should be depolarizing (first 0.04 s of QRS). The so-called "0.04-sec vector" is therefore said to point away from the infarction. *Anterior MI* is detected as highly negative Q waves (with smaller R waves) mainly in leads V5, V6, I and aVL. Q wave abnormalities can persist for years after MI (→ **I 2/3**), so they may not necessarily be indicative of an acute infarction. *ST elevation* points to ischemic but not (yet) necrotic parts of the myocardium. This can be observed: (1) in myocardial ischemia (angina pectoris), (2) in the initial phase of transmural MI, (3) in nontransmural MI, and (4) along the margins of a transmural MI that occurred a few hours to a few days prior (→ **I 4**). The ST segment normalizes within 1 to 2 days of MI, but the *T wave* remains inverted for a couple of weeks (→ **I 5** and **2**).

Excitation in Electrolyte Disturbances

Hyperkalemia. *Mild hyperkalemia* causes various changes, like elevation of the MDP (→ p. 192) in the SA node. It can sometimes have positive chronotropic effects (→ p. 193 B3c). In *severe hyperkalemia*, the more positive MDP leads to the inactivation of Na^+ channels (→ p. 46) and to a reduction in the slope and amplitude of APs in the AV node (negative dromotropic effect; → p. 195 B4). Moreover, the K^+ conductance (g_K) rises, and the PP slope becomes flatter due to a negative chronotropic effect (→ p. 195 B3a). Faster myocardial repolarization decreases the cytosolic Ca^{2+} conc. In extreme cases, the pacemaker is also brought to a standstill (*cardiac paralysis*). **Hypokalemia** (moderate) has positive chronotropic and inotropic effects (→ p. 195 B3a), whereas **hypercalcemia** is thought to raise the g_K and thereby shortens the duration of the myocardial AP.

ECG. Changes in serum K^+ and Ca^{2+} induce characteristic changes in myocardial excitation.


◆ *Hyperkalemia* (> 6.5 mmol/L): tall, peaked T waves and conduction disturbances associated with an increased PQ interval and a widened QRS. Cardiac arrest can occur in extreme cases.

◆ *Hypokalemia* (< 2.5 mmol/L): ST depression, biphasic T wave (first positive, then negative) followed by a positive U wave.


◆ *Hypercalcemia* (> 2.75 mmol/L total calcium): shortened QT interval due to a shortened ST segment.

◆ *Hypocalcemia* (< 2.25 mmol/L total calcium): prolonged QT interval.


F. Wilson chest leads (unipolar)




G. Determination of largest mean QRS vector (QRS axis) using ECG leads I–III



H. Electrical axis of the heart



I. ECG changes in coronary infarction



Arrhythmias are pathological changes in cardiac *impulse generation or conduction* that can be visualized by ECG. **Disturbances of impulse generation** change the sinus rhythm. *Sinus tachycardia* (→ **A2**): The sinus rhythm rises to 100 min^{-1} or higher e.g., due to physical exertion, anxiety, fever (rise of about 10 beats/min for each 1 °C) or hyperthyroidism. *Sinus bradycardia:* The heart rate falls below 60 min^{-1} (e.g., due to hypothyroidism). In both cases the rhythm is regular whereas in *sinus arrhythmias* the rate varies. In adolescents, sinus arrhythmias can be physiological and respiration-dependent (heart rate increases during inspiration and decreases during expiration).

Ectopic pacemakers. Foci in the atrium, AV node or ventricles can initiate abnormal *ectopic* (heterotopic) impulses, even when normal (*nomotopic*) stimulus generation by the SA node is taking place (→ **A**). The rapid discharge of impulses from an atrial focus can induce **atrial tachycardia** (serrated baseline instead of normal P waves), which triggers a ventricular response rate of up to 200 min^{-1}. Fortunately, only every second or third stimulus is transmitted to the ventricles because part of the impulses arrive at the Purkinje fibers (longest APs) during their refractory period. Thus, Purkinje fibers act as impulse *frequency filters*. Elevated atrial contraction rates of up to 350 min^{-1} are defined as **atrial flutter**, and all higher rates are defined as **atrial fibrillation** (up to 500 min^{-1}). Ventricular stimulation is then totally irregular (**absolute arrhythmia**). **Ventricular tachycardia** is a rapid train of impulses originating from a ventricular (ectopic) focus, starting with an extrasystole (ES) (→ **B3**; second ES). The heart therefore fails to fill adequately, and the stroke volume decreases. A ventricular ES can lead to **ventricular fibrillation** (extremely frequent and uncoordinated contractions; → **B4**). Because of failure of the ventricle to transport blood, ventricular fibrillation can be fatal.

Ventricular fibrillation mainly occurs when an ectopic focus fires during the **relative refractory period** of the previous AP (called the "*vulnerable phase*" synchronous with T wave on the ECG; → p. 195 A). The APs triggered during this period have *smaller slopes, lower propagation velocities, and shorter durations*. This leads to re-excitation of myocardial areas that have already been stimulated (*re-entry cycles*). Ventricular fibrillation can be caused by electrical accidents and can usually be corrected by timely electrical *defibrillation*.


Extrasystoles (ES). The spread of impulses arising from an supraventricular (atrial or nodal) ectopic focus to the ventricles can disturb their sinus rhythm, leading to a *supraventricular arrhythmia*. When **atrial extrasystoles** occur, the P wave on the ECG is distorted while the QRS complex remains normal. **Nodal extrasystoles** lead to retrograde stimulation of the atria, which is why the P wave is negative and is either masked by the QRS complex or appears shortly thereafter (→ **B1** right). Since the SA node often is discharged by a supraventricular extrasystole, the interval between the R wave of the extrasystole (R_{ES}) and the next normal R wave increases by the amount of time needed for the stimulus to travel from the focus to the SA node. This is called the *post-extrasystole pause*. Thereby, the *RR intervals* are as follows: $R_{ES}R > RR$ and ($RR_{ES} + R_{ES}R$) < 2 RR (→ **B1**).

Ventricular (or infranodal) **ES** (→ **B2, B3**) distorts the QRS complex of the ES. If the sinus rate is slow enough, the ES will cause a ventricular contraction between two normal heart beats; this is called an *interpolated* (or interposed) ES (→ **B2**). If the sinus rate is high, the next sinus stimulus reaches the ventricles while they are still refractory from the ectopic excitation. Ventricular contraction is therefore blocked until the next sinus stimulus arrives, resulting in a *compensatory pause*, where $RR_{ES} + R_{ES}R = 2$ RR.


Disturbances of impulse conduction: AV block. *First-degree* AV block: prolonged but otherwise normal impulse conduction in the AV node (PQ interval > 0.2 sec); *second-degree* AV block: only every second (2:1 block) or third (3:1 block) impulse is conducted. *Third-degree* AV block: no impulses are conducted; sudden cardiac arrest may occur (*Adam–Stokes attack* or *syncope*). Ventricular atopic pacemakers then take over (ventricular bradycardia with normal atrial excitation rate), resulting in partial or total disjunction of QRS complexes and P waves (→ **B5**). The heart rate drops to 40 to 55 min^{-1} when the AV node acts as the pacemaker (→ **B5**), and to a mere 25 to 40 min^{-1} when tertiary (ventricular) pacemakers take over. Artificial pacemakers are then used.

Bundle branch block: disturbance of conduction in a branch of the bundle of His. Severe QRS changes occur because the affected side of the myocardium is activated by the healthy side via abnormal pathways.


A. Nomotopic impulse generation with normal conduction



1 Normal sinus rhythm




2 Sinus tachycardia




B. Heterotopic impulse generation (1–5) and disturbances of impulse conduction (5)




1 Nodal (AV) extrasystole (ES) with post-extrasystolic pause






2 Interpolated ventricular extrasystole (ES)




3 Ventricular tachycardia following extrasystole (ES)



4 Ventricular fibrillation



5 Total AV block with ventricular escape rhythm



(Partly after Riecker)

The relationship between the volume (length) and pressure (tension) of a ventricle illustrates the interdependence between muscle length and force in the specific case of the heart (→ p. 66ff.). The **work diagram** of the heart can be constructed by plotting the changes in *ventricular pressure over volume* during one complete cardiac cycle (→ **A1**, points A-D-S-V-A, pressure values are those for the left ventricle).

The following *pressure–volume curves* can be used to construct a **work diagram of the ventricles**:

- **Passive (or resting) pressure–volume curve:** Indicates the pressures that result passively (without muscle contraction) at various ventricular volume loads (→ **A1, 2**; blue curve).
- **Isovolumic peak curve** (→ **A1, 2**, green curves): Based on experimental measurements made using an isolated heart. Data are generated for various volume loads by measuring the peak ventricular pressure at a constant ventricular volume during contraction. The contraction is therefore *isovolumetric (isovolumic)*, i.e., ejection does not take place (→ **A2**, vertical arrows).
- **Isotonic** (or **isobaric**) **peak curve** (→ **A1, 2**, violet curves). Also based on experimental measurements taken at various volume loads under isotonic (isobaric) conditions, i.e., the ejection is controlled in such a way that the ventricular pressure remains constant while the volume decreases (→ **A2**, horizontal arrows).
- **Afterloaded peak curve**: (**A1, 2**, orange curves). Systole (→ p. 192) consists of an *isovolumic* contraction phase (→ **A1**, A–D and p. 193 A, phase I) followed by an *auxotonic* ejection phase (volume decreases while pressure continues to rise) (→ **A1**, D–S and p. 193 A, phase II). This type of mixed contraction is called an *afterloaded contraction* (see also p. 67 B). At a given volume load (preload) (→ **A1**, point A), the afterloaded peak value changes (→ **A1**, point S) depending on the aortic end-diastolic pressure (→ **A1**, point D). All the afterloaded peak values are represented on the curve, which appears as a (nearly) straight line connecting the isovolumic and isotonic peaks for each respective volume load (point A) (→ **A1**, points T and M).


Ventricular work diagram. The pressure–volume relationships observed during the cardiac cycle (→ p. 192) can be plotted as a work diagram, e.g., for the left ventricle (→ **A1**): The *end-diastolic volume* (**EDV**) is 125 mL (→ **A1**, point A). During the *isovolumetric contraction phase*, the pressure in the left ventricle rises (all valves closed) until the diastolic aortic pressure (80 mmHg in this case) is reached (→ **A1**, point D). The aortic valve then opens. During the *ejection phase*, the ventricular volume is reduced by the *stroke volume* (**SV**) while the pressure initially continues to rise (→ p. 190, *Laplace's law*, Eq. 8.4b: P_{tm} ↑ because r ↓ and w ↑). Once maximum (systolic) pressure is reached (→ **A1**, point S), the volume will remain virtually constant, but the pressure will drop slightly until it falls below the aortic pressure, causing the aortic valve to close (→ **A1**, point K). During the *isovolumetric relaxation* phase, the pressure rapidly decreases to (almost) 0 (→ **A1**, point V). The ventricles now contain only the *end-systolic volume* (**ESV**), which equals 60 mL in the illustrated example. The ventricular pressure rises slightly during the filling phase (passive pressure–volume curve).

Cardiac Work and Cardiac Power


Since work (J = N · m) equals pressure (N · m^{-2} = Pa) times volume (m^3), the area within the working diagram (→ **A1**, pink area) represents the **pressure/volume (P/V) work** achieved by the left ventricle during systole (13,333 Pa · 0.00008 m^3 = 1.07 J; right ventricle: 0.16 J). In systole, the bulk of cardiac work is achieved by active contraction of the myocardium, while a much smaller portion is attributable to passive elastic recoil of the ventricle, which stretches while filling. This represents *diastolic filling work* (→ **A1**, blue area under the blue curve), which is shared by the ventricular myocardium (indirectly), the atrial myocardium, and the respiratory and skeletal muscles (→ p. 206, venous return).

Total cardiac work. In addition to the cardiac work performed by the left and right ventricles in systole (ca. 1.2 J at rest), the heart has to generate 20% more energy (0.24 J) for the pulse wave (→ p. 190, windkessel). Only a small amount of energy is required to accelerate the blood at rest (1% of total cardiac work), but the energy requirement rises with the heart rate. The total **cardiac power** (= work/time) at rest (70 min^{-1} = 1.17 s^{-1}) is approximately 1.45 J · 1.17 s^{-1} = 1.7 W.

A. Work diagram of the heart (left ventricle)



B. Effects of pretension (preload) (1), heart rate and sympathetic stimuli (2) on myocardial force and contraction velocity



(See text on next page)

(After Sonnenblick)

Frank–Starling mechanism (**FSM**): The heart *autonomously* responds to changes in ventricular volume load or aortic pressure load by adjusting the stroke volume (SV) in accordance with the myocardial *preload* (resting tension; → p. 66 ff.). The FSM also functions to maintain an equal SV in both ventricles to prevent congestion in the pulmonary or systemic circulation.

Preload change. When the volume load (preload) *increases*, the start of isovolumic contraction shifts to the right along the passive P–V curve (→ **A1**, from point A to point A_1). This increases end-diastolic volume (EDV), stroke volume (SV), cardiac work and end-systolic volume (ESV) (→ **A**).

Afterload change. When the aortic pressure load (afterload) *increases*, the aortic valve will not open until the pressure in the left ventricle has risen accordingly (→ **A2**, point D_t). Thus, the SV in the short transitional phase (SV_t) will decrease, and ESV will rise (ESV_t). Consequently, the start of the isovolumic contraction shifts to the right along the passive P–V curve (→ **A2**, point A_2). SV will then normalize (SV_2) despite the increased aortic pressure (D_2), resulting in a relatively large increase in ESV (ESV_2).

Preload or **afterload-independent changes** in myocardial contraction force are referred to as **contractility** or **inotropism**. It increases in response to norepinephrine (NE) and epinephrine (E) as well as to increases in heart rate (β_1-adrenoceptor-mediated, positive inotropic effect and frequency inotropism, respectively; → p. 196). This causes a number of effects, particularly, an increase in isovolumic pressure peaks (→ **A3**, green curves). The heart can therefore pump against increased pressure levels (→ **A3**, point D_3) and/or eject larger SVs (at the expense of the ESV) (→ **A3**, SV_4).

While changes in the preload only affect the **force** of contraction (→ p. 205 B1), changes in contractility also affect the **velocity** of contraction (→ p. 205/B2). The steepest increase in isovolumic pressure per unit time (*maximum dP/dt*) is therefore used as a measure of contractility in clinical practice. dP/dt is increased E and NE and decreased by bradycardia (→ p. 205 B2) or heart failure.

Venous Return


Blood from the capillaries is collected in the veins and returned to the heart. The **driving forces** for this venous return (→ **B**) are: (a) *vis a tergo*, i.e., the postcapillary blood pressure (BP) (ca. 15 mmHg); (b) the suction that arises due to lowering of the cardiac valve plane in systole; (c) the pressure exerted on the veins during skeletal muscle contraction (*muscle pump*); the valves of veins prevent the blood from flowing in the wrong direction, (d) the increased abdominal pressure together with the lowered intrathoracic pressure during inspiration (P_{pl}; → p. 108), which leads to thoracic venous dilatation and suction (→ p. 208).

Orthostatic reflex. When rising from a supine to a standing position (orthostatic change), the blood vessels in the legs are subjected to additional hydrostatic pressure from the blood column. The resulting vasodilation raises blood volume in the leg veins (by ca. 0.4 L). Since this blood is taken from the *central blood volume*, i.e., mainly from pulmonary vessels, venous return to the left atrium decreases, resulting in a decrease in stroke volume and cardiac output. A reflexive increase (*orthostatic reflex*) in heart rate and peripheral resistance therefore occurs to prevent an excessive drop in arterial BP (→ pp. 7 E and 214 ff.); *orthostatic collapse* can occur. The drop in central blood volume is more pronounced when standing than when walking due to muscle pump activity. Conversely, pressure in veins above the heart level, e.g., in the cerebral veins, decreases when a person stands still for prolonged periods of time. Since the venous pressure just below the diaphragm remains constant despite changes in body position, it is referred to as a *hydrostatic indifference point*.


The **central venous pressure** (**CVP**) is measured at the right atrium (normal range: 0–12 cm H_2O or 0–9 mmHg). Since it is mainly dependent on the blood volume, the CVP is used to monitor the blood volume in clinical medicine (e.g., during a transfusion). Elevated CVP (> 20 cm H_2O or 15 mmHg) may be pathological (e.g., due to heart failure or other diseases associated with cardiac pump dysfunction), or physiological (e.g., in pregnancy).

A. Factors influencing cardiac action


1 Increase in filling (preload)




2 Increase in blood pressure (afterload)



3 Increase in contractility



B. Venous return



The term blood pressure (BP) *per se* refers to the arterial BP in the systemic circulation. The maximum BP occurs in the aorta during the systolic ejection phase; this is the **systolic pressure** (P_s); the minimum aortic pressure is reached during the isovolumic contraction phase (while the aortic valves are closed) and is referred to as the **diastolic pressure** (P_d) (→ **A1** and p. 193, phase I in A2). The systolic–diastolic pressure difference (P_s–P_d) represents the **blood pressure amplitude,** also called **pulse pressure** (**PP**), and is a function of the stroke volume (SV) and arterial compliance (C = dV/dP, → p. 190). When C decreases at a constant SV, the systolic pressure P_s will rise more sharply than the diastolic pressure P_d, i.e., the PP will increase (common in the elderly; described below). The same holds true when the SV increases at a constant C.

If the **total peripheral resistance** (TPR, → p. 190) **increases** while the SV ejection time remains constant, then P_s and the P_d will increase by the same amount (no change in PP). However, increases in the TPR normally lead to retardation of SV ejection and a decrease in the ratio of arterial volume rise to peripheral drainage during the ejection phase. Consequently, P_s rises less sharply than P_d and PP decreases.

Normal range. P_d optimally ranges from 60 to 80 mm Hg and P_s from 100 to 120 mm Hg at rest (while sitting or reclining). A P_s of 120–139 mm Hg and/or a P_d of 80–89 mm Hg are considered to be prehypertensive (JNC-7 classification) (→ **C**). Optimal BP regulation (→ p. 214) is essential for proper tissue perfusion.

Abnormally low BP (**hypotension**) can lead to *shock* (→ p. 220), *anoxia* (→ p. 130) and tissue destruction. Chronically elevated BP (P_s > 140 and/or P_d > 90; **hypertension;** → p. 218) also causes damage because important vessels (especially those of the heart, brain, kidneys and retina) are injured.

The **mean BP** (= the average measured over time) is the decisive factor of peripheral perfusion (→ p. 190).

The mean BP can be determined by continuous BP measurement using an arterial catheter, etc. (→ **A**). By *attenuating* the pressure signal, only the $\bar{P}$ is recorded. It is calculated as follows: $\bar{P} \approx {}^1/_3 (2\,P_d + P_s)$.

Although the mean BP falls slightly as the blood travels from the aorta to the arteries, the P_s in the greater arteries (e.g., femoral artery) is usually higher than in the aorta (**A1** *v.* **A2**) because their compliance is lower than that of the aorta (see pulse wave velocity, p. 192).


Direct invasive BP measurements show that the BP curve in arteries distal to the heart is not synchronous with that of the aorta due to the time delay required for passage of the pulse wave (3–10 m/s; → p. 192); its shape is also different (→ **A1/A2**).

The **BP is routinely measured** externally (at the level of the heart) according to the *Riva-Rocci* method by **sphygmomanometer** (→ **B**). An inflatable cuff is snugly wrapped around the arm and a stethoscope is placed over the brachial artery at the crook of the elbow. While reading the manometer, the cuff is inflated to a pressure higher than the expected P_s (the radial pulse disappears). The air in the cuff is then slowly released (2–4 mmHg/s). The first sounds synchronous with the pulse (*Korotkoff sounds*) indicate that the cuff pressure has fallen below the P_s. This value is read from the manometer. These sounds first become increasingly louder, then more quiet and muffled and eventually disappear when the cuff pressure falls below the P_d (second reading).


Reasons for false BP readings. When re-measuring the blood pressure, the cuff pressure must be completely released for 1 to 2 min. Otherwise venous pooling can mimic elevated P_d. The cuff of the sphygmomanometer should be 20% broader than the diameter of the patient's upper arm. Falsely high P_d readings can also occur if the cuff is too loose or too small relative to the arm diameter (e.g., in obese or very muscular patients) or if measurement has to be made at the thigh.

The **blood pressure in the pulmonary artery** is much lower than the aortic pressure (→ p. 188). The pulmonary vessels have relatively thin walls and their environment (air-filled lung tissue) is highly compliant. Increased cardiac output from the right ventricle therefore leads to expansion and thus to decreased resistance of the pulmonary vessels (→ **D**). This prevents excessive rises in pulmonary artery pressure during physical exertion when cardiac output rises. The pulmonary vessels also function to buffer short-term fluctuations in blood volume (→ p. 206).


A. Arterial blood-pressure curve




B. Blood-pressure measurement with sphygmomanometer (Riva–Rocci)



C. Age-dependency of blood pressure



D. Blood pressure and blood flow rate



Nutrients and waste products are exchanged across the walls of the capillaries and postpapillary venules (*exchange vessels*; → p. 190). Their endothelia can contain small (ca. 2–5 nm) or large (20–80 nm, especially in the kidneys and liver) *functional pores:* permeable, intercellular fissures or endothelial fenestrae, respectively. The degree of endothelial permeability varies greatly from one organ to another. Virtually all endothelia allow water and inorganic ions to pass, but most are largely impermeable to blood cells and large protein molecules. Transcytosis and carriers (→ p. 26f.) allow for passage of certain larger molecules.

Filtration and reabsorption. About 20 L/day of fluid is filtered (excluding the kidneys) into the interstitium from the body's exchange vessels. About 18 L/day of this fluid is thought to be reabsorbed by the capillaries and venules, (see below). The remaining 2 L/day or so make up the **lymph flow** and thereby return to the bloodstream (→ **A**). The *filtration or reabsorption rate* Q_f is a factor of the endothelial **filtration coefficient K_f** (= water permeability k · exchange area A) and the **effective filtration pressure P_{eff}** ($Q_f = K_f \cdot P_{eff}$). P_{eff} is calculated as the hydrostatic pressure difference ΔP minus the oncotic pressure difference Δπ (→ p. 383) across the capillary wall (*Starling's relationship*; → **A**), where ΔP = capillary pressure (P_{cap}) minus interstitial pressure (P_{int}, normally ≈ 0 mmHg). At the level of the heart, ΔP at the arterial end of the systemic capillaries is about 30 mmHg and decreases to about 22 mmHg at the venous end. Since Δπ ($\pi_{Kap} - \pi_{int}$) ≈ 24 mmHg; → **A**) counteracts ΔP, the initially high filtration rate (P_{eff} = +6 mmHg) drops off along the capillary and when P_{eff} = 0 stops completely (filtration pressure equilibrium). A short (< 1 min) drop in P_{eff} below 0 causes reabsorption into the lumens of capillaries and venules. Rhythmic contraction (1–20 min^{-1}) of the arterioles (**vasomotion**; → **A**) may play a role by briefly decreasing P_{cap} (and therefore ΔP) to values less than Δπ, making P_{eff} negative. Since ΔP is only 10 mm Hg in the lungs, the pulmonary P_{eff} is negative to start with and therefore generally no filtration occurs.

In parts of the body below the heart, the effects of **hydrostatic pressure** from the blood column increase the pressure in the capillary lumen (in the feet ≈ 90 mmHg). The filtration rate in these regions therefore rise, especially when standing still. This is counteracted by two "self-regulatory" mechanisms: (1) the outflow of water results in an increase in the luminal protein concentration (and thus Δπ) along the capillaries (normally the case in glomerular capillaries, → p. 152); (2) increased filtration results in an increase in P_{int} and a consequent decrease in ΔP.

Edema. Fluid will accumulate in the interstitial space (*extracellular edema*), portal venous system (*ascites*), and pulmonary interstice (*pulmonary edema*) if the volume of filtered fluid is higher than the amount returned to the blood.


Causes of edema (→ **B**):


- *Increased capillary pressure* (→ **B1**) due to precapillary vasodilatation (P_{cap} ↑), especially when the capillary permeability to proteins also increases (σ_{prot} ↓ and Δπ ↓) due, for example, to infection or anaphylaxis (histamine etc.). Hypertension in the portal vein leads to ascites.
- *Increased venous pressure* (P_{cap} ↑, → **B2**) due, for example, to venous thrombosis or heart failure (*cardiac edema*).
- *Decreased concentration of plasma proteins*, especially albumin, leading to a drop in Δπ (→ **B3** and p. 385 A) due, for example, to loss of proteins (proteinuria), decreased hepatic protein synthesis (e.g., in liver cirrhosis), or to increased breakdown of plasma proteins to meet energy requirements (*hunger edema*).
- *Decreased lymph drainage* due, e.g., to lymph tract compression (tumors), severance (surgery), obliteration (radiation therapy) or obstruction (bilharziosis) can lead to *localized edema* (→ **B4**).
- *Increased hydrostatic pressure* promotes edema formation in lower regions of the body (e.g., in the ankles; → **B**).

Diffusion. Although dissolved particles are dragged through capillary walls along with filtered and reabsorbed water (solvent drag; → p. 24), diffusion plays a much greater role in the exchange of solutes. *Net diffusion* of a substance (e.g., O_2, CO_2) occurs if its plasma and interstitial conc. are different.


A. Exchange of fluids via capillaries

P_{eff} (effective filtration pressure) = ΔP (hydrostatic pressure difference) − $\Delta\pi$ (oncotic pressure difference)
= internal/external pressure difference





B. Causes of edema



Coronary arteries. The blood flow to the myocardium is supplied by the two coronary arteries that arise from the aortic root. The right coronary artery (approx. 1/7th of the blood) usually supplies the greater portion of the right ventricle, while the left coronary artery (6/7th of the blood) supplies the left ventricle (→ **A**). The contribution of both arteries to blood flow in the septum and posterior wall of the left ventricle varies.

Coronary blood flow ($\dot{Q}_{cor}$) is phasic, i.e., the amount of blood in the coronary arteries fluctuates during the cardiac cycle due to extremely high rises in extravascular tissue pressure during systole (→ **B, C**). The blood flow in the epicardial coronary artery branches and subepicardial vessels remains largely unaffected by these pressure fluctuations. However, the *subendocardial vessels* of the *left ventricle* are compressed during systole when the extravascular pressure in that region (≈ pressure in left ventricle, P_{LV}) exceeds the pressure in the lumen of the vessels (→ **C**). Consequently, the left ventricle is mainly supplied during diastole (→ **B** middle). The fluctuations in right ventricular blood flow are much less distinct because right ventricular pressure (P_{RV}) is lower (→ **B, C**).

Myocardial O_2 consumption ($\dot{V}O_2$) is defined as $\dot{Q}_{cor}$ times the arteriovenous O_2 concentration difference, $(C_a–C_v)_{O2}$. The myocardial $(C_a–C_v)_{O2}$ is relatively high (0.12 L/L blood), and *oxygen extraction* at rest ($[C_a–C_v]_{O2}/C_aO_2$ = 0.12/0.21) is almost 60% and, thus, not able to rise much further. Therefore, an increase in $\dot{Q}_{cor}$ is practically the only way to increase myocardial $\dot{V}O_2$ when the O_2 demand rises (→ **D**, right side).

Adaptation of the myocardial O_2 supply according to need is therefore primarily achieved by *adjusting vascular resistance* (→ **D**, left side). The (distal) coronary vessel resistance can normally be reduced to about 1/4 the resting value (*coronary reserve*). The coronary blood flow $\dot{Q}_{cor}$ (approx. 250 mL/min at rest) can therefore be increased as much as 4–5 fold. In other words, approx. 4 to 5 times more O_2 can be supplied during maximum physical exertion.

Arteriosclerosis (atherosclerosis) of the coronary arteries leads to luminal narrowing and a resultant decrease in poststenotic pressure. Dilatation of the distal vessels then occurs as an autoregulatory response (see below). Depending on the extent of the stenosis, it may be necessary to use a fraction of the coronary reserve, even during rest. As a result, lower or insufficient quantities of O_2 will be available to satisfy increased O_2 demand, and *coronary insufficiency* may occur (→ **D**)


Myocardial O_2 demand increases with cardiac output (increased pressure–volume–work/time; → p. 204f), i.e., in response to increases in heart rate and/or contractility, e.g., during physical exercise (→ **D**, right). It also increases as a function of mural tension (T_{ventr}) times the duration of systole (*tension–time index*). Since $T_{ventr} = P_{ventr} \cdot r_{ventr}/2w$ (*Laplace's law* → Eq. 8.4b, p. 190), O_2 demand is greater when the ventricular pressure (P_{ventr}) is high and the stroke volume small than when P_{ventr} is low and the stroke volume high, even when the same amount of work ($P \times V$) is performed. In the first case, the **efficiency of the heart** is reduced. When the ventricular pressure P_{ventr} is elevated, e.g., in *hypertension*, the myocardium therefore requires more O_2 to perform the same amount of work (→ **D**, right).

Since the myocardial metabolism is aerobic, an increased O_2 demand quickly has to lead to vasodilatation. The following factors are involved in the **coronary vasodilatation**:


- **Metabolic factors**: (a) oxygen deficiency since O_2 acts as a vasoconstrictor; (b) Adenosine; oxygen deficiencies result in insufficient quantities of AMP being re-converted to ATP, leading to accumulation of *adenosine*, a degradation product of AMP. This leads to A_2 receptor-mediated vasodilatation; (c) Accumulation of lactate and H^+ ions (from the anaerobic myocardial metabolism); (d) prostaglandin I_2.
- **Endothelial factors**: ATP (e.g., from platelets), bradykinin, histamine and acetylcholine are vasodilators. They liberate nitric oxide (NO) from the endothelium, which diffuses into vascular muscle cells to stimulate vasodilatation (→ p. 281 E).
- **Neurohumoral factors**: Norepinephrine released from sympathetic nerve endings and adrenal epinephrine have a vasodilatory effect on the distal coronary vessels via β_2 adrenoceptors.

Myocardial energy sources. The myocardium can use the available glucose, free fatty acids, lactate and other molecules for ATP production. The oxidation of each of these three energy substrates consumes a certain fraction of myocardial O_2 (O_2 extraction coefficient); accordingly, each contributes approx. one-third of the produced ATP at rest. The myocardium consumes increasing quantities of *lactate* from the skeletal muscles during physical exercise (→ **A**, → p. 72 and 284).


A. Blood supply, O_2 and substrate consumption of heart muscle




B. Coronary blood flow



C. Systolic pressures in heart



D. Components of O_2 balance in myocardium



The blood flow must be regulated to ensure an adequate blood supply, even under changing environmental conditions and stress (cf. p. 74). This implies (a) optimal regulation of cardiac activity and blood pressure (*homeostasis*), (b) adequate perfusion of all organ systems, and (c) shunting of blood to active organ systems (e.g., muscles) at the expense of the resting organs (e.g., gastrointestinal tract) to keep from overtaxing the heart (→ **A**).

Regulation of blood flow to the organs is mainly achieved by changing the *diameter of blood vessels*. The muscle tone (tonus) of the vascular smooth musculature changes in response to (1) *local stimuli* (→ **B2a/b**), (2) *hormonal signals* (→ **B3 a/b**) and (3) *neuronal signals* (→ **B1 a/b**). Most blood vessels have an intermediary muscle tone at rest (*resting tone*). Many vessels dilate in response to denervation, resulting in a *basal tone*. This occurs due to spontaneous depolarization of smooth muscle in the vessels (see also p. 70).

Local Regulation of Blood Flow (Autoregulation)

Autoregulation has two **functions**:

◆ Autoregulatory mechanisms help to maintain a *constant blood flow* to certain organs when the blood pressure changes (e.g., renal vessels constrict in response to rises in blood pressure; → p. 150).

◆ Autoregulation also functions to *adjust the blood flow* according to changes in metabolic activity of an organ (*metabolic autoregulation*); the amount of blood flow to the organ (e.g., cardiac and skeletal muscle; → **A** and p. 212) can thereby increase many times higher than the resting level.

Types of autoregulatory **mechanism:**

◆ **Myogenic effects** arising from the vascular musculature of the lesser arteries and arterioles (*Bayliss effect*) ensure that these vessels *contract* in response to blood pressure-related dilatation (→ **B2a**) in certain organs (e.g., kidneys, gastrointestinal tract and brain), but not in others (e.g., skin and lungs).

◆ **Oxygen deficiencies** generally cause the blood vessels to *dilate*. Hence, the degree of blood flow and O_2 uptake increase with increasing O_2 consumption. In the lungs, on the other hand, a low P_{O_2} in the surrounding alveoli causes the vessels to *contract* (*hypoxic vasoconstriction*; → p. 122).

◆ **Local metabolic (chemical) effects**: An increase in local concentrations of *metabolic products* such as CO_2, H^+, ADP, AMP, adenosine, and K^+ in the interstitium has a *vasodilatory effect*, especially in precapillary arterioles. The resulting rise in blood flow not only improves the supply of substrates and O_2, but also accelerates the efflux of these metabolic products from the tissue. The blood flow to the *brain* and *myocardium* (→ p. 212) is almost entirely subject to local metabolic control. Both local metabolic effects and O_2 deficiencies lead to an up to 5-fold increase in blood flow to an affected region in response to the decreased blood flow (*reactive hyperemia*).

◆ **Vasoactive substances**: A number of vasoactive substances such as prostaglandins play a role in autoregulation (see below).

Hormonal Control of Circulation


Vasoactive substances. Vasoactive hormones either have a direct effect on the vascular musculature (e.g., epinephrine) or lead to the local release of vasoactive substances (e.g., nitric oxide, endothelin) that exert local paracrine effects (→ **B**).

◆ **Nitric (mon)oxide (NO)** acts as a *vasodilatory* agent. NO is released from the *endothelium* when acetylcholine (M receptors), ATP, endothelin (ET_B receptors), or histamine (H_1 receptors) binds with an endothelial cell (→ p. 280). NO then diffuses to and relaxes vascular myocytes in the vicinity.


◆ **Endothelin-1** can lead to *vasodilatation* by inducing the release of NO from the *endothelium* by way of ET_B receptors (see above), or can cause *vasoconstriction* via ET_A receptors in the vascular musculature. When substances such as angiotensin II or ADH (= vasopressin; V_1 receptor) bind to an endothelial cell, they release endothelin-1, which diffuses to and constricts the adjacent vascular muscles with the aid of ET_A receptors.

◆ **Epinephrine** (**E**): High concentrations of E from the adrenal medulla (→ p. 86) have a *vasoconstrictive* effect (α_1-adrenoceptors), whereas low concentrations exert *vasodilatory* effects by way of β_2 adrenoceptors in the *myocardium, skeletal muscle* and *liver* (→ **C**). The effect of E mainly depends on which type of adrenoceptor is predominant in the organ. α_1- ▶

A. Blood flow to organs



B. Vasoconstriction and vasodilatation



▶ adrenoceptors are predominant in the blood vessels of the *kidney* and *skin*.

◆ **Eicosanoids** (→ p. 271): Prostaglandin (PG) $F_{2\alpha}$ and the thromboxanes A_2 (released from platelets, → p. 102) and B_2 have *vasoconstrictive* effects, while PGI_2 (= prostacyclin, e.g. released from endothelium) and PGE_2 have vasodilatory effects. Another vasodilator released from the endothelium (e.g., by bradykinin; see below) opens K^+ channels in vascular myocytes and hyperpolarizes them, leading to a drop in the cytosolic Ca^{2+} concentration. This endothelium-derived hyperpolarizing factor (EDHF), has been identified as a 11,12-epoxyeicosatrienoic acid (11,12-EET).

◆ **Bradykinin and kallidin** are *vasodilatory* agents cleaved from kininogens in blood plasma by the enzyme kallikrein. **Histamine** also acts as a vasodilator. All three substances influence also vessel permeability (e.g., during infection) and blood clotting.

Neuronal Regulation of Circulation

Neuronal regulation of *blood flow* (→ **B1a/b**) mainly involves the *lesser arteries* and *greater arterioles* (→ p. 190), while that of *venous return* to the heart (→ p. 206) can be controlled by dilating or constricting the *veins* (changes in their blood storage capacity). Both mechanisms are usually controlled by the **sympathetic nervous system** (→ **B1a** and p. 78ff.), whereby **norepinephrine** (NE) serves as the postganglionic transmitter (except in the sweat glands). NE binds with the α_1 adrenoceptors on blood vessels, causing them to constrict (→ **B**). Vasodilatation is usually achieved by decreasing the tonus of the sympathetic system (→ **B1b**). This does not apply to blood vessels in salivary glands (increased secretion) or the genitals (erection), which dilate in response to *parasympathetic* stimuli. In this case, vasoactive substances (bradykinin and NO, respectively) act as the mediators. Some neurons release calcitonin gene-related peptide (CGRP), a potent vasodilator.


Neuronal regulation of blood flow to organs occurs mainly: (a) via *central co-innervation* (e.g., an impulse is simultaneously sent from the cerebral cortex to circulatory centers when a muscle group is activated, or (b) via *neuronal feedback* from the organs whose activity level and metabolism have changed. If the neuronal and local metabolic mechanisms are conflicting (e.g., when sympathetic nervous stimulation occurs during skeletal muscle activity), the metabolic factors will predominate. Vasodilatation therefore occurs in the active **muscle** while the sympathetic nervous system reduces the blood flow to the inactive muscles. Blood flow to the **skin** is mainly regulated by neuronal mechanisms for the purpose of controlling heat disposal (*temperature control*; → p. 226). Hypovolemia and hypotension lead to *centralization of blood flow*, i.e., vasoconstriction in the kidney (oliguria) and skin (pallor) occurs to increase the supply of blood to vital organs such as the heart and central nervous system (→ p. 220).

During exposure to extremely low temperatures, the cold-induced vasoconstriction of cutaneous vessels is periodically interrupted to supply the skin with blood to prevent tissue damage (**Lewis response**). Stimulation of nociceptor fibers in the skin can cause their axon collaterals to release neuropeptides (substance P, CGRP) which are responsible for vasodilatation and skin reddening in the area (**axon reflex**).

Central regulation of blood flow (→ **C**) is the responsibility of the CNS areas in the medulla oblongata and pons. They receive information from **circulatory sensors (S)** or **receptors** (a) in the high-pressure system (barosensors or pressure sensors, S_P, in the aorta and carotid artery); (b) in the low-pressure system (stretch sensors in the vena cava and atria, S_A and S_B); and (c) in the left ventricle (S_V). The sensors measure *arterial blood pressure* (S_P), *pulse rate* (S_P and S_V) and filling pressure in the low pressure system (indirect measure of *blood volume*). The A sensors (S_A) mainly react to atrial contraction, whereas the B sensors (S_B) react to passive filling stretch (→ **C2**). If the measured values differ from the set-point value, the *circulatory control centers* of the CNS transmit regulatory impulses through efferent nerve fibers to the heart and blood vessels (→ **D** and p. 5 C2).

Situated laterally in the circulatory "center" is a **pressor area** (→ **C**, reddish zone), the neurons of which (blue arrows) continuously transmit sympathetic nerve impulses to the ▶

C. Central regulation of blood flow



▶ heart to increase its activity (heart rate, conduction and contractility). Their effects on vessels are predominantly vasoconstrictive (resting tone). The pressor area is in close contact with more medial neurons (**depressor area**, light blue area in **C**). The pressor and depressor areas are connected to the dorsal nuclei of the vagus nerve (→ **C**, green), the stimulation of which reduces the heart rate and cardiac impulse conduction rate (→ **C**, orange arrows).

Homeostatic circulatory reflexes include signals along afferent nerve tracts (→ **D3a/b**) that extend centrally from the pressosensors in the aorta and carotid sinus (→ **C**, green tracts). The main purpose of homeostatic control is to maintain the *arterial blood pressure* at a stable level. Acute increases in blood pressure heighten the rate of afferent impulses and activate the depressor area. By way of the vagus nerve, parasympathetic neurons (→ **C**, orange tract) elicit the depressor reflex response, i.e., they decrease the *cardiac output* (*CO*). In addition, inhibition of sympathetic vessel innervation causes the vessels to dilate, thereby reducing the *peripheral resistance* (TPR; → **D4a/b**). Both of these mechanisms help to lower acute increases in blood pressure. Conversely, an acute drop in blood pressure leads to activation of pressor areas, which stimulates a rise in CO and TPR as well as venous vasoconstriction (→ **C**, blue tracts), thereby raising the blood pressure back to normal.

Due to the *fast adaptation* of pressosensors (*differential characteristics,* → p. 314ff.), these regulatory measures apply to *acute changes in blood pressure*. Rising, for example, from a supine to a standing position results in rapid redistribution of the blood volume. Without homeostatic control (*orthostatic reflex*; → p. 7, E and p. 206), the resulting change in venous return would lead to a sharp drop in arterial blood pressure. The circulatory centers also respond to falling P_{O_2} or rising P_{CO_2} in the blood (cross-links from respiratory center) to raise the blood pressure as needed.

In individuals with chronic **hypertension**, the input from the pressosensors is normal because they are fully adapted. Therefore, circulatory control centers cannot respond to and decrease the high pressures. On the contrary, they may even help to "fix" the blood pressure at the high levels. Chronic hypertension leads to stiffening of the carotid sinus. This may also contribute to decreasing the sensitivity of carotid pressosensors in hypertension.

A temporary *increase in venous return* (e.g., after an intravenous infusion) also leads to an increase in heart action (→ **D**, right). This mechanism is known as the **Bainbridge reflex**. The physiological significance of this reflex is, however, not entirely clear, but it may complement the Frank–Starling mechanism (→ p. 204ff.).

Hypertension


Hypertension is defined as a chronic increase in the systemic arterial blood pressure. The general criterion for diagnosis of hypertension is consistent elevation of resting blood pressure to > 90 mmHg and/or > 140 mmHg diastolic and systolic, respectively (→ p. 208). Untreated or inadequately managed hypertension results in stress and compensatory hypertrophy of the left ventricle which can ultimately progress to *left heart failure*. Individuals with hypertension are also at risk for arteriosclerosis and its sequelae (myocardial infarction, stroke, renal damage, etc.). Therefore, hypertension considerably shortens the life expectancy of a large fraction of the population.

The **main causes of hypertension** are (a) increased extracellular fluid (ECF) volume with increased venous return and therefore increased cardiac output (*volume hypertension*) and (b) increased total peripheral resistance (*resistance hypertension*). As hypertension always leads to vascular changes resulting in increased peripheral resistance, type *a* hypertension eventually proceeds to type *b* which, regardless of how it started, ends in a vicious circle.

The ECF volume increases when more NaCl (and water) is absorbed than excreted. The usually high intake of dietary salt may therefore play a role in the development of **essential hypertension** (primary hypertension), the most common type of hypertension, at least in patients sensitive to salt. Volume hypertension can even occur when a relatively low salt intake can no longer be balanced. This can occur in renal insufficiency or when an adrenocortical tumor produces uncontrolled amounts of aldosterone, resulting in Na^+ retention.

Other important cause of hypertension is **pheochromocytoma**, a tumor that secretes epinephrine and norepinephrine and therefore raises the CO and TPR. **Renal hypertension** can occur due to renal artery stenosis and renal disease. This results in the increased secretion of *renin*, which in turn raises the blood pressure via the renin–angiotensin–aldosterone (RAA) system (→ p. 186).

D. Circulatory reflexes



Arterial blood pressure rises	**1. Stimulus**	**Venous return rises Atrial pressure rises**
Pressosensors in: a) Aorta b) Carotid artery c) Left ventricle	**2. Sensors**	d) Atrial and venous stretch sensors
a) Glossopharyngeal nerve (IXth nerve) b) Vagus nerve (Xth nerve)	**3. Afferent path**	c) Vagus nerve (Xth nerve)
a) Stimulation of parasympathetic system b) Inhibition of sympathetic system	**4. Efferent path**	c) Stimulation of sympathetic system
Bradycardia Cardiac output decreases Vasodilatation Peripheral resistance decreases	**5. Response**	Tachycardia, myocardial contractility increases
Arterial blood pressure decreases	**6. Goal achieved**	**Cardiac output rises**

Circulatory shock is characterized by acute or subacute progressive *generalized failure of the circulatory system* with disruption of the microcirculation and *failure to maintain adequate blood flow to vital organs*. In most cases, the **cardiac output** (**CO**) **is insufficient** due to a variety of reasons, which are explained below.

◆ **Hypovolemic shock** is characterized by reduced central venous pressure and *reduced venous return*, resulting in an inadequate stroke volume (Frank–Starling mechanism). The blood volume can be reduced due to bleeding (*hemorrhagic shock)* or any other conditions associated with the external **loss of fluids** from the gastrointestinal tract (e.g., severe vomiting, chronic diarrhea), the kidneys (e.g., in diabetes mellitus, diabetes insipidus, high-dose diuretic treatment) or the skin (burns, profuse sweating without fluid intake). An *internal loss* of blood can also occur, e.g., due to bleeding into soft tissues, into the mediastinum or into the pleural and abdominal space.

◆ **Cardiogenic shock**: Acute *heart failure* can be caused by acute myocardial infarction, acute decompensation of heart failure or impairment of cardiac filling, e.g. in pericardial tamponade. The central venous pressure is higher than in hypovolemic shock.

◆ Shock can occur due to **hormonal causes**, such as adrenocortical insufficiency, diabetic coma or insulin overdose (hypoglycemic shock).

◆ **Vasogenic shock**: Reduced cardiac output can also be due to peripheral vasodilatation (absence of pallor) and a resultant drop of venous return. This occurs in Gram-positive septicemia (*septic shock*), *anaphylactic shock*, an immediate hypersensitivity reaction (food or drug allergy, insect bite/sting) in which vasoactive substances (e.g., histamines) are released.

Symptoms. Hypovolemic and cardiovascular shock are characterized by *decreased blood pressure* (weak pulse) *increased heart rate*, *pallor* with cold sweats (not observed with shock caused by vasodilatation), reduced urinary output (*oliguria*) and extreme *thirst*.

Shock index. The ratio of pulse rate (beats/min) to systolic blood pressure (mmHg), or *shock index*, provides a rough estimate of the extent of volume loss. An index of up to 0.5 indicates normal or $< 10\%$ blood loss; up to 1.0 = < 20–30% blood loss and impending shock; up to 1.5 = > 30–50% blood loss and manifest shock.


Most of the symptoms described reflect the **counterregulatory measures** taken by the body during the *non-progressive phase* of shock in order to ward off progressive shock (→ **A**). Rapid-acting mechanisms for *raising the* blood pressure and slower-acting mechanisms to *compensate for volume losses* both play a role.

Blood pressure compensation (→ **A** left): A drop in blood pressure *increases sympathetic tonus* (→ **A1** and p. 216). *Arterial vasoconstriction* (absent in shock due to vasodilatation) shunts the reduced cardiac output from the skin (pallor), abdominal organs and kidneys (oliguria) to vital organs such as the coronary arteries and brain. This is known as **centralization of blood flow** (→ **A2**). Sympathetic constriction of venous capacitance vessels (which raises ventricular filling), tachycardia and positive inotropism increase the diminished cardiac output to a limited extent.

Compensation for volume deficits (→ **A,** right): When shock is imminent, the resultant drop in blood pressure and peripheral vasoconstriction lead to a *reduction of capillary filtration pressure*, allowing interstitial fluid to enter the bloodstream. Atrial stretch sensors detect the decrease in ECF volume (reduced atrial filling) and transmit signals to stop the atria from secreting atriopeptin (= ANP) and to start the secretion of antidiuretic hormone (ADH) from the posterior lobe of the pituitary (*Gauer–Henry reflex*; → p. 170). *ADH* induces vasoconstriction (V_1 receptors) and water retention (V_2 receptors). The drop in renal blood pressure triggers an increase in *renin secretion* and activation of the renin–angiotensin–aldosterone (RAA) system (→ p. 186). If these measures are successful in warding off the impending shock, the lost red blood cells are later replaced (via increased renal erythropoietin secretion, → p. 88) and the plasma protein concentration is normalized by increased hepatic synthesis.

Manifest (or progressive) shock will develop if these homeostatic compensation mechanisms are unable to prevent impending shock and the patient does not receive medical treatment (infusion, etc.). Severe hypotension (< 90 mmHg systolic or < 60 mmHg mean blood pressure) can persist for extended periods, even in spite of volume replacement. The resulting development of hypoxia leads to organ damage and **multiple organ failure**, ultimately culminating in **irreversible shock** and death.

A. Compensation mechanisms for impending hypovolemic shock



Placenta. The maternal placenta acts as the "gut" (absorption of nutrients), "kidneys" (removal of waste products) and "lungs" of the fetus (uptake of O_2 and elimination of CO_2). Although the *fetal O_2-hemoglobin dissociation curve* is shifted to the left compared to that of adults (→ p. 129 C), only 60% (0.6) of placental hemoglobin is saturated with O_2 (→ **A**).

In the fetus, not yet active or hardly active organs such as the lungs receive little blood. The **fetal cardiac output** (from both ventricles) is about 0.2 L/min per kg body weight. The **fetal heart rate** rises from an initial 65 min^{-1} (week 5) to 130–160 min^{-1} in later weeks. Approx. 50% of the blood ejected from the heart flows through the placenta, the other half supplies the body (35%) and lungs (15%) of the fetus. This is supplied by the left and right heart, which function essentially *in parallel* until after the birth (see below).


Fetal circulation. The blood flows through the fetal body as follows (→ **A**): After being *arterialized in the* **placenta**, the blood passes into the fetus via the *umbilical vein* and part of it travels through the **ductus venosus** (Arantii), thereby bypassing the liver. When entering the inferior vena cava, the blood *mixes with venous blood* from the lower half of the body. Guided by special folds in the vena cava, the mixed blood passes directly from right atrium to the left atrium through an opening in the atrial septum (**foramen ovale**). From the left atrium, it then proceeds to the left ventricle. While in the right atrium, the blood mingles with venous blood from the superior vena cava (only slight mixing), which is received by the right ventricle. Only about one-third of this blood reaches the lungs (due to high flow resistance since the lungs are not yet expanded, and due to hypoxic vasoconstriction, → **C** and p. 122). The other two-thirds of the blood travels through the **ductus arteriosus** (Botalli) to the aorta (*right-to-left shunt*). Due to the low peripheral resistance (placenta), the **blood pressure** in the aorta is relatively low—only about 65 mmHg towards the end of pregnancy.

The arteries of the head and upper body are supplied with partly arterialized blood from the left ventricle (→ **A**). This is important since brain tissue is susceptible to hypoxia. The remaining blood leaves the aorta and mixes with venous blood from the ductus arteriosus. As a result, the blood supplied to the lower half of the body has a relatively low O_2 concentration (O_2 saturation = 0.3; → **A**). The majority of this blood returns via the *umbilical arteries* to the placenta, where it is oxygenated again.


Circulation during birth. The exchange of O_2, CO_2, nutrients, and waste materials through the placenta stops abruptly during birth. This leads to a rise in blood P_{CO_2}, triggering chemosensors (→ p. 132) that induce a strong breathing reflex. The resultant *inspiratory movement* causes negative pressure (suction) in the thoracic cavity, which removes the blood from the placenta and umbilical vein (*placental transfusion*) and expands the lungs. The unfolding of the lungs and the rise in alveolar P_{O_2} reduce the resistance in the pulmonary circulation, and the blood flow increases while the pressure decreases (→ **B1, 2**). Meanwhile, the resistance in the systemic circulation increases due to occlusion or clamping of the umbilical cord. This changes the direction of blood flow in the **ductus arteriosus**, resulting in a *left-to-right shunt*. The pulmonary circulation therefore receives aortic blood for a few days after birth. The right atrial filling volume decreases due to the lack of placental blood, while that of the left atrium increases due to the increased pulmonary blood flow. Due to the resultant pressure gradient from the left to right atrium and to a decrease in vasodilatory prostaglandins, the **foramen ovale** closes after birth. The ductus arteriosus and ductus venosus also close, and the systemic and pulmonary circulation now form serial circuits. The closure of the ductus arteriosus is promoted by the rise in blood P_{O2} (*a mitochondrial O_2 sensor forms H_2O_2→ K^+ channels blocked → depolarization → L-type Ca^{2+} channels open→ vasoconstriction*).

Shunts occur when the foramen ovale or ductus arteriosus remains open, placing a strain on the heart. In **patent foramen ovale** (atrial septum defect), the blood flows from left atrium → right atrium (left-to-right shunt) → right ventricle (*volume overload*) → lungs → left atrium. In **patent ductus arteriosus**, the blood flows from aorta → pulmonary artery (= left-to-right shunt) → lungs (*pressure overload*) → aorta.

A. Fetal circulation




B. Pulmonary circulation before and after birth



(After Rudolph)

C. Hypoxic vasoconstriction in fetus



(After Levine) (Measured in lamb fetus)

The body temperature of humans remains relatively constant despite changes in the environmental temperature. This **homeothermy** applies only to the **core temperature** (≈ 37 °C) of the body. The extremities and skin ("*shell*") exhibit **poikilothermy**, i.e., their temperature varies to some extent with environmental temperature. In order to maintain a constant core temperature, the body must balance the *amount of heat it produces and absorbs* with the *amount it loses*; this is **thermoregulation** (→ p. 226).

Heat production. The amount of heat produced is determined by *energy metabolism* (→ p. 230). At rest, approximately 56% of total heat production occurs in the internal organs and about 18% in the muscles and skin (→ **A2**, top). During *physical exercise*, heat production increases several-fold and the percentage of heat produced by muscular work can rise to as much as 90% (→ **A2**, bottom). To keep warm, the body may have to generate additional voluntary (limb movement) and involuntary (shivering) muscle contractions. Newborns also have tissue known as **brown fat**, which enables them to produce additional heat without shivering (→ p. 227). Cold stimulates a reflex pathway resulting in norepinephrine release (β_3-adrenergic receptors) in fatty tissues, which in turn stimulates (1) lipolysis and (2) the expression of *lipoprotein lipase (LPL)* and *thermogenin (UCP1)*. LPL increases the supply of free fatty acids (→ p. 256). Thermogenin localized in the inner mitochondrial membrane is an uncoupling protein that functions as an H^+ uniporter (→ p. 230). It short-circuits the H^+ gradient across the inner mitochondrial membrane (→ p. 17, B2), thereby uncoupling the (heat-producing) respiratory chain of ATP production.

Heat produced in the body is absorbed by the bloodstream and conveyed to the body surface. In order for this **internal flow of heat** to occur, the temperature of the body surface must be lower than that of the body interior. The *blood supply to the skin* is the chief determinant of heat transport to the skin (→ p. 226).


Heat loss occurs by the physical processes of radiation, conduction, convection, and evaporation (→ **B**).

1. Radiation (→ **B1, C**). The amount of heat lost by radiation from the skin is chiefly determined by the temperature of the radiator (fourth power of its absolute temperature). Heat net–radiates from the body surface to objects or individuals when they are cooler than the skin, and net–radiates to the body from objects (sun) that are warmer than the skin. Heat radiates from the body into the environment when no radiating object is present (night sky). Heat radiation does not require the aid of any vehicle and is hardly affected by the air temperature (air itself is a poor radiator). Therefore, the body loses heat to a cold wall (despite warm air in between) and absorbs radiation from the sun or an infrared radiator without air (space) or cold air, respectively, in between.


2. Conduction and **convection** (→ **B2, C**). These processes involve the transfer of heat from the skin to cooler air or a cooler object (e.g. sitting on rock) in contact with the body (*conduction*). The amount of heat lost by conduction to air increases greatly when the warmed air moves away from the body by natural *convection* (heated air rises) or forced convection (wind).

3. Evaporation (→ **B3, C**). The first two mechanisms alone are unable to maintain adequate temperature homeostasis at high environmental temperatures or during strenuous physical activity. Evaporation is the means by which the body copes with the additional heat. The water lost by evaporation reaches the skin surface by diffusion (*insensible perspiration*) and by neuron-activated **sweat** glands (→ **B3**, pp. 78ff. and 227 D). About 2428 kJ (580 kcal) of heat are lost for each liter of water evaporating and thereby cooling the skin. At temperatures above 36 °C or so, heat loss occurs by evaporation only (→ **C**, right). At even higher environmental temperatures, heat is absorbed by radiation and conduction/convection. The body must lose larger amounts of heat by evaporation to make up for this. The surrounding air must be relatively dry in order for heat loss by evaporation to occur. Humid air retards evaporation. When the air is extremely humid (e.g., in a tropical rain forest), the average person cannot tolerate temperatures above 33 °C, even under resting conditions.


A. Relative contribution of organs to body weight and heat production



B. Mechanisms of heat loss



C. Heat production at different environmental temperatures (unclothed, at rest)



Thermoregulation maintains the **core temperature** (→ **A**) at a constant **set point** (≈ **37 °C**) despite fluctuations in heat absorption, production, and loss (→ p. 224). The core temperature exhibits *circadian variation*. It fluctuates by about 0.6 °C and is lowest around 3 a.m., and highest around 6 p.m. (→ p. 387 C). The set point changes are controlled by an intrinsic *biological clock* (→ p. 336). Extended set-point fluctuations happen during the menstrual cycle (→ p. 301, A3) and fever.

The *control center* for body temperature and *central thermosensors* are located in the **hypothalamus** (→ p. 332). Additional thermosensors are located in the spinal cord and skin (→ p. 316). The control center compares the actual core temperature with the set-point value and initiates measures to counteract any deviations (→ **D** and p. 4f.).

When the **core temperature rises** above the set point (e.g., during exercise), the body increases the internal heat flow (→ p. 224) by *dilating the blood vessels* of the skin. Moreover, arteriovenous anastomoses open in the periphery, especially in the fingers. The blood volume transported per unit time then not only conveys more heat, but also reduces the countercurrent exchange of heat between the arteries and their accompanying veins (→ **B**). In addition, venous return in the extremities is *re-routed* from the deep, accompanying veins to the superficial veins. **Sweat secretion** also increases. The evaporation of sweat cools the skin, thereby creating the core/skin temperature gradient needed for the internal heat flow. *Central warm sensors* emit the signals that activate the sweat glands. (In this case, the thermosensors of the skin do not detect warmth because their environment is cooler than the core temperature). The efferent nerve fibers to the sweat glands are cholinergic fibers of the sympathetic nervous system (→ **D**).

Acclimatization to high environmental temperatures (e.g., in the tropics) is a slow process that often takes years. Characteristically, the sweat secretion rate rises, the salt content of the sweat decreases, and thirst (→ p. 170ff) and thus H_2O intake increase.


When the **core temperature falls** below set point, the body checks heat loss by constricting the blood vessels in the shell (→ **A**, left) and increases heat production by generating voluntary and involuntary (*shivering*) muscle activity (→ **D**). Although infants can quickly become hypothermic because of their high surface/volume ratio, their *brown fat* allows them to produce additional heat (*non-shivering thermogenesis*; → p. 224). Upon exposure to low ambient temperatures, these three mechanisms are activated by the cold receptors of the skin (→ p. 316) *before* the core temperature falls.

The range of ambient temperatures between the sweating and shivering thresholds is known as the **thermoneutral zone**. It lies between ca. 27 °C and 32 °C in the nearly unclothed test subject. The only thermoregulatory measure necessary within this range is variation of blood flow to the skin. The narrow range of this zone shows the thermoregulatory importance of **behavior**. It involves choosing the appropriate clothing, seeking shade, heating or cooling our dwellings, etc. Behavioral adaptation is the chief factor in survival at extreme ambient temperatures (→ **C**).


The thermoneutral zone is subjectively perceived as the **comfort zone**. 95% of all subjects wearing normal office attire and performing normal office activities perceive an indoor climate with the following conditions to be comfortable: ambient and radiant (wall) temperature ≈ 23 °C, wind velocity < 0.1 m/s, and relative humidity ≈ 50%. A resting, unclothed subject feels comfortable at about 28 °C and ca. 31 °C to 36 °C in water depending on the thickness of subcutaneous fat (heat isolator).

Fever. *Exogenous* (e.g., bacteria) and *endogenous pyrogens* (various interleukins and other cytokines from macrophages) can cause the set-point temperature to rise above normal. This is triggered by prostaglandin PGE_2 in the hypothalamus. In the initial phase of fever, the core temperature (although at its normal level) is too low compared to the elevated set-point. This results in shivering to raise the core temperature. As the fever decreases, i.e. the set-point returns toward the normal temperature, the core temperature is now too warm compared to the normalized set-point, resulting in vasodilatation and sweating to lower the core temperature again.


A. Temperature zones of the body




B. Arteriovenous exchange of heat



C. Environmental temperature and temperature control



D. Neural factors affecting thermoregulation



An **adequate diet** must meet the body's energy requirements and provide a minimum of carbohydrates, proteins (incl. all essential amino acids) and fats (incl. essential fatty acids). Minerals (incl. trace elements), vitamins, and sufficient quantities of water are also essential. To ensure a normal passage time, especially through the colon, the diet must also provide a sufficient amount of *roughage* (indigestible plant fibers—cellulose, lignin, etc.).

The **total energy expenditure** (**TEE**) or *total metabolic rate* consists of (1) the *basal metabolic rate* (**BMR**), (2) the *activity energy costs,* and the (3) *diet-induced thermogenesis* (DIT; → p. 230, 233 A). TEE equals BMR when measured (a) in the morning (b) 20 h after the last meal, (3) resting, reclining, (4) at normal body temp., and (5) at a comfortable ambient temp. (→ p. 226). The BMR varies according to sex, age, body size and weight. The BMR for a young adult is ca. 7300 kJ/day (≈ 1740 kcal/day; see p. 380 for units) in men, and ca. 20% lower in women. During **physical activity**, TEE increases by the following factors: 1.2-fold for sitting quietly, 3.2-fold for normal walking, and 8-fold for forestry work. Top athletes can perform as much as 1600 W (=J/s) for two hours (e.g., in a marathon) but their daily TEE is much lower. TEE also increases at various degrees of **injury** (1.6-fold for sepsis, 2.1-fold for burns). 1 °C of **fever** increases TEE 1.13-fold.

Protein, fats and carbohydrates are the three **basic energy substances** (→ **B**).

An adequate intake of **protein** is needed to maintain a proper *nitrogen balance*, i.e., balance of dietary intake and excretory output of nitrogen. The minimum requirement for protein is 0.5 g/kg BW per day (*functional minimum*). About half of dietary protein should be animal protein (meat, fish, milk and eggs) to ensure an adequate supply of *essential amino acids* such as histidine, isoleucine, leucine, lysine, methionine, phenylalanine, threonine, tryptophan and valine (children also require arginine). The content of essential amino acids in most vegetable proteins is only about 50% of animal protein.

Carbohydrates (starch, sugar, glycogen) and **fats** (animal and vegetable fats and oils) provide the largest portion of the energy requirement. They are basically interchangeable sources of energy. The energy contribution of carbohydrates can fall to about 10% (normally 60%) before metabolic disturbances occur.

Fat is not essential provided the intake of *fat-soluble vitamins* (vitamins E, D, K and A) and *essential fatty acids* (linoleic acid) is sufficient. About 25–30% of dietary energy is supplied by fat (one-third of which is supplied as essential fatty acids; → **A**), although the proportion rises according to energy requirements (e.g., about 40% during heavy physical work).


Western diets contain generally too much energy (more fats than carbohydrates!) considering the generally low level of physical activity of the Western lifestyle. Alcohol also contains superfluous energy (ca. 30 kJ/g = 7.2 kcal/g). The excessive intake of dietary energy leads to weight gain and obesity (→ p. 232).

An adequate intake of **minerals** (inorganic compounds), especially calcium (800 mg/day; → p. 292ff.), iron (10–20 mg/day; → p. 90) and iodine (0.15 mg/day; → p. 288), is essential for proper body function. Many **trace elements** (As, F, Cu, Si, V, Sn, Ni, Se, Mn, Mo, Cr, Co) are also essential. The normal diet provides sufficient quantities of them, but excessive intake has toxic effects.

Vitamins (A, B_1, B_2, B_6, B_{12}, C, D_2, D_3, E, H (biotin), K_1, K_2, folic acid, niacinamide, pantothenic acid) are compounds that play a vital role in metabolism (usually function as coenzymes). However, the body cannot produce (or sufficient quantities of) them.


A deficiency of vitamins (hypovitaminosis) can lead to specific conditions such as night blindness (vit. A), scurvy (vit. C), rickets (vit. D = calciferol; → p. 294), anemia (vit. B_{12} = cobalamin; folic acid; → p. 90), and coagulation disorders (vit. K; → p. 104). An excessive intake of certain vitamins like vitamin A and D, on the other hand, can be toxic *(hypervitaminosis)*.

A. Energy content of foodstuffs and energy requirement



* Recommended values for an adult male weighing 70 kg, during light physical activity

B. Chemical structure of fats, proteins and carbohydrates



The chemical energy of foodstuffs is first converted into energy-rich substances such as **creatine phosphate** and **adenosine triphosphate (ATP)**. Energy, work and amount of heat are expressed in joules (J) or calories (cal) (→ p. 380). The energy produced by hydrolysis of ATP (→ p. 41) is then used to fuel muscle activity, to synthesize many substances, and to create concentration gradients (e.g., Na^+ or Ca^{2+} gradients; → p. 26ff.). During all these energy conversion processes, part of the energy is always converted to *heat* (→ p. 38ff.).

In **oxidative (aerobic) metabolism** (→ p. 39 C), carbohydrates and fat combine with O_2 to yield CO_2, water, high-energy compounds (ATP etc.) and heat. When a foodstuff is completely oxidized, its biologically useable energy content is therefore equivalent to its physical **caloric value (CV)**.

The **bomb calorimeter** (→ **A**), a device consisting of an insulated combustion chamber in a tank of water, is used to *measure the CV* of foodstuffs. A known quantity of a foodstuff is placed in the combustion chamber of the device and incinerated in pure O_2. The surrounding water heats up as it absorbs the heat of combustion. The degree of warming is equal to the caloric value of the foodstuff.

Fats and carbohydrates are completely oxidized to CO_2 and H_2O in the body. Thus, their **physiological fuel value (PFV)** is identical to their CV. The mean PFV is 38.9 kJ/g (= 9.3 kcal/g) for fats and 17.2 kJ/g (= 4.1 kcal/g) for digestible carbohydrates (→ p. 229 A). In contrast, **proteins** are not completely broken down to CO_2 and water in the human body but yield urea, which provides additional energy when it is oxidized in the bomb calorimeter. The CV of proteins (ca. 23 kJ/g) is therefore greater than their PFV, which is a mean of about 17.2 kJ/g or 4.1 kcal/g (→ p. 229 A).

At rest, most of the energy supplied by the diet is converted to **heat**, since hardly any external mechanical work is being performed. The heat produced is equivalent to the internal energy turnover (e.g., the work performed by the heart and respiratory muscles or expended for active transport or synthesis of substances).

In **direct calorimetry** (→ **B**), the amount of heat produced is measured directly. The test subject, usually an experimental animal, is placed in a small chamber immersed in a known volume of ice. The amount of heat produced is equivalent to the amount of heat absorbed by the surrounding water or ice. This is respectively calculated as the rise in water temperature or the amount of ice that melts.

In **indirect calorimetry**, the amount of heat produced is determined indirectly by measuring the amount of O_2 consumed ($\dot{V}_{O_2}$; → p. 120). This method is used in humans. To determine the total metabolic rate (or TEE; → p. 228) from $\dot{V}_{O_2}$, the **caloric equivalent (CE)** of a foodstuff oxidized in the subject's metabolism during the measurement must be known. The CE is calculated from the PFV and the amount of O_2 needed to oxidize the food. The PFV of *glucose* is 15.7 kJ/g and 6 mol of O_2 (6×22.4 L) are required to oxidize 1 mol (= 180 g) of glucose (→ **C**). The oxidation of 180 g of glucose therefore generates 2827 kJ of heat and consumes 134.4 L of O_2 resulting in a CE of 21 kJ/L. This value represents the CE for glucose under standard conditions (0 °C; → **C**). The mean CE of the basic nutrients at 37 °C is 18.8 kJ/L O_2 (carbohydrates), 17.6 kJ/L O_2 (fats) and 16.8 kJ/L O_2 (proteins).

The oxidized nutrients must be known in order to calculate the metabolic rate from the CE. The **respiratory quotient (RQ)** is a rough measure of the nutrients oxidized. $RQ = \dot{V}_{CO_2}/\dot{V}_{O_2}$ (→ p. 120). For pure carbohydrates oxidized, RQ = 1.0. This can be illustrated for *glucose* as follows:

$$C_6H_{12}O_6 + 6\ O_2 \rightleftharpoons 6\ CO_2 + 6\ H_2O \qquad [10.1]$$


The oxidation of the fat *tripalmitin* yields:

$$2\ C_{51}H_{98}O_6 + 145\ O_2 \rightleftharpoons 102\ CO_2 + 98\ H_2O \qquad [10.2]$$


The RQ of tripalmitin is therefore 102/145 = 0.7. Since the protein fraction of the diet stays relatively constant, each RQ between 1 and 0.7 can be assigned a CE (→ **D**). Using the known CE, the TEE can be calculated as $CE \cdot \dot{V}_{O_2}$.

Food increases the TEE (**diet–induced thermogenesis, DIT**) because energy must be consumed to absorb and store the nutrients. The DIT of protein is higher than that of other substances, e.g., glucose.


A. Bomb calorimeter




B. Direct calorimetry (Lavoisier)



C. Oxidation of glucose: fuel value, CE and RQ



D. RQ and caloric equivalent relative to nutrient composition



Fat depots are by far the body's largest **energy reserve**. Accurate long-term homeostasis of energy absorption and consumption is necessary to keep the size of the fat depots constant, i.e., to maintain *lipostasis*. Since a person's body weight (BW) mainly varies with the weight of the fat depots, it is obvious that energy homeostasis is synonymous with the **regulation of body weight** (→ **A**).

The **body mass index (BMI)** is commonly used to determine whether an individual is underweight, overweight or in the normal weight range. BMI is calculated from body weight (kg) and height (m) as follows:

$$\text{BMI} = \text{bodyweight [kg]}/(\text{height [m]})^2 \quad [10.3]$$

The normal BMI range is 19–24 in women and 20–25 in men. The "normal" BMI range is defined as the values at which the mean life expectancy is highest. An abnormally high body mass index (BMI > 24 or 25 = overweight; BMI > 30 = obesity) reduces the life expectancy since this is often associated with diabetes mellitus (type II), hypertension and cardiac disease.

The hypothalamus with its arcuate nucleus and its subordinated centers for "satiety" (paraventricular nucleus) and "hunger" (lateral hypothalamus) is the regulatory center (→ p. 4) for body weight (→ **B**). **Leptin**, a 16-kDa proteohormone produced by fat cells, communicates *afferent messages* concerning the size of fat depots to the hypothalamus. The plasma leptin concentration rises as fat cell mass increases. The availability of glucose is communicated to the hypothalamus via the concentration of insulin (→ p. 284).

Efferent commands from the hypothalamus cause (a) reduced nutrient absorption and increased energy consumption when plasma leptin are high ("fat reserve high!"), and (b) the reverse when plasma leptin levels are low ("fat reserve low!") (→ **B**, bottom).

Effects of Leptin. Leptin binds with *type b leptin receptors* (LRb = **Ob-Rb**) of the hypothalamus (mainly in the arcuate nucleus, but also the paraventricular nucleus and other locations) which leads to weight loss.

The effects of leptin are chiefly mediated by two neurotransmitters located in the hypothalamus: α-*MSH* and *NPY* (→ **B**).


Leptin stimulates the release of CART (cocaine- and amphetamine-regulated transcript, see below) as well as **α-MSH** (α-melanocyte-stimulating hormone), one of the melanocortins (MC) synthesized from POMC (→ p. 282). α-MSH, via MC4 receptors in various areas of the hypothalamus and the dorsal nucleus of the vagus nerve, inhibits the absorption of nutrients and increases sympathetic nervous activity and energy consumption.

An involuntary increase in ordinary skeletal muscle activity and tone appears to contribute to the latter. In addition, there are **uncoupling proteins** (type UCP2 and UCP3) in skeletal muscle and white fat that make the membranes of the mitochondria more permeable to H^+, thereby uncoupling the respiratory chain (→ p. 39 C). As a result, chemical energy is converted into more heat and less ATP. The action of these UCPs, the expression of which is directly or indirectly stimulated by α-MSH, is therefore similar to that of thermogenin (UCP1; → p. 224).

◆ **NPY.** Leptin and α-MSH (via MC3-R), as well as insulin, inhibits the release of NPY (neuropeptide Y) in the arcuate nucleus, a neuropeptide that stimulates hunger and appetite via a series of neurons, increases the parasympathetic activity and reduces energy consumption.

Besides the long-term regulation of fat deposits, there are other neurotransmitters and neuropeptides whose release is linked to leptin, some of which are released in the gastrointestinal tract. Some like ghrelin, *orexin A/B* and *norepinephrine* (α_2-adrenoceptors) are **orexigenic**, i.e. they stimulate the appetite, while others like CCK, CRH, CART, insulin, and serotonin are **anorexigenic**. Peptides like PYY, CCK, GLP-1 (glucagon-like peptide amides), somatostatin, glucagon, and GRP (gastrin-releasing peptide) signal *satiety*, i.e., that one has had enough to eat. Together with stretch receptors of the stomach wall, these **satiety peptides** help to limit the amount of food consumed with each meal.

Since **NPY** increases the secretion of gonadotropin-releasing hormone (**GnRH**), extreme weight loss results in amenorrhea (→ **B**). Certain genetic defects which affect leptin production, LRb or, most commonly, MC4-R, result in **obesity** early in childhood. The body weight can exceed 100 kg by age ten. Leptin deficiency is treated with recombinant leptin. In *Prader–Willi syndrome* the obesity is a consequence of elevated ghrelin production in the gastrointestinal tract.


A. Energy homeostasis
Energy reserve
(body weight)
Decrease
Increase
Physical activity
Energy for absorption and nutrient storage
Basal metabolic rate
Absorption of:
Proteins
Fats
Carbohydrates
B. Regulation of body weight by leptin, α-MSH and NPY
Weight loss
Food intake
Gastro-intestinal tract
Ghrelin
Leptin
Glucose
Pancreas
Insulin
Weight gain
Leptin
Cortex
Limbic system
Brain stem
Fat reserve
Fat reserve
Arcuate nucleus
α-MSH CART
NPY AgRP
NPY AgRP
α-MSH CART
Corticoliberin
Somatoliberin
Gonadoliberin
Food intake
Energy consumption
Parasympathetic activity
Food intake
Energy consumption
Sympathetic activity

Food covering the body's energy and nutrient requirements (→ p. 230ff.) must be swallowed, processed and broken down (**digestion**) before it can be **absorbed** from the intestines. The three-layered GI **musculature** ensures that the GI contents are properly mixed and transported. The **passage time** through the different GI segments varies and is largely dependent on the composition of the food (see **A** for mean passage times).

Solid food is chewed and mixed with **saliva**, which lubricates it and contains immunocompetent substances (see below) and enzymes. The **esophagus** rapidly transports the food bolus to the stomach. The lower esophageal sphincter opens only briefly to allow the food to pass. The **proximal stomach** mainly serves as a food reservoir. Its tone determines the rate at which food passes to the **distal stomach**, where it is further processed (chyme formation) and its proteins are partly broken down. The distal stomach (including the pylorus) is also responsible for portioning chyme delivery to the small intestine. The stomach also secretes *intrinsic factor* (→ p. 90).

In the **small intestine**, enzymes from the **pancreas** and small intestinal mucosa break down the nutrients into absorbable components. HCO_3^- in pancreatic juices neutralizes the acidic chyme. Bile salts in **bile** are essential for fat digestion. The products of digestion (monosaccharides, amino acids, dipeptides, monoacylglyerols and free fatty acids) as well as water and vitamins are absorbed in the small intestine.


Waste products (e.g. bilirubin) to be excreted reach the feces via bile secreted by the **liver**. The liver has various other metabolic functions. It serves, for example, as an obligatory relay station for metabolism and distribution of substances absorbed from the intestine (via the portal vein, see below), synthesizes plasma proteins (incl. albumin, globulins, clotting factors, apolipoproteins etc.) and detoxifies foreign substances (*biotransformation*) and metabolic products (e.g., ammonia) before they are excreted.

The **large intestine** is the last stop for water and ion absorption. It is colonized by *bacteria* and contains storage areas for feces (**cecum, rectum**).

Immune defense. The large internal surface area of the GI tract (roughly 100 m^2) requires a very effective immune defense system. Saliva contains *mucins, immunoglobulin A (IgA)* and *lysozyme* that prevent the penetration of pathogens. *Gastric juice* has a bactericidal effect. *Peyer's patches* supply the GI tract with immunocompetent lymph tissue. *M cells* (special membranous cells) in the mucosal epithelium allow antigens to enter Peyer's patches. Together with *macrophages*, the Peyer's patches can elicit immune responses by secreting **IgA** (→ p. 98). IgA is transported to the intestinal lumen by transcytosis (→ p. 30). In the epithelium, IgA binds to a secretory component, thereby protecting it from digestive enzymes. Mucosal epithelium also contains *intraepithelial lymphocytes* (**IEL**) that function like T killer cells (→ p. 98). Transmitter substances permit reciprocal communication between IEL and neighboring enterocytes. Macrophages of the hepatic sinusoids (*Kupffer's cells*) are additional bastions of immune defense. The physiological colonies of **intestinal flora** in the large intestine prevent the spread of pathogens. IgA from breast milk protects the GI mucosa of neonates.

Blood flow to the stomach, gut, liver, pancreas and spleen (roughly 30% of cardiac output) is supplied by the three main branches of the abdominal aorta. The intestinal circulation is regulated by local reflexes, the autonomic nervous system, and hormones. Moreover, it is *autoregulatory*, i.e., largely independent of systemic blood pressure fluctuations. Blood flow to the intestines rises sharply after meals (acetylcholine, vasoactive intestinal peptide VIP, etc. function as vasodilatory transmitters) and falls during physical activity (transmitters: norepinephrine, etc.). The venous blood carries substances absorbed from the intestinal tract and enters the liver via the **portal vein**. Some components of absorbed fat are absorbed by the *intestinal lymph*, which transports them to the greater circulation while bypassing the liver.

A. Function of gastrointestinal organs



(After Kahle, Leonhardt & Platzer)

Endocrine and paracrine hormones and neurotransmitters control GI *motility, secretion, perfusion and growth*. Reflexes proceed within the mesenteric and submucosal plexus (*enteric nervous system, ENS*), and external innervation modulates ENS activity.

Local reflexes are triggered by stretch sensors in the walls of the esophagus, stomach and gut or by chemosensors in the mucosal epithelium and trigger the contraction or relaxation of neighboring smooth muscle fibers. *Peristaltic reflexes* extend further towards the oral (ca. 2 mm) and anal regions (20–30 mm). They are mediated in part by interneurons and help to propel the contents of the lumen through the GI tract (*peristalsis*).

External innervation of the GI tract (cf. p. 78ff.) comes from the *parasympathetic nervous system* (from lower esophagus to ascending colon) and *sympathetic nervous system*. Innervation is also provided by *visceral afferent fibers* (in sympathetic or parasympathetic nerves) through which the afferent impulses for *supraregional reflexes* flow.

ENS function is largely independent of external innervation, but **external innervation** has some advantages (a) rapid transfer of signals between relatively distant parts of the GI tract via the abdominal ganglia (short visceral afferents) or CNS (long visceral afferents); (b) GI tract function can be ranked subordinate to overall body function (c) GI tract activity can be processed by the brain so the body can become aware of them (e.g., stomach ache).

Neurotransmitters. *Norepinephrine* (**NE**) is released by the adrenergic postganglionic neurons, and *acetylcholine* (**ACh**) is released by pre- and postganglionic (enteric) fibers (→ p. 78ff.). **VIP** (vasoactive intestinal peptide) mediates the relaxation of circular and vascular muscles of the GI tract. **Met- and leu-enkephalin** intensify contraction of the pyloric, ileocecal and lower esophageal sphincters by binding to opioid receptors. **GRP** (gastrin-releasing peptide) mediates the release of gastrin. **CGRP** (calcitonin gene-related peptide) stimulates the release of somatostatin (**SIH**).

All **endocrine hormones** effective in the GI tract are *peptides* produced in endocrine cells of the mucosa. (a) *Gastrin* and *cholecystokinin* (**CCK**) and (b) *secretin* and **GIP** are structurally similar; so are glucagon (→ p. 284ff.) and **VIP**. High concentrations of hormones from the same family therefore have very similar effects.

Gastrin occurs in short (G17 with 17 amino acids, AA) and long forms (G34 with 34 AA). G17 comprises 90% of all antral gastrin. Gastrin is secreted in the antrum and duodenum. Its release (→ **A1**) via *gastrin-releasing peptide* (**GRP**) is subject to neuronal control; gastrin is also released in response to stomach wall stretching and protein fragments in the stomach. Its secretion is inhibited when the pH of the gastric/duodenal lumen falls below 3.5 (→ **A1**). The main effects of gastrin are acid secretion and gastric mucosal growth (→ **A2**).


Cholecystokinin, CCK (33 AA) is produced throughout small intestinal mucosa. Long-chain fatty acids, AA and oligopeptides in the lumen stimulate the release of CCK (→ **A1**). It causes the gallbladder to contract and inhibits emptying of the stomach. In the pancreas, it stimulates growth, production of enzymes and secretion of HCO_3^- (via secretin, see below) (→ **A2**).

Secretin (27 AA) is mainly produced in the duodenum. Its release is stimulated by acidic chyme (→ **A1**). Secretin inhibits acid secretion and gastric mucosal growth and stimulates HCO_3^- secretion (potentiated by CCK), pancreatic growth and hepatic bile flow (→ **A2**).

GIP (glucose-dependent insulinotropic peptide, 42 AA; formerly called gastric inhibitory polypeptide = enterogastrone) is produced in the duodenum and jejunum and released via protein, fat and carbohydrate fragments (e.g., glucose) (→ **A1**). GIP inhibits acid secretion (→ **A2**) and stimulates insulin release (this is why oral glucose releases more insulin than intravenous glucose).

Motilin (22 AA) is released by neurons in the small intestine and regulates interdigestive motility (→ **A1, 2**).

Paracrine transmitters. Histamine, somatostatin and prostaglandin are the main paracrine transmitters in the GI tract.


A. Gastrointestinal hormones
Stretch
Peptides, amino acids
H+
Neuronal
Glucose
Fatty acids
inhibits
GRP
ACh
Gastrin
Secretin
Motilin
GIP
CCK
Antrum
Duodenum
Jejunum
Ileum
1 Stimulus for release and site of secretion
Stimulates
Inhibits
Acid secretion
Pepsinogen secretion
Motility (digestive)
Motility (interdigestive)
Emptying
Mucosal growth
Stomach
HCO3- secretion
Enzyme secretion
Growth
Insulin secretion
Pancreas
Pancreas (B cells)
Bile flow
HCO3- secretion
Bile ducts
Gallbladder emptying
Gallbladder
Mucosal growth
Motility (interdigestive)
Gut
Satiety
Brain
2 Main effects of gastrointestinal hormones
(Partly after L. R. Johnson)

The **functions** of saliva are reflected by its **constituents.** *Mucins* serve to lubricate the food, making it easier to swallow, and to keep the mouth moist to facilitate masticatory and speech-related movement. Saliva *dissolves* compounds in food, which is a prerequisite for taste buds stimulation (→ p. 344) and for dental and oral hygiene. Saliva has a *low NaCl* concentration and is *hypotonic*, making it suitable for rinsing of the taste receptors (NaCl) while eating. Infants need saliva to seal the lips when suckling. Saliva also contains α-amylase, which starts the digestion of starches in the mouth, while *immunoglobulin A* and *lysozyme* are part of the immune defense system (→ p. 94ff.). The high HCO_3^- concentration in saliva results in a pH of around 7, which is optimal for α-amylase-catalyzed digestion. Swallowed saliva is also important for buffering the acidic gastric juices refluxed into the esophagus (→ p. 240). The secretion of profuse amounts of saliva before vomiting also prevents gastric acid from damaging the enamel on the teeth. Saliva secretion is very dependent on the body water content. A low content results in decreased saliva secretion—the mouth and throat become dry, thereby evoking the sensation of *thirst*. This is an important mechanism for maintaining the fluid balance (→ pp. 170 and 186).

Secretion rate. The rate of saliva secretion varies from 0.1 to 4 mL/min (10–250 μL/min per gram gland tissue), depending on the degree of stimulation (→ **B**). This adds up to about 0.5 to 1.5 L per day. At 0.5 mL/min, 95% of this rate is secreted by the *parotid gland* (serous saliva) and *submandibular gland* (mucin-rich saliva). The rest comes from the sublingual glands and glands in the buccal mucosa.


Saliva secretion occurs in *two steps*: The *acini* (*end pieces*) produce **primary saliva** (→ **A, C**) which has an electrolyte composition similar to that of plasma (→ **B**). Primary saliva secretion in the acinar cells is the result of *transcellular Cl^- transport*: Cl^- is actively taken up into the cells (secondary active transport) from the blood by means of a Na^+-K^+-$2Cl^-$ cotransport carrier and is released into the lumen (as with HCO_3^-) via anion channels, resulting in a lumen-negative transepithelial potential (L**N**TP) that drives Na^+ paracellularly into the lumen. Water also follows passively (osmotic effect). Primary saliva is modified in **excretory ducts**, yielding **secondary saliva**. As the saliva passes through the excretory ducts, Na^+ and Cl^- are reabsorbed and K^+ and (carbonic anhydrase-dependent) HCO_3^- is secreted into the lumen. The saliva becomes *hypotonic* (far below 100 mOsm/kg H_2O; → **B**) because Na^+ and Cl^- reabsorption is greater than K^+ and HCO_3^- secretion and the ducts are relatively impermeable to water (→ **B**). If the secretion rate rises to values much higher than 100 μL/(min · g), these processes lag behind and the composition of secondary saliva becomes similar to that of primary saliva (→ **B**).

Salivant stimuli. *Reflex stimulation* of saliva secretion occurs in the larger salivary glands (→ **D**). Salivant stimuli include the smell and taste of food, tactile stimulation of the buccal mucosa, mastication and nausea. *Conditioned reflexes* also play a role. For instance, the routine clattering of dishes when preparing a meal can later elicit a salivant response. Sleep and dehydration inhibit saliva secretion. Saliva secretion is stimulated via the sympathetic and parasympathetic nervous systems (→ **C2**):


◆ **Norepinephrine** triggers the secretion of highly viscous saliva with a high concentration of mucin via β_2 adrenoreceptors and cAMP. *VIP* also increases the cAMP concentration of acinar cells.

◆ **Acetylcholine**: (a) With the aid of M_1 cholinoceptors and IP_3 (→ pp. 82 and 276), acetylcholine mediates an increase in the cytosolic Ca^{2+} concentration of acinar cells. This, in turn, increases the conductivity of luminal anion channels, resulting in the production of watery saliva and increased exocytosis of salivary enzymes. (b) With the aid of M_3 cholinergic receptors, ACh mediates the contraction of *myoepithelial cells* around the acini, leading to emptying of the acini. (c) ACh enhances the production of kallikreins, which cleave *bradykinin* from plasma kininogen. Bradykinin and **VIP** (→ p. 236) dilate the vessels of the salivary glands. This is necessary because maximum saliva secretion far exceeds resting blood flow.


A. Saliva secretion




B. Electrolytes in saliva



C. (1) Mechanism and (2) control of saliva secretion in acinar cells



D. Stimulation of saliva secretion



The upper third of the esophageal wall consists of striated muscle, the rest contains smooth muscle. During the process of swallowing, or deglutition, the tongue pushes a bolus of food into the throat (→ **A1**). The nasopharynx is reflexively blocked, (→ **A2**), respiration is inhibited, the vocal chords close and the epiglottis seals off the trachea (→ **A3**) while the *upper esophageal sphincter* opens (→ **A4**). A peristaltic wave forces the bolus into the stomach (→ **A5, B1,2**). If the bolus gets stuck, stretching of the affected area triggers a *secondary peristaltic wave.*

The **lower esophageal sphincter** opens at the start of deglutition due to a *vagovagal reflex* (*receptive relaxation*) mediated by VIP- and NO-releasing neurons (→ **B3**). Otherwise, the lower sphincter remains closed to prevent the reflux of aggressive gastric juices containing pepsin and HCl.

Esophageal motility is usually checked by measuring pressure in the lumen, e.g., during a peristaltic wave (→ **B1–2**). The resting pressure within the lower sphincter is normally 20–25 mmHg. During receptive relaxation, esophageal pressure drops to match the low pressure in the proximal stomach (→ **B3**), indicating opening of the sphincter.

In *achalasia*, receptive relaxation fails to occur and food collects in the esophagus.

Pressure in the lower esophageal sphincter is *decreased* by VIP, CCK, NO, GIP, secretin and progesterone (→ p. 236) and *increased* by acetylcholine, gastrin and motilin. Increased abdominal pressure (external pressure) also increases sphincter pressure because part of the lower esophageal sphincter is located in the abdominal cavity.

Gastroesophageal reflux. The sporadic reflux of gastric juices into the esophagus occurs fairly often. Reflux can occur while swallowing (lower esophageal sphincter opens for a couple of seconds), due to unanticipated pressure on a full stomach or to *transient opening of the sphincter* (lasts up to 30 seconds and is part of the *eructation reflex*). Gastric reflux greatly reduces the pH in the distal esophagus.

Protective mechanisms to prevent damage to the esophageal mucosa after gastroesophageal reflux include 1. **Volume clearance**, i.e., the rapid return of refluxed fluid to the stomach via the esophageal peristaltic reflex. A refluxed volume of 15 mL, for example, remains in the esophagus for only 5 to 10 s (only a small amount remains). 2. **pH clearance.** The pH of the residual gastric juice left after volume clearance is still low, but is gradually increased during each act of swallowing. In other words, the saliva that is swallowed buffers the residual gastric juice.

Vomiting


Vomiting mainly serves as a *protective reflex* but is also an important clinical symptom of conditions such as intracranial bleeding and tumors. The act of vomiting is heralded by **nausea**, increased salivation and retching (→ **C**). The **vomiting center** is located in the medulla oblongata within the reticular formation. It is mainly controlled by chemosensors of the *area postrema*, which is located on the floor of the fourth ventricle; this is called the *chemosensory trigger zone* (CTZ). The blood-brain barrier is less tight in the area postrema.

The **CTZ** is **activated** by nicotine, other toxins, and dopamine agonists like apomorphine (used as an emetic). Cells of the CTZ have receptors for neurotransmitters responsible for their neuronal control. The vomiting center can also be activated independent of the CTZ, for example, due to abnormal stimulation of the organ of balance (*kinesia, motion sickness*), overextension of the stomach or intestines, delayed gastric emptying and inflammation of the abdominal organs. Nausea and vomiting often occur during the first trimester of pregnancy (*morning sickness*) and can exacerbate to *hyperemesis gravidarum* leading to vomiting-related disorders (see below).

During the **act of vomiting**, the diaphragm remains in the inspiratory position and the abdominal muscles quickly contract exerting a high pressure on the stomach. Simultaneous contraction of the duodenum blocks the way to the gut; the lower esophageal sphincter then relaxes, resulting in ejection of the stomach contents via the esophagus.


The sequelae of **chronic vomiting** are attributable to reduced food intake (*malnutrition*) and the related loss of gastric juices, swallowed saliva, fluids and intestinal secretions. In addition to *hypovolemia*, non-respiratory *alkalosis* due to the loss of gastric acid (10–100 mmol H^+/L gastric juice) also develops. This is accompanied by *hypokalemia* due to the loss of K^+ in the vomitus (nutrients, saliva, gastric juices) and urine (hypovolemia-related *hyperaldosteronism*; → p. 182 ff.).

A. Deglutition




(After Rushmer & Hendron)

B. Esophageal motility



C. Vomiting



Structure. The *cardia* connects the esophagus to the upper stomach (*fundus*), which merges with the body (*corpus*) followed by the *antrum* of the stomach. The lower outlet of the stomach (*pylorus*) merges with the duodenum (→ **A**). Stomach **size** is dependent on the degree of gastric filling, but this distension is mainly limited to the proximal stomach (→ **A, B**). The stomach **wall** has an outer layer of longitudinal muscle fibers (only at curvatures; regulates stomach length), a layer of powerful circular muscle fibers, and an inner layer of oblique muscle fibers. The mucosa of the **tubular glands** of the fundus and corpus contain *chief cells* (**CC**) and *parietal cells* (**PC**) (→ **A**) that produce the constituents of gastric juice (→ p. 244). The gastric mucosa also contains *endocrine cells* (that produce gastrin in the antrum, etc.) and *mucous neck cells* (**MNC**).


Functional anatomy. The stomach can be divided into a proximal and a distal segment (→ **A**). A vagovagal reflex triggered by swallowing a bolus of food causes the lower esophageal sphincter to open (→ p. 240) and the **proximal stomach** to dilate for a short period (*receptive relaxation*). This continues when the food has entered the stomach (vagovagal *accommodation reflex*). As a result, the internal pressure hardly rises in spite of the increased filling. Tonic contraction of the proximal stomach, which mainly serves as a *reservoir*, slowly propel the gastric contents to the **distal stomach**. Near its upper border (middle third of the corpus) is a *pacemaker zone* (see below) from which peristaltic waves of contraction arise due mainly to local stimulation of the stomach wall (in response to reflex stimulation and gastrin; → **D1**). The peristaltic waves are strongest in the antrum and spread to the pylorus. The chyme is thereby driven towards the pylorus (→ **C5, 6, 1**), then compressed (→ **C2, 3**) and propelled back again after the pylorus closes (→ **C3, 4**). Thereby, the food is *processed*, i.e., *ground*, mixed with gastric juices and digested, and fat is *emulsified*.

The distal stomach contains **pacemaker cells** (*interstitial Cajal cells*), the membrane potential of which oscillates roughly every 20 s, producing characteristic *slow waves* (→ p. 246). The velocity (0.5–4 cm/s) and amplitude (0.5–4 mV) of the waves increases as they spread to the pylorus. Whether and how often contraction follows such an excitatory wave depends on the sum of all neuronal and hormonal influences. Gastrin increases the response frequency and the pacemaker rate. Other hormones like GIP inhibit this motility directly, whereas somatostatin (SIH) does so indirectly by inhibiting the release of GRP (→ **D1** and p. 236).


Gastric emptying. Solid food remains in the stomach until it has been broken down into small particles (diameter of < 1 mm) and suspended in chyme. The chyme then passes to the duodenum. The time required for 50% of the ingested volume to leave the stomach varies, e.g., 10—20 min for water and 1–4 hours for solids (carbohydrates < proteins < fats). Emptying is mainly dependent on the *tone of the proximal stomach* and *pylorus*. *Motilin stimulates* emptying of the stomach (tone of proximal stomach rises, pylorus dilates), whereas decreases in the pH or osmolality of chyme or increases in the amount of long-chain free fatty acids or (aromatic) amino acids *inhibit* gastric emptying. Chemosensitive enterocytes and brush cells of the small intestinal mucosa, enterogastric reflexes and certain hormones (CCK, GIP, secretin and gastrin; → p. 236) mediate these regulatory activities (→ **D2**). The **pylorus** is usually slightly open during the process (free flow of "finished" chyme). It contracts only 1) at the end of "antral systole" (see above) in order to retain solid food and 2) when the duodenum contracts in order to prevent the reflux of harmful bile salts. If such reflex does occur, refluxed free amino acids not normally present in the stomach elicit reflex closure of the pylorus (→ **D2**).

Indigestible substances (bone, fiber, foreign bodies) do not leave the stomach during the digestive phase. Special contraction waves called *migrating motor complexes* (**MMC**) pass through the stomach and small intestine roughly every 1.5 hours during the ensuing **interdigestive phase**, as determined by an intrinsic "biological clock." These peristaltic waves transport indigestible substances from the stomach and bacteria from the small intestine to the large intestine. This "clearing phase" is controlled by *motilin*.


A. Anatomy of the stomach




B. Gastric filling



C. Motility cycle of distal stomach



D. Factors that influence gastric motility



The *tubular glands* of the gastric fundus and corpus secrete 3–4 L of gastric juice each day. *Pepsinogens* and *lipases* are released by chief cells and *HCl* and *intrinsic factor* (→ p. 262) by parietal cells. *Mucins* and HCO_3^- are released by mucous neck cells and other mucous cells on the surface of the gastric mucosa.

Pepsins function as endopeptidases in protein digestion. They are split from pepsinogens exocytosed from chief cells in the glandular and gastric lumen at a pH of < 6. Acetylcholine (ACh), released locally in response to H^+ (and thus indirectly also to gastrin) is the chief activator of this reaction.

Gastric acid. The pH of the gastric juice drops to ca. 0.8 during peak HCl secretion. Swallowed food buffers it to a pH of 1.8–4, which is optimal for most pepsins and gastric lipases. The low pH contributes to the *denaturation* of dietary proteins and has a *bactericidal effect*.

HCl secretion (→ **A**). The *H^+-K^+-ATPase* in the luminal membrane of parietal cells drives H^+ ions into the glandular lumen in exchange for K^+ (primary active transport, → **A1** and p. 26), thereby raising the H^+ conc. in the lumen by a factor of ca. 10^7. K^+ taken up in the process circulates back to the lumen via *luminal K^+ channels*. For every H^+ ion secreted, one HCO_3^- ion leaves the blood side of the cell and is exchanged for a Cl^- ion via an *anion antiporter* (→ **A2**). (The HCO_3^- ions are obtained from CO_2 + OH^-, a reaction catalyzed by carbonic anhydrase, CA). This results in the intracellular accumulation of Cl^- ions, which diffuse out of the cell to the lumen via *Cl^- channels* (→ **A3**). Thus, one Cl^- ion reaches the lumen for each H^+ ion secreted.

The **activation of parietal cells** (see below) leads to the opening of *canaliculi*, which extend deep into the cell from the lumen of the gland (→ **B**). The canaliculi are equipped with a brush border that greatly increases the luminal surface area which is densely packed with membrane-bound H^+-K^+-ATPase molecules. This permits to increase the secretion of H^+ ions from 2 mmol/hour at rest to over 20 mmol/hour during digestion.


Gastric acid secretion is **stimulated** in phases by neural, local gastric and intestinal factors (→ **B**). Food intake leads to reflex secretion of gastric juices, but deficient levels of glucose in the brain can also trigger the reflex. The optic, gustatory and olfactory nerves are the afferents for this partly *conditioned reflex* (→ p. 238), and efferent impulses flow via the *vagus nerve*. *ACh* directly activates parietal cells in the fundus (M_3 cholinoceptors → **B2**). *GRP* (gastrin-releasing peptide) released by neurons stimulates *gastrin* secretion from G cells in the antrum (→ **B3**). Gastrin released into the systemic circulation in turn activates the parietal cells via CCK_B receptors (= gastrin receptors). The glands in the fundus contain H (histamine) cells or ECL cells (enterochromaffin-like cells), which are activated by gastrin (CCK_B receptors) as well as by ACh and β_3 adrenergic substances (→ **B2**). The cells release *histamine*, which has a paracrine effect on neighboring parietal cells (H_2 receptor). Local gastric and intestinal factors also influence gastric acid secretion because chyme in the antrum and duodenum stimulates the secretion of gastrin (→ **B1** and p. 237 A).

Factors that inhibit gastric juice secretion: (a) A pH of < 3.0 in the antral lumen inhibits **G cells** (negative feedback, → **B1, 3**) and activates antral **D cells**, which secrete SIH (→ p. 236), which in turn has a paracrine effect. SIH inhibits **H cells** in the fundus as well as G cells in the antrum (→ **B2, 3**). CGRP released by neurons (→ p. 236) activates D cells in the antrum and fundus, (→ **B2, 3**). (c) Secretin and GIP released from the small intestine have a retrograde effect on gastric juice secretion (→ **B1**). This adjusts the composition of chyme from the stomach to the needs of the small intestine.


Protection of the gastric mucosa from destructive gastric juices is chiefly provided by (a) a *layer of mucus* and (b) *HCO_3^- secretion* by the underlying mucous cells of the gastric mucosa. HCO_3^- diffuses through the layer of mucus and buffers the acid that diffuses into it from the lumen. *Prostaglandins* PGE_2 and PGI_2 promote the secretion of HCO_3^-.

Anti-inflammatory drugs that inhibit cyclooxygenase 1 and thus prostaglandin production (→ p. 271) impair this mucosal protection and can result in ulcer development.

A. HCl secretion by parietal cells



B. Regulation of gastric acid secretion



The main function of the small intestine (SI) is to finish digesting the food and to absorb the accumulated breakdown products as well as water, electrolytes and vitamins.

Structure. The SI of live human subjects is about 2 m in length. It arises from the pylorus as the *duodenum* and continues as the *jejunum*, and ends as the *ileum*, which merges into the large intestine. From outside inward, the SI consists of an outer serous coat (*tunica serosa*, → **A1**), a layer of *longitudinal muscle fibers* (→ **A2**), the *myenteric plexus* (Auerbach's plexus, → **A3**), a layer of circular muscle fibers (→ **A4**), the *submucous plexus* (Meissner's plexus, → **A5**) and a *mucous layer* (tunica mucosa, → **A6**), which is covered by epithelial cells (→ **A13–15**). The SI is supplied with blood vessels (→ **A8**), lymph vessels (→ **A 9**), and nerves (→ **A10**) via the *mesentery* (→ **A7**). The surface area of the epithelial-luminal interface is roughly 300–1600 times larger (> 100 m^2) than that of a smooth cylindrical pipe because of the *Kerckring's folds* (→ **A11**), the *intestinal villi* (→ **A12**), and the *enterocytic microvilli*, or the *brush border* (→ **A13**).

Ultrastructure and function. *Goblet cells* (→ **A15**) are interspersed between the resorbing *enterocytes* (→ **A14**). The mucus secreted by goblet cells acts as a protective coat and lubricant. *Intestinal glands* (crypts of Lieberkühn, → **A16**) located at the bases of the villi contain (a) undifferentiated and mitotic cells that differentiate into villous cells (see below), (b) mucous cells, (c) endocrine and paracrine cells that receive information about the composition of chyme from chemosensor cells, and (d) immune cells (→ p. 234). The chyme composition triggers the secretion of endocrine hormones and of paracrine mediators (→ p. 236). The tubuloacinar *duodenal glands* (Brunner's glands), located deep in the intestinal wall (tela submucosa) secrete a HCO_3^--rich fluid containing urogastrone (*human epidermal growth factor*), an important stimulator of epithelial cell proliferation.

Cell replacement. The tips of the villi are continually shed and replaced by new cells from the crypts of Lieberkühn. Thereby, the entire SI epithelium is renewed every 3–6 days. The dead cells disintegrate in the lumen, thereby releasing enzymes, stored iron, etc.


Intestinal motility is autonomously regulated by the enteric nervous system, but is influenced by hormones and external innervation (→ p. 236). Local *pendular movements* (by longitudinal muscles) and *segmentation* (contraction/relaxation of circular muscle fibers) of the SI serve to mix the intestinal contents and bring them into contact with the mucosa. This is enhanced by movement of the intestinal villi (lamina muscularis mucosae). *Reflex peristaltic waves* (30–130 cm/min) propel the intestinal contents towards the rectum at a rate of ca. 1 cm/min. These waves are especially strong during the interdigestive phase (→ p. 242).

Peristaltic reflex. Stretching of the intestinal wall during the passage of a bolus (→ **B**) triggers a reflex that constricts the lumen behind the bolus and dilates that ahead of it. Controlled by interneurons, cholinergic type 2 motoneurons with prolonged excitation simultaneously activate circular muscle fibers behind the bolus and longitudinal musculature in front of it. At the same time the circular muscle fibers in front of the bolus are inhibited (accommodation) while those behind it are disinhibited (→ **B** and p. 236).


Pacemakers. The intestine also contains pacemaker cells (*interstitial Cajal cells*). The membrane potential of these cells oscillates between 10 and 20 mV every 3–15 min, producing *slow waves* (→ **C1**). Their amplitude can rise (less negative potential) or fall in response to neural, endocrine or paracrine stimuli. A series of action potentials (spike bursts) are fired once the membrane potential rises above a certain threshold (ca. –40 mV) (→ **C2**). *Muscle spasms* occur if the trough of the wave also rises above the threshold potential (→ **C3**).

Impulse conduction. The spike bursts are conducted to myocytes via *gap junctions* (→ p. 19, 70). The myocytes then contract rhythmically at the same frequency (or slower). Conduction in the direction of the anus dwindles after a certain distance (→ **D**, pacemaker zone), so more distal cells (with a lower intrinsic rate) must assume the pacemaker function. Hence, peristaltic waves of the small intestine only move in the anal direction.


A. Structure of the small intestine (schematic)




B. Peristaltic reflex



C. Slow waves and spikes



D. Pacemaker rate



The *exocrine part* of the pancreas secretes 1–2 L of pancreatic juice into the duodenum each day. The pancreatic juice contains HCO_3^-, which neutralizes (pH 7–8) HCl-rich chyme from the stomach, and mostly inactive precursors of *digestive enzymes*.

Pancreatic secretions are similar to saliva in that they are produced in two stages: (1) Cl^- is secreted in the **acini** by secondary active transport, followed by passive transport of Na^+ and H_2O (→ p. 238 C1). These primary secretions have an ion composition corresponding to that of plasma (→ **A1** and **A2**) and also contain *digestive proenzymes* and other proteins (exocytosis; → p. 30). (2) HCO_3^- is added to the primary secretions (in exchange for Cl^-) in the intercalated and intralobular **ducts**; Na^+ and H_2O follow by passive transport (→ **B**). As a result, the HCO_3^- concentration of pancreatic juice rises to over 100 mmol/L, while the Cl^- concentration falls (→ **A3**). Unlike saliva (→ p. 239 B), the osmolality and Na^+/K^+ concentrations of the pancreatic juice remain constant (→ **A1** and **A2**). During the digestive phase, most of the pancreatic juice is secreted from the ducts (→ **A3**).

HCO_3^- is secreted from the luminal membrane of the ducts via an anion exchanger (AE) that simultaneously reabsorbs Cl^- from the lumen (→ **B1**). Cl^- returns to the lumen via a Cl^- channel, which is more frequently opened by **secretin** to ensure that the amount of HCO_3^- secreted is not limited by the availability of Cl^- (→ **B2**).

In **cystic fibrosis** (mucoviscidosis), this CFTR channel (**c**ystic **f**ibrosis **t**ransmembrane **c**onductance **r**egulator) is impaired.

The secreted HCO_3^- is absorbed in part from the blood via a Na-HCO_3^- symporter (NBC; → **B3**), in part is the product of the CO_2 + OH^- reaction in cytosol (→ **B4**) catalyzed by carbonic anhydrase (CA). For each HCO_3^- molecule secreted, one H^+ ion leaves the cell on the blood side via an Na^+/H^+ exchanger (NHE1 → **B5**).

Pancreatic juice **secretion is controlled** in the acini by cholinergic (vagal) mechanisms and by the hormone cholecystokinin (CCK, vagal stimulation seems to be enhanced by CCK_A receptors) (→ **C** and p. 236). Both cause an elevation of cytosolic concentration of Ca^{2+}, $[Ca^{2+}]_i$, which stimulates Cl^- and (pro-)enzyme secretion. Trypsin in the small intestinal lumen deactivates CCK release via a feedback loop (→ **D**). *Secretin* increases HCO_3^- and H_2O secretion by the ducts. CCK and vagal acetylcholine (ACh) potentiate this effect by raising $[Ca^{2+}]_i$. The hormones also have a growth-promoting effect.

A high dietary intake of soya beans inhibits trypsin and results in CCK being secreted also during interdigestive phases, which leads to an increased incidence of pancreatic cancer.

The pancreatic enzymes have a pH optimum of 7–8. Insufficient HCO_3^- secretion (e.g., in cystic fibrosis) results in inadequate neutralization of chyme and therefore in impaired digestion.

Proteolysis is catalyzed by proteases, which are secreted in their inactive form, i.e., as *proenzymes*: *trypsinogen 1–3, chymotrypsinogen A and B, proelastase 1 and 2* and *procarboxypeptidase A1, A2, B1* and *B2*. They are activated only when they reach the intestine, where an *enteropeptidase* first converts trypsinogen to **trypsin** (→ **D**), which then converts chymotrypsinogen into active *chymotrypsin*. Trypsin also activates many other pancreatic proenzymes including proelastases and procarboxypeptidases. Trypsins, chymotrypsins and elastases are *endoproteases*, i.e., they split certain peptide bonds within protein chains. Carboxypeptidases A and B are *exopeptidases*, i.e., they split amino acids off the carboxyl end of the chain.


Pathological activation of the proenzymes within the pancreas causes the organ to digest itself (*acute pancreatic necrosis*).

Carbohydrate catabolism. *α-Amylase* is secreted in active form and splits starch and glycogen into maltose, maltotriose and α-limit dextrin. These products are further digested by the intestinal epithelium (→ p. 261).


Lipolysis. *Pancreatic lipase* (see p. 254ff.) is the most important enzyme for lipolysis. It is secreted in its active form and breaks triacylglycerol to 2-monoacylglycerol and free fatty acids. Pancreatic lipase activity depends on the presence of *colipases*, generated from pro-colipases in pancreatic secretions (with the aid of trypsin). *Bile salts* are also necessary for fat digestion (→ p. 250).

Other important pancreatic enzymes include (pro-) phospholipase A_2, RNases, DNases, and a carboxylesterase.


A. Electrolyte concentration in plasma and pancreatic juice




B. Secretion in pancreatic duct cells



C. Control of pancreatic juice secretion



D. Trypsin: activation and effects



Bile components. Bile contains electrolytes, bile salts (bile acids), cholesterol, lecithin (phosphatidylcholine), bilirubin diglucuronide, steroid hormones, medications etc. (→ **A**). *Bile salts* are essential for fat digestion. Most of the other components of bile leave the body via the feces (excretory function of the liver → p. 252).

Bile formation. Hepatocytes secrete ca. 0.7 L/day of bile into *biliary canaliculi* (→ **A**), the fine canals formed by the cell membranes of adjacent hepatocytes. The sinusoidal and canalicular membranes of the hepatocytes contain numerous carriers that absorb bile components from the blood and secrete them into the canaliculi, resp.

Bile salts (BS). The liver synthesizes *cholate* and *chenodeoxycholate* (primary bile salts) from *cholesterol*. The intestinal bacteria convert some of them into secondary bile salts such as *deoxycholate* and *lithocholate*. Bile salts are conjugated with taurine or glycine in the liver and are secreted into the bile in this form (→ **A**). This conjugation is essential for micelle formation in the bile and gut.

Hepatic bile salt carriers. *Conjugated bile salts* in sinusoidal blood are actively taken up by **NTCP** (Na^+ taurocholate cotransporting polypeptide; secondary active transport), and transported against a steep concentration gradient into the canaliculi (primary active transport) by the ATP-dependent carrier **hBSEP** (human bile salt export pump), also referred to as **cBAT** (canalicular bile acid transporter).

Enterohepatic circulation of BS. Unconjugated bile salts are immediately reabsorbed from the bile ducts (cholehepatic circulation). Conjugated bile salts enter the duodenum and are reabsorbed from the terminal ileum by the Na^+ symport carrier ISBT (= **i**leal **s**odium **b**ile acid co**t**ransporter) and circulated back to the liver (*enterohepatic circulation*; → **B**) once they have been used for fat digestion (→ p. 254). The total bile salt pool (2–4 g) recirculates about 6–10 times a day, depending on the fat content of the diet. Ca. 20–30 g of bile salts are required for daily fat absorption.

Choleresis. Enterohepatic circulation raises the bile salt concentration in the portal vein to a high level during the digestive phase. This (a) inhibits the hepatic synthesis of bile salts (cholesterol-7α-hydroxylase; negative feedback; → **B**) and (b) stimulates the secretion of bile salts into the biliary canaliculi. The latter effect increases the bile flow due to osmotic water movement, i.e., causes *bile salt-dependent choleresis* (→ **C**). *Bile salt-independent choleresis* is, caused by secretion of other bile components into the canaliculi as well as of HCO_3^- (in exchange for Cl^-) and H_2O into the *bile ducts* (→ **C**). The latter form is increased by the vagus nerve and secretin.


Gallbladder. When the sphincter of Oddi between the common bile duct and duodenum is closed, *hepatic bile* (*C bile*) is diverted to the gallbladder, where it is concentrated (approx. 1 : 10) and stored (→ **D**). The gallbladder epithelium reabsorbs Na^+, Cl^- and water (→ **D1**) from the stored bile, thereby greatly raising the concentration of specific bile components (bile salts, bilirubin-*di*-glucuronide, cholesterol, phosphatidylcholine, etc.). If bile is used for fat digestion (or if a peristaltic wave occurs in the interdigestive phase, → p. 242), the gallbladder contracts and its contents are mixed in portions with the duodenal chyme (→ **D2**).

Cholesterol in the bile is transported inside *micelles* formed by aggregation of cholesterol with lecithin and bile salts. A change in the ratio of these three substances in favor of cholesterol (→ **E**) leads to the precipitation of cholesterol crystals responsible for gallstone development in the highly concentrated *gallbladder bile* (*B bile*). The red and green dots in **E** show the effects of two different ratios.


Gallbladder contraction is *triggered* by CCK (→ p. 236), which binds to CCK_A receptors, and the neuronal plexus of the gallbladder wall, which is innervated by preganglionic parasympathetic fibers of the vagus nerve (→ **D2**).

CGRP (→ p. 236) and substance P (→ p. 86) released by sensory fibers appear to stimulate the gallbladder musculature indirectly by increasing acetylcholine release. The sympathetic nervous system *inhibits* gallbladder contractions via α_2 adrenoreceptors located on cholinergic fiber terminals. As *cholagogues*, fatty acids and products of protein digestion (→ p. 236) as well as egg yolk and $MgSO_4$ effectively stimulate CCK secretion.


A. Bile components and hepatic secretion of bile




B. Enterohepatic circulation of bile salts




C. Bile flow



D. Gallbladder



E. Micelle-mediated "dissolution" of cholesterol in the bile



The **liver detoxifies** and **excretes** many mostly lipophilic substances, which are either generated during metabolism (e.g., bilirubin or steroid hormones) or come from the intestinal tract (e.g., the antibiotic chloramphenicol). However, this requires prior **biotransformation** of the substances. In the *first step* of the process, reactive OH, NH_2 or COOH groups are enzymatically added (e.g., by monooxygenases) to the hydrophobic substances. In the *second step*, the substances are *conjugated* with glucuronic acid, acetate, glutathione, glycine, sulfates, etc. The conjugates are now water-soluble and can be either further processed in the kidneys and excreted in the urine, or secreted into bile by liver cells and excreted in the feces. Glutathione conjugates, for example, are further processed in the kidney and excreted as mercapturic acids in the urine.

Carriers. The canalicular membrane of hepatocytes contains various carriers, most of which are directly fueled by ATP (see also p. 250). The principal carriers are: **MDR1** (multidrug resistance protein 1) for relatively hydrophobic, mainly cationic metabolites, **MDR3** for phosphatidylcholine (→ p. 250), and **cMOAT** (canalicular multispecific organic anion transporter = multidrug resistance protein MRP2) for conjugates (formed with glutathione, glucuronic acid or sulfate) and many other organic anions.

Bilirubin sources and conjugation. Ca. 85% of all bilirubin originates from the *hemoglobin* in erythrocytes; the rest is produced by other hemoproteins like cytochrome (→ **A** and **B**). When degraded, the globulin and iron components (→ p. 90) are cleaved from hemoglobin. Via intermediate steps, *biliverdin* and finally *bilirubin*, the yellow bile pigment, are then formed from the porphyrin residue. Each gram of hemoglobin yields ca. 35 mg of bilirubin. Free unconjugated bilirubin (*"indirect" bilirubin*) is poorly soluble in water, yet lipid-soluble and toxic. It is therefore *complexed with albumin* when present in the blood (2 mol bilirubin : 1 mol albumin), but not when absorbed by hepatocytes (→ **A**). Bilirubin is conjugated (catalyzed by *glucuronyltransferase*) with 2 molecules of *UDP-glucuronate* (synthesized from glucose, ATP and UTP) in the liver cells yielding **bilirubin di**(or **bis)glucuronide** (*"direct" bilirubin*). It is a yellow water-soluble substance secreted into the biliary canaliculi by primary active transport mechanisms (cMOAT, see above).

Bilirubin excretion. 200–250 mg of bilirubin is excreted in the bile each day. Ca. 90% of it is *excreted in the feces*. In the gut, bacteria break bilirubin down into the colorless compound, *stercobilinogen* (→ **B**). It is partly oxidized into *stercobilin*, the brown compound that colors the stools. About 10% of all bilirubin diglucuronide is deconjugated by intestinal bacteria and returned to the liver in this lipophilic form (partly as stercobilinogen) via enterohepatic circulation. A small portion (ca. 1%) reaches the systemic circulation and is excreted by the kidneys as *urobilinogen* = stercobilinogen (see below) (→ **B**). The renal excretion rate increases when the liver is damaged.

Jaundice. The *plasma bilirubin concentration* normally does not exceed 17 μmol/L (= 1 mg/dL). Concentrations higher than 30 μmol/L (1.8 mg/dL) lead to yellowish discoloration of the sclera and skin, resulting in **jaundice** (**icterus**). **Types of jaundice:**


1. **Prehepatic jaundice**. When excessive amounts of bilirubin are formed, for example, due to increased hemolysis, the liver can no longer cope with the higher load unless the plasma bilirubin concentration rises. Thus, *unconjugated (indirect) bilirubin* is mainly elevated in these patients.

2. **Intrahepatic jaundice**. The main causes are (a) liver cell damage due to toxins (*Amanita*) or infections (*viral hepatitis*) resulting in the impairment of bilirubin transport and conjugation; (b) deficiency or absence of the glucuronyltransferase system in the newborn (Crigler–Najjar syndrome); (c) inhibition of glucuronyltransferase, e.g., by steroids; (d) impaired secretion of bilirubin into the biliary canaliculi due to a congenital defect (Dubin–Johnson syndrome) or other reasons (e.g., drugs, steroid hormones).


3. **Posthepatic jaundice**: Impairment of the flow of bile occurs due to an obstruction (e.g., stone or tumor) in the bile ducts, usually accompanied by elevated serum concentrations of already *conjugated (direct) bilirubin* and alkaline phosphatase—both of which are normal components of bile.

Types 2a, 2d and 3 jaundice are associated with increased urinary concentrations of conjugated bilirubin, leading to brownish discoloration of the urine. In type 3 jaundice, the stools are gray due to the lack of bilirubin in the intestine and the resulting absence of stercobilin formation.

A. Conjugation and secretion of bilirubin in the liver



B. Bilirubin metabolism and excretion



The average **intake of fats** (butter, oil, margarine, milk, meat, sausages, eggs, nuts etc.) is roughly 60–100 g/day, but there is a wide range of individual variation (10–250 g/day). Most fats in the diet (90%) are neutral fats or *triacylglycerols* (triglycerides). The rest are phospholipids, cholesterol esters, and fat-soluble vitamins (vitamins A, D, E and K). Over 95% of the lipids are normally absorbed in the small intestine.

Lipid digestion (→ **A**). Lipids are poorly soluble in water, so special mechanisms are required for their digestion in the watery environment of the gastrointestinal tract and for their subsequent absorption and transport in plasma (→ p. 256). Although small quantities of undegraded triacylglycerol can be absorbed, dietary fats must be hydrolyzed by enzymes before they can be efficiently absorbed. Optimal enzymatic activity requires the prior mechanical *emulsification* of fats (mainly in the distal stomach, → p. 242) because emulsified *lipid droplets* (1–2 μm; → **B1**) provide a much larger surface (relative to the mass of fat) for lipases.

Lipases, the fat digesting enzymes, originate from the lingual glands, gastric fundus (chief and mucous neck cells) and *pancreas* (→ **A** and p. 248). About 10–30% of dietary fat intake is hydrolyzed in the stomach, while the remaining 70–90% is broken down in the duodenum and upper jejunum. Lingual and gastric lipases have an acid pH optimum, whereas pancreatic lipase has a pH optimum of 7–8. Lipases become active at the fat/oil and water interface (→ **B**). **Pancreatic lipase** (triacylglycerol hydrolase) develops its lipolytic activity (max. 140 g fat/min) in the presence of **colipase** and Ca^{2+}. *Pro-colipase* in pancreatic juice yields colipase after being activated by trypsin. In most cases, the pancreatic lipases split *triacylglycerol* (TG) at the 1st and 3rd ester bond (p. 229 B). This process requires the addition of water and yields free *fatty acids (FFA)* and *2-monoacylglycerol*.

A **viscous-isotropic phase** with aqueous and hydrophobic zones then forms around the enzyme (→ **B2**). *Ca^{2+} excesses* or *monoacylglycerol deficiencies* result in the conversion of the fatty acids into *calcium soaps*, which are later excreted.


Phospholipase A_2 (from pro-phospholipase A_2 in pancreatic juice—activated by trypsin) cleaves the 2nd ester bond of the phospholipids (mainly phosphatidylcholine = lecithin) contained in micelles. The presence of *bile salts* and *Ca^{2+}* is required for this reaction.

An **unspecific carboxylesterase** (= unspecific lipase = cholesterol ester hydrolase) in pancreatic secretions also acts on cholesterol esters on micelles as well as all three ester bonds of TG and esters of vitamins, A, D and E.


This lipase is also present in human breast **milk** (but not cow's milk), so breast-fed infants receive the digestive enzyme required to break down milk fat along with the milk. Since the enzyme is heat-sensitive, pasteurization of human milk significantly reduces the infant's ability to digest milk fat to a great extent.

2-Monoacylglycerols, *long-chain free fatty acids* and other lipids aggregate with *bile salts* (→ p. 248) to spontaneously form **micelles** in the small intestine (→ **B3**). (Since short-chain fatty acids are relatively polar, they can be absorbed directly and do not require bile salts or micelles). The micelles are only about 20–50 nm in diameter, and their surface-to-volume ratio is roughly 50 times larger than that of the lipid droplets in emulsions. They facilitate close contact between the products of fat digestion and the wall of the small intestine and are therefore essential for lipid absorption. The polar side of the substances involved (mainly conjugated bile salts, 2-monoacylglycerol and phospholipids) faces the watery environment, and the non-polar side faces the interior of the micelle. Totally apolar lipids (e.g., cholesterol esters, fat-soluble vitamins and lipophilic poisons) are located inside the micelles. Thus, the apolar lipids remain in the lipophilic milieu (*hydrocarbon continuum*) during all these processes until they reach the lipophilic brush border membrane of the epithelium. They are then absorbed by the mucosa cells via dissolution in the membrane or by a passive transport mechanism (e.g., carriers in the case of free fatty acids). Although fat absorption is completed by the time the chyme reaches the end of the jejunum, the *bile salts* released from micelles are only absorbed in the terminal ileum and then recycled (enterohepatic circulation; → p. 251 B).

A. Lipid digestion: overview



B. Lipid digestion: degradation and micelle formation



(After Patton)

Lipids in the blood are transported in **lipoproteins, LP**s (→ **A**), which are molecular aggregates (microemulsions) with a core of very hydrophobic lipids such as *triacylglycerols* (**TG**) and *cholesterol esters* (**CHO-esters**) surrounded by a layer of amphipathic lipids (phospholipids, cholesterol). LPs also contain several types of proteins, called apolipoproteins. LPs are differentiated according to their size, density, lipid composition, site of synthesis, and their apolipoprotein content. **Apolipoproteins** (**Apo**) function as *structural elements* of LPs (e.g. ApoAII and ApoB48), *ligands* (ApoB100, ApoE, etc.) for LP receptors on the membranes of LP target cells, and as *enzyme activators* (e.g. ApoAI and ApoCII).

Chylomicrons transport lipids (mainly *triacylglycerol, TG*) from the gut to the periphery (via intestinal lymph and systemic circulation; → **D**), where their ApoCII activates endothelial lipoprotein lipase (**LPL**), which *cleaves FFA* from TG. The FFA are mainly absorbed by myocytes and fat cells (→ **D**). With the aid of ApoE, the *chylomicron remnants* deliver the rest of their TG, cholesterol and cholesterol ester load to the hepatocytes by receptor-mediated endocytosis (→ **B, D**).

Cholesterol (CHO) and the TG imported from the gut and newly synthesized in the liver are exported inside **VLDL** (very low density lipoproteins) from the liver to the periphery, where they by means of their ApoCII also activate **LPL**, resulting in the *release of FFA* (→ **D**). This results in the loss of ApoCII and exposure of ApoE. VLDL remnants or **IDL** (intermediate-density lipoproteins) remain. Ca. 50% of the IDL returns to the liver (mainly bound by its ApoE on LDL receptors; see below) and is reprocessed and exported from the liver as VLDL (→ **B**).

The other 50% of the IDL is converted to **LDL** (low density lipoprotein) after coming in contact with hepatic lipase (resulting in loss of ApoE and exposure of ApoB100). Two-thirds of the LDLs deliver their CHO and CHO-esters to the liver, the other third transfers its CHO to extrahepatic tissue (→ **B**). Binding of ApoB100 to **LDL receptors** is essential for both processes (see below).

High-density lipoproteins (**HDL**) exchange certain apoproteins with chylomicrons and VLDL and absorb superfluous CHO from the extrahepatic cells and blood (→ **B**). With their ApoAI, they activate the plasma enzyme **LCAT** (lecithin–cholesterol acyltransferase), which is responsible for the partial esterification of CHO. HDL also deliver cholesterol and CHO-esters to the liver and steroid hormone-producing glands with *HDL receptors* (ovaries, testes, adrenal cortex).


Triacylglycerol (TG)

Dietary TGs are broken down into *free fatty acids* (**FFA**) and *2-monoacylglycerol* (**MG**) in the gastrointestinal tract (→ **C** and p. 254). Since short-chain FFAs are water-soluble, they can be absorbed and transported to the liver via the portal vein. Long-chain FFAs and MGs are not soluble in water. They are re-synthesized to TG in the mucosa cells (→ **C**). (The FFAs needed for TG synthesis are carried by FFA-binding proteins from the cell membrane to their site of synthesis, i.e., the smooth endoplasmic reticulum.) Since TGs are not soluble in water, they are subsequently loaded onto **chylomicrons,** which are exocytosed into the extracellular fluid, then passed on to the intestinal lymph (thereby by-passing the liver), from which they finally reach the greater circulation (→ **C, D**). (Plasma becomes cloudy for about 20–30 minutes after a fatty meal due to its chylomicron content). The *liver* also synthesizes TGs, thereby taking the required FFAs from the plasma or synthesizing them from glucose. Hepatic TGs are loaded onto **VLDL** (see above) and subsequently secreted into the plasma (→ **D**).

Since the export capacity of this mechanism is limited, an excess of FFA or glucose (→ **D**) can result in the accumulation of TGs in the liver (*fatty liver*).


Free fatty acids (FFAs) are high-energy substrates used for energy metabolism (→ p. 230). Fatty acids circulating in the blood are mainly transported in the form of TG (in *lipoproteins*) whereas plasma FFA are *complexed with albumin*. Fatty acids are removed from TGs of chylomicrons and VLDL by lipoprotein lipase (**LPL**) localized on the luminal surface of the capillary endothelium of many organs (mainly in fat tissue and muscles) (→ **D**). ApoCII on the surface of TGs and VLDL activates LPL. The **in-** ▶

A. Lipoproteins



	Chylomicrons	VLDL	LDL	HDL
Diameter	80–500 nm	ca. 50 nm	ca. 20 nm	ca. 10 nm
Apolipoproteins	AI, B_{48}, CII+III, E	B_{100}, CII+III, E	B_{100}, CIII, E	AI, III+IV, CIII, D

B. Sources and fate of cholesterol



▶ **sulin** secreted after a meal *induces LPL* (→ **D**), which promotes the rapid degradation of reabsorbed dietary TGs. LPL is also activated by *heparin* (from endothelial tissue, mast cells, etc.), which helps to eliminate the chylomicrons in cloudy plasma; it therefore is called a *clearance factor*. Albumin-complexed FFAs in plasma are mainly transported to the following **target sites** (→ **D**):

◆ *Cardiac muscle, skeletal muscle, kidneys (cortex) and other organs*, where they are oxidized to CO_2 and H_2O in the mitochondria (β oxidation) and used as a **source of energy**.

◆ *Fat cells* (→ **D**), which use the FFAs to synthesize TG and also store the TG. When energy requirements increase or intake decreases, the FFAs are recleaved from triacylglycerol in the fat cells (lipolysis) and transported to the area where they are needed (→ **D**). *Lipolysis is stimulated* by epinephrine, glucagon and cortisol and *inhibited* by insulin (→ p. 284ff.).


◆ The *liver*, where the FFAs are oxidized or used to synthesize TG.


Cholesterol (CHO)

Cholesterol esters (CHO-esters), like TGs, are apolar lipids. In the watery milieu of the body, they can only be transported when incorporated in lipoproteins (or bound to proteins) and can be used for metabolism only after they have been converted to CHO, which is more polar (→ **B**). CHO-esters serve as *stores* and in some cases the transported form of CHO. CHO-esters are present in all lipoproteins, but are most abundant (42%) in LDL (→ **A**).

Cholesterol is an important constituent of cell membranes (→ p. 14). Moreover, it is a precursor for *bile salts* (→ **B** and p. 250), *vitamin D* (→ p. 294), and *steroid hormones* (→ p. 296ff.). Each day ca. 0.6 g of CHO is lost in the feces (reduced to *coprosterol*) and sloughed off skin. The bile salt loss amounts to about 0.5 g/day. These losses (minus the dietary CHO intake) must be compensated for by continuous resynthesis of CHO in the intestinal tract and liver (→ **B**). CHO supplied by the diet is absorbed in part as such and in part in esterified form (→ **B**, lower right). Before it is reabsorbed, CHO-esters are split by *unspecific pancreatic carboxylesterase* to CHO, which is absorbed in the upper part of the small intestine (→ **B**, bottom). *Mucosal cells* contain an enzyme that re-esterifies part of the absorbed CHO: **ACAT** (acyl-CoA-cholesterol acyltransferase) so that both cholesterol and CHO-esters can be integrated in chylomicrons (→ **A**). CHO and CHO-esters in the *chylomicron remnants* (see above) are transported to the liver, where lysosomal acid lipases again break the CHO-esters down into CHO. This CHO and that taken up from other sources (LDL, HDL) leave the liver (→ **B**): 1. by excretion into the bile (→ p. 250), 2. by conversion into bile salts which also enter the bile (→ p. 251 B), and 3. by incorporation into VLDL, the hepatic lipoprotein for export of lipids to other tissues. Under the influence of LPL (see above), the VLDL yield IDL and later **LDL** (→ **B**, left). The LDL transport CHO and CHO-esters to cells with **LDL receptors** (hepatic and extrahepatic cells; → **B**, top). The receptor density on the cell surface is adjusted according to the prevailing CHO requirement. Like hepatic cells (see above) extrahepatic cells take up the LDL by receptor-mediated endocytosis, and lysosomal acid lipases reduce CHO-esters to CHO (→ **B**, top right). The cells can then insert the CHO in their cell membranes or use it for steroid synthesis. A *cholesterol excess* leads to (a) inhibition of CHO synthesis in the cells (3-HMG-CoA-reductase) and (b) activation of ACAT, an enzyme that esterifies and stores CHO in the form of its ester (see above).

Hyperlipoproteinemia. An excess of lipids in the blood can be reflected by elevation of triacylglycerol levels and/or CHO levels (> 200–220 mg/dL serum; affects about one in five adults in Western countries). In the most severe form, *familial hypercholesterolemia*, a genetic defect causes elevated plasma CHO concentrations from birth on, which can result in myocardial infarction in juvenile age. The disease is caused by genetic defects of the high-affinity LDL receptors. The serum CHO level rises since the cells take up smaller quantities of cholesterol-rich LDLs. Extrahepatic tissues synthesize larger quantities of CHO because 3-HMG-CoA-reductase fails to inhibit CHO synthesis due to the decreased absorption of LDLs. As a result, more LDLs bind to the low-affinity *scavenger receptors* that mediate the storage of CHO in macrophages, cutaneous tissues, and blood vessels. Hypercholesterolemia therefore increases the risk of arteriosclerosis and coronary disease.


C. Fat absorption
Fats
Lipases
Micelle
Bile
Liver
Apolar lipids
Short-chain FFA
Bile salts
Intestinal lumen
Glucose
MG
TG
TG synthesis
Cholesterol
CHO-esters
Phospholipids
Fat-soluble vitamins
Apolipoproteins
Chylomicrons
Jejunum
Mucosal cell in Ileum
Enterohepatic circulation
Lymph
To systemic blood
Portal venous blood
(Cf. legends for Plate 10.14B)


D. Source and fate of triacylglycerols and free fatty acids
Intestine
Diet
Triacylglycerine (TG)
Glucose
Free fatty acids (FFA) and monoacylglycerol in micelles
Intestinal lymph
max. 15 g/h
Energy metabolism
FFA
Liver
Pancreatic lipase
Pancreas
in VLDL
TG
Storage of excess fat
Chylomicron residues and IDL
Insulin
max. 4 g/h
In chylo-microns
LPL
Blood
FFA
Release from stores 2–9 g/h
Epinephrine
Glucagon
Cortisol
Storage in fat cells
Energy metabolism in muscle, heart, etc.

Carbohydrates provide half to two-thirds of the energy requirement (→ p. 228). At least 50% of dietary carbohydrates consist of *starch* (amylose and amylopectin), a polysaccharide; other important dietary carbohydrates are cane sugar (saccharose = sucrose) and milk sugar (lactose). Carbohydrate digestion starts in the mouth (→ **A1** and p. 238). *Ptyalin*, an **α-amylase** found in saliva, breaks starches down into oligosaccharides (*maltose, maltotriose,* α *limit dextrins*) in a neutral pH environment. This digestive process continues in the proximal stomach, but is interrupted in the distal stomach as the food is mixed with acidic gastric juices. A pancreatic α-amylase, with a pH optimum of 8 is mixed into the chyme in the duodenum. Thus, polysaccharide digestion can continue to the final oligosaccharide stage mentioned above. The carbohydrates can be only **absorbed** in the form of monosaccharides. Thus, the enzymes *maltase* and *isomaltase* integrated in the luminal brush border membrane of enterocytes break down *maltose, maltotriose* and α *limit dextrins* into **glucose** as the final product. As in the renal tubules (→ p. 160), glucose is first actively taken up by the Na^+ symport carrier SGLT1 into mucosal cells (→ **A2**, p. 29 B1) before passively diffusing into the portal circulation via *GLUT2*, the glucose uniport carrier (facilitated diffusion; → p. 22). The hydrolysis of *saccharose, lactose, and trehalose* is catalyzed by other brush border enzymes: lactase, saccharase (sucrase) and trehalase. In addition to glucose, these reactions release *galactose* (from lactose), which is absorbed by the same carriers as glucose, and *fructose*, which crosses the enterocytes by passive uniporters, GLUT5 in the luminal and GLUT2 in the basolateral membrane (→ **A2**).

Lactase deficiency. Lactose cannot be broken down and absorbed unless sufficient lactase is available. Lactase deficiencies lead to diarrhea 1) because water is retained in the intestinal lumen due to osmotic mechanisms, and 2) because intestinal bacteria convert the lactose into toxic substances.


Protein digestion starts in the stomach (→ **B1**). *HCl* in the stomach denatures proteins and converts the three secreted *pepsinogens* into about eight different **pepsins**. At a pH of 2–5, these *endopeptidases* split off proteins at sites where tyrosine or phenylalanine molecules are incorporated in the peptide chain. The pepsins become inactive in the small intestine (pH 7–8). Pancreatic juice also contains proenzymes of other peptidases that are activated in the duodenum (→ p. 248). The endopeptidases *trypsin, chymotrypsin* and *elastase* hydrolyze the protein molecules into short-chain peptides. *Carboxypeptidase A and B* (from the pancreas) as well as *dipeptidases* and *aminopeptidase* (brush border enzymes) act on proteins at the end of the peptide chain, breaking them down into tripeptides, dipeptides, and (mostly) individual amino acids. These cleavage products are absorbed in the duodenum and jejunum.

Amino acids (AA) are transported by a number of specific carriers (→ **B2)** similar to those found in the kidneys (→ p. 160). Neutral (without net charge) and anionic ("acid") L-amino acids are transported with Na^+ symporters (secondary active transport; → p. 28) from the intestinal lumen into mucosal cells, from which they passively diffuse with carriers into the blood. Cationic ("basic") L-amino acids such as L-arginine$^+$, L-lysine$^+$ and L-ornithine$^+$ are partly taken up into the enterocytes by Na^+ independent mechanisms, as the membrane potential is a driving force for their uptake. *Anionic amino acids* like L-glutamate$^-$ and L-aspartate$^-$ which, for the most part, are broken down in the mucosal cells, also have their own (Na^+ and K^+ dependent) carrier systems. *Neutral amino acids* use several different transporters.


AA absorption disorders can be congenital and affect various amino acid groups. These disorders are often associated with defects of renal tubular reabsorption (renal aminoaciduria, e.g. cystinuria).

Dipeptides and tripeptides can be absorbed as intact molecules by a symport carrier (PepT1). The carrier is driven by an H^+ gradient (→ **B2**), which in turn is generated by H^+ secretion (tertiary active H^+-peptide symport, → p. 29 B5). Amino acids generally are much more rapidly absorbed as dipeptides and tripeptides than as free amino acids. Once they enter the cells, the peptides are hydrolyzed to free amino acids.

A. Carbohydrate digestion and absorption of monosaccharides



B. Protein digestion and absorption of amino acids and oligopeptides



Since higher animals cannot synthesize **cobalamins** (**vitamin B_{12}**), they must obtain this *cobalt-containing coenzyme* from the diet. Animal products (liver, kidneys, fish, eggs, milk) are the main source.

Cobalamin biochemistry. Aqua- and OH-cobalamin are precursors of the two active forms, methyl- and adenosylcobalamin. *Methylcobalamin* is needed to form methionine from homocysteine; cobalamin transfers the methyl group required for this from N^5-methyltetrahydrofolate (see below) to homocysteine. Some enzymes, e.g. methyl-malonyl-CoA mutase, need *adenosylcobalamin* to break and form carbon–carbon bonds.


Cobalamins are relatively large and lipophobic molecules that require **transport proteins** (→ **A**). During passage through the GI tract, plasma and other compartments, cobalamins bind to (1) *intrinsic factor* (**IF**), which is secreted by gastric parietal cells; (2) *transcobalamin II* (**TC II**) in plasma; and (3) *R proteins* in plasma (**TC I**), and granulocytes (**TC III**), saliva, bile, milk, etc. Gastric acid releases cobalamin from **dietary proteins**. In most cases, the cobalamin then binds to R protein in saliva or (if the pH is high) to IF (→ **A1**). The R protein is digested by trypsin in the duodenum, resulting in the release of cobalamin, which is then bound by (trypsin-resistant) **intrinsic factor**. The mucosa of the *terminal ileum* has highly specific receptors for the cobalamin-IF complex. IT binds to these receptors and is absorbed by *receptor-mediated endocytosis*, provided a pH of > 5.6 and Ca^{2+} ions are available (→ **A2**). The receptor density and, thus, the absorption rate increases during pregnancy. Cobalamin binds to TC I, II and III in **plasma** (→ **A3**). TC II mainly distributes cobalamin to all cells undergoing division (TC II receptors, endocytosis). TC III (from granulocytes) transports excess cobalamin and unwanted cobalamin derivatives to the **liver** (TC III receptors), where it is either stored or excreted in the bile. TC I has a half-life of roughly 10 days and serves as a short-term depot for cobalamin in the plasma.

A vegan diet or disturbed cobalamin absorption can lead to severe **deficiency symptoms** like pernicious anemia and spinal cord damage (funicular myelosis). It takes years for these symptoms to manifest as the body initially has a reserve of 1000 times the daily requirement of 1 µg (→ p. 90).

Folic acid/folate (= pteroylglutamate). *N^5, N^{10}-methylenetetrahydrofolate*, the metabolically active form of folic acid (daily requirement: 0.1–0.2 mg) is needed for *DNA synthesis* (formation of deoxythymidylate from deoxyuridylate). Folate in the **diet** usually occurs in forms that contain up to seven glutamyl residues (γ-linked peptide chain; *Pte-Glu_7*) instead of pteroylglutamate (*Pte-Glu_1*). Since only Pte-Glu_1 can be absorbed from the lumen of the proximal jejunum (→ **B**), its polyglutamyl chain must be shortened before absorption. This is done by *pteroylpolyglutamate hydrolases* located in the luminal membrane of enterocytes. The **absorption** of Pte-Glu_1 in exchange for OH^- is mediated by a specific transporter. In mucosal cells, Pte-Glu_1 is than broken down to yield N^5-methyltetrahydrofolate (5-Me-H_4-folate) and other metabolites. If already present in the ingested food, these metabolites are absorbed from the intestinal lumen by the aforementioned mechanism. (The same applies to the cytostatic drug, *methotrexate*.) *Methylcobalamin* is needed to convert 5-Me-H_4-folate to tetrahydrofolate (see above). The body stores about 7 mg of folic acid, enough for several months (cf. *folic acid deficiency*, → p. 90).

The **other water-soluble vitamins**—B_1 (thiamin), B_2 (riboflavin), C (ascorbic acid), and H (biotin, niacin)—are absorbed via Na^+ symport carriers (→ **C**). Vitamin C is absorbed from the ileum, whereas vitamins B_1, B_2, and H are absorbed from the jejunum. Members of the vitamin B_6 group (pyridoxal, pyridoxine, pyridoxamine) are probably absorbed by passive mechanisms.

Fat-soluble vitamins—A (retinol), D_3 (cholecalciferol), E (tocopherol), K_1 (phylloquinone), and K_2 (menaquinone)—must be incorporated into **micelles** for absorption (cf. lipid digestion, p. 254). The exact absorption mechanism has not yet been explained, though it is known to be partly saturation- and energy-dependent. Fat-soluble vitamins are incorporated into chylomicrons and VLDL for transport in plasma (→ p. 256ff.).


A. Cobalamin (B_{12}) transport
Cobalamin (vitamin B_{12})
In the diet: 5–15 µg/day (min. 1–5)
B_{12}
Protein x
HCl
pH
Protein x
From saliva
Stomach
B_{12}
R-protein
Intrinsic factor
Duodenum
1
B_{12}
R-protein
Pancreas
B_{12}
R-Protein
Trypsin
B_{12}
IF
B_{12}
Terminal ileum
2
Specific binding to receptors of ileal mucosa
Ca^{2+}
B_{12}
IF
pH>5.6
Transcellular B_{12} transport (ca. 1–2 µg/day)
B_{12}
TCIII
TCII
TCI
3
Plasma
Plasma-"reserve"
Liver
Storage (3–5 mg)
Cell metabolism
Excretion
B. Absorption of folic acid
Pte–Glu–Glu–Glu...
Folic acid
In the diet 0.6 mg/day (min. 0.05)
$Pte–Glu_1^-$
$Me–H_4–Pte–Glu$
Jejunum
Pass into blood
OH^-
$Pte–Glu_1^-$
$Me–H_4–Pte–Glu$
Glu–Glu...
Pteroyl-polyglutamate hydrolase
Lumen
Mucosal cell (jejunum)
C. Secondary active vitamin absorption
Na^+
Na^+
Na^+
Vitamins
Vit. B_1, B_2, H: Jejunum
Vit. C: Ileum
ATP
K^+
Lumen
Mucosal cell
Blood

The average intake of water (in beverages and foodstuffs) is roughly 1.5 L per day. An additional 7 L of fluid are secreted into the gastrointestinal (GI) tract (saliva, gastric juices, bile, pancreatic juice and intestinal secretions), whereas only about 0.1 L/day is eliminated in the feces. The digestive tract must therefore absorb a net volume of at least 8.4 L of water per day. GI **absorption of water** occurs mainly in the jejunum and ileum, with smaller quantities being absorbed by the colon (→ **A**). Water is driven through the intestinal epithelium by osmosis. When solutes (Na^+, Cl^-, etc.) are absorbed in the intestine, water follows (→ **B**). (The stool contains only small quantities of Na^+, Cl^- and water.) Conversely, the secretion of substances into the lumen or the ingestion of non-absorbable substances leads to water fluxes into the lumen. Poorly absorbable substances therefore act as *laxatives* (e.g. sulfate, sorbitol, polyethylene glycol).

Water absorption is mainly driven by the **absorption of Na^+, Cl^-** and **organic compounds** (→ **B**). The luminal concentration of Na^+ and Cl^- steadily decreases from the duodenum to the colon. That of Na^+, for example, is approximately 145 mmol/L in the duodenum, 125 mmol/L in the ileum and only 40 mmol/L in the colon (→ **C**). Na^+ is absorbed by various **mechanisms**, and the *Na^+-K^+-ATPase* on the basolateral cell membrane is the primary driving mechanism (→ p. 26) for all of them (→ **B, D**).

◆ **Symport of Na^+ and organic substances** (→ see pp. 26ff. and 260): Na^+ passively influxes into cells of the duodenum and jejunum via symporter carriers, which actively cotransport glucose, amino acids, phosphates and other compounds (secondary active transport; → **D1**). Since this is an electrogenic transport mechanism (→ p. 28), a *lumen-negative transepithelial potential* (**LN**TP; → p. 164) forms that drives Cl^- out of the lumen (→ **D2**).

◆ **Parallel transport of Na^+ and Cl^-**: Na^+ ions in the lumen of the ileum are exchanged for H^+ ions (→ **D3**) while Cl^- is exchanged for HCO_3^- at the same time (→ **D4**). The H^+ ions combine with HCO_3^- to yield $H_2O + CO_2$, which diffuse out of the lumen. Most Na^+, Cl^- and, by subsequent osmosis, H_2O is absorbed by this electroneutral transport mechanism.

◆ **Na^+ diffusion**: Na^+ in the colon is mainly absorbed through luminal *Na^+ channels* (→ **D5**). This type of Na^+ transport is electrogenic and aldosterone-dependent (→ p. 184). The related lumen-negative transepithelial potential (**LN**TP, see above) either leads to K^+ secretion or drives Cl^- out of the lumen (→ **D2**).


The **Cl^- secretion** mechanism of epithelial cells (mainly *Lieberkühn's crypts*, → p. 247, A16) is similar to that of the acini of salivary glands (→ p. 238). The efflux of Cl^- into the lumen and the associated efflux of Na^+ and water are stimulated by cAMP and regulated by neurons and hormones such as VIP (vasoactive intestinal peptide) and prostaglandins. The physiological function of this form of H_2O secretion could be to dilute viscous chyme or to ensure the recirculation of water (from the crypts → lumen → villi → crypts) to promote the absorption of poorly soluble substances.

Cholera toxin inhibits the GTPase of the G_s proteins (→ p. 276), thereby maintaining a maximal cAMP concentration and therefore a marked increase in Cl^- secretion. In response to it, large quantities of water and Na^+ are secreted into the lumen, which can lead to severe diarrhea (up to 1 L/hour!).


In addition to **HCO_3^-** from pancreatic juice, HCO_3^- is also secreted into the intestinal lumen by the small and large intestine (→ **A**). **K^+** is secreted (aldosterone-dependent) by crypt cells of the colon (luminal K^+ concentration ≈ 90 mmol/l!) and reabsorbed via the H^+-K^+ pump of the surface epithelium (similar to the mechanism in the stomach; → p. 245 A). The aldosterone-dependent K^+ secretion/absorption ratio determines the net amount of K^+ excreted (→ **A** and p. 182). *Diarrhea* results in losses of K^+ and HCO_3^- (hypokalemia and metabolic acidosis; → p. 142).

Ca^{2+}. The stool contains one-third of the dietary Ca^{2+} intake. Ca^{2+} is absorbed in the upper part of the small intestine (→ **A**) with the aid of intracellular *calcium-binding protein* (**CaBP**). Calcitriol increases CaBP synthesis, thereby increasing Ca^{2+} absorption (→ p. 294). Deficiencies of vitamin D or substances that form water-insoluble compounds with Ca^{2+} (phytin, oxalate, fatty acids) decrease Ca^{2+} absorption. **Mg^{2+}** is absorbed by similar mechanisms, but **iron (Fe)** is absorbed by a different mechanism (→ p. 90).


A. Water and electrolyte absorption in the gut




B. Na^+ and H_2O absorption in the gut (model)



C. Na^+ and K^+ exchange in ileum



D. Na^+ and Cl^- absorption in gut



Anatomy. The terminal end of the gastrointestinal tract includes the *large intestine* (*cecum* and *colon*, ca. 1.3 m in length) and *rectum*. The large intestinal mucosa has characteristic pits (crypts), most of which are lined with mucus-forming cells (*goblet cells*). Some of the surface cells are equipped with a brush border membrane and reabsorb ions and water.

The large intestine has two **main functions**: (1) It serves as a *reservoir* for the intestinal contents (cecum, ascending colon, rectum). (2) It absorbs water and electrolytes (→ p. 264), so the ca. 500–1500 mL of chyme that reaches the large intestine can be reduced to about 100–200 mL. The large intestine is not an essential organ; therefore, large segments of the intestine can be removed—e.g., for treatment of cancer.

Water instilled into the **rectum** via an *enema* is reabsorbed. Anally delivered drugs (*suppositories*) also diffuse through the intestinal wall into the bloodstream. Substances administered by this route bypass the liver and also escape the effects of gastric acid and digestive enzymes.

Motility. Thera are different local mixing movements of the large intestine, e.g., powerful segmentation contractions associated with pouch formation (*haustration*) and anterograde or retrograde *peristaltic waves* (pacemaker located in transverse colon). Thus, stool from the colon can also be transported to the cecum. Additionally, *mass movements* occur 2–3 times daily (→ **A**). They are generally stimulated by a meal and are caused by the gastrocolic reflex and gastrointestinal hormones.

The typical sequence of **mass movement** can be observed on X-ray films after administration of a barium meal, as shown in the diagrams (→ **A1 – 8**). **A1**, barium meal administered at 7:00 a.m. **A2**, 12 noon: the barium mass is already visible in the last loop of the ileum and in the cecum. Lunch accelerates the emptying of the ileum. **A3**, about 5 minutes later, the tip of the barium mass is choked off. **A4**, shortly afterwards, the barium mass fills the transverse colon. **A5**, haustration divides the barium mass in the transverse colon, thereby mixing its contents. **A6–8**, a few minutes later (still during the meal), the transverse colon suddenly contracts around the leading end of the intestinal contents and rapidly propels them to the sigmoid colon.


Intestinal bacteria. The intestinal tract is initially sterile at birth, but later becomes colonized with orally introduced anaerobic bacteria during the first few weeks of life. The large intestine of a healthy adult contains 10^{11} to 10^{12} bacteria per mL of intestinal contents; the corresponding figure for the ileum is roughly 10^6/mL. The low pH inside the stomach is an important barrier against pathogens. Consequently, there are virtually no bacteria in the upper part of the small intestine (0–10^4/mL). Intestinal bacteria increase the activity of intestinal immune defenses (*"physiological inflammation"*), and their metabolic activity is useful for the host. The bacteria synthesize vitamin K and convert indigestible substances (e.g. cellulose) or partially digested saccharides (e.g. lactose) into absorbable short-chain fatty acids and *gases* (methane, H_2, CO_2).

The **anus** is normally closed. Anal closure is regulated by Kohlrausch's valve (transverse rectal fold), the puborectal muscles, the (involuntary) internal and (voluntary) external anal sphincter muscles, and a venous spongy body. Both sphincters contract tonically, the internal sphincter (smooth muscle) intrinsically or stimulated by sympathetic neurons (L_1, L_2) via α-adrenoceptors, the external sphincter muscle (striated muscle) by the pudendal nerve.

Defecation. Filling of the upper portion of the rectum (*rectal ampulla*) with intestinal contents stimulates the rectal stretch receptors (→ **B2**), causing *reflex relaxation of the internal sphincter* (accommodation via VIP neurons), *constriction of the external sphincter*, and an *urge to defecate*. If the (generally voluntary) decision to defecate is made, the rectum shortens, the puborectal and external anal sphincter muscles relax, and (by a spinal parasympathetic reflex via S_2–S_4) annular contractions of the circular muscles of the descending colon, sigmoid colon and rectum—assisted by increased abdominal pressure—propel the feces out of the body (→ **B**). The normal **frequency of bowel evacuation** can range from 3 times a day to 3 times a week, depending on the dietary content of indigestible fiber (e.g. cellulose, lignin). Frequent passage of watery stools (*diarrhea*) or infrequent stool passage (*constipation*) can lead to various disorders.


Stool (feces; → C). The average adult excretes 60–80 g of feces/day. Diarrhea can raise this over 200 g/d. Roughly $^1/_4$ of the feces is composed of *dry matter*, in which in turn about $^1/_3$ is attributable to bacteria.

A. Mass movement in large intestine




(After Hertz & Newton)

B. Anal closure and defecation



C. Composition of feces



Unlike unicellular organisms, multicellular organisms have numerous specialized groups of cells and organs, the many different functions of which must be expediently *integrated* and *coordinated* (see also p. 2). In mammals, the **nervous system** and **endocrine system** are chiefly responsible for control and integration, while the **immune system** serves as an information system for corporal immune defense (→ p. 94ff.). These systems communicate by way of *electrical and/or chemical* **signals** (→ **A**).

Nerve impulses and hormonal signals serve to **control and regulate** (→ p. 4) the metabolism and internal milieu (blood pressure, pH, water and electrolyte balance, temperature, etc.), physical growth and maturation, reproductive functions, sexual response, and responses to the social environment. The signals received by sensors (= sensory receptors) in the inner organs, musculoskeletal system, skin and the sensory organs, as well as psychological factors, skeletal muscles and other factors also play a part in regulation and control. The signals are used by many *feedback mechanisms* in the body (→ p. 4).

Nerve fibers are specifically adapted for rapid transmission of finely graded signals. The nervous system consists of the **central nervous system** (CNS; → p. 312ff.) and **peripheral nervous system** . The latter consists of:

- The **somatic nervous system**, which conducts impulses from non-visceral sensors to a center (afferent neurons) and controls the skeletal musculature (efferent neurons).
- The **peripheral autonomic nervous system** (→ p. 78ff.), which consists of efferent neurons and mainly functions to control the circulatory system, inner organs and sexual functions. It is supplemented by:
- **Visceral afferent neurons**, i.e., nerve fibers that conduct signals from inner organs to a center. They are usually located in the same nerves as autonomous fibers (e.g., in vagus nerve); and the
- **Enteric nervous system**, which integrates the local functions of the esophagus, stomach and gut (→ p. 236).

Hormones. Like neurotransmitters (see below) and the immune system's cytokines and chemokines (→ p. 94ff.), hormones serve as *messenger substances* that are mainly utilized for *slower, long-term* transmission of signals. **Endocrine hormones** are carried by the blood to target structures great distances away. **Paracrine hormones** (and other paracrine transmitters) only act on cells in the immediate vicinity of the cells from which they are released. Hormones that act on the cells that produced the messenger substance are referred to as **autocrine hormones**.


Hormones are synthesized in specialized glands, tissues and cells (e.g., *neuroendocrine cells*). Their **target organ** is either a subordinate endocrine gland (*glandotropic hormone*) or non-endocrine tissue (*aglandotropic hormone*). The **target cells** have high-affinity binding sites (**receptors**) for their specific hormone, so very low concentrations of the hormone suffice for signal transduction (10^{-6} to 10^{-12} mol/L). The receptors on the target cells pick out the substances specifically intended for them from a wide variety of different messenger substances in their environment.

Hormones work closely with the nervous system to regulate *digestion, metabolism, growth, maturation, physical* and *mental development, maturation, reproduction, adaptation,* and the internal milieu of the body (*homeostasis*) (→ **A**). Most of these actions are predominately autonomous functions subject to central control by the **hypothalamus**, which is controlled by higher centers of the brain (→ p. 332).

Neurotransmitters released at chemical **synapses** of nerve endings transmit signals to postsynaptic nerve fibers, muscles or glands (→ p. 50ff.). Some neuropeptides released by presynaptic neurons also exert their effects in neighboring synapses, resulting in a kind of "paracrine" action.

Neurons can also secrete hormones, e.g., epinephrine, oxytocin and antidiuretic hormone. Some transmitter substances of the immune system, e.g. thymosin and various cytokines, also have endocrine effects.

A. Regulation of autonomic nervous system functions (overview)



Hormones are messenger substances that convey information signals relevant to cell function (→ p. 268). **Endocrine hormones**, i.e., those transported in the bloodstream, are produced in *endocrine glands* such as the hypothalamus, thyroid, parathyroid glands, adrenal medulla, pancreatic islets, ovaries and testes. They are also synthesized in diffusely scattered *endocrine cells* of the CNS, in C cells of the thyroid, and in the thymus, atria, kidneys, liver, gastrointestinal tract, etc. **Paracrine hormones**, i.e., those that affect nearby cells only (tissue hormones or *mediators*; see below) are secreted by cells widely distributed throughout the body.

Types of hormone.

1. **Peptide hormones** (→ **A**, dark blue areas) and **glycoprotein hormones** (→ **A**, light blue areas) are hydrophilic hormones stored in *secretory granules* and released by exocytosis as required. Multiple hormones can be produced from a single gene (→ e.g., POMC gene, p. 282) by variable splicing and posttranslational modification (→ p. 8 ff.) .

2. **Steroid hormones** (→ **A**, yellow areas) and **calcitriol** are chemically related lipophilic hormones metabolized from *cholesterol* (→ pp. 294, 296). They are not stored, but are synthesized as needed.

3. **Tyrosine derivatives** (→ **A**, orange areas) include (a) the *hydrophilic catecholamines* dopamine, epinephrine and norepinephrine (→ p. 84) and (b) *lipophilic thyroid hormones* (T_3, T_4; → p. 288).

The **lipophilic hormones** in (2) and (3b) are **transported** in the blood while bound to plasma proteins. Corticosteroids are carried bound to globulin and albumin, testosterone and estrogen to sex hormone-binding globulin and T_3 and T_4 to albumin and two other plasma proteins (→ p. 286).

Hormone receptors. The receptors (docking sites) for glycoprotein hormones, peptide hormones and catecholamines are transmembrane proteins (→ p. 14) that bind to their specific hormone on the outer cell surface. Many of these hormones induce the release of intracellular **second messengers** that transmit the hormone signal inside the cell. cAMP, cGMP, IP_3, DAG, Ca^{2+} and NO function as second messengers (and sometimes as third messengers; → p. 276ff.). Some peptide hormones like insulin, prolactin, atriopeptin and numerous growth factors bind to cell surface receptors with cytosolic domains with *enzymatic activity* (→ p. 280). Steroid hormones, on the other hand, enter the cells themselves (→ p. 280). Once they bind to *cytosolic receptor proteins*, steroid hormones (as well as calcitriol, T_3 and T_4) are transported to the cell nucleus, where they influence transcription (genomic action). A target cell can have different receptors for different hormones (e.g., insulin and glucagon) or different receptors for a single hormone (e.g., α_1 and β_2 adrenoceptors for epinephrine).

Hierarchy of hormones (→ **A**). The secretion of hormones is often triggered by neural impulses from the CNS. The *hypothalamus* is the main neurohormonal control center (→ p. 282 and 332). Hypothalamic neurons extend to the posterior pituitary (neurohypophysis). The hormones are secreted either by the hypothalamus itself or by the posterior pituitary. Hypothalamic hormones also control hormone release from the *anterior pituitary* (adenohypophysis). Anterior pituitary *glandotropic hormones* control *peripheral endocrine glands* (→ **A top**, green areas), which release the end-hormone (→ **A**). The original signal can be *amplified* or *modulated* at these relay sites (→ p. 274).

Pituitary hormones. Hypothalamic hormones control *anterior pituitary* hormone secretion by either stimulating or inhibiting hormone production. They are therefore called *releasing hormones (RH)* or *release-inhibiting hormones (IH)*, resp. (→ **A** and table). Most anterior pituitary hormones are glandotropic (→ p. 282). The *posterior pituitary* hormones are released by neuronal signals and are mainly aglandotropic (→ p. 282).

Other **endocrine hormones** are secreted largely independent of the hypothalamic–pituitary axis, e.g., *pancreatic hormones*, *parathyroid hormone (PTH)*, *calcitonin* and *calcitriol*, *angiotensin II*, *aldosterone* (→ p. 184ff.), *erythropoietin* (→ p. 88) and *gastrointestinal hormones* (→ p. 236). *Atriopeptin* is secreted from the heart atrium in response to stretch stimuli (→ p. 170), whereas the release of *melatonin* is subject to afferent neuron control (→ p. 336).

Some of these hormones (e.g., angiotensin II) and *tissue hormones* or **mediators** exert *paracrine effects* within endocrine and exocrine glands, the stomach wall, other organs, and on inflammatory processes. Bradykinin (→ pp. 216 and 238), histamine (→ pp. 100 and 244), serotonin (5-hydroxytryptamine, → p. 102) and eicosanoids are members of this group.

Eicosanoids. Prostaglandins (PG), thromboxane (TX), leukotrienes and epoxyeicosatrienoates are eicosanoids (Greek εικοσι = twenty [C atoms]) derived in humans from the fatty acid **arachidonic acid (AA)**. (Prostaglandins derived from AA have the index number 2). AA occurs as an ester in the phospholipid layer of the cell membranes and is obtained from dietary sources (meat), synthesized from linoleic acid, an essential fatty acid, and released by diacylglycerol lipase (→ p. 278).

Pathways of **eicosanoid synthesis** from arachidonic acid (AA):
1. *Cyclooxygenase pathway:* Cyclooxygenase (COX)-1 and COX-2 convert AA into PGG_2, which gives rise to PGH_2, the primary substance of the biologically active compounds PGE_2, PGD_2, $PGF_{2\alpha}$, PGI_2 (prostacyclin) and TXA_2. COX-1 and 2 are inhibited by nonsteroidal anti-inflammatory drugs (e.g., Aspirin®).
2. *Lipoxygenase pathway*: Leukotriene A_4 is synthesized from AA (via the intermediate 5-HPETE = 5-hydroperoxyeicosatetraenoate) by way of 5-lipoxygenase (especially in neutrophilic granulocytes). Leukotriene A_4 is the parent substance of the leukotrienes C_4, D_4 and E_4. The significance of 12-lipoxygenase (especially in thrombocytes) is not yet clear, but *15-lipoxygenase* is known to produce vasoactive *lipoxins* (LXA_4, LXB_4).
3. *Cytochrome P450-epoxygenase* produces epoxyeicosatrienoates (EpETrE = EE).

Typical **effects of eicosanoids:**


PGE_2 dilates the bronchial and vascular musculature (and keeps the lumen of the fetal ductus arteriosus and foramen ovale open; → p. 222), stimulates intestinal and uterine contractions, protects the gastric mucosa (→ p. 244), inhibits lipolysis, increases the glomerular filtration rate (GFR), plays a role in fever development (→ p. 226), sensitizes nociceptive nerve endings (pain) and increases the permeability of blood vessels (inflammation). **PGD_2** induces bronchoconstriction. **PGI_2** (**prostacyclin**) synthesized in the endothelium, is vasodilatory and inhibits platelet aggregation. **TXA_2**, on the other hand, occurs in platelets, promotes platelet aggregation and acts as a vasoconstrictor (→ p. 102). **11,12-EpETrE** has a vasodilatory effect (= EDHF, → p. 216).


Hormones (h.) of the hypothalamus and pituitary

Name*	Abbreviation/synonyme
Hypothalamus	
The suffix "-liberin" denotes releasing h. (RH) or factor (RF); "-statin" is used for release-inhibiting h. (IH) or factors (IF)	
Corticoliberin	Corticotropin RH, CRH, CRF
Gonadoliberin	Gonadotropin RH, Gn-RH; ICSH
Prolactostatin	Prolactin IH, PIH, PIF, dopamine
Somatoliberin	Somatotropin RH, SRH, SRF, GHRH, GRH
Somatostatin**	Somatotropin (growth h.) IH, SIH
Thyroliberin	Thyrotropin RH, TRH, TRF
Anterior lobe of the pituitary	
Corticotropin	Adrenocorticotropic h. (ACTH)
Follitropin	Follicle-stimulating h. (FSH)
Lutropin	Luteinizing h. (LH), interstitial cell-stimulating h. (ICSH)
Melanotropin	α-Melanocyte-stimulating h. (α-MSH), α-melanocortin
Somatotropin	Somatotropic h. (STH), growth h. (GH)
Thyrotropin	Thyroid stimulating h. (TSH)
Prolactin	PRL, lactogenic (mammotropic) h.
Posterior lobe of the pituitary	
Oxytocin	–
Adiuretin	Anti-diuretic h. ADH, (arginine-) vasopressin (AVP)

* Names generally recommended by IUPAC-IUB Committee on Biochemical Nomenclature.
** Also synthesized in gastrointestinal organs, etc.

A. The hormones (simplified overview excluding tissue hormones)




End-hormone
Functions (simplified)
Testosterone
Estrogens
Gestagens (progesterone)
Thyroxin (T_4)
↓ Deiodinization
Triiodothyronine (T_3)
Somatomedins (IGF)
Angiotensin II
Mineralocorticoids
Glucocorticoids
Androgens
Epinephrine (norepinephrine)
Erythropoietin
Calcitriol
Somatostatin (SIH)
Glucagon
Insulin
Antagonistic
Parathyroid hormone
Calcitonin (CT)
Antagonistic
Maturation
Reproduction
Metabolism
Circulation, blood
Water and mineral balance
Per-mis-sive
and others

Hormones and other humoral signals function to provide **feedback control**, a mechanism in which the response to a signal feeds back on the signal generator (e.g., endocrine gland). The speed at which control measures are implemented depends on the rate at which the signal substance is broken down—the quicker the degradation process, the faster and more flexible the control.

In **negative feedback control**, the response to a feedback signal opposes the original signal. In the example shown in **A1**, a rise in plasma cortisol in response to the release of corticoliberin (corticotropin-releasing hormone, CRH) from the hypothalamus leads to down-regulation of the signal cascade "CRH ⇒ ACTH ⇒ adrenal cortex," resulting in a decrease in cortisol secretion. In shorter feedback loops, ACTH can also negatively feed back on the hypothalamus (→ **A2**), and cortisol, the *end-hormone*, can negatively feed back on the anterior pituitary (→ **A3**). In some cases, the *metabolic parameter* regulated by a hormone (e.g., plasma glucose concentration) rather then the hormone itself represents the feedback signal. In the example (→ **B**), glucagon increases blood glucose levels (while insulin decreases them), which in turn inhibits the secretion of glucagon (and stimulates that of insulin). *Neuronal signals* can also serve as feedback (*neuroendocrine feedback*) used, for example, to regulate plasma osmolality (→ p. 170).

In **positive feedback control**, the response to the feedback amplifies the original signal and heightens the overall response (e.g., in *autocrine regulation*; see below).

The higher hormone not only controls the synthesis and excretion of the end-hormone, but also controls the **growth of peripheral endocrine gland**. If, for example, the end-hormone concentration in the blood is too low despite maximum synthesis and secretion of the existing endocrine cells, the gland will enlarge to increase end-hormone production. This type of **compensatory hypertrophy** is observed for instance in goiter development (→ p. 290) and can also occur after surgical excision of part of the gland.

Therapeutic administration of a hormone (e.g., cortisone, a cortisol substitute) have a similar effect on higher hormone secretion (ACTH and CRH in the example) as that of the end-hormone (cortisol in the example) normally secreted by the peripheral gland (adrenal cortex in this case). *Long-term* administration of an end-hormone would therefore lead to inhibition and atrophy of the endocrine gland or cells that normally produce that hormone. This is known as **compensatory atrophy**.

A **rebound effect** can occur if secretion of the higher hormone (e.g., ACTH) is temporarily elevated after discontinuation of end-hormone administration.


The **principal functions** of *endocrine hormones, paracrine hormones* and other humoral transmitter substances are to control and regulate:

- *enzyme activity* by altering the conformation (*allosterism*) or inhibiting/stimulating the synthesis of the enzyme (induction);
- *transport processes*, e.g., by changing the rate of insertion and synthesis of ion channels/carriers or by changing their opening probability or affinity;
- *growth* (see above), i.e., increasing the rate of mitosis (*proliferation*), "programmed cell death" (*apoptosis*) or through cell differentiation or dedifferentiation;
- *secretion of other hormones*. Regulation can occur via endocrine pathways (e.g., ACTH-mediated cortisol secretion; → **A5**), a short portal vein-like circuit within the organ (e.g., effect of CRH on ACTH secretion, → **A4**), or the effect of cortisol from the adrenal cortex on the synthesis of epinephrine in the adrenal medulla, (→ **A6**), or via paracrine pathways (e.g., the effect of somatostatin, SIH, on the secretion of insulin and glucagon; → **B**).


Cells that have receptors for their own humoral signals transmit **autocrine signals** that function to

- exert *negative feedback control* on a target cell, e.g., to discontinue secretion of a transmitter (e.g., norepinephrine; → p. 84);
- *coordinate* cells of the same type (e.g., in growth);
- exert *positive feedback control* on the secreting cell or to cells of the same type. These mechanisms serve to amplify weak signals as is observed in the eicosanoid secretion or in T cell monoclonal expansion (→ p. 96ff.).

A. Regulation of cortisol and epinephrine concentrations in plasma



B. Control of blood glucose



Hormones, neurotransmitters (→ p. 55 and p. 82), cytokines and chemokines (→ p. 94ff.) act as *messenger substances* (**first messengers**) that are transported to their respective target cells by extracellular pathways. The target cell has a high-affinity binding site (**receptor**) for its *specific* messenger substance.

Glycoprotein and peptide messengers as well as **catecholamines** bind to cell surface receptors on the target cell. *Binding of the messenger to its receptor* (with certain exceptions, e.g. insulin and prolactin; → p. 280) triggers certain protein-protein interactions (and sometimes protein-phospholipid interactions). This leads to the release of secondary messenger substances (**second messengers**) that forward the signal within the cell. Cyclic adenosine monophosphate (cAMP), cyclic guanosine monophosphate (cGMP), inositol 1,4,5-trisphosphate (IP_3), 1,2-diacylglycerol (DAG) and Ca^{2+} are such second messengers. Since the molecular structure of the receptor ensures that the effect of the first messenger will be specific, multiple first messengers can use the same second messenger. Moreover, the intracellular concentration of the second messenger can be raised by one messenger and lowered by another. In many cases, different types of receptors exist for a single first messenger.

cAMP as a Second Messenger

For a cAMP-mediated response to occur, the cell membrane must contain stimulatory (G_s) or inhibitory (G_i) **G proteins** (guanyl nucleotide-binding proteins) (→ **A1**). These G proteins consist of three subunits—alpha (α_S or α_i), beta (β) and gamma (γ)—and are therefore *heterotrimers*. Guanosine diphosphate (GDP) is bound to the α-subunit of an inactive G protein. Once the first **messenger (M)** binds to the **receptor (Rec.)**, the M–Rec. complex conjugates with the G_s-GDP (or G_i-GDP) molecule (→ **A2**). GDP is then replaced by cytosolic GTP, and the $\beta\gamma$-subunit and the M–Rec. complex dissociate from the α-subunit if Mg^{2+} is present (→ **A3**). α_s-GTP or α_i-GTP remain as the final products. **Adenylate cyclase** on the inside of the cell membrane is activated by α_s-GTP (cytosolic *cAMP concentration rises*) and inhibited by α_i-GTP (*cAMP concentration falls*; → **A3**).


G_s-activating messengers. ACTH, adenosine (A_{2A} and A_{2B} rec.), antidiuretic hormone = vasopressin (V_2 rec.), epinephrine and norepinephrine (β_1, β_2, β_3 adrenoceptors), calcitonin, CGRP, CRH, dopamine (D_1 and D_5 rec.), FSH, glucagon, histamine (H_2 rec.), oxytocin (V_2 rec., see above), many prostaglandins (DP, IP, EP_2 and EP_4 rec.), serotonin = 5-hydroxytryptamine (5-HT_4 and 5-HT_7 rec), secretin and VIP activate G_s proteins, thereby **raising cAMP levels**. TRH and TSH induce partial activation.

G_i-activating messengers. Some of the above messenger substances also activate G_i proteins (thereby **lowering cAMP levels**) using a different binding receptor. Acetylcholine (M_2 and M_4 rec.), adenosine (A_1 and A_3 rec.), epinephrine and norepinephrine (α_2 adrenoceptors), angiotensin II, chemokines, dopamine (D_2, D_3 and D_4 rec.), GABA ($GABA_B$ rec.), glutamate ($mGLU_{2-4}$ and $mGLU_{6-8}$ rec.), melatonin, neuropeptide Y, opioids, serotonin = 5-hydroxytryptamine (5-HT_1 rec.), somatostatin and various other substances activate G_i proteins.

Effects of cAMP. cAMP activates type A protein kinases (**PKA = protein kinase A**) which then activate other proteins (usually enzymes and membrane proteins, but sometimes the receptor itself) by **phosphorylation** (→ **A4**). The specific response of the cell depends on the type of protein phosphorylated, which is determined by the type of protein kinases present in the target cell. Phosphorylation converts the proteins from an inactive to an active form or vice versa.

Hepatic glycogenolysis, for instance, is dually increased by cAMP and PKA. Glycogen synthase catalyzing glycogen synthesis is inactivated by phosphorylation whereas glycogen phosphorylase stimulating glycogenolysis is activated by cAMP-mediated phosphorylation.

Signal transduction comprises the entire signaling pathway from the time the first messenger binds to the cell to the occurrence of cellular effect, during which time the signal can be (a) *modified* by other signals and (b) *amplified* by many powers of ten. A single adenylate cyclase molecule can produce numerous cAMP and PKA molecules, which in turn can phosphorylate an enormous number of enzyme molecules. The interposition of more kinases can lead to the formation of long kinase cascades that additionally amplify the original signal while receiving further regulatory signals. ▶


A. cAMP as second messenger
Extracellular space
First messenger
Stimulatory messenger
e.g., epinephrine (β adrenoceptors)
Messenger (M) binds to receptor (R)
Inhibitory messenger
e.g., epinephrine (α2 adrenoceptor)
Cell membrane
1
GDP
Gs protein
Adenylate cyclase
Gi protein
Intracellular space
M-R complex binds to G protein
2
α-GTP influences adenylate cyclase
3
Mg2+
GTP
Stimulates
Inhibits
Deactivation:
Ms level decreases
Mi level decreases
cAMP
Return to inactive state
5
GTPase splits to form GDP
ATP
Second messenger
cAMP
Phospho-diesterase
5'-AMP
Degradation of cAMP
Protein kinase A
Activates
Phosphatases
6
Proteins
Phosphorylation
PO4
ADP
Protein
Cell response
4

▶ **Deactivation of the signaling cascade** (→ **A**, **right** panel) is induced by the α-subunit in that its GTP molecule splits off GDP and P_i after reacting with its *GTPase* (→ **A5**), and the subunit subsequently binds to the βγ subunits to again form the trimeric G protein. *Phosphodiesterase* also converts cAMP into inactive 5′-AMP (→ **A4, A6**), and *phosphatases* dephosphorylate the protein previously phosphorylated by protein kinase A (→ **A4**). Another way to inactivate a receptor in the presence of high messenger concentrations is to make the receptor insensitive by phosphorylating it (*desensitization*).

Cholera toxin inhibits the GTPase, thereby blocking its deactivating effect on adenylate cyclase (→ **A5**). This results in extremely high levels of intracellular cAMP. When occurring in intestinal cells, this can lead to severe diarrhea (→ p. 264). **Pertussis** (whooping cough) **toxin** and **forskolin** also lead to an increase in the cytosolic cAMP concentration. Pertussis toxin does this by inhibiting G_i protein and thereby blocking its inhibitory effect on adenylate cyclase, while forskolin directly activates adenylate cyclase. **Theophylline** and **caffeine** inhibit the conversion of cAMP to 5′-AMP, which extends the life span of cAMP and prolongs the effect of the messenger.

Certain **ion channels** are regulated by G_s, G_i and other G proteins (**G_o**) with or without the aid of adenylate cyclase. Some Ca^{2+} channels are activated by G_s proteins and inactivated by G_o proteins, whereas some K^+ channels are activated by G_o proteins and (the βγ subunits of) G_i proteins (→ p. 83 B). **G_{olf}** in olfactory receptors, **transducin** in retinal rods (→ p. 354ff.), and **α-gustducin** in gustatory sensors are also members of the G protein family (→ p. 344).

IP_3 and DAG as Second Messengers

As in the case of G_s proteins, once the first messenger using this transduction pathway binds to its receptor outside the cell, the α_q subunit dissociates from the heterotrimeric **G_q protein** and activates phospholipase C-β (**PLC-β**) on the inside of the cell membrane (→ **B1**). PLC-β converts phosphatidylinositol 4,5-bisphosphate (*PIP_2*), to **inositol 1,4,5-trisphosphate** (**IP_3**) and **diacylglycerol** (**DAG**). IP_3 and DAG function as parallel second messengers with different actions that are exerted either independently or jointly (→ **B1**).

IP_3 is a hydrophilic molecule carried via the cytosol to Ca^{2+} stores within the cell (mainly in the endoplasmic reticulum; → p. 36). IP_3 binds there to Ca^{2+} channels to open them (→ **B2**), leading to an efflux of Ca^{2+} from the intracellular stores into the cytosol. In the cytosol, Ca^{2+} acts as a *third messenger* that regulates various cell functions, e.g., by interacting with the cAMP signaling chain. Many Ca^{2+}-related activities are mediated by *calmodulin*, a calcium-binding protein (→ pp. 36 and 70).

DAG is a lipophilic molecule that remains in the cell membrane and has two main functions:


- DAG is broken down by diacylglycerol lipase to yield *arachidonic acid*, a precursor of eicosanoids (→ **B3** and p. 271).
- DAG activates *protein kinase C* (**PKC**). PKC is Ca^{2+}-dependent (hence the "C") because the Ca^{2+} released by IP_3 (see above) is needed to transfer PKC from the cytosol to the intracellular side of the cell membrane (→ **B4**). Thus activated PKC phosphorylates the serine or threonine residues of many proteins.

PKC triggers a series of other phosphorylation reactions (high signal amplification) that ultimately lead to the phosphorylation of **MAP kinase** (mitogen-activated protein kinase). It enters the cell nucleus and activates *Elk-1*, a gene-regulating protein. *NF-κB*, another gene-regulating protein, is also released in response to PKC phosphorylation. In addition, PKC activates *Na^+/H^+ antiporters*, thereby raising the **cellular pH**—a stimulus that triggers many other cellular reactions.


IP_3 and DAG activating messengers include acetylcholine (M_1 and M_3 cholinoceptors), antidiuretic hormone = vasopressin (V_1 rec.), epinephrine and norepinephrine (α_1 adrenoceptor), bradykinin, CCK, endothelin, gastrin, glutamate ($mGLU_1$ and $mGLU_5$ rec.), GRP, histamine (H_1 rec.), leukotrienes, neurotensin, oxytocin and various prostaglandins (FP, TP, and EP_1 rec.), serotonin = 5-hydroxytryptamine ($5\text{-}HT_2$ rec.), tachykinin, thromboxane A_2. TRH and TSH induce partial activation.

Deactivation of the signaling cascade can also be achieved through *self-inactivation* of the G proteins involved (GTP cleavage) and phosphatase (see above) as well as by degradation of IP_3. ▶

B. Diacylglycerol (DAG) and inositol 1,4,5-trisphosphate (IP_3) as second messengers



C. Tyrosine kinase receptors



▶ **Enzyme-Linked Cell Surface Receptors For Messenger Substances**

These (G protein-independent) receptors, together with their cytosolic domains, act as enzymes that are activated when a messenger binds to the receptor's extracellular domain. There are five classes of these receptors:

1. Receptor guanylyl cyclases convert GTP into the second messenger cGMP, which activates protein kinase G (PKG; see below). The *atriopeptin receptor* belongs to this class.

2. Receptor tyrosine kinases (→ **C**), phosphorylate proteins (of same or different type) at the OH group of their tyrosyl residues. The receptors for *insulin* and various *growth factors* (GF) such as e.g., E[epidermal]GF, PDGF, N[nerve]GF, F[fibroblast]GF, H[hepatocyte]GF, and I[insulin-like]GF-1 belong to this class of receptors.

Signals regarding first messenger binding (e.g., EGF and PDGF) are often transferred inside the cell via binding of two receptors (**dimerization**; **C1a** ⇒ **C1b**) and subsequent mutual phosphorylation of their cytosolic domain (**autophosphorylation**, → **C1b**). The receptor for certain hormones, like *insulin* and *IGF-1*, is from the beginning a heterotetramer ($\alpha_2\beta_2$) that undergoes autophosphorylation before phosphorylating another protein (*insulin receptor substrate-1*, *IRS-1*) that in turn activates intracellular target proteins containing SH2 domains (→ **C2**).

3. Receptor serine/threonine kinases, which like the *TGF-β receptor*, function similar to kinases in Group 2, the only difference being that they phosphorylate serine or threonine residues of the target protein instead of tyrosine residues (as with PKC; see above).

4. Tyrosine kinase-associated receptors are those where the receptor works in combination with non-receptor tyrosine kinases (chiefly proteins of the Src family) that phosphorylate the target protein. The receptors for *STH*, *prolactin*, *erythropoietin* and numerous *cytokines* belong to this group.

5. Receptor tyrosine phosphatases remove phosphate groups from tyrosine residues. The CD45 receptor involved in T cell activation belongs to this group.

Hormones with Intracellular Receptors

Steroid hormones (→ p. 272 ff., yellow areas), calcitriol and thyroid hormones are like other hormones in that they induce a *specific cell response* with the difference being that they activate a different type of signaling cascade in the cell. They are *lipid-soluble* substances that freely penetrate the cell membrane.

Steroid hormones bind to their respective *cytoplasmic receptor protein* in the target cell (→ **D**). This binding leads to the dissociation of inhibitory proteins (e.g., heat shock protein, HSP) from the receptors. The *hormone–receptor protein complex* (H–R complex) then migrates to the cell nucleus (*translocation*), where it activates (**induces**) or inhibits the transcription of certain genes. The resulting increase or decrease in synthesis of the respective protein (e.g., AIPs; → p. 184) is responsible for the actual cell response (→ **D**).

Triiodothyronine (T_3; → p. 288ff.) and **calcitriol** (→ p. 294) bind to their respective receptor proteins in the cell nucleus (*nuclear receptors*). These receptors are *hormone-activated transcription factors*. Those of calcitriol can induce the transcription of calcium-binding protein, which plays an important role in interstitial Ca^{2+} absorption (→ p. 264).


Recent research indicates that steroid hormones and calcitriol also regulate cell function by **non-genomic control mechanisms**.

Nitric Oxide as a Transmitter Substance


In nitrogenergic neurons and endothelial tissues, **nitric (mon)oxide (NO)** is released by Ca^{2+}/calmodulin-mediated activation of neuronal or endothelial **nitric oxide synthase (NOS)** (→ **E**). Although NO has a half-life of only a few seconds, it diffuses into neighboring cells (e.g., from endothelium to vascular myocytes) so quickly that it activates **cytoplasmic guanylyl cyclase**, which converts GTP into **cGMP** (→ **E**). Acting as a second messenger, cGMP activates *protein kinase G* (**PKG**), which in turn decreases the cytosolic Ca^{2+} concentration $[Ca^{2+}]_i$ by blocking the nuclear IP_3 receptor (via IRAG) and other means. This leads to *vasodilatation* (e.g., in coronary arteries).

Penile erections are produced by cGMP-mediated vasodilatation of the deep arteries of the penis (→ p. 308). The erection can be prolonged by drugs that inhibit cGMP-specific phosphodiesterase type 5, thereby delaying the degradation of cGMP (e.g., sildenafil citrate = Viagra®).

D. Mode of action of steroid hormones



E. Nitric oxide (NO) as a transmitter substance



In the **hypothalamus**, (1) humoral signals from the periphery (e.g., from circulating cortisol) can be converted to efferent neuronal signals, and (2) afferent neuronal signals can be converted to endocrine messengers (*neurosecretion*).

The first case is possible because the hypothalamus is situated near **circumventricular organs** like the organum vasculosum laminae terminalis (OVLT), subfornical organ, the median eminence of the hypothalamus, and the neurohypophysis. Since there is no blood-brain barrier there, hydrophilic peptide hormones can also enter.

The hypothalamus is closely connected to other parts of the CNS (→ p. 332). It controls many autonomous regulatory functions and its neuropeptides influence higher brain functions. The hypothalamus is related to the sleeping-waking rhythm (→ p. 336) and to psychogenic factors. Stress, for example, stimulates the release of cortisol (via CRH, ACTH) and can lead to the cessation of hormone-controlled menstruation (amenorrhea).

Neurosecretion. Hypothalamic neurons synthesize hormones, incorporate them in granules that are transported to the ends of the axons (*axoplasmic transport* → p. 42), and secrete them into the *bloodstream*. In this way, oxytocin and ADH are carried from magnocellular hypothalamic nuclei to the neurohypophysis, and RHs and IHs (and ADH) reach the *median eminence* of the hypothalamus (→ **A**). The *action potential-triggered* exocytotic release of the hormones into the bloodstream is mediated by Ca^{2+} influx into the nerve endings (→ p. 50ff.).

Oxytocin (Ocytocin) and **antidiuretic hormone** (ADH) are two posterior pituitary hormones that enter the systemic circulation directly. **ADH** induces water retention in the renal collecting ducts (V_2-rec.; → p. 166) and induces vasoconstriction (endothelial V_1 rec.) by stimulating the secretion of endothelin-1 (→ p. 214ff.). ADH-bearing neurons also secrete ADH into the portal venous circulation (see below). The ADH and CRH molecules regulate the secretion of ACTH by the adenohypophysis. **Oxytocin** promotes uterine contractions and milk ejection (→ p. 306). In nursing mothers, suckling stimulates nerve endings in the nipples, triggering the secretion of oxytocin (and prolactin, → p. 305) via neurohumoral reflexes.


Releasing hormones (RH) or **liberins** that stimulate hormone release from the adenohypophysis (Gn-RH, TRH, SRH, CRH; → p. 272 ff.) are secreted by hypothalamic neurons into a kind of **portal venous system** and travel only a short distance to the anterior lobe (→ **A**). Once in its vascular network, they trigger the release of anterior pituitary hormones into the systemic circulation (→ **A**).

Some anterior pituitary hormones are regulated by release-**inhibiting hormones (IH)** or **statins**, such as SIH and PIH = dopamine (→ p. 272ff.). Peripheral hormones, ADH (see above) and various neurotransmitters such as neuropeptide Y (NPY), norepinephrine (NE), dopamine, VIP and opioids also help to regulate anterior pituitary functions (→ p. 274).

The four **glandotropic hormones** (ACTH, TSH, FSH and LH) and the **aglandotropic hormones** (prolactin and GH) are secreted from the anterior pituitary (→ **A**). The secretion of **growth hormone (GH** = somatotropic hormone, STH) is subject to control by GH-RH, SIH and IGF-1. GH stimulates protein synthesis (*anabolic action*) and skeletal growth with the aid of *somatomedins* (growth factors formed in the liver), which play a role in sulfate uptake by cartilage. Somatomedin C = insulin-like growth factor-1 (IGF-1) inhibits the release of GH by the anterior pituitary via negative feedback control. GH has lipolytic and glycogenolytic actions that are independent of somatomedin activity.

Proopiomelanocortin (POMC) is a peptide precursor not only of ACTH, but (inside or outside the anterior pituitary) also of β-endorphin and α-melanocyte-stimulating hormone (α-MSH = α-melanocortin). β-endorphin has analgesic effects in the CNS and immunomodulatory effects, while α-MSH in the hypothalamus helps to regulate the body weight (→ p. 232) and stimulates peripheral melanocytes.

A. Hypothalamic–pituitary hormone secretion (schematic)



Glucose is the *central energy carrier* of the human metabolism. The brain and red blood cells are fully glucose-dependent. The **plasma glucose concentration** (blood sugar level) is determined by the level of glucose *production* and *consumption*.

The following terms are important for proper understanding of carbohydrate metabolism (→ **A, C**):

1. Glycolysis generally refers to the anaerobic conversion of glucose to lactate (→ p. 72). This occurs in the red blood cells, renal medulla, and skeletal muscles (→ p. 72). Aerobic oxidation of glucose occurs in the CNS, heart, skeletal muscle and in most other organs.

2. Glycogenesis, i.e., the synthesis of glycogen from glucose (in liver and muscle), facilitates the storage of glucose and helps to maintain a constant plasma glucose concentration. Glycogen stored in a muscle can only be used by that muscle.

3. Glycogenolysis is the breakdown of glycogen to glucose, i.e., the opposite of glycogenesis.

4. Gluconeogenesis is the production of glucose (in liver and renal cortex) from non-sugar molecules such as amino acids (e.g., glutamine), lactate (produced by anaerobic glycolysis in muscles and red cells), and glycerol (from lipolysis).

5. Lipolysis is the breakdown of triacylglycerols into glycerol and free fatty acids.

6. Lipogenesis is the synthesis of triacylglycerols (for storage in fat depots).

Islets of Langerhans in the *pancreas* play a primary role in carbohydrate metabolism. Three cell types (A, B, D) have been identified so far (→ p. 275 B). 25% of all islet cells are type A (α) cells that produce **glucagon**, 60% are B (β) cells that synthesize **insulin**, and 10% are D (δ) cells that secrete somatostatin (**SIH**). These hormones mutually influence the synthesis and secretion of each other (→ p. 275 B). Islet cells in the pancreas head synthesize *pancreatic polypeptide*, the physiological function of which is not yet clear. High concentrations of these hormones reach the liver by way of the portal venous circulation.

Function. Pancreatic hormones (1) ensure that ingested food is stored as glycogen and fat (insulin); (2) mobilize energy reserves in response to food deprivation, physical activity or stress (glucagon and the non-pancreatic hormone epinephrine); (3) maintain the plasma glucose concentration as constant as possible (→ **A**); and (4) promote growth.

Insulin


Synthesis. Insulin is a 6 kDa peptide (51 amino acids, AA) formed by the C chain cleaved from *proinsulin* (84 AA), the precursor of which is *preproinsulin*, a preprohormone. Insulin contains two peptide chains (A and B) held together by disulfide bridges **Degradation**: Insulin has a half-life of about 5–8 min and is degraded mainly in liver and kidneys.

Secretion. Insulin is secreted in pulsatile bursts, mainly in response to *increases in the blood levels of glucose* (→ **B right**), as follows: plasma glucose ↑ → glucose in B cells ↑ → glucose oxidation ↑ → cytosolic ATP ↑ → closure of ATP-gated K^+ channels → depolarization → opening of voltage-gated Ca^{2+} channels → cytosolic Ca^{2+} ↑. The rising Ca^{2+} in B cells leads to (a) *exocytosis* of insulin and (b) re-opening of K^+ channels (deactivated by feedback control). **Stimulation.** Insulin secretion is stimulated mainly during food digestion via acetylcholine (vagus nerve), gastrin, secretin, GIP (→ p. 236) and GLP-1 (glucagon-like peptide = enteroglucagon), a peptide that dissociates from intestinal proglucagon. Certain amino acids (especially arginine and leucine), free fatty acids, many pituitary hormones and some steroid hormones also increase insulin secretion. **Inhibition.** Epinephrine and norepinephrine (α_2-*adrenoceptors*; → **A, B**), *SIH* (→ p. 275 B) and the neuropeptide *galanin* inhibit insulin secretion. When *hypoglycemia* occurs due, e.g., to fasting or prolonged physical exercise, the low blood glucose concentration is sensed by central chemosensors for glucose, leading to reflex activation of the sympathetic nervous system.

The **insulin receptor** is a heterotetramer ($\alpha_2\beta_2$) consisting of two extracellular α subunits and two transmembranous β subunits. The α subunits bind the hormone. Once the β subunits are autophosphorylated, they act as *receptor tyrosine kinases* that phosphorylate *insulin receptor substrate*-1 (IRS-1). Intracellular proteins with SH2 domains are phosphorylated by IRS-1 and pass on the signal (→ p. 279 C3).

Action of insulin (→ **A, B, C**). Insulin has *anabolic* and *lipogenic* effects, and promotes the *storage of glucose*, especially in the liver, where it activates enzymes that *promote glycolysis* and *glycogenesis* and *suppresses* those involved in *gluconeogenesis*. Insulin also *increases the number of GLUT-4* uniporters in skeletal myo- ▶

A. Glucose metabolism (simplified overview)



▶ cytes. All these actions serve to **lower the plasma glucose concentration** (which increases after food ingestion). About two-thirds of the glucose absorbed by the intestines after a meal (postprandial) is temporarily stored and kept ready for mobilization (via glucagon) during the interdigestive phase. This provides a relatively constant supply of glucose for the glucose-dependent CNS and vital organs in absence of food ingestion. Insulin increases the *storage of amino acids* (AA) in the form of proteins, especially in the skeletal muscles (*anabolism*). In addition, it promotes growth, *inhibits extrahepatic lipolysis* (→ p. 259, D) and affects K^+ *distribution* (→ p. 182).

Hypoglycemia develops when the insulin concentration is too high. Glucose levels of < 2 mmol/L (35 mg/dL) produce glucose deficiencies in the brain, which can lead to coma and *hypoglycemic shock*.

The **excessive intake of carbohydrates** can overload glycogen stores. The liver therefore starts to convert glucose into fatty acids, which are transported to and stored in fatty tissues in the form of *triacylglycerols* (→ p. 259 D).

Diabetes mellitus (DM). One type of DM is *insulin-dependent diabetes mellitus* **(IDDM),** or type 1 DM, which is caused by an insulin deficiency. Another type is *non-insulin-dependent DM* **(NIDDM)**, or type 2 DM, which is caused by the decreased efficacy of insulin and sometimes occurs even in conjunction with increased insulin concentrations. DM is characterized by an abnormally high plasma glucose concentration (*hyperglycemia*), which leads to *glucosuria* (→ p. 158). Large quantities of *fatty acids* are liberated since lipolysis is no longer inhibited (→ p. 257 D). The fatty acids can be used to produce energy via acetylcoenzyme A (acetyl-CoA); however, this leads to the formation of acetoacetic acid, acetone (*ketosis*), and β-oxybutyric acid (*metabolic acidosis*, → p. 142). Because hepatic fat synthesis is insulin-independent and since so many fatty acids are available, the liver begins to store triacylglycerols, resulting in the development of *fatty liver*.

Glucagon, Somatostatin and Somatotropin

Glucagon released from A (α) cells is a peptide hormone (29 AA) derived from *proglucagon* (glicentin). The granules in which glucagon is stored are secreted by exocytosis. Secretion is **stimulated** by amino acids (AA) from digested proteins (especially alanine and arginine) as well as by hypoglycemia (e.g., due to fasting, prolonged physical exercise; → **B**) and sympathetic impulses (via β_2 adrenoceptors; → **A**). Glucagon secretion is **inhibited** by glucose and SIH (→ p. 275, B) as well as by high plasma concentrations of free fatty acids.

The **actions** of glucagon (→ **A, B, C**) (via cAMP; → p. 276) mainly antagonize those of insulin. Glucagon maintains a normal *blood glucose level between meals* and during phases of increased glucose consumption to ensure a constant energy supply. It does this (a) by increasing glycogenolysis (in liver not muscle) and (b) by stimulating gluconeogenesis from lactate, AA (protein degradation = catabolism) and glycerol (from *lipolysis*).


Increased plasma concentrations of **amino acids (AA)** stimulate insulin secretion which would lead to hypoglycemia without the simultaneous ingestion of glucose. Hypoglycemia normally does not occur, however, since AA also stimulate the release of glucagon, which increases the blood glucose concentration. Glucagon also stimulates gluconeogenesis from AA, so some of the AA are used for energy production. In order to increase protein levels in patients, glucose must therefore be administered simultaneously with therapeutic doses of AA to prevent their metabolic degradation.

Somatostatin (SIH). Like insulin, SIH stored in D cells (**SIH 14** has 14 AA) is released in response to increased plasma concentrations of glucose and arginine (i.e., after a meal). Through *paracrine* pathways (via G_i-linked receptors), SIH inhibits the release of insulin (→ p. 275, B). Therefore, SIH inhibits not only the release of gastrin, which promotes digestion (→ p. 245, B3), but also interrupts the insulin-related storage of nutrients. SIH also inhibits glucagon secretion (→ p. 275 B). This effect does not occur in the presence of a glucose deficiency because of the release of catecholamines that *decrease* SIH secretion.

Somatotropin (STH) = growth hormone (GH). The short-term effects of GH are similar to those of insulin; its action is mediated by somatomedins (→ p. 282). In the long-term, GH increases the blood glucose concentration and promotes growth.

The effects of **glucocorticoids** on carbohydrate metabolism are illustrated on plate **C** and explained on p. 298.

B. Hormonal control of blood glucose concentration



C. Hormonal effects on carbohydrate and fat metabolism

Hormone **Function**	Insulin Satiated ← Buffer	Glucagon → Hungry	Epinephrine Stress, exercise	Cortisol Supply
Glucose				
Uptake by cell	+ Muscle, fat		+ Muscle	− Muscle, fat
Glycolysis	+	−	+	−
Gluconeogenesis (liver)	−	+	+	+
Glycogen				
Synthesis ⇄ Lysis	← Liver, muscle	→ Liver	→ Liver, muscle	← Liver
Fat				
Synthesis ⇄ Lysis	← Liver, fat	→ Fat	→ Fat	→ Fat

The thyroid gland contains spherical follicles (50–500 μm in diameter). Follicle cells synthesize the two iodine-containing thyroid hormones **thyroxine** (**T_4,** tetraiodothyronine) and **triiodothyronine** (**T_3**). T_3 and T_4 are bound to the glycoprotein *thyroglobulin* (→ **B2**) and stored in the colloid of the follicles (→ **A1, B1**). The synthesis and release of T_3/T_4 is controlled by the *thyroliberin* (= *thyrotropin-releasing hormone*, **TRH**)-*thyrotropin* (**TSH**) *axis* (→ **A**, and p. 272ff.). T_3 and T_4 influence physical growth, maturation and metabolism. The *parafollicular cells* (*C cells*) of the thyroid gland synthesize *calcitonin* (→ p. 294).

Thyroglobulin, a dimeric glycoprotein (660 kDa) is synthesized in the thyroid cells. TSH stimulates the transcription of the thyroglobulin gene. Thyroglobulin is stored in vesicles and released into the colloid by exocytosis (→ **B1** and p. 30).

Iodine uptake. The iodine needed for hormone synthesis is taken up from the bloodstream as iodide (I^-). It enters thyroid cells through secondary active transport by the $2Na^+$-I^- symport carrier (NIS) and is concentrated in the cell ca. 25 times as compared to the plasma (→ **B2**). Via cAMP, **TSH** increases the transport capacity of basolateral I^- uptake up to 250 times. Other anions competitively inhibit I^- uptake; e.g., ClO_4^-, SCN^- and NO_2^-.

Hormone synthesis. I^- ions are continuously transported from the intracellular *I^- pool* to the apical (colloidal) side of the cell by a I^-/Cl^- antiporter, called *pendrin*, which is stimulated by **TSH**. With the aid of *thyroid peroxidase* (TPO) and an H_2O_2 generator, they are oxidized to elementary I_2^0 along the microvilli on the colloid side of the cell membrane. With the help of TPO, the I^0 reacts with about 20 of the 144 tyrosyl residues of *thyroglobulin* (→ **C**). The phenol ring of the tyrosyl residue is thereby iodinated at the 3 and/or 5 position, yielding a protein chain containing either *diiodotyrosine (DIT)* residues and/or *monoiodotyrosine (MIT)* residues. These steps of synthesis are stimulated by TSH (via IP_3?) and inhibited by thiouracil, thiocyanate, glutathione, and other reducing substances. The structure of the thyroglobulin molecule allows the iodinated tyrosyl residues to react with each other in the thyrocolloid. The phenol ring of one DIT (or MIT) molecule links with another DIT molecule (ether bridges). The resulting thyroglobulin chain now contains *tetraiodothyronine residues* and (less) *triiodothyronine* residues (→ **C**). These are the *storage* form of T_4 and T_3.


TSH also stimulates **T_3 and T_4 secretion**. The iodinated thyroglobulin in thyrocolloid are reabsorbed by the cells via endocytosis (→ **B3, C**). The endosomes fuse with primary lysosomes to form phagolysosomes in which thyroglobulin is hydrolyzed by proteases. This leads to the release of T_3 and T_4 (ca. 0.2 and 1–3 mol per mol of thyroglobulin, respectively). T_3 and T_4 are then secreted into the bloodstream (→ **B3**). With the aid of *deiodase*, I^- meanwhile is split from concomitantly released MIT and DIT and becomes reavailable for synthesis.

Control of T_3/T_4 secretion. TSH secretion by the anterior pituitary is stimulated by **TRH**, a hypothalamic tripeptide (→ p. 282) and inhibited by **somatostatin (SIH)** (→ **A** and p. 272). The effect of TRH is modified by T_4 in the plasma. As observed with other target cells, the T_4 taken up by the thyrotropic cells of the anterior pituitary is converted to T_3 by *5′-deiodase*. T_3 reduces the density of TRH receptors in the pituitary gland and inhibits TRH secretion by the hypothalamus. The secretion of TSH and consequently of T_3 and T_4 therefore decreases (*negative feedback circuit*). In neonates, cold seems to stimulate the release of TRH via neuronal pathways (thermoregulation, → p. 226). **TSH** is a heterodimer (26 kDa) consisting of an α subunit (identical to that of LH and FSH) and a β subunit. *TSH controls all thyroid gland functions*, including the uptake of I^-, the synthesis and secretion of T_3 and T_4 (→ **A-C**), the blood flow and growth of the thyroid gland.


Goiter (struma) is characterized by diffuse or nodular enlargement of the thyroid gland. Diffuse goiter can occur due to an iodine deficiency, resulting in T_3/T_4 deficits that ultimately lead to increased secretion of TSH. Chronic elevation of TSH leads to the proliferation of follicle cells, resulting in goiter development (*hyperplastic goiter*). This prompts an increase in T_3/T_4 synthesis, which sometimes normalizes the plasma concentrations of T_3/T_4 (*euthyroid goiter*). This type of goiter often persists even after the iodide deficiency is rectified.

Hypothyroidism occurs when TSH-driven thyroid enlargement is no longer able to compensate for the T_3/T_4 deficiency (*hypothyroid goiter*). This type of ▶

A. Thyroid hormones (overview)



B. Hormone synthesis and secretion



goiter can also occur due to a congenital disturbance of T_3/T_4 synthesis (see below) or thyroid inflammation. **Hyperthyroidism** occurs when a thyroid tumor (*hot node*) or diffuse struma (e.g., in *Grave's disease*) results in the overproduction of T_3/T_4, independent of TSH. In the latter case, an autoantibody against the TSH receptor binds to the TSH receptor. Its effects mimic those of TSH, i.e., it stimulates T_3/T_4 synthesis and secretion.

T_3/T_4 transport. T_3 and T_4 occur at a ratio of 1 : 40 in the plasma, where > 99% of them (mainly T_4) are bound to plasma proteins: *thyroxine-binding globulin* (**TBG**), thyroxine-binding prealbumin (**TBPA**), and *serum albumin*. TBG transports two-thirds of the T_4 in the blood, while TBPA and serum albumin transport the rest. Less than 0.3% of the total T_3/T_4 in blood occurs in an unbound (free) form, although only the unbound molecules have an effect on the target cells. Certain drugs split T_3 and T_4 from protein bonds, resulting in increased plasma concentrations of the free hormones.

Potency of T_3/T_4. T_3 is 3–8 times more potent than T_4 and acts more rapidly (half-life of T_3 is 1 day, that of T_4 7 days). Only ca. 20% of all circulating T_3 originate from the thyroid; the other 80% are produced by the liver, kidneys, and other target cells that cleave iodide from T_4. The conversion of T_4 to T_3 is catalyzed by microsomal **5′-deiodase**, which removes iodine from the 5′ position on the outer ring (→ **D**). T_3 is therefore the more potent hormone, while T_4 is mainly ascribed a *storage function* in plasma.

The inactive form of T_3 called **reverse T_3 (rT_3)** is produced from T_4 when the iodine is split from the inner ring with the aid of a 5- (not 5′-)deiodase. Approximately equal amounts of T_3 and rT_3 are normally produced in the periphery (ca. 25 μg/day). When a person fasts, the resulting *inhibition of 5′-deiodase* decreases T_3 synthesis (to *save energy*, see below) while rT_3 synthesis increases. *Pituitary 5′-deiodase* is not inhibited, so TSH secretion (unwanted in this case) is suppressed by the negative feedback.


T_3/T_4 receptors are *hormone-sensitive transcription factors* located in the cell nuclei. Hormone–receptor complexes bind to regulator proteins of certain genes in the nuclei and influence their transcription.

The **actions of T_3/T_4** are numerous and mainly involve the *intermediate metabolism*. The thyroid hormones increase the number of *mitochondria* and its cristae, increase Na^+-K^+-ATPase activity and modulate the cholesterol metabolism. This results in an increase in *energy turnover* and a corresponding rise in O_2 *consumption* and *heat production*. T_3 also specifically stimulates heat production by increasing the expression of the uncoupling protein *thermogenin* in brown fat (→ p. 224). T_3 also influences the efficacy of other hormones. Insulin, glucagon, GH and epinephrine lose their energy turnover-increasing effect in *hypothyroidism*, whereas the sensitivity to epinephrine increases (heart rate increases, etc.) in *hyperthyroidism*. T_3 is thought to increase the density of β-adrenoceptors. T_3 also stimulates *growth* and *maturation*, especially of the brain and bones.


Cretinism occurs due to neonatal T_3/T_4 deficiencies and is marked by growth and maturation disorders (dwarfism, delayed sexual development, etc.) and central nervous disorders (intelligence deficits, seizures, etc.). The administration of thyroid hormones in the first six months of life can prevent or reduce some of these abnormalities.

Iodine metabolism (→ **D**). Iodine circulates in the blood as either (1) inorganic I^- (2–10 μg/L), (2) organic non-hormonal iodine (traces) and (3) protein-bound iodine (PBI) within T_3 and T_4 (35–80 μg iodine/L). The average daily requirement of iodine is ca. 150 μg; larger quantities are required in fever and hyperthyroidism (ca. 250–500 μg/day). Iodine excreted from the body must be replaced by the diet (→ **D**). Sea salt, seafood, and cereals grown in iodine-rich soil are rich in iodine. Iodized salt is often used to supplement iodine deficiencies in the diet. Since iodine passes into the breast milk, nursing mothers have a higher daily requirement of iodine (ca. 200 μg/day).

C. Synthesis, storage and mobilization of the thyroid hormones



D. Iodine balance



Calcium, particularly ionized calcium (Ca^{2+}), plays a central role in the regulation of numerous cell functions (→ pp. 36, 62ff., 194, 278). Calcium accounts for 2% of the body weight. Ca. 99% of the calcium occurs in bone while 1% is dissolved in body fluids. The total calcium conc. in serum is normally 2.1–2.6 mmol/L. Ca. 50% of it is **free Ca^{2+}** (**1.1–1.3 mmol/L**) while ca. 10% is bound in complexes and 40% is bound to proteins (mainly albumin; → p. 180).

Calcium protein binding increases as the pH of the blood rises since the number of Ca^{2+} binding sites on protein molecules also rises with the pH. The Ca^{2+} conc. accordingly *decreases in alkalosis* and rises in acidosis (by about 0.21 mmol/L Ca^{2+} per pH unit). Alkalosis (e.g., due to hyperventilation) and hypocalcemia (see below) can therefore lead to *tetany*.

The **calcium metabolism** is tightly regulated to ensure a balanced intake and excretion of Ca^{2+} (→ **A**). The *dietary intake of Ca^{2+}* provides around 12–35 mmol of Ca^{2+} each day (1 mmol = 2 mEq = 40 mg). Milk, cheese, eggs and "hard" water are particularly rich in Ca^{2+}. When calcium homeostasis is maintained, most of the ingested Ca^{2+} is excreted in the feces, while the remainder is excreted in the urine (→ p. 180). When a calcium deficiency exists, up to 90% of the ingested Ca^{2+} is absorbed by the intestinal tract (→ **A** and p. 264).

Pregnant and nursing mothers have higher Ca^{2+} requirements because they must also supply the fetus or newborn infant with calcium. The fetus receives ca. 625 mmol/day of Ca^{2+} via the placenta, and nursed infants receive up to 2000 mmol/day via the breast milk. In both cases, the Ca^{2+} is used for bone formation. Thus, many women develop a Ca^{2+} deficiency during or after pregnancy.

Phosphate metabolism is closely related to calcium metabolism but is less tightly controlled. The daily intake of phosphate is about 1.4 g; 0.9 g of intake is absorbed and usually excreted by the kidneys (→ p. 180). The **phosphate concentration** in serum normally ranges from 0.8–1.4 mmol/L.


Calcium phosphate salts are sparingly soluble. When the product of Ca^{2+} conc. times phosphate conc. (*solubility product*) exceeds a certain threshold, calcium phosphate starts to precipitate in solutions, and the deposition of calcium phosphate salts occurs. The salts are chiefly deposited in the bone, but can also precipitate in other organs. The infusion of phosphate leads to a decrease in the serum calcium concentration since calcium phosphate accumulates in bone. Conversely, hypophosphatemia leads to hypercalcemia (Ca^{2+} is released from bone).

Hormonal control. Calcium and phosphate homeostasis is predominantly regulated by *parathyroid hormone* and *calcitriol*, but also by calcitonin to a lesser degree. These hormones mainly affect three organs: the *intestines,* the *kidneys* and the *bone* (→ **B** and **D**).

Parathyrin or parathyroid hormone (PTH) is a peptide hormone (84 AA) secreted by the *parathyroid glands*. **Ca^{2+} sensors** in cells of the *parathyroid glands* regulate PTH synthesis and secretion in response to changes in the plasma concentration of *ionized Ca^{2+}* (→ p. 36). More PTH is secreted into the bloodstream whenever the Ca^{2+} conc. falls below normal (*hypocalcemia*). Inversely, PTH secretion decreases when the Ca^{2+} level rises (→ **D**, left panel). The primary function of PTH is to **normalize decreased Ca^{2+}** conc. in the blood (→ **D**). This is accomplished as follows: (1) PTH activates osteoclasts, resulting in bone breakdown and the *release of Ca^{2+}* (and phosphate) from the **bone**; (2) PTH accelerates the final step of calcitriol synthesis in the kidney, resulting in *increased reabsorption of Ca^{2+}* from the **gut**; (3) in the **kidney,** PTH increases calcitriol synthesis and Ca^{2+} reabsorption, which is particularly important due to the increased Ca^{2+} supply resulting from actions (1) and (2). PTH also *inhibits renal phosphate reabsorption* (→ p. 180), resulting in hypophosphatemia. This, in turn, stimulates the release of Ca^{2+} from the bone or prevents the precipitation of calcium phosphate in tissue (solubility product; see above).


Hypocalcemia occurs due to a deficiency (*hypoparathyroidism*) or lack of efficiency (*pseudohypoparathyroidism*) of PTH, which can destabilize the resting potential enough to produce *muscle spasms* and *tetany*. These deficiencies can also lead to a secondary calcitriol deficiency. An excess of PTH (*hyperparathyroidism*) and malignant osteolysis overpower the Ca^{2+} control mechanisms, leading to **hypercalcemia**. The long-term elevation of Ca^{2+} results in calcium deposition (e.g., in the kidneys). Ca^{2+} conc. exceeding 3.5 mmol/L lead to coma, renal insufficiency and cardiac arrhythmias. ▶

A. Calcium metabolism




* 1 mmol Ca^{2+} = 2 mEq Ca^{2+} = 40 mg Ca^{2+}

B. Factors affecting the blood Ca^{2+} concentration



C. Calcitriol synthesis



▶ **Calcitonin (CT)**, or *thyrocalcitonin*, is a peptide hormone (32 AA). It is mainly synthesized in the parafollicular cells (C cells) of the thyroid gland, which also contain Ca^{2+} sensors (→ p. 36). *Hypercalcemia* increases the plasma calcitonin conc. (→ **D**, **right** panel), whereas calcitonin can no longer be detected when the calcium conc. [Ca^{2+}] falls below 2 mmol/L. *Calcitonin normalizes elevated serum* Ca^{2+} conc. mainly by acting on **bone**. Osteoclast activity is inhibited by calcitonin (and stimulated by PTH). Calcitonin therefore increases the uptake of Ca^{2+} by the bone—at least temporarily (→ **D5**). Some *gastrointestinal hormones* accelerate calcitonin secretion, thereby enhancing the postprandial absorption of Ca^{2+} by bone. These effects (and perhaps the restraining effect of calcitonin on digestive activities) function to prevent postprandial hypercalcemia and the (unwanted) inhibition of PTH secretion and increased renal excretion of the just absorbed Ca^{2+}. Calcitonin also acts on the kidneys (→ **D6**).

Calcitriol (1,25-$(OH)_2$-cholecalciferol) is a lipophilic, steroid-like hormone synthesized as follows (→ **C**): **Cholecalciferol** (vitamin D_3) is produced from hepatic *7-dehydrocholesterol* in the **skin** via an intermediate product (*previtamin D*) in response to UV light (sun, tanning lamps). Both substances bind to *vitamin D-binding protein* (DBP) in the blood, but cholecalciferol is preferentially transported because of its higher affinity. Previtamin D therefore remains in the skin for a while after UV light exposure (short-term storage). Calcidiol (25-OH-cholecalciferol) and calcitriol bind to DBP. An estrogen-dependent rise in DBP synthesis occurs during pregnancy.

Cholecalciferol (vitamin D_3) is administered to compensate for inadequate UV exposure. The recommended daily dosage in children is approximately 400 units = 10 μg; adults receive half this amount. Plant-derived **ergocalciferol** (vitamin D_2) is equally effective as animal-derived vitamin D_3. The following actions apply for both forms.


Cholecalciferol is converted to **calcidiol** (25-OH-cholecalciferol) in the liver. Vitamin D is mainly *stored as calcidiol* because the plasma conc. of calcidiol is 25 μg/L, and its half-life is 15 days. **Calcitriol** (1,25-$(OH)_2$-cholecalciferol), the hormonally active form, is mainly synthesized in the **kidneys** (→ **C**), but also in the placenta. The plasma conc. of **calcitriol is regulated** by renal 1-α-hydroxylase (final step of synthesis) and by 24-hydroxylase, an enzyme that deactivates calcitriol.

The **calcitriol concentration rises** in response to *hypocalcemia*-related *PTH* secretion (→ **D2**), to *phosphate deficiency* and to *prolactin* (lactation). All three inhibit 24-hydroxylase and activate 1-α-hydroxylase. It **decreases** due to several negative feedback loops, i.e. due to the fact that calcitriol (a) directly inhibits 1-α-hydroxylase, (b) inhibits parathyroid hormone secretion, and (c) normalizes the (decreased) plasma conc. of Ca^{2+} and phosphate by increasing the intestinal absorption of Ca^{2+} and phosphate (see below). Calcium and phosphate inhibit 1-α-hydroxylase, while phosphate activates 24-hydroxylase.

Target organs. Calcitriol's primary target is the **gut**, but it also acts on the *bone, kidneys, placenta, mammary glands, hair follicles, skin* etc. It binds with its nuclear receptor and induces the expression of calcium-binding protein and Ca^{2+}-ATPase (→ pp. 280 and 36). Calcitriol has also genomic effects. Calcitriol *increases the intestinal absorption of* Ca^{2+} (→ **D4**) and *promotes mineralization of the bone*, but an **excess of calcitriol** leads to *decalcification* of the bone, an effect heightened by PTH. Calcitriol also increases the transport of Ca^{2+} and phosphate at the kidney (→ p. 178), placenta and mammary glands.

In transitory **hypocalcemia**, the bones act as a temporary *Ca^{2+} buffer* (→ **D**) until the Ca^{2+} deficit has been balanced by a calcitriol-mediated increase in Ca^{2+} absorption from the gut. If too little calcitriol is available, skeletal demineralization will lead to **osteomalacia** in adults and **rickets** in children. **Vitamin D deficiencies** are caused by inadequate dietary intake, reduced absorption (fat maldigestion), insufficient UV light exposure, and/or reduced 1-α-hydroxylation (renal insufficiency). Skeletal demineralization mostly occurs due to the prolonged increase in parathyroid hormone secretion associated with chronic hypocalcemia (*compensatory hyperparathyroidism*).

D. Hormonal regulation of the blood Ca^{2+} concentration



Cholesterol is the precursor of steroid hormones (→ **A**). Cholesterol is mainly synthesized in the **liver**. It arises from acetylcoenzyme A (acetyl-CoA) via a number of intermediates (e.g., squalene, lanosterol) and is transported to the endocrine glands by lipoproteins (→ p. 258). Cholesterol can be synthesized de novo also in the adrenal cortex, but not in the placenta (→ p. 306). Since only small quantities of steroid hormones are stored in the organs of origin, i.e., the adrenal cortex, ovaries, testes and placenta (→ p. 306), they must be synthesized from the cellular cholesterol pool as needed.

Cholesterol contains 27 carbon atoms. **Pregnenolone** (21 C atoms; → **A, a**), the precursor of steroid hormones, arises from cholesterol via numerous intermediates. Pregnenolone also yields **progesterone** (→ **A, b**), which is not only a potent hormone itself (female sex hormone; → p. 300ff.), but can act as the precursor of all other steroid hormones, i.e., (1) the adrenocortical hormones with 21 carbon atoms (→ **A**, yellow and orange fields); (2) male sex hormones (androgens, 19 carbon atoms) synthesized in the testes (→ p. 308), ovaries and adrenal cortex (→ **A**, green and blue fields); and (3) female sex hormones (*estrogens*, 18 carbon atoms; → p. 300ff.) synthesized in the ovaries (→ **A**, red zones).

The precursors for steroid hormone synthesis are present in all steroid hormone glands. The type of hormone produced and the site of hormone synthesis depend on (1) the type of receptors available for the superordinate control hormones (ACTH, FSH, LH, etc.) and (2) the dominant enzyme responsible for changing the structure of the steroid molecule in the hormone-producing cells of the gland in question. The **adrenal cortex** contains 11-, 17- and 21-hydroxylases—enzymes that introduce an OH group at position C21, C17 or C11, respectively, of the steroid molecule (→ **A**, top left panel for numerical order). Hydroxylation at C21 (→ **A, c**)—as realized in the *glomerular zone* of the adrenal cortex—makes the steroid insensitive to the effects of 17-hydroxylase. As a result, only **mineralocorticoids** like corticosterone and aldosterone (**A, d** ⇒ **e**; see also p. 184) can be synthesized. Initial hydroxylation at C17 (→ **A, f** or **g**) results in the synthesis of **glucocorticoids**—realized mainly in the *fascicular zone* of the adrenal cortex (→ **A, h** ⇒ **j** ⇒ **k**)—and **17-ketosteroids**, steroids with a keto group at C17 (→ **A**, **l** and **m**). Glucocorticoids and 17-ketosteroids can therefore be synthesized from 17α-hydroxypregnenolone without the aid of progesterone (→ **A**, **n** ⇒ **h** ⇒ **j**).


The **estrogens** (→ p. 304) *estrone* and *estradiol* can be directly or indirectly synthesized from 17-ketosteroids (→ **A**, **o** ⇒ **p**); they are produced indirectly by way of testosterone (→ **A**, **q** ⇒ **r** ⇒ **p**). The true active substance of certain target cells for androgens (e.g., in the prostate) is either *dihydrotestosterone* or *estradiol* ; both are synthesized from testosterone (→ **A,s** and **A,r**, respectively).

17-ketosteroids are synthesized by the gonads (testes and ovaries) and adrenal cortex. Since they are found in the urine, the *metyrapone test* of pituitary function is used to assess the *ACTH reserve* based on urinary 17-ketosteroids levels. ACTH secretion is normally subject to feedback control by glucocorticoids (→ p. 298). Metyrapone inhibits 11-hydroxylase activity (→ **A, d** and **j**), which leaves ACTH unsuppressed in healthy subjects. Urinary 17-ketosteroid levels should therefore increase after metyrapone administration. An abnormality of ACTH secretion can be assumed when this does not occur in patients with a healthy adrenal cortex.

Degradation of steroid hormones occurs mainly in the **liver**. Their OH groups are usually linked to *sulfate* or *glucuronic acid* molecules and the coupling products are ultimately excreted in the bile or urine (→ pp. 160, 183 and 250). The chief urinary metabolite of the estrogens is *estriol*, while that of the gestagens (mainly progesterone and 17α-hydroxyprogesterone) is *pregnanediol* (→ p. 306). Pregnanediol levels in urine can be measured to confirm or exclude *pregnancy* (pregnanediol test).

Chronically increased estrogen levels due, for example, to decreased estrogen degradation secondary to liver damage, can lead to breast development (*gynecomastia*) in the male, among other things. For normal estrogen ranges, see table on p. 304.

A. Biosynthesis of steroid hormones



The **mineralocortico(stero)ids** *aldosterone*, corticosterone and 11-desoxycorticosterone (→ pp. 184ff. and 296) are synthesized in the *glomerular zone* of the **adrenal cortex** (→ **A1**), whereas the **glucocortico(stero)ids** *cortisol* (hydrocortisone) and cortisone (→ p. 296, small quantities) are synthesized in the *fascicular zone* (→ **A2**). **Androgens** are synthesized in the *reticular zone* of the adrenal cortex (→ **A3**). One of the androgens is *dehydroepiandrosterone* (DHEA), which is used (partly in its sulfated form, DHEA-S) to synthesize various sex hormones in other tissues (→ p. 306).

Cortisol transport. Most of the plasma cortisol is bound to *transcortin*, or *cortisol-binding globulin* (*CBG*), a specific transport protein with a high-affinity binding site for cortisol. Cortisol is released in response to conformational changes of CBG due to inflammation etc.

CRH and **ACTH** regulate cortisol synthesis and secretion (→ **A4**, **A5**; see also p. 272). ACTH ensures also structural preservation of the adrenal cortex and supplies cortisol precursors, e.g., by forming cholesterol from its esters, by de novo synthesis of cholesterol and by converting it to progesterone and 17α-hydroxyprogesterone (→ pp. 258 and 296). *ACTH secretion* is stimulated by *CRH* and epinephrine and inhibited (negative feedback control) by *cortisol* with or without the aid of CRH (→ **A**; see also p. 275 A).

A **circadian rhythm** of CRH secretion and thus of ACTH and cortisol secretion can be observed. The peak secretion is in the morning (→ **B**, mean values). Continuous hormone conc. sampling at short intervals have shown that ACTH and cortisol are secreted in 2–3-hour *episodes* (→ **B**).

Receptor proteins (→ p. 280) for glucocorticoids can be found in virtually every cell. Glucocorticoids are vital hormones that exert numerous **effects**, the most important of which are listed below.

Carbohydrate and amino acid (**AA**) **metabolism** (see also pp. 285 A and 287 C): Cortisol uses amino acids (AA) derived from protein degradation to increase the plasma glucose concentration (*gluconeogenesis*), which can lead to the so-called *steroid diabetes* in extreme cases. Thus, cortisol has a *catabolic* effect (degrades proteins) that results in the increased excretion of urea.

Cardiovascular function: Glucocorticoids increase myocardial contractility and vasoconstriction due to enhancement of catecholamine effects (→ pp. 196 and 216). These are described as *permissive effects* of cortisol. Cortisol increases the synthesis of epinephrine in the adrenal medulla (→ **A6**) and of angiotensinogen in the liver (→ p. 186).

Especially when administered at high doses, glucocorticoids induce **anti-inflammatory and anti-allergic effects** because they stabilize lymphokine synthesis and histamine release (→ p. 100). On the other hand, interleukin-1, interleukin-2 and TNF-α (e.g., in severe infection) leads to increased secretion of CRH and high cortisol conc. (see below).


Renal function: Glucocorticoids delay the *excretion of water* and help to maintain a normal glomerular filtration rate. They can react also with aldosterone receptors but are converted to cortisone by *11β-hydroxysteroid oxidoreductase* in aldosterone target cells. Normal cortisol conc. are therefore ineffective at the aldosterone receptor. High conc., however, have the same effect as aldosterone (→ p. 184).

Gastric function: Glucocorticoids weaken the protective mechanisms of the gastric mucosa. Thus, high-dose glucocorticoids or stress (see below) increase the risk of gastric ulcers (→ p. 244).


Cerebral function: High glucocorticoid conc. change hypothalamic (→ **A**) and electrical brain activity (EEG) and lead to psychic abnormalities.

Stress: Physical or mental stress increases cortisol secretion as a result of increased CRH secretion and increased sympathetic tone (→ **A**). Many of the aforementioned effects of cortisol therefore play a role in the body's response to stress (activation of energy metabolism, increase in cardiac performance, etc.). In severe physical (e.g., sepsis) or mental stress (e.g., depression), the cortisol plasma conc. remains at a very high level (up to 10 times the normal value) throughout the day.

A. Adrenal gland



B. Circadian rhythm of ACTH and cortisol secretion



Oogenesis. The development of the female gametes (ova) extends from the oogonium stage to the primary oocyte stage (in the primordial follicle), starting long before birth. Oogenesis therefore occurs much sooner than the corresponding stages of spermatogenesis (→ p. 308). The fetal phase of oogenesis is completed by the first week of gestation; these oocytes remain latent until puberty. In the sexually mature female, a fertilizable ovum develops in the graafian follicles approximately every 28 days.

Menstrual cycle. After the start of sexual maturation, a woman starts to secrete the following hormones in a cyclic (approx.) 28-day rhythm (→ **A1, A2**). *Gonadoliberin* (= *gonadotropin-releasing hormone*, Gn-RH) and *dopamine* (PIH) are secreted by the hypothalamus. *Follicle-stimulating hormone* (FSH), *luteinizing hormone* (LH) and *prolactin* (PRL) are released by the anterior pituitary. *Progesterone*, *estrogens* (chiefly estradiol, E_2) and *inhibin* are secreted by the ovaries. Gn-RH controls the *pulsatile secretion* of FSH and LH (→ p. 302), which in turn regulate the secretion of estradiol and progesterone. The female sex functions are controlled by the periodic release of hormones, the purpose of which is to produce a fertilizable egg in the ovaries each month (→ **A4**) and produce an environment suitable for sperm reception (*fertilization*) and implantation of the fertilized ovum (*nidation*) (→ **A5**). This cyclic activity is reflected by the monthly *menses* (*menstruation*) which, by definition, marks the start of the menstrual cycle.

Girls in Central Europe usually have their first menstrual period (**menarche**) around the age of 13. By about age 40, the cycle becomes increasingly irregular over a period of up to 10 years (**climacteric**) as the end of the reproductive period nears. The last menses (**menopause**) generally occurs around the age of 48–52.

A menstrual cycle can last 21–35 days. The second half of the cycle (**luteal phase** = secretory phase) usually lasts 14 days, while the first half (**follicular phase** = proliferative phase) lasts 7–21 days. **Ovulation** separates the two phases (→ **A**). If the cycle length varies by more than 2–3 days, ovulation generally does not occur. Such *anovulatory cycles* account for 20% of all cycles in healthy females.

In addition to general changes in the body and mood, the following changes occur in the ovaries, uterus and cervix during the menstrual cycle (→ **A**):


Day 1: Start of menstruation (lasting about 2–6 days).

Days 1–14 (variable, see above): The **follicular phase** starts on the first day of menstruation. The endometrium thickens to become prepared for the implantation of the fertilized ovum during the luteal phase (→ **A5**), and about 20 ovarian follicles mature under the influence of FSH. One of these becomes the *dominant follicle*, which produces increasing quantities of *estrogens* (→ **A4** and p. 300). The small cervical os is blocked by a viscous mucous plug.

Day 14 (variable, see above): **Ovulation**. The amount of *estrogens* produced by the follicle increases rapidly between day 12 and 13 (→ **A2**). The increased secretion of LH in response to higher levels of estrogen leads to ovulation (→ **A1, A4**; see also p. 302). The *basal body temperature* (measured on an empty stomach before rising in the morning) rises about 0.5°C about 1–2 days later and remains elevated until the end of the cycle (→ **A3**). This temperature rise generally indicates that ovulation has occurred. During ovulation, the *cervical mucus* is less viscous (it can be stretched into long threads—*spinnbarkeit*) and the cervical os opens slightly to allow the sperm to enter.

Days 14–28: The **luteal phase** is characterized by the development of a *corpus luteum* (→ **A4**), which secretes *progesterone*, (→ **A2**); an increase in mucoid secretion from the uterine glands also occurs (→ **A5**). The endometrium is most responsive to progesterone around the 22nd day of the cycle, which is when *nidation* should occur if the ovum has been fertilized. Otherwise, progesterone and estrogens now inhibit Gn-RH secretion (→ p. 302), resulting in degeneration of the corpus luteum. The subsequent rapid decrease in the plasma concentrations of estrogens and progesterone (→ **A2**) results in constriction of endometrial blood vessels and ischemia. This ultimately leads to the breakdown and discharge of the uterine lining and to bleeding, i.e., menstruation (→ **A5**).

A. Menstrual cycle



In sexually mature women, **gonadoliberin** or **gonadotropin-releasing hormone (Gn-RH)** is secreted in one-minute pulses every 60–90 min in response to signals from various neurotransmitters. This, in turn, induces the pulsatile secretion of FSH and LH from the anterior pituitary. If the rhythm of Gn-RH secretion is much faster or continuous, less FSH and LH will be secreted, which can result in infertility. The LH : FSH secretion ratio changes during the course of the menstrual cycle. Their release must be therefore subject to additional factors besides Gn-RH.

The secretion of LH and FSH is, for example, subject to **central nervous effects** (psychogenic factors, stress) mediated by various **transmitters** circulating in the portal blood in the hypothalamic region, e.g., norepinephrine (NE) and neuropeptide Y (NPY) as well as by ovarian hormones, i.e., by *estrogens* (estrone, estradiol, estriol, etc.), *progesterone* and *inhibin*. Ovarian hormones affect Gn-RH secretion indirectly by stimulating central nerve cells that activate Gn-RH-secreting neurons by way of neurotransmitters such as norepinephrine and NPY and inhibit Gn-RH secretion by way of GABA and opioids.

FSH production again increases toward the end of the luteal phase (→ p. 301, A1). In the **early follicular phase** (→ **A1**), FSH induces the proliferation of the *stratum granulosum* in about 20 follicles and stimulates the secretion of *aromatase* in their *granulosa cells*. Aromatase catalyzes the conversion of the androgens *testosterone* and *androstenedione* to estradiol (E_2) and estrone (E_1) (→ p. 297 A, steps *r* and *o*). Estrogens are synthesized in *theca cells* and absorbed by granulosa cells. Although relatively small amounts of LH are secreted (→ **A1** and p. 301 A1), this is enough to activate theca cell-based enzymes (17β-hydroxysteroid dehydrogenase and C17/C20-lyase) that help to produce the androgens needed for estrogen synthesis. The follicle-based estrogens increase their own FSH receptor density. The follicle with the highest estrogen content is therefore the most sensitive to FSH. This loop has a self-amplifying effect, and the follicle in question is selected as the *dominant follicle* around the 6th day of the cycle (→ **A2**). In the **mid-follicular phase**, estrogens restrict FSH and LH secretion (via negative feedback control and with the aid of *inhibin*; → **A2**) but later stimulate LH receptor production in granulosa cells. These cells now also start to produce progesterone (start of *luteinization*), which is absorbed by the theca cells (→ **A3**) and used as precursor for further increase in androgen synthesis (→ p. 297 A, steps *f* and *l*).


Inhibin and estrogens secreted by the dominant follicle increasingly inhibit FSH secretion, thereby decreasing the estrogen production in other follicles. This leads to an androgen build-up in and **apoptosis of the unselected follicles**.

Increasing quantities of LH and FSH are released in the **late follicular phase** (→ **A3**), causing a sharp rise in their plasma concentrations. The **FSH peak** occurring around day 13 of the cycle induces the *first meiotic division* of the ovum. Estrogens increase the LH secretion (mainly via the hypothalamus), resulting in the increased production of androgens and estrogens (*positive feedback*) and a rapid rise in the LH conc. (*LH surge*). The **LH peak** occurs around **day 14** (→ **A2**). The follicle ruptures and discharges its ovum about 10 hours later (**ovulation**). Ovulation does not take place if the LH surge does not occur or is too slow. Pregnancy is not possible in the absence of ovulation.

Luteal phase (→ **A4**). LH, FSH and estrogens transform the ovarian follicle into a *corpus luteum*. It actively secretes large quantities of **progesterone** (progestational hormone), marking the beginning of the luteal phase (→ **A**). Estrogens and progesterone now *inhibit* the secretion of FSH and LH directly and indirectly (e.g., through inhibition of Gn-RH; see above), causing a rapid drop in their plasma conc. This *negative feedback* leads to a marked drop in the plasma conc. of estrogens and progesterone towards the end of the menstrual cycle (approx. day 26), thereby triggering the menses (→ p. 301, A2). FSH secretion starts to rise just before the start of menstruation (→ **A4**).

Combined administration of estrogens and gestagens during the first half of the menstrual cycle prevents ovulation. Since ovulation does not occur, pregnancy cannot take place. Most **contraceptives** work according to this principle.

A. Hormonal control of the menstrual cycle



Estrogens are steroid hormones with 18 carbon atoms. Estrogens are primarily synthesized from the 17-ketosteroid *androstenedione*, but testosterone can also be a precursor (→ p. 297 A). The *ovaries*, (granulosa and theca cells), *placenta* (→ p. 304), *adrenal cortex*, and in *Leydig's cells* (interstitial cells) of the *testes* (→ p. 308) are the physiological **sites of estrogen synthesis.**. In some target cells for testosterone, it must first be converted to estradiol to become active.

Estradiol (E_2) is the most potent estrogen (E). The potencies of **estrone (E_1)** and **estriol (E_3)** are relatively low in comparison ($E_2 : E_1 : E_3$ = 10 : 5 : 1). Most estrogens (and testosterone) circulating in the blood are bound to *sex hormone-binding globulin (SHBG)*. Estriol (E_3) is the chief degradation product of estradiol (E_2).

Oral administration of estradiol has virtually no effect because almost all of the hormone is removed from the bloodstream during its first pass through the liver. Therefore, other estrogens (with a different chemical structure) must be used for effective **oral estrogen therapy**.

Actions of Estrogens. Although estrogens play a role in the development of female sex characteristics, they are not nearly as important as the androgens for male sexual development (→ p. 308). The preparatory action of estrogen is often required for optimal progesterone effects (e.g., in the uterus; see below). Other important effects of estrogens in human females are as follows.

◆ **Menstrual cycle.** Estrogens accelerate maturation of the ovarian follicle during the menstrual cycle (→ p. 306 and table). In the *uterus*, estrogen promotes the proliferation (thickening) of the endometrium and increases uterine muscle contraction. In the *vagina*, estrogen thickens the mucosal lining, leading to the increased discharge of glycogen-containing epithelial cells. The liberated glycogen is used for an increased production of lactic acid by Döderlein's bacillus. This lowers the vaginal pH to 3.5–5.5, thereby reducing the risk of vaginal infection. In the *cervix*, the mucous plug sealing the cervical os functions as a barrier that prevents sperm from entering the uterus. Estrogens change the consistency of the cervical mucus, making it more conducive to sperm penetration and survival, especially around the time of ovulation.

◆ **Fertilization.** In the female body, estrogens prepare the sperm to penetrate and fertilize the ovum (*capacitation*) and regulate the speed at which the ovum travels in the fallopian tube.

◆ **Extragonadal effects of estrogen.** During *puberty*, estrogens stimulate breast development, induces changes in the vagina and in the distribution of subcutaneous fat, and (together with androgens) stimulate the growth of pubic and axillary hair.

Since estrogens increase the coagulability of the blood, the administration of estrogens (e.g., in contraceptives) increases the risk of thrombosis.

Estrogens also promote renal salt and water retention. Estrogens slow longitudinal bone growth, accelerate epiphyseal closure (in men and women) and increase osteoblast activity. Estrogen deficiencies in menopause consequently lead to the loss of bone mass (*osteoporosis*). Estrogens induce a decrease in LDL and a rise in VLDL and HDL concentrations (→ p. 256ff.), which is why arteriosclerosis is less common in premenopausal women than in men. Estrogen also makes the *skin* thinner and softer, reduces the sebaceous glands, and increases fat deposits in subcutaneous tissue. Lastly, estrogen influences a number of *central nervous functions*, e.g., sexual response, social behavior, and mood.

Plasma concentrations of estradiol and progesterone (ng/mL)

Phase	Estradiol	Progesteron
Women		
Early follicular phase	0.06	0.3
Mid- and late follicular phase	0.1 ⇒ 0.4	1.0
Ovulation	0.4	2.0
Mid-luteal phase	0.2	8–16
Pregnancy	7–14	40 ⇒ 130
Day 1 after parturition		20
Men	0.05	0.3

Progesterone

Progesterone, the most potent progestational (pregnancy-sustaining) hormone, is a steroid

hormone (21 C atoms) synthesized from cholesterol via pregnenolone (→ p. 297). It is produced in the corpus luteum, ovarian follicles and placenta (→ p. 306) of the female, and in the adrenal cortex of males and females. Like cortisol, most circulating progesterone is bound to cortisol-binding globulin (CBG = transcortin). Like estradiol (E_2), most progesterone is broken down during its first pass through the liver, so oral doses of progesterone are almost completely ineffective. *Pregnanediol* is the most important degradation product of progesterone.

Actions of progesterone. The *main functions* of progesterone are to prepare the female genital tract for implantation and maturation of the fertilized ovum and to **sustain pregnancy** (→ see table). Progesterone counteracts many of the effects induced by estrogens, but various effects of progesterone depend on the preparatory activity or simultaneous action of estrogens. During the follicular phase, for example, estrogens increases the density of progesterone receptors, while simultaneous estrogen activity is needed to induce mammary growth (see below).

◆ The **uterus** is the chief target organ of progesterone. Once estrogen induces endometrial thickening, progesterone stimulates growth of the uterine muscle (myometrium), restructures the endometrial glands (→ p. 300), alters the blood supply to the endometrium, and changes the glycogen content. This represents the transformation from a proliferative endometrium to a secretory endometrium, with a peak occurring around day 22 of the cycle. Progesterone later plays an important role in the potential implantation (nidation) of the fertilized ovum because it reduces myometrial activity (important during pregnancy), narrows the **cervical os**, and changes the consistency of the cervical mucous plug so that it becomes virtually impregnable to sperm.

◆ Progesterone inhibits the release of LH during the luteal phase. The administration of gestagens like progesterone during the follicular phase *inhibits ovulation*. Together with its effects on the cervix (see above) and its inhibitory effect on capacitation (→ p. 304), progesterone can therefore have a contraceptive effect (“**mini pill**”).

◆ High levels of progesterone have an anesthetic effect on the **central nervous system**.

◆ Progesterone also increases the susceptibility to epileptic fits and exerts thermogenic action, i.e., it raises the basal body temperature (→ p. 300). In addition, a decrease in the progesterone concentration is also believed to be responsible for the mood changes and depression observed before menstruation (*premenstrual syndrome, PMS*) and after pregnancy (*postpartum depression*).

◆ In the **kidneys**, progesterone slightly inhibits the effects aldosterone, thereby inducing increased NaCl excretion.

Prolactin and Oxytocin

The secretion of **prolactin (PRL)** is inhibited by prolactin-inhibiting hormone (**PIH = dopamine**) and stimulated by thyroliberin (**TRH**) (→ p. 272). Prolactin increases the hypothalamic secretion of PIH in both men and women (negative feedback control). Conversely, estradiol (E_2) and progesterone inhibit PIH secretion (indirectly via transmitters, as observed with Gn-RH; see above). Consequently, prolactin secretion rises significantly during the second half of the menstrual cycle and during pregnancy. Prolactin (together with estrogens, progesterone, glucocorticoids and insulin) stimulate *breast enlargement* during pregnancy and *lactogenesis* after parturition. In breast-feeding, stimulation of the nerve endings in the nipples by the suckling infant stimulates the secretion of prolactin (**lactation reflex**). This also increases release of oxytocin which triggers *milk ejection* and increases uterine contractions, thereby increasing lochia discharge after birth. When the mother stops breast-feeding, the prolactin levels drop, leading to the rapid stoppage of milk production.

Hyperprolactinemia. Stress and certain drugs inhibit the secretion of PIH, causing an increase in prolactin secretion. *Hypothyroidism* (→ p. 290) can also lead to hyperprolactinemia, because the associated increase in TRH stimulates the release of prolactin. Hyperprolactinemia inhibits ovulation and leads to *galactorrhea*, i.e., the secretion of milk irrespective of pregnancy. Some women utilize the anti-ovulatory effect of nursing as a natural method of birth control, which is often but not always effective.

Beside its other functions, the **placenta** produces most of the hormones needed during pregnancy (→ p. 222). *Ovarian hormones* also play a role, especially at the start of pregnancy (→ **A**).

Placental hormones. The primary hormones produced by the placenta are *human chorionic gonadotropin* (**hCG**), *corticotropin-releasing hormone* (**CRH**), *estrogens, progesterone, human placental lactogen* (**hPL**), and *pro-opiomelanocortin* (POMC; → p. 282). hCG is the predominant hormone during the first trimester of pregnancy (3-month period calculated from the beginning of the last menses). Maternal conc. of hPL and CRH-controlled estrogens rise sharply during the third trimester (→ **B**). Placental hormones are distributed to mother and fetus. Because of the close connection between maternal, fetal and placental hormone synthesis, they are jointly referred to as the **fetoplacental unit** (→ **A**).

Human chorionic gonadotropin (hCG) (a) stimulates the synthesis of steroids like DHEA and DHEA-S by the fetal adrenal cortex (see below); (b) suppresses follicle maturation in the maternal ovaries, and (c) maintains the production of progesterone and estrogen in the corpus luteum (→ **A1**) until the 6th week of gestation, i.e., until the placenta is able to produce sufficient quantities of the hormones.

Most **pregnancy tests** are based on the fact that hCG is detectable in the urine about 6–8 days after conception. Since the levels of estrogen and progesterone greatly increase during pregnancy (see table on p. 304), larger quantities of these hormones and their metabolites *estriol* and *pregnanediol* are excreted in the urine. Therefore, their conc. can also be measured to test for pregnancy.


In contrast to other endocrine organs, the placenta has to receive the appropriate precursors (cholesterol or androgens, → p. 296) from the maternal and fetal adrenal cortex, respectively, before it can synthesize progesterone and estrogen (→ **A2**). The **fetal adrenal cortex (FAC)** is sometimes larger than the kidneys and consists of a *fetal zone* and an *adult zone*. The placenta takes up cholesterol and pregnenolone and uses them to synthesize progesterone. It is transported to the fetal zone of the FAC, where it is converted to *dehydroepiandrosterone* (**DHEA**) and *dehydroepiandrosterone sulfate* (**DHEA-S**). DHEA and DHEA-S pass to the **placenta**, where they are used for *estrogen synthesis*. Progesterone is converted to *testosterone* in the *testes* of the male fetus.

Human placental lactogen (hPL = human chorionic somatomammotropin, HCS) levels rise steadily during pregnancy. Like prolactin (→ p. 305), hPL stimulates mammary enlargement and lactogenesis in particular and, like GH (→ p. 282), stimulates physical growth and development in general. hPL also seems to increase maternal plasma glucose conc.

Corticotropin-releasing hormone (CRH) secreted by the *placenta* seems to play a key role in the **hormonal regulation of birth**. The plasma levels of maternal CRH increase exponentially from the 12th week of gestation on. This rise is more rapid in premature births and slower in post-term births. In other words, the rate at which the CRH concentration rises seems to determine the duration of the pregnancy. Placental CRH stimulates the release of ACTH by the fetal pituitary, resulting in increased cortisol production in the adult zone of FAC; this again stimulates the release of CRH (positive feedback). CRH also stimulates lung development and the production of DHEA and DHEA-S in the fetal zone of FAC.


The maternal estrogen conc. rises sharply towards the **end of the pregnancy**, thereby counteracting the actions of progesterone, including its pregnancy-sustaining effect. Estrogens induce oxytocin receptors (→ p. 305), α_1-adrenoceptors (→ p. 84ff.), and gap junctions in the uterine musculature (→ p. 16ff.), and uterine cells are depolarized. All these effects increase the responsiveness of the uterine musculature. The simultaneous increase in progesterone synthesis triggers the production of collagenases that soften the taut cervix. Stretch receptors in the uterus respond to the increase in size and movement of the fetus. Nerve fibers relay these signals to the hypothalamus, which responds by secreting larger quantities of oxytocin which, in turn, increases uterine contractions (positive feedback). The gap junctions conduct the spontaneous impulses from individual pacemaker cells in the fundus across the entire myometrium at a rate of approximately 2 cm/s (→ p. 70).

A. Hormone synthesis in placenta, mother and fetus: fetoplacental unit



Steroid hormones:
P = progesterone; DHEA(-S) = dehydroepiandrosterone (sulfate); E = estrogens

B. Hormone concentrations in plasma during pregnancy



Androgens (male sex hormones) are steroid hormones with 19 C atoms. This group includes potent hormones like *testosterone* (**T**) and *5α-dihydrotestosterone* (**DHT**) and less potent *17-ketosteroids* (**17-KS**) such as DHEA (→ p. 296). In males, up to 95% of testosterone is synthesized by the *testes* (→ **A2**) and 5% by the *adrenal cortex* (→ **AI**). The *ovaries* and adrenal cortex synthesize testosterone in females. The plasma testosterone conc. in males is about 15 times higher than in females, but decreases with age. Up to 98% of testosterone circulating in blood is bound to plasma proteins (albumin and sex hormone-binding globulin, SHBG; → **A2**).

The testes secrete also small quantities of **DHT** and **estradiol** (E_2). Larger quantities of DHT (via *5-α-reductase*) and estradiol are synthesized from testosterone (via *aromatase*) by their respective target cells. A portion of this supply is released into the plasma. DHT and testosterone bind to the same intracellular receptor. Estradiol influences many functions in the male, e.g., epiphyseal cartilage and ejaculate formation and pituitary and hypothalamic activity.

Testosterone secretion is **regulated** by luteinizing hormone (= LH, also called ICSH, → p. 271), the pulsatile secretion of which is controlled by Gn-RH at 1.5- to 2-hourly intervals, as in the female. LH stimulates the release of testosterone from Leydig's cells (interstitial cells) in the testes (→ **A2**), whereas testosterone and estradiol inhibit LH and Gn-RH secretion (negative feedback).

Gn-RH also induces the release of **FSH**, which stimulates the secretion of **inhibin** and induces the expression of *androgen-binding protein* (**ABP**) in Sertoli cells of the testes (→ **A3**). Testosterone cannot induce spermatogenesis without the help of ABP (see below). FSH also induces the formation of LH receptors in the interstitial cells of Leydig. Testosterone, DHT, estradiol and inhibin inhibit the secretion of FSH (negative feedback; → **A**). **Activin**, the physiological significance of which is still unclear, inhibits FSH secretion.

Apart from the important **effects of testosterone** on male sexual differentiation, spermatogenesis and sperm growth as well as on the functions of the genitalia, prostate and seminal vesicle (see below), testosterone also induces the *secondary sex characteristics* that occur in males around the time of puberty, i.e., body hair distribution, physique, laryngeal size (voice change), acne, etc. In addition, testosterone is necessary for normal sex drive (*libido*), procreative capacity (*fertility*) and coital capacity (*potentia coeundi*) in the male. Testosterone also stimulates *hematopoiesis* and has *anabolic properties*, leading to increased muscle mass in males. It also has central nervous effects and can influence behavior—e.g., cause aggressiveness.


Sexual development and differentiation. The *genetic sex* (→ **B**) determines the development of the sex-specific *gonads* (gamete-producing glands). The germ cells (*spermatogonia*; see below) then migrate into the gonads. The *somatic sex* is female when the subsequent somatic sex development and sex differentiation occurs in the absence of testosterone (→ **C**). Male development requires the presence of testosterone in both steps (→ **C**) with or without the aid of additional factors (e.g., calcitonin gene-related peptide, CGRP?) in certain stages of development (e.g., descent of testes into scrotum).

High conc. of testosterone, either natural or synthetic (anabolic steroids), lead to masculinization (*virilization*) of the female (→ **C**).


Testicular function. *Spermatogenesis* occurs in several stages in the testes (target organ of testosterone) and produces *sperm* (*spermatozoa*) (→ **A3**). Sperm are produced in the *seminiferous tubules* (total length, ca. 300 m), the epithelium of which consists of *germ cells* and *Sertoli cells* that support and nourish the spermatogenic cells. The seminiferous tubules are strictly separated from other testicular tissues by a *blood–testis barrier*. The testosterone required for sperm maturation and semen production (→ p. 310) must be bound to androgen-binding protein (**ABP**) to cross the barrier.

Spermatogonia (→ **B**) are primitive sex cells. At puberty, a spermatogonium divides mitotically to form two daughter cells. One of these is kept as a lifetime *stem cell* reservoir (in contrast to oogonia in the female; → p. 300). The other undergoes several divisions to form a **primary spermatocyte**. It undergoes a *first meiotic division* (MD1) to produce two **secondary spermatocytes**, each of which undergoes a *second meiotic division* (MD2), producing a total of four **spermatids**, which ultimately differentiate into *spermatozoa*. After MD1, the spermatocytes have a single (haploid) set of chromosomes.


A. Control and transport of androgenic hormones; effects of testosterone on the testes



B. Genetic sex determination



C. Effect of androgens on sexual differentiation



Sexual response in the male (→ **A1**). Impulses from tactile receptors on the skin in the genital region (especially the glans penis) and other parts of the body (*erogenous areas*) are transmitted to the *erection center* in the sacral spinal cord (S2–S4), which conducts them to parasympathetic neurons of the pelvic splanchnic nerves, thereby triggering **sexual arousal**. Sexual arousal is decisively influenced by stimulatory or inhibitory *impulses from the brain* triggered by sensual perceptions, imagination and other factors. Via nitric oxide (→ p. 280), efferent impulses lead to dilatation of deep penile artery branches (helicine arteries) in the erectile body (corpus cavernosum), while the veins are compressed to restrict the drainage of blood. Moreover, voluntary and involuntary contractions ot the ischiocavernosus muscle increase the pressure in the erectile body well above the systolic blood pressure. This causes the penis to stiffen and rise (**erection**). The *ejaculatory center* in the spinal cord (L2 –L3) is activated when arousal reaches a certain threshold (→ **A2**). Immediately prior to ejaculation, efferent sympathetic impulses trigger the partial evacuation of the prostate gland and the **emission** of semen from the *vas deferens* to the posterior part of the urethra. This triggers the **ejaculation reflex** and is accompanied by **orgasm**, the apex of sexual excitement. The effects of orgasm can be felt throughout the entire body, which is reflected by perspiration and an increase in respiratory rate, heart rate, blood pressure, and skeletal muscle tone. During ejaculation, the internal sphincter muscle closes off the urinary bladder while the vas deferens, seminal vesicles and bulbospongiosus and ischiocavernosus muscles contract rhythmically to propel the semen out of the urethra.


Semen. The fluid expelled during ejaculation (2–6 mL) contains 35–200 million sperm in a nutrient fluid (*seminal plasma*) composed of various substances, such as prostaglandins (from the prostate) that stimulate uterine contraction. Once semen enters the vagina during **intercourse**, the alkaline seminal plasma increase the vaginal pH to increase sperm motility. At least one sperm cell must reach the ovum for fertilization to occur.

Sexual response in the female (→ A2). Due to impulses similar to those in the male, the erectile tissues of the clitoris and vestibule of the vagina engorge with blood during the erection phase. Sexual arousal triggers the release of secretions from glands in the labia minora and transudates from the vaginal wall, both of which lubricate the vagina, and the nipples become erect. On continued stimulation, afferent impulses are transmitted to the lumbar spinal cord, where sympathetic impulses trigger **orgasm** (**climax**). The vaginal walls contract rhythmically (*orgasmic cuff*), the vagina lengthens and widens, and the uterus becomes erect, thereby creating a space for the semen. The cervical os also widens and remains open for about a half an hour after orgasm. Uterine contractions begin shortly after orgasm (and are probably induced locally by oxytocin). Although the accompanying physical reactions are similar to those in the male (see above), there is a wide range of variation in the orgasmic phase of the female. Erection and orgasm are not essential for conception.

Fertilization. The fusion of sperm and egg usually occurs in the *ampulla* of the fallopian tube. Only a small percentage of the sperm expelled during ejaculation (1000–10 000 out of 10^7 to 10^8 sperm) reach the fallopian tubes (*sperm ascension*). To do so, the sperm must penetrate the mucous plug sealing the cervix, which also acts as a sperm reservoir for a few days. In the time required for them to reach the ampullary portion of the fallopian tube (about 5 hours), the sperm must undergo certain changes to be able to fertilize an ovum; this is referred to as **capacitation** (→ p. 304).

After ovulation (→ p. 300ff.) the ovum enters the tube to the uterus (*oviduct*) via the abdominal cavity. When a sperm makes contact with the egg (via chemotaxis), species-specific sperm-binding receptors on the ovum are exposed and the proteolytic enzyme *acrosin* is thereby activated (**acrosomal reaction**). Acrosin allows the sperm to penetrate the cells surrounding the egg (*corona radiata*). The sperm bind to receptors on the envelope surrounding the ovum (*zona pellucida*) and enters the egg. The membranes of both cells then *fuse*. The ovum now undergoes a *second meiotic division*, which concludes the act of *fertilization*. Rapid proteolytic changes in the receptors on the ovum (**zona pellucida reaction**) prevent other sperm from entering the egg. Fertilization usually takes place on the first day after intercourse and is only possible within 24 hours after ovulation.

A. Sexual response pathways



The *brain* and *spinal cord* make up the *central nervous system* (**CNS**) (→ **A**). The spinal cord is divided into similar *segments*, but is 30% shorter than the spinal column. The **spinal nerves** exit the spinal canal at the level of their respective vertebrae and contains the afferent somatic and visceral fibers of the *dorsal root*, which project to the spinal cord, and the efferent somatic (and partly autonomic) fibers of the *anterior root*, which project to the periphery. Thus, a nerve is a bundle of nerve fibers that has different functions and conducts impulses in different directions (→ p. 42).

Spinal cord (→ **A**). Viewed in cross-section, the spinal cord has a dark, butterfly-shaped inner area (*gray matter*) surrounded by a lighter outer area (*white matter*). The four wings of the gray matter are called *horns* (cross-section) or columns (longitudinal section). The *anterior horn* contains motoneurons (projecting to the muscles), the *posterior horn* contains interneurons. The cell bodies of most afferent fibers lie within the **spinal ganglion** outside the spinal cord. The white matter contains the axons of ascending and descending tracts.

Brain (→ **D**). The main parts of the brain are the *medulla oblongata* (→ **D7**) *pons* (→ **D6**), *mesencephalon* (→ **D5**), *cerebellum* (→ **E**), *diencephalon* and *telencephalon* (→ **E**). The medulla, pons and mesencephalon are collectively called the **brain stem**. It is structurally similar to the spinal cord but also contains cell bodies (nuclei) of *cranial nerves*, neurons controlling *respiration* and *circulation* (→ pp. 132 and 214ff.) etc. The **cerebellum** is an important control center for balance and motor function (→ p. 328ff.). Pons and cerebellum form the *metencephalon*.

Diencephalon. The *thalamus* (→ **C6**) of the diencephalon functions as a relay station for most afferents, e.g., from the eyes, ears and skin as well as from other parts of the brain. The *hypothalamus* (→ **C9**) is a higher autonomic center (→ p. 332), but it also plays a dominant role in endocrine function (→ p. 268ff.) as it controls the release of hormones from the adjacent *hypophysis* (→ **D4**).


The **telencephalon** consists of the cortex and nuclei important for motor function, the **basal ganglia**, i.e. *caudate nucleus* (→ **C5**), *putamen* (→ **C7**), *globus pallidus* (→ **C8**), and parts of the *amygdala* (→ **C10**). The amygdaloid nucleus and *cingulate gyrus* (→ **D2**) belong to the **limbic system** (→ p. 332). The **cerebral cortex** consists of four *lobes* divided by fissures (sulci), e.g., the *central sulcus* (→ **D1, E**) and *lateral sulcus* (→ **C3, E**). According to *Brodmann's map*, the cerebral cortex is divided into histologically distinct regions (→ **E**, italic letters) that generally have different functions (→ **E**). The *hemispheres* of the brain are closely connected by nerve fibers of the *corpus callosum* (→ **C1, D3**).

Cerebrospinal Fluid


The brain is surrounded by external and internal *cerebrospinal fluid (CSF) spaces* (→ **B**). The internal CSF spaces are called *ventricles*. The two lateral ventricles, I and II, (→ **B, C2**) are connected to the IIIrd and IVth ventricle and to the central canal of the spinal cord (→ **B**). Approximately 650 mL of CSF forms in the *choroid plexus* (→ **B, C4**) and drains through the *arachnoid villi* each day (→ **B**). The *blood–brain barrier* and the *blood–CSF barrier* prevents the passage of most substances except CO_2, O_2, water and lipophilic substances. (As an exception, the *circumventricular organs* of the brain such as the *organum vasculosum laminae terminalis* (OVLT; → p. 282) and the *area postrema* (→ p. 282) have a less tight blood–brain barrier.) Certain substances like glucose and amino acids can cross the blood–brain barrier with the aid of carriers, whereas proteins cannot. The ability or inability of a drug to cross the blood–brain barrier is an important factor in pharmacotherapeutics.

Lesions that obstruct the drainage of CSF (e.g. brain tumors) result in cerebral compression; in children, they lead to fluid accumulation (hydrocephalus).


A. Central nervous system (CNS)




B. Cerebrospinal fluid spaces of the brain




C. Brain: Cross-sectional view



D. Brain: Hemisection through middle



E. Areas of cortex



With our **senses**, we receive huge quantities of **information** from the surroundings (10^9 bits/s). Only a small portion of it is consciously perceived (10^1–10^2 bits/s); the rest is either subconsciously processed or not at all. Conversely, we transmit ca. 10^7 bits/s of information to the environment through speech and motor activity, especially facial expression (→ **A**).

A **bit** (binary digit) is a single unit of information (1 byte = 8 bits). The average page of a book contains roughly 1000 bits, and TV images convey more than 10^6 bits/s.

Stimuli reach the body in *different forms of energy*, e.g., electromagnetic (visual stimuli) or mechanical energy (e.g., tactile stimuli). Various *sensory receptors* or **sensors** for these stimuli are located in the five "classic" sense organs (eye, ear, skin, tongue, nose) at the body surface as well as inside the body (e.g., proprioceptors, vestibular organ). (In this book, sensory receptors are called sensors to distinguish them from binding sites for hormones and transmitters.) The sensory system extracts four stimulatory elements: *modality, intensity, duration, and localization*. Each type of sensor is specific for a unique or *adequate stimulus* that evokes specific sensory **modalities** such as sight, sound, touch, vibration, temperature, pain, taste, smell, as well as the body's position and movement, etc. Each modality has several *submodalities*, e.g., taste can be sweet or bitter, etc.

In **secondary sensors** (e.g., gustatory and auditory sensors), sensor and afferent fibers are separated by a synapse, whereas **primary sensors** (e.g., olfactory sensors and nocisensors) have their own afferent fibers.

A stimulus induces a change in *sensor potential* (**transduction**), which results in depolarization of the sensor cell (in most types; → **B1**) or hyperpolarization as in retinal sensors. The stronger the stimulus, the greater the *amplitude* of the sensor potential (→ **C1**). Once the sensor potential exceeds a certain threshold, it is **transformed** into an **action potential**, **AP** (→ **B1**; p. 46ff.).

Coding of signals. The stimulus is encoded in *AP frequency* (impulses/s = Hz), i.e., the higher the sensor potential, the higher the AP frequency (→ **C2**). This information is decoded at the next synapse: The higher the frequency of arriving APs, the higher the *excitatory postsynaptic potential* (EPSP; → 50ff.). New APs are fired by the postsynaptic neuron when the EPSP exceeds a certain threshold (→ **B2**).


Frequency coding of APs is a more reliable way of transmitting information over long distances than amplitude coding because the latter is much more susceptible to change (and falsification of its information content). At the synapse, however, the signal must be amplified or attenuated (by other neurons), which is better achieved by amplitude coding.

Adaptation. At constant stimulation, most sensors adapt, i.e., their potential decreases (→ p. 358). The potential of slowly adapting sensors becomes **p**roportional to stimulus intensity (*P sensors* or *tonic sensors*). Fast-adapting sensors respond only at the onset and end of a stimulus. They sense **d**ifferential changes in the stimulus intensity (*D sensors* or *phasic sensors*). *PD sensors* have both characteristics (→ p. 316).


Central processing. In a first phase, inhibitory and stimulatory impulses conducted to the CNS are integrated—e.g., to increase the *contrast* of stimuli (→ **D**; see also p. 360). In this case, stimulatory impulses originating from adjacent sensors are attenuated in the process (*lateral inhibition*). In a second step, a **sensory impression** of the stimuli (e.g. "green" or "sweet") takes form in low-level areas of the sensory cortex. This is the first step of subjective sensory physiology. Consciousness is a prerequisite for this process. Sensory impressions are followed by their interpretation. The result of it is called **perception**, which is based on experience and reason, and is subject to individual interpretation. The impression "green," for example, can evoke the perception "There is a tree" or "This is a meadow."

Absolute threshold (→ pp. 346ff., 358, 368), difference threshold (→ pp. 346ff., 358, 374), spatial and temporal summation (→ pp. 52, 358), receptive field (→ p. 360), habituation and sensitization are other important concepts of sensory physiology. The latter two mechanisms play an important role in learning processes (→ p. 340).


A. Reception, perception and transmission of information




B. Stimulus processing and information coding



C. Stimulus, sensor and action potential relationships



D. Contrasting



Somatovisceral sensibility is the collective term for all sensory input from receptors or *sensors* of the body (as opposed to the sensory organs of the head). It includes the areas of proprioception (→ p. 318), nociception (→ p. 320), and skin or surface sensitivity.

The **sense of touch** (taction) is essential for perception of *form, shape*, and *spatial nature* of objects (*stereognosis*). Tactile sensors are located predominantly in the palm, especially in the fingertips, and in the tongue and oral cavity. Stereognostic perception of an object requires that the CNS integrate signals from adjacent receptors into a spatial pattern and coordinate them with **tactile motor function**.

Mechanosensors. *Hairless areas* of the skin contain the following mechanosensors (→ **A**), which are afferently innervated by myelinated nerve fibers of class II/Aβ (→ p. 49 C):

- The spindle-shaped **Ruffini's corpuscle** (→ **A3**) partly encapsulates the afferent axon branches. This unit is a *slowly adapting* (SA) pressosensor of the **SA2** type. They are P sensors (→ p. 314). Thus, the greater the pressure on the skin (depth of indentation or weight of an object), the higher the AP frequency (→ **B1**).
- **Merkel's cells** (→ **A2**) are in synaptic contact to meniscus-shaped axon terminals. These complexes are pressure-sensitive **SA1** sensors. They are PD sensors (combination of **B1** and **B2**) since their AP frequency is not only dependent on the pressure intensity but also on the rate of its change (dp/dt).
- **Meissner's corpuscles** (→ **A1**) are composed of lamellar cell layers between which club-shaped axons terminate. This unit represents a *rapidly adapting* pressure sensor (**RA** *sensor*) that responds only to pressure changes, dp/dt (pure *D sensor* or *velocity sensor*). The RA sensors are specific for *touch* (skin indentation of 10–100 μm) and low-frequency *vibration* (10–100 Hz). **Hair follicle receptors** (→ **A5**), which respond to bending of the hairs, assume these functions in *hairy areas* of the skin.
- **Pacinian corpuscles** (→ **A4**) are innervated by a centrally situated axon. They *adapt very rapidly* and therefore respond to changes in pressure change velocity, i.e. to *acceleration* (d^2p/dt^2), and sense high-frequency vibration (100–400 Hz; indentation depths < 3 μm). The AP frequency is proportional to the vibration frequency (→ **B3**). These accelaration sensors also play a role in proprioception (→ p. 318).

Resolution. RA and SA1 sensors are densely distributed in the mouth, lips and fingertips, especially in the index and middle finger (about 100/cm²). They can distinguish closely adjacent stimuli as separate, i.e., each afferent axon has a *narrow receptive field*. Since the signals do not converge as they travel to the CNS, the ability of these sensors in the mouth, lips and fingertips to distinguish between two closely adjacent tactile stimuli, i.e. their *resolution*, is very high.


The **spatial threshold for two-point discrimination**, i.e., the distance at which two simultaneous stimuli can be perceived as separate, is used as a measure of tactile resolution. The spatial thresholds are roughly 1 mm on the fingers, lips and tip of the tongue, 4 mm on the palm of the hand, 15 mm on the arm, and over 60 mm on the back.

SA2 receptors and **pacinian corpuscles** have a broad receptive field (the exact function of SA2 receptors is not known). Pacinian corpuscles are therefore well adapted to detect vibrations, e.g., earth tremors.


Two types of **thermosensors** are located in the skin: *cold sensors* for temperatures < 36 °C and *warm sensors* for those > 36 °C. The lower the temperature (in the 20–36 °C range), the higher the AP frequency of the cold receptors. The reverse applies to warm receptors in the 36–43 °C range (→ **C**). Temperatures ranging from 20° to 40 °C are subject to *rapid adaptation of thermosensation* (PD characteristics). Water warmed, for example, to 25 °C initially feels cold. More extreme temperatures, on the other hand, are persistently perceived as cold or hot (this helps to maintain a constant core temperature and prevent skin damage). The density of these cold and warm sensors in most skin areas is low as compared to the much higher densities in the mouth and lips. (That is why the lips or cheeks are used for temperature testing.)

Different sensors are responsible for thermoception at temperatures exceeding 45 °C. These **heat sensors** are also used for the perception of pungent substances such as *capsaicin*, the active constituent of hot chili peppers. Stimulation of VR1 receptors (vanilloid receptor type 1) for capsaicin mediates the opening of cation channels in nociceptive nerve endings, which leads to their depolarization.


A. Skin sensors




B. Response of skin sensors for pressure (1), touch (2) and vibration (3)



C. Response of thermosensors



D. PD proprioception: Response to velocity and angle of joint flexion (text on next page)



Proprioception is the mechanism by which we sense the *strength* that our muscles develop as well as the *position* and *movement* of our body and limbs. The *vestibular organ* (→ p. 348) and *cutaneous mechanosensors* (→ p. 316) assist the *proprioceptors* in muscle spindles, joints and tendons. Sensors of *Golgi tendon organs* are located near muscle–tendon junctions.

Muscle spindles (→ **A1**) contain proportional (P) and differential (D) sensors for monitoring of **joint position** and **movement**. The *velocity of position change* is reflected by a transient rise in impulse frequency (D sensor; → p. 317 D1, spike), and the final joint *position* is expressed as a constant impulse frequency (P-sensor, → p. 317 D2, plateau). Muscle spindles function to **regulate muscle length**. They lie parallel to the skeletal muscle fibers (*extrafusal muscle fibers*) and contain their own muscle fibers (*intrafusal muscle fibers*). There are two types of intrafusal muscle fibers: (1) *nuclear chain fibers* (P sensors) and (2) *nuclear bag fibers* (D sensors). The endings of *type Ia* afferent neurons coil around both types, whereas *type II* neurons wind around the nuclear chain fibers only (neuron types described on p. 49 C). These *annulospiral endings* detect longitudinal stretching of intrafusal muscle fibers and report their length (type Ia and II afferents) and changes in length (Ia afferents) to the spinal cord. The efferent γ *motoneurons* (fusimotor fibers) innervate both intrafusal fiber types, allowing variation of their length and stretch sensitivity (→ **A1, B1**).

Golgi tendon organs (→ **A2**) are arranged in series with the muscle and respond to the contraction of only a few motor units or more. Their primary function is to **regulate muscle tension**. Impulses from Golgi tendon organs (conveyed by *type Ib* afferents), the skin and joints, and muscle spindles (some of which are type Ia and II afferent fibers), as well as descending impulses, are jointly integrated in *type Ib interneurons* of the spinal cord; this is referred to as **multimodal integration** (→ **D2**). Type Ib interneurons inhibit α motoneurons of the muscle from which the Ib afferent input originated (*autogenous inhibition*) and activate antagonistic muscles via excitatory interneurons (→ **D5**).

Monosynaptic stretch reflex (→ **C**). Muscles spindles are also affected by sudden stretching of a skeletal muscle, e.g. due to a tap on the tendon attaching it. Stretching of the muscle spindles triggers the activation of type Ia afferent impulses (→ **B2, C**), which enter the spinal cord via the dorsal root and terminate in the ventral horn at the α motoneurons of the same muscle. This type Ia afferent input therefore induces contraction of the same muscle by only one synaptic connection. The reflex time for this monosynaptic stretch reflex is therefore very short (ca. 30 ms). This is classified as a *proprioceptive reflex,* since the stimulation and response arise in the same organ. The monosynaptic stretch reflex **functions** to rapidly correct "involuntary" changes in muscle length and joint position.


Supraspinal activation (→ **B3**). Voluntary muscle contractions are characterized by *co-activation* of α and γ neurons. The latter adjust the muscle spindles (length sensors) to a certain set-point of length. Any deviations from this set-point due, for example, to unexpected shifting of weight, are compensated for by readjusting the α-innervation (*load compensation reflex*). Expected changes in muscle length, especially during complex movements, can also be more precisely controlled by (centrally regulated) γ fiber activity by increasing the preload and stretch sensitivity of the intrafusal muscle fibers (*fusimotor set*).

Hoffmann's reflex can be also used to test the stretch reflex pathway. This can be done by positioning electrodes on the skin over (mixed) muscle nerves and subsequently recording the muscle contraction induced by electrical stimuli of different intensity.

Polysynaptic circuits, also arising from type II afferents complement the stretch reflex. If a stretch reflex (e.g., knee-jerk reflex, → **C, D**) occurs in an extensor muscle, the α motoneurons of the antagonistic flexor muscle must be inhibited via *inhibitory Ia interneurons* to achieve efficient extension (→ **D1**).


Deactivation of stretch reflex is achieved by inhibiting muscle contraction as follows: 1) The muscle spindles relax, thereby allowing the deactivation of type Ia fibers; 2) the Golgi tendon organs inhibit the α motoneurons via type Ib interneurons (→ **D2**); 3) the α motoneurons are inhibited by the interneurons (*Renshaw cells*; → **D4**) that they themselves stimulated via axon collaterals (*recurrent inhibition*; → **D3**; p. 323 C1).

A. Muscle spindles (1) and Golgi tendon organs (2)




B. Muscle spindle function

1 Initial length of muscle




2 Spindle activated by "involuntary" muscle stretching




Reflex contraction of skeletal muscle to bring muscle back to initial length

3 Supraspinal activation


"Voluntary" change in muscle length with pre-setting (via γ fibers) of
– a set-point for length (α/γ co-activation)
– an increased sensor sensitivity (fusimotor set)



C. Monosynaptic stretch reflex



D. Polysynaptic circuits



Pain is an unpleasant sensory experience associated with discomfort. It is protective insofar as it signals that the body is being threatened by an injury (*noxa*). *Nociception* is the perception of noxae via *nocisensors*, neural conduction and central processing. The *pain* that is ultimately felt is a subjective experience. Pain can also occur without stimulation of nocisensors, and excitation of nocisensors does not always evoke pain.

All body tissues except the brain and liver contain sensors for pain, i.e., **nocisensors** or *nociceptors* (→ **A**). Nocisensors are bead-like endings of peripheral axons, the somata of which are located in dorsal root ganglia and in nuclei of the trigeminal nerve. Most of these fibers are slowly conducting C fibers (< 1 m/s); the rest are myelinated Aδ fibers (5–30 m/s; fiber types described on p. 49 C).

When an injury occurs, one first senses sharp "fast pain" (Aδ fibers) before feeling the dull "slow pain" (C fibers), which is felt longer and over a broader area. Since nocisensors do not adapt, the pain can last for days. Sensitization can even lower the stimulus threshold.

Most nocisensors are **polymodal sensors** (C fibers) activated by mechanical stimuli, chemical mediators of inflammation, and high-intensity heat or cold stimuli. **Unimodal nociceptors**, the less common type, consist of *thermal nocisensors* (Aδ fibers), *mechanical nocisensors* (Aδ fibers), and "*dormant" nocisensors*. Thermal nocisensors are activated by extremely hot (> 45 °C) or cold (< 5 °C) stimuli (→ p. 316). Dormant nocisensors are chiefly located in internal organs and are "awakened" after prolonged exposure (sensitization) to a stimulus, e.g., inflammation.

Nocisensors can be inhibited by opioids (**desensitization**) and stimulated by prostaglandin E_2 or bradykinin, which is released in response to inflammation (**sensitization**; → **A**). Endogenous opioids (e.g., dynorphin, enkephalin, endorphin) and exogenous opioids (e.g., morphium) as well as inhibitors of prostaglandin synthesis (e.g. acetylsalicyclic acid [Aspirin®]; → p. 271) are therefore able to alleviate pain (*analgesic action*).

Inflammatory sensitization (e.g., sunburn) lowers the threshold for noxious stimuli, leading to excessive sensitivity (*hyperalgesia*) and additional pain resulting from non-noxious stimuli to the skin (*allodynia*), e.g., touch or warm water (37 °C). Once the nocisensors are stimulated, they start to release neuropeptides such as substance P or CGRP (calcitonin gene-related peptide) that cause inflammation of the surrounding vessels (**neurogenic inflammation)**.

Projected pain. Damage to nociceptive fibers causes pain (neurogenic or neuropathic) that is often projected to and perceived as arising from the periphery. A prolapsed disk compressing a spinal nerve can, for example, cause leg pain. Nociceptive fibers can be blocked by cold or local anesthesia.


Nociceptive tracts (→ **C1**). The central axons of nociceptive somatic neurons and nociceptive afferents of internal organs end on neurons of the dorsal horn of the spinal cord. In many cases, they terminate on the same neurons as the skin afferents.

Referred pain (→ **B**). Convergence of somatic and visceral nociceptive afferents is probably the main cause of referred pain. In this type of pain, noxious visceral stimuli cause a perception of pain in certain skin areas called **Head's zones**. That for the heart, for example, is located mainly in the chest region. Myocardial ischemia is therefore perceived as pain on the surface of the chest wall (angina pectoris) and often also in the lower arm and upper abdominal region.

In the spinal cord, the neuroceptive afferents cross to the opposite side (decussation) and are conducted in the **tracts of the anterolateral funiculus**—mainly in the spinothalamic tract—and continue centrally via the brain stem where they join nociceptive afferents from the head (mainly trigeminal nerve) to the **thalamus** (→ **C1**). From the ventrolateral thalamus, sensory aspects of pain are projected to S1 and S2 areas of the **cortex**. Tracts from the medial thalamic nuclei project to the limbic system and other centers.

Components of pain. Pain has a *sensory component* including the conscious perception of site, duration and intensity of pain; a *motor component* (e.g., defensive posture and withdrawal reflex; → p. 322), an *autonomic component* (e.g., tachycardia), and an *affective component* (e.g., aversion). In addition, **pain assessments** based on the memory of a previous pain experience can lead to **pain-related behavior** (e.g., moaning).

In the thalamus and spinal cord, nociception can be **inhibited via descending tracts** with the aid of various transmitters (mainly opioids). The nuclei of these tracts (→ **C2**, blue) are located in the *brain stem* and are mainly activated via the nociceptive spinoreticular tract (negative feedback loop).


A. Nociception
Sensitization
via bradykinin,
prostaglandin E_2,
serotonin
Acute
noxa
Nocisensor
Desensitization
via opioids,
SIH, galanin, etc.
B. Referred pain
Converging
neurons
From
skin
Ischemia
From
heart
C. Ascending and descending tracts for nociception
1 Ascending nociceptive tracts
2 Descending nociceptive tracts
(mainly inhibitory)
Cortex
Medial
thalamus
Lateral
thalamus
Hypo-
thalamus
Skin of face and cornea
Nocisensors
C fiber
Aδ fiber
Trigeminal
nerve
Motoaxon
Brain stem
Spinothalamic
tract
Skin of trunk and limbs
Nocisensors
Aδ fiber
C fiber
Sympathetic
axon
Motoaxon
Spinal cord
Hypo-
thalamus
Central
gray layer
Lateral
reticular
formation
Nucleus
raphe
magnus
Medial
reticular
formation
Segmental
inhibition
(Aβ afferents)
(After R. F. Schmidt)

Unlike proprioceptive reflexes (→ p. 318), polysynaptic reflexes are activated by sensors that are spatially separate from the effector organ. This type of reflex is called *polysynaptic*, since the reflex arc involves many synapses in series. This results in a relatively *long reflex time*. The intensity of the response is dependent on the duration and intensity of stimulus, which is temporally and spatially summated in the CNS (→ p. 52). Example: itching sensation in nose ⇒ sneezing. The response spreads when the stimulus intensity increases (e.g., coughing ⇒ choking cough). *Protective reflexes* (e.g., withdrawal reflex, corneal and lacrimal reflexes, coughing and sneezing), *nutrition reflexes* (e.g., swallowing, sucking reflexes), *locomotor reflexes*, and the various *autonomic reflexes* are polysynaptic reflexes. Certain reflexes, e.g., plantar reflex, cremasteric reflex and abdominal reflex, are used as diagnostic tests.

Withdrawal reflex (→ **A**). *Example*: A painful stimulus in the sole of the right foot (e.g., stepping on a tack) leads to flexion of all joints of that leg (**flexion reflex**). Nociceptive afferents (→ p. 320) are conducted via stimulatory interneurons (→ **A1**) in the spinal cord to motoneurons of ipsilateral *flexors* and via inhibitory interneurons (→ **A2**) to motoneurons of ipsilateral *extensors* (→ **A3**), leading to their relaxation; this is called *antagonistic inhibition*. One part of the response is the **crossed extensor reflex**, which promotes the withdrawal from the injurious stimulus by increasing the distance between the nociceptive stimulus (e.g. the tack) and the nocisensor and helps to support the body. It consists of contraction of extensor muscles (→ **A5**) and relaxation of the flexor muscles in the contralateral leg (→ **A4, A6**). Nociceptive afferents are also conducted to other segments of the spinal cord (ascending and descending; → **A7, A8**) because different extensors and flexors are innervated by different segments. A noxious stimulus can also trigger flexion of the ipsilateral arm and extension of the contralateral arm (*double crossed extensor reflex*). The noxious stimulus produces the perception of pain in the brain (→ p. 318).

Unlike monosynaptic stretch reflexes, polysynaptic reflexes occur through the *co-activation of α and γ motoneurons* (→ p. 318). The *reflex excitability* of α motoneurons is largely **controlled by supraspinal centers** via multiple interneurons (→ p. 326). The brain can therefore shorten the reflex time of spinal cord reflexes when a noxious stimulus is anticipated.


Supraspinal lesions or interruption of descending tracts (e.g., in paraplegics) can lead to exaggeration of reflexes (**hyperreflexia**) and stereotypic reflexes. The absence of reflexes (**areflexia**) corresponds to specific disorders of the spinal cord or peripheral nerve.


Synaptic Inhibition


GABA (γ-aminobutyric acid) and glycine (→ p. 55f.) function as inhibitory transmitters in the spinal cord. **Presynaptic inhibition** (→ **B**) occurs frequently in the CNS, for example, at synapses between type Ia afferents and α motoneurons, and involves *axoaxonic synapses* of GABAergic interneurons at presynaptic nerve endings. GABA exerts inhibitory effects at the nerve endings by increasing the membrane conductance to Cl^- ($GABA_A$ receptors) and K^+ ($GABA_B$ receptors) and by decreasing the conductance to Ca^{2+} ($GABA_B$ receptors). This decreases the release of transmitters from the nerve ending of the target neuron (→ **B2**), thereby lowering the amplitude of its postsynaptic EPSP (→ p. 50). The *purpose* of presynaptic inhibition is to reduce certain influences on the motoneuron without reducing the overall excitability of the cell.

In **postsynaptic inhibition** (→ **C**), an *inhibitory interneuron* increases the membrane conductance of the postsynaptic neuron to Cl^- or K^+, especially near the axon hillock, thereby short-circuiting the depolarizing electrical currents from excitatory EPSPs (→ p. 52ff.).

The interneuron responsible for postsynaptic inhibition is either activated by feedback from axonal collaterals of the target neurons (**recurrent inhibition** of motoneurons via glycinergic Renshaw cells; → **C1**) or is directly activated by another neuron via feed-forward control (→ **C2**). Inhibition of the ipsilateral extensor (→ **A2, A3**) in the flexor reflex is an example of *feed-forward inhibition*.


A. Withdrawal reflex
Activated motoneuron
Inhibited motoneuron
Afferent neuron
Left flexors relaxed
Left extensors contracted
Right extensors relaxed
Right flexors contracted
1
2
3
4
5
6
7
8
Stimulatory interneuron
Inhibitory interneuron
Nociception in right foot


B. Presynaptic inhibition
1 Uninhibited
e.g. Ia afferent
Inhibitory interneuron
Stimulatory transmitter
e.g. α motoneuron
mV
0
AP
s
2 Inhibited
Inhibitory transmitter
Stimulatory transmitter
mV
0
s


C. Postsynaptic inhibition
1
Feedback inhibition
2
Feed-forward inhibition
Renshaw cell
Axon collaterals
Inhibitory interneuron
To agonist (e.g., flexor)
To antagonist (e.g., extensor)

The **posterior funiculus–lemniscus system** (→ **C**, green) is the principal route by which the somatosensory cortex S1 (postcentral gyrus) receives sensory input from skin sensors and propriosensors. Messages from the skin (*superficial sensibility*) and locomotor system (*proprioceptive sensibility*) reach the spinal cord via the *dorsal roots*. Part of these primarily afferent fibers project in *tracts of the posterior funiculus* without synapses to the *posterior funicular nuclei* of the caudal medulla oblongata (nuclei cuneatus and gracilis). The tracts of the posterior funiculi exhibit a somatotopic arrangement, i.e., the further cranial the origin of the fibers the more lateral their location. At the *medial lemniscus*, the secondary afferent somatosensory fibers cross to the contralateral side (decussate) and continue to the posterolateral ventral nucleus (PLVN) of the **thalamus**, where they are also somatotopically arranged. The secondary afferent trigeminal fibers (lemniscus trigeminalis) end in the *posteromedial ventral nucleus* (PMVN) of the thalamus. The tertiary afferent somatosensory fibers end at the quaternary somatosensory neurons in the **somatosensory cortex S1**. The main **function** of the posterior funiculus–lemniscus pathway is to relay information about tactile stimuli (pressure, touch, vibration) and joint position and movement (proprioception) to the brain cortex via its predominantly rapidly conducting fibers with a high degree of spatial and temporal resolution.

As in the motor cortex (→ p. 327 B), each body part is assigned to a corresponding projection area in the **somatosensory cortex S1** (→ **A**) following a *somatotopic arrangement* (→ **B**). Three features of the organization of S1 are (1) that one hemisphere of the brain receives the information from the contralateral side of the body (tracts decussate in the medial lemniscus; → **C**); (2) that most neurons in S1 receive afferent signals from tactile sensors in the fingers and mouth (→ p. 316); and (3) that the afferent signals are processed in columns of the cortex (→ p. 335 A) that are activated by specific types of stimuli (e.g., touch).


Anterolateral spinothalamic pathway (→ **C**; violet). Afferent signals from nocisensors, thermosensors and the second part of pressure and touch afferent neurons are already relayed (partly via interneurons) at various levels of the *spinal cord*. The secondary neurons cross to the opposite side at the corresponding segment of the spinal cord, form the lateral and ventral *spinothalamic tract* in the anterolateral funiculus, and project to the thalamus (PLVN). The tertiary afferent fibers then reach the somatosensory cortex S1.

Descending tracts (from the cortex) can inhibit the flow of sensory input to the cortex at all relay stations (spinal cord, medulla oblongata, thalamus). The main function of these tracts is to modify the receptive field and adjust stimulus thresholds. When impulses from different sources are conducted in a common afferent, they also help to suppress unimportant sensory input and selectively process more important and interesting sensory modalities and stimuli (e.g., eavesdropping).


Hemiplegia. (→ **D**) *Brown–Séquard syndrome* occurs due to hemisection of the spinal cord, resulting in ipsilateral paralysis and loss of various functions below the lesion. The injured side exhibits *motor paralysis* (initially flaccid, later spastic) and loss of tactile sensation (e.g., impaired two-point discrimination, → p. 316). An additional loss of pain and temperature sensation occurs on the contralateral side (*dissociated paralysis*).

Reticular activating system. (→ **E**) The sensory input described above as well as the input from the sensory organs are specific, whereas the reticular activating system (RAS) is an *unspecific system*. The RAS is a complex processing and integrating system of cells of the *reticular formation* of the brainstem. These cells receive *sensory input* from all sensory organs and ascending spinal cord pathways (e.g., eyes, ears, surface sensitivity, nociception), basal ganglia, etc. Cholinergic and adrenergic output from the RAS is conducted along descending pathways to the spinal cord and along ascending "unspecific" thalamic nuclei and "unspecific" thalamocortical tracts to almost all cortical regions (→ p. 335 A), the limbic system and the hypothalamus. The ascending RAS or **ARAS** controls the state of consciousness and the degree of wakefulness (*arousal activity*; → p. 338).


A. Sensory centers of the brain




B. Somatotopic organization of S1




C. Somatosensory tracts



D. Hemiplegia


Right half of spinal cord severed between L1 and L2
Motor tracts
Tracts of the posterior funiculus
Tracts of the antero-lateral funiculus
Ipsilateral
Contralateral
Loss of tactile sensation
Motor paralysis
Loss of nociception and temperature sensation

E. Unspecific system



Coordinated muscular movements (walking, grasping, throwing, etc.) are functionally dependent on the *postural motor system*, which is responsible for maintaining upright posture, balance, and spatial integration of body movement. Since control of postural motor function and muscle coordination requires the simultaneous and uninterrupted flow of sensory impulses from the periphery, this is also referred to as **sensorimotor function**.

α **motoneurons** in the anterior horn of the spinal cord and in cranial nerve nuclei are the terminal tracts for skeletal muscle activation. Only certain parts of the corticospinal tract and type Ia afferents connect to α motoneurons monosynaptically. Other afferents from the periphery (propriosensors, nocisensors, mechanosensors), other spinal cord segments, the motor cortex, cerebellum, and motor centers of the brain stem connect to α motoneurons via hundreds of inhibitory and stimulatory interneurons per motoneuron.

Voluntary motor function. Voluntary movement requires a series of actions: decision to move ⇒ programming (recall of stored subprograms) ⇒ command to move ⇒ execution of movement (→ **A1–4**). Feedback from afferents (re-afferents) from motor subsystems and information from the periphery is constantly integrated in the process. This allows for adjustments before and while executing voluntary movement.

The neuronal activity associated with the first two phases of voluntary movement activates numerous motor areas of the cortex. This electrical brain activity is reflected as a negative **cortical expectancy potential**, which can best be measured in association areas and the vertex. The more complex the movement, the higher the expectancy potential and the earlier its onset (roughly 0.3–3 s).

The **motor cortex** consists of three main areas (→ **C**, top; → see p. 313 E for area numbers): (a) *primary motor area*, M1 (area 4), (b) *premotor area*, PMA (lateral area 6); and (c) *supplementary motor area*, SMA (medial area 6). The motor areas of the cortex exhibit somatotopic organization with respect to the target muscles of their fibers (shown for M1 in **B**) and their mutual connections.

Cortical afferents. The cortex receives motor input from (a) the *body periphery* (via thalamus ⇒ S1 [→ p. 325 A] ⇒ sensory association cortex ⇒ PMA); (b) the *basal ganglia* (via thalamus ⇒ M1, PMA, SMA [→ **A2**] ⇒ prefrontal association cortex); (c) the *cerebellum* (via thalamus ⇒ M1, PMA; → **A2**); and (d) sensory and posterior parietal areas of the *cortex* (areas 1–3 and 5–7, respectively).

Cortical efferents. (→ **C, D, E, F**) Motor output from the cortex is mainly projected to (a) the spinal cord, (b) subcortical motor centers (see below and p. 330), and (c) the contralateral cortex via commissural pathways.

The **pyramidal tract** includes the *corticospinal tract* and part of the *corticobulbar tract*. Over 90% of the pyramidal tract consists of thin fibers, but little is known about their function. The thick, rapidly conducting **corticospinal tract** (→ **C**) project to the spinal cord from areas 4 and 6 and from areas 1–3 of the sensory cortex. Some of the fibers connect monosynaptically to α and γ motoneurons responsible for finger movement (precision grasping). The majority synapse with interneurons of the spinal cord, where they influence input from peripheral afferents as well as motor output (via Renshaw's cells) and thereby spinal reflexes.

Function of the Basal Ganglia

Circuitry. The basal ganglia are part of multiple parallel **corticocortical signal loops**. *Associative loops* arising in the frontal and limbic cortex play a role in mental activities such as assessment of sensory information, adaptation of behavior to emotional context, motivation, and long-term action planning. The function of the *skeletomotor* and *oculomotor loops* (see below) is to coordinate and control the velocity of movement sequences. Efferent projections of the basal ganglia *control thalamocortical signal conduction* by (a) attenuating the inhibition (*disinhibiting effect*, direct mode) of the *thalamic motor nuclei* and the *superior colliculus*, respectively, or (b) by intensifying their inhibition (indirect mode).

The principal **input** to the basal ganglia comes from the putamen and caudate nucleus, which are collectively referred to as the **striatum**. Neurons of the striatum are activated by tracts from the entire **cortex** and use *glutamate* as their transmitter (→ **D**). Once activated, ▶

A. Events from decision to move to execution of movement

1 Decision

Cortical and subcortical motivation areas

Associative cortex

"I want the ball"

Somato-sensory function

1a Impulse to move

"Here's how to get it"

1b Strategy

Hearing

Vision

2 Programming

"Here's the program"

(participating muscles, temporal sequence, strength of contraction)

Area 6

Area 4

Basal ganglia

Cere-bellum

Motor cortex

Cerebellum

Basal ganglia

Motor thalamus

3 Command to move

"Now do it!"

Sensory feedback

Reflex systems, motoneurons

(After V. B. Brooks)

4 Execution of movement

Photo: M. Jeannerod

C. Descending motor tracts

SMA (area 6, medial)

PMA (area 6, lateral)

M1 (area 4)

S1 (areas 1–3)

Area 5 and 7

Cortex

Internal capsule

Pyramidal tract

Tracts to
- Striatum (some **x**)
- Thalamus (some **x**)
- Red nucleus (**x**)
- Pons
- Olive
- Reticular formation (some **x**)

Pons

Cortico-bulbar tract

To nuclei cuneatus and gracilis (**x**)

Pyramidal decussation

x = decussate

Lateral cortico-spinal tract (**x**)

Ventral cortico-spinal tract

Spinal cord

α and γ motoneurons and interneurons

B. Somatotopic organization of primary motor area (M1) of the cortex

Tongue

Throat

▶ neurons of the striatum release an inhibitory transmitter (GABA) and a co-transmitter—either *substance P* (SP) or *enkephalin* (Enk., → **D**; → p. 55). The principal **output** of the basal ganglia runs through the *pars reticularis of the substantia nigra* (**SNr**) and the *pars interna of the globus pallidus* (**GPi**), both of which are inhibited by SP/GABAergic neurons of the striatum (→ **D**).

Both SNr and GPi inhibit (by GABA) the ventrolateral thalamus with a high level of spontaneous activity. Activation of the striatum therefore leads to **disinhibition of the thalamus** by this **direct pathway**. If, however, enkephalin/GABA-releasing neurons of the striatum are activated, then they inhibit the *pars externa* of the *globus pallidus* (**GPe**) which, in turn, inhibits (by GABA) the subthalamic nucleus. The subthalamic nucleus induces glutamatergic activation of SNr and GPi. The ultimate effect of this **indirect pathway** is **increased thalamic inhibition**. Since the thalamus projects to motor and prefrontal cortex, a corticothalamocortical loop that influences skeletal muscle movement (**skeletomotor loop**) via the putamen runs through the basal ganglia. An **oculomotor loop** projects through the caudate nucleus, pars reticularis and superior colliculus and is involved in the control of eye movement (→ pp. 348, 366). *Descending tracts* from the SNr project to the tectum and nucleus pedunculus pontinus.

The fact that the *pars compacta of the substantia nigra* (**SNc**) showers the entire striatum with **dopamine** (dopaminergic neurons) is of pathophysiological importance (→ **D**). On the one hand, dopamine binds to D1 receptors (rising cAMP levels), thereby activating SP/GABAergic neurons of the striatum; this is the direct route (see above). On the other hand, dopamine also reacts with D2 receptors (decreasing cAMP levels), thereby inhibiting enkephalin/GABAergic neurons; this is the indirect route. These effects of dopamine are essential for normal striatum function. Degeneration of more than 70% of the dopaminergic neurons of the pars compacta results in *excessive inhibition* of the motor areas of the thalamus, thereby impairing voluntary motor function. This occurs in **Parkinson's disease** and can be due genetic predisposition, trauma (e.g., boxing), cerebral infection and other causes. The characteristic **symptoms** of disease include poverty of movement (*akinesia*), slowness of movement (*bradykinesia*), a festinating gait, small handwriting (*micrography*), masklike facial expression, muscular hypertonia (*rigor*), bent posture, and a *tremor* of resting muscles ("money-counting" movement of thumb and fingers).

Function of the Cerebellum


The cerebellum contains as many neurons as the rest of the brain combined. It is an important **control center for motor function** that has afferent and efferent connections to the cortex and periphery (→ **F**, **top** panel). The cerebellum is involved in the planning, execution and control of movement and is responsible for motor adaptation to new movement sequences (*motor learning*). It is also cooperates with higher centers to control attention, etc.

Anatomy (→ **F, top**). The *archeocerebellum* (flocculonodular lobe) and *paleocerebellum* (pyramids, uvula, paraflocculus and parts of the anterior lobe) are the phylogenetically older parts of the cerebellum. These structures and the pars intermedia form the **median cerebellum**. The *neocerebellum* (posterior lobe of the body of the cerebellum) is the phylogenetically younger part of the cerebellum and forms the **lateral cerebellum**. Based on the origin of their principal efferents, the archicerebellum and vermis are sometimes referred to as the *vestibulocerebellum*, the paleocerebellum as the *spinocerebellum*, and the neocerebellum as the *pontocerebellum*. The cerebellar cortex is the folded (fissured) superficial gray matter of the cerebellum consisting of an outer molecular layer of Purkinje cell dendrites and their afferents, a middle layer of Purkinje cells (Purkinje somata), and an inner layer of granular cells. The outer surface of the cerebellum exhibits small, parallel convolutions called *folia*.


The **median cerebellum** and pars intermedia of the cerebellum mainly control postural and supportive motor function (→ **F1,2**) and oculomotor function (→ pp. 348 and 366). **Input:** The median cerebellum receives *afference copies* of spinal, vestibular and ocular origin and *efference copies* of descending motor signals to the skeletal muscles. **Output** from the median cerebellum flows through the intracerebellar fastigial, globose, and emboliform nuclei to motor centers of the spinal cord and brain stem and to extracerebellar vestibular nuclei (mainly Deiter's nucleus). These centers control oculomotor function and influence locomotor and postural/supportive motor function via the vestibulospinal tract.

The **lateral cerebellum** (hemispheres) mainly takes part in programmed movement (→ **F3**), but its plasticity also permits motor adaptation and the learning of motor sequences. The hemispheres have two-way ▶

D. Basal ganglia: afferent and efferent tracts



E. Centers, tracts and afferents for postural motor function



▶ connections to the cortex. **Input**: **a.** Via the pontine nuclei and mossy fibers, the lateral cerebellum receives input from cortical centers for movement planning (e.g., parietal, prefrontal and premotor *association cortex*; sensorimotor and visual areas). **b.** It also receives input from cortical and subcortical motor centers via the inferior olive and climbing fibers (see below). **Output** from the lateral cerebellum projects across motor areas of the thalamus from the dentate nucleus to motor areas of the cortex.

Lesions of the *median cerebellum* lead to disturbances of balance and oculomotor control (vertigo, nausea, pendular nystagmus) and cause trunk and gait ataxia. Lesions of the *lateral cerebellum* lead to disturbances of initiation, coordination and termination of goal-directed movement and impair the rapid reprogramming of diametrically opposing movement (diadochokinesia). The typical patient exhibits tremor when attempting voluntary coordinated movement (*intention tremor*), difficulty in measuring the distances during muscular movement (*dysmetria*), pendular rebound motion after stopping a movement (*rebound phenomenon*), and inability to perform rapid alternating movements (*adiadochokinesia*).

The cerebellar cortex exhibits a uniform neural **ultrastructure and circuitry**. All **output** from the cerebellar cortex is conducted via neurites of approximately 15×10^6 Purkinje cells. These GABAergic cells project to and *inhibit* neurons of the fastigial, emboliform, dentate, and lateral vestibular nuclei (Deiter's nucleus; → **F**, **right** panel).

Input and **circuitry**: Input from the spinal cord (spinocerebellar tracts) is relayed by the *inferior olive* and projected via stimulatory (1 : 15 diverging) **climbing fibers** that terminate on a band of Purkinje cells extending across the folia of the cerebellum, forming the *sagittal excitatory foci*. The climbing fibers use aspartate as their transmitter. Serotoninergic fibers from the raphe nuclei and noradrenergic fibers from the locus caeruleus terminate also on the excitatory foci. **Mossy fibers** (pontine, reticular and spinal afferents) excite the granular cells. Their axons form T-shaped branches (*parallel fibers*). In the molecular layer, they densely converge (ca. $10^5 : 1$) on strips of Purkinje cells that run alongside the folium; these are called *longitudinal excitatory foci*. It is assumed that the climbing fiber system (at the "crossing points" of the perpendicular excitatory foci) amplify the relatively weak signals of mossy fiber afferents to Purkinje cells. Numerous interneurons (Golgi, stellate and basket cells) heighten the contrast of the excitatory pattern on the cerebellar cortex by lateral and recurrent inhibition.


Postural Motor Control

Simple *stretch reflexes* (→ p. 318) as well as the more complicated *flexor reflexes* and *crossed extensor reflexes* (→ p. 322) are controlled at the level of the **spinal cord**.

Spinal cord transection (paraplegia) leads to an initial loss of peripheral reflexes below the lesion (areflexia, spinal shock), but the reflexes can later be provoked in spite of continued transection.

The spinal reflexes are mainly subordinate to supraspinal centers (→ **E**). Postural motor function is chiefly controlled by **motor centers of the brain stem** (→ **E1**), i.e., the *red nucleus*, vestibular nuclei (mainly *lateral vestibular nucleus*), and parts of the *reticular formation*. These centers function as relay stations that pass along information pertaining to postural and labyrinthine **postural reflexes** required to maintain *posture* and *balance* (involuntary). Postural reflexes function to regulate muscle tone and eye adaptation movements (→ p. 349 B). **Input** is received from the equilibrium organ (*tonic labyrinthine reflexes*) and from proprioceptors in the neck (*tonic neck reflexes*). The same afferents are involved in postural reflexes (labyrinthine and neck reflexes) that help to maintain the body in its normal position. The trunk is first brought to its normal position in response to inflow from neck proprioceptors. Afferents projecting from the cerebellum, cerebral motor cortex (→ **C**), eyes, ears, and olfactory organ as well as skin receptors also influence postural reflexes. *Statokinetic reflexes* also play an important role in the control of body posture and position. They play a role e.g. in startle reflexes and nystagmus (→ p. 366).

Descending tracts to the spinal cord arising from the red nucleus and medullary reticular formation (*rubrospinal* and *lateral reticulospinal tracts*) have a generally inhibitory effect on α and γ motoneurons (→ p. 318) of extensor muscles and an excitatory effect on flexor muscles (→ **E2**). Conversely, the tracts from Deiter's nucleus and the pontine areas of the reticular formation (*vestibulospinal* and *medial reticulospinal tracts*) inhibit the flexors and excite the α and γ fibers of the extensors.



Transection of the brain stem below the red nucleus leads to *decerebrate rigidity* because the extensor effect of Deiter's nucleus predominates.

The **integrating and coordinating function** of the sensorimotor system can be illustrated in two tennis players. When one player serves, the body of the other player moves to meet the ball (*goal-directed movement*) while using the right leg for support and the left arm for balance (*postural motor control*). The player keeps his eye on the ball (*oculomotor control*) and the visual area of the cortex assesses the trajectory and velocity of the ball. The associative cerebral cortex initiates the movement of returning the ball while taking the ball, net, other side of the court, and position of the opponent into consideration. Positional adjustments may be necessary when returning the ball. Using the movement concept programmed in the cerebellum and basal ganglia, the motor cortex subsequently executes the directed movement of returning the ball. In doing so, the player may "slice" the ball to give it an additional spinning motion (*acquired rapid directed movement*).

The **hypothalamus** coordinates all autonomic and most endocrine processes (→ p. 266ff.) and integrates signals for control of internal milieu, sleep–wake cycle, growth, mental/physical development, reproduction and other functions. The hypothalamus receives numerous sensory and humoral signals (→ **A**). Peptide hormones can circumvent the blood–brain barrier by way of the *circumventricular organs* (→ p. 282).

Afferents. *Thermosensors* for control of body temperature (→ p. 226), *osmosensors* for regulation of osmolality and water balance (→ p. 168), and glucose sensors for maintenance of a minimum *glucose concentration* are located within the hypothalamus. Information about the current status of the internal milieu is neuronally projected to the hypothalamus from distant sensors, e.g., thermosensors in the *skin*, osmosensors in the *liver* (→ p. 170), and stretch sensors in the cardiac *atria* (→ p. 216ff.). The hypothalamus/circumventricular organs also contain receptors for various hormones (e.g., for cortisol and angiotensin II), some of which form part of control loops for energy metabolism and metabolic homeostasis (e.g., receptors for cortisol, ACTH, CRH, leptin, and CCK). For functions related to *growth* and *reproduction*, the hypothalamus receives hormonal signals from the gonads and input from neuronal afferents that report cervical widening at the beginning of the birth process and breast stimulation (suckling reflexes), among other things.

The **limbic system** (→ **A**) and other areas of the brain influence hypothalamic function. The limbic system controls inborn and acquired *behavior* ("*program selection*") and is the seat of instinctive behavior, emotions and motivation ("inner world"). It controls the expression of emotions conveying important *signals to the environment* (e.g., fear, anger, wrath, discomfort, joy, happiness). Inversely, signals from the environment (e.g., odors) are closely associated to behavior.

The limbic system has *cortical components* (hippocampus, parahippocampal gyrus, cingulate gyrus, parts of olfactory brain) and *subcortical components* (amygdaloid body, septal nuclei, anterior thalamic nucleus). It has reciprocal connections to the lateral hypothalamus (chiefly used for recall of "programs", see below) and to the temporal and frontal cortex.

Its connections to the **cortex** are primarily used to perceive and assess signals from the "outer world" and from memories. Processing of both types of input is important for behavior.


Programmed behavior (→ **A**). The lateral hypothalamus has various programs to control lower hormonal, autonomic and motor processes. This is reflected internally by numerous autonomic and hormonal activities, and is reflected outwardly by different types of behavior.

Different programs exist for different behavioral reactions, for example:

- **Defensive behavior** ("fight or flight"). This program has somatic (repulsive facial expression and posture, flight or fight behavior), hormonal (epinephrine, cortisol) and autonomic (sympathetic nervous system) components. Its activation results in the release of energy-rich free fatty acids, the inhibition of insulin release, and a decrease in blood flow to the gastrointestinal tract as well as to rises in cardiac output, respiratory rate, and blood flow to the skeletal muscles.
- **Physical exercise**. The components of this program are similar to those of defensive behavior.
- **Nutritive behavior**, the purpose of which is to ensure an adequate supply, digestion and intake of foods and liquids. This includes searching for food, e.g. in the refrigerator, activation of the parasympathetic system with increased gastrointestinal secretion and motility in response to food intake, postprandial reduction of skeletal muscle activity and similar activities.
- **Reproductive behavior**, e.g., courting a partner, neuronal mechanisms of sexual response, hormonal regulation of pregnancy (→ p. 306), etc.
- **Thermoregulatory behavior**, which enables us to maintain a relatively constant core temperature (→ p. 226), even in extreme ambient temperatures or at the high level of heat production during strenuous physical work.

Monoaminergic neuron systems contain neurons that release the monoamine neurotransmitters norepinephrine, epinephrine, dopamine, and serotonin. These neuron tracts extend from the brain stem to almost all parts of the brain and play an important role in the overall regulation of behavior. Experimental activation of noradrenergic neurons, for example, led to positive reinforcement (liking, rewards), whereas the serotoninergic neurons are thought to be associated with dislike. A number of psychotropic drugs target monoaminergic neuron systems.

A. Limbic system and hypothalamus



Proper function of the cerebral cortex is essential for *conscious perception, planning, action*, and *voluntary movement* (→ p. 324ff.).

Cortical ultrastructure and **neuronal circuitry** (→ **A**). The cerebral cortex consists of six layers, I–VI, lying parallel to the brain surface. Vertically, it is divided into columns and modules (diameter 0.05–0.3 mm, depth 1.3–4.5 mm) that extend through all six layers.

Input from specific and unspecific areas of the thalamus terminate mainly on layers IV and on layers I and II, respectively (→ **A3**); those from other areas of the cortex terminate mainly on layer II (→ **A2**). The large and small **pyramidal cells** (→ **A1**) comprise 80% of all cells in the cortex and are located in layers V and III, respectively (glutamate generally serves as the transmitter, e.g., in the striatum; → p. 327 D). The pyramidal cell axons leave the layer VI of their respective columns and are the sole source of **output** from the cortex. Most of the axons project to other areas of the ipsilateral cortex (association fibers) or to areas of the contralateral cortex (commissural fibers) (→ **A2**); only a few extend to the periphery (→ **A4** and p. 327 C). Locally, the pyramidal cells are connected to each other by axon collaterals. The *principal dendrite* of a pyramidal cell projects to the upper layers of its column and has many thorn-like processes (**spines**) where many thalamocortical, commissural and association fibers terminate (see also p. 342ff.). The afferent fibers utilize various transmitters, e.g., glutamate norepinephrine, dopamine, serotonin, acetylcholine and histamine. Inside the cerebral cortex, information is processed by many morphologically variable **stellate cells** (→ **A1**), some of which have stimulatory effects (VIP, CCK and other peptide transmitters), while others have inhibitory effects (GABA). Dendrites of pyramidal and stellate cells project to neighboring columns, so the columns are connected by thousands of threads. **Plasticity** of pyramidal cell synapses — i.e., the fact that they can be modified in conformity with their activity pattern — is important for the learning process (→ p. 340).

Cortical potentials. Similar to electrocardiography, collective fluctuations of electrical potentials (brain waves) in the cerebral cortex can be recorded by **electroencephalography** using electrodes applied to the skin over the cranium (→ **B**). The EPSPs contribute the most to the electroencephalogram (**EEG**) whereas the share of the relatively low IPSPs (→ p. 50ff.) generated at the synapses of pyramidal cell dendrites is small. Only a portion of the rhythms recorded in the EEG are produced directly in the cortex (α and γ waves in conscious perception; see below). Lower frequency waves from other parts of the brain, e.g. α waves from the thalamus and θ waves from the hippocampus, are "forced on" the cortex (*brain wave entrainment*).


By convention, downward **deflections of the EEG** are positive. Generally speaking, depolarization (excitation) of deeper layers of the cortex and hyperpolarization of superficial layers cause downward deflection (+) and vice versa.

Brain wave types. The electrical activity level of the cortex is mainly determined by the degree of *wakefulness* and can be distinguished based on the amplitude (a) and frequency (f) of the waves (→ **B, C**). **α Waves** ($f \approx 10$ Hz; $a \approx 50\,\mu V$), which predominate when an adult subject is awake and relaxed (with eyes closed), are generally detected in multiple electrodes (*synchronized activity*). When the eyes are opened, other sensory organs are stimulated, or the subject solves a math problem, the α waves subside (α blockade) and **β waves** appear ($f \approx 20$ Hz). The amplitude of β waves is lower than that of α waves, and they are chiefly found in occipital (→ **B**) and parietal regions when they eyes are opened. The frequency and amplitude of β waves varies greatly in the different leads (*desynchronization*). β Waves reflect the increased attention and activity (arousal activity) of the *ascending reticular activating system* (ARAS; → p. 324 and 338). **γ Waves** (> 30 Hz) appear during learning activity. Low-frequency **θ waves** appear when drowsiness descends to sleep (sleep stages A/B/C; → **D**); they transform into even slower **δ waves** during deep sleep (→ **C, D**).


The EEG is used to diagnose epilepsy (localized or generalized paroxysmal waves and spikes; → **C**), to assess the degree of brain maturation, monitor anesthesia, and to determine brain death (*isoelectric EEG*).

Magnetoencephalography (MEG), i.e. recording magnetic signals induced by cortical ion currents, can be combined with the EEG to precisely locate the site of cortical activity (resolution a few mm).


A. Cortical layers I–VI (multiple view of a single-cortex column)



B. Recording the electroencephalogram (EEG)




C. EEG curves



D. Stages of sleep, REM sleep

(See also text on next page)



The daily sleep–wake cycle and other **circadian rhythms** (diurnal rhythms) are controlled by *endogenous rhythm generators*. The *central biological clock* (*oscillator*) that times these processes is located in the *suprachiasmatic nucleus* (**SCN**) of the hypothalamus (→ **A**). The endogenous circadian rhythm occurs in cycles of roughly 24–25 hours, but is unadulterated only when a person is completely isolated from the outside influences (e.g., in a windowless basement, dark cave, etc.). External *zeitgebers* (entraining signals) synchronize the biological clock to precise 24-hour cycles. The *zeitgeber* slows or accelerates the endogenous rhythm, depending on which phase it is in. It takes several days to "reset" the biological clock, e.g., after a long journey from east to west (*jet lag*).

The main **external zeitgeber** for 24-hour synchronization of the sleep–wake cycle is bright light (photic entrainment). Light stimuli are directly sensed by a small, *melanopsin*-containing fraction of retinal ganglion cells and conducted to the SCN via the retinohypothalamic tract (→ **A2, 3**).

Signals from the *zeitgeber* also reaches the **epiphysis** (pineal body, pineal gland), where it inhibits the secretion of **melatonin** which is high at night. Since it exerts its effects mainly on the SCN, administration of melatonin before retiring at night can greatly reduce the time required to "reset" the biological clock. The main reason is that it temporally "deactivates" the SCN (via MT_2 receptors), thereby excluding most nocturnal neuronal input (except light stimuli).

Important genetic **"cogwheels"** of the central biological clock of mammals were recently discovered (→ **A1**). Neurons of the SCN contain specific proteins (CLOCK and BMAL1), the PAS domains of which bind to form heterodimers. The resulting CLOCK/BMAL1 complexes enter the cell nuclei, where their promoter sequences (E-box) bind to period (*per*) oscillator genes *per*1, *per*2, and *per*3, thereby activating their transcription. After a latency period, expression of the genes yields the proteins PER1, PER2, and PER3, which jointly function as a trimer to block the effect of CLOCK/BMAL1, thereby completing the negative feedback loop. The mechanism by which this cycle activates subsequent neuronal actions (membrane potentials) is still unclear.

Via various effector systems of the CNS (→ **A4**), the coupled cells of the SCN (→ **A**) bring about circadian rhythms of hormone secretion (→ p. 298), core temperature (→ p. 226 and 387 C), reception of food, and physical exercise (→ p. 232) as well as sleep–wake cycles (→ **A5**, **B** and p. 339).

Various **stages of sleep** can be identified in the EEG (p. 334 and 335 D). When a normal person who is awake, relaxed and has the eyes closed (α waves) starts to fall asleep, the level of consciousness first descends to *sleep phase A* (dozing), where only a few isolated α waves can be detected. Drowsiness further descends to *sleep stage B* (or 1), where θ waves appear, then to *stage C* (or 2) where a burst of fast waves (sleep spindles) and isolated waves (K complexes) can be recorded, and ultimately to the stages of *deep sleep* (stages D/E or 3/4), characterized by the appearance of δ waves. Their amplitude increases while their frequency drops to a minimum in phase E (→ p. 335 D).


This phase is therefore referred to as *slow-wave sleep* (**SWS**). The arousal threshold is highest about 1 hour after a person falls asleep. Sleep then becomes less deep and the first episode of *rapid eye movement* (**REM**) occurs. This completes the first *sleep cycle*. During REM sleep, most of the skeletal muscles become atonic (inhibition of motoneurons) while the breathing and heart rate increase. The face and fingers suddenly start to twitch, and penile erection and rapid eye movements occur. All other stages of sleep are collectively referred to as *non-REM sleep* (**NREM**). Sleepers aroused from REM sleep are more often able to describe their dreams than when aroused from NREM sleep. The **sleep cycle** normally lasts about 90 min and is repeated 4–5 times each night (→ p. 333 D).

Towards morning, NREM sleep becomes shorter while the REM episodes increase from 10 min to > 30 min.


Infants sleep longest (about 16 hours/day, 50 % REM), 10-year-olds sleep an average 10 hours (20 % REM), young adults sleep 7–8 hours a day, and adults over 50 sleep an average 6 hours (both 20 % REM). The proportion of SWS decreases in favor of stage C sleep.

When a person is **deprived of REM sleep**, the duration of the next REM phase increases. The first two to three sleep cycles (**core sleep**) are essential. Total **sleep deprivation** leads to death, but the reason is still unclear.

A. Circadian rhythm generator in suprachiasmatic nucleus (SCN)



B. Circadian rhythm of sleep–wake cycle



(After Aschoff)

Consciousness. Selective attention, abstract thinking, the ability to verbalize experiences, the capacity to plan activities based on experience, self-awareness and the concept of values are some of the many characteristics of *consciousness*. Consciousness enables us to deal with difficult environmental conditions (adaptation). Little is known about the brain activity associated with consciousness and controlled attention (LCCS, see below), but we do know that subcortical activation systems such as the reticular formation (→ p. 324, A1) and corticostriatal systems that inhibit the afferent signals to the cortex in the thalamus (→ p. 328) play an important role.

Attention. Sensory stimuli arriving in the *sensory memory* are evaluated and compared to the contents of the long-term memory within fractions of a second (→ p. 341 **C**). In routine situations such as driving in traffic, these stimuli are unconsciously processed (*automated attention*) and do not interfere with other reaction sequences such as conversation with a passenger. Our *conscious, selective (controlled) attention*, on the other hand, is stimulated by novel or ambiguous stimuli, the reaction to which (e.g., the setting of priorities) is controlled by vast parts of the brain called the *limited capacity control system* (**LCCS**). Since our capacity for selective attention is therefore limited, it normally is utilized only in stress situations.


Consciousness and attention are linked to wakefulness, which is maintained in the reticular formation of the brain stem by multiple neuron groups that transmit nonspecific ascending activating impulses via the thalamus to wide areas of the forebrain: the ascending reticular activating (arousal) system (ARAS, → **A1** and p. 324 and 325 E). The transmitter in these fibers is acetylcholine (ACh) from the medial parabrachial nucleus, the lateroposterior and pedunculopontine tegmental nuclei (→ **A1**, LTN, PPN). Alongside this cholinergic system, a monoaminergic system also operates, which consists of the locus caeruleus (→ **A1**, LC) with norepinephrine (NE), the raphe nuclei with serotonin (= 5-hydroxytryptamine, 5-HT), the ventral periaqueductal gray substance (→ **A**, vPAG) with dopamine and the tuberomamillar nucleus (→ **A**, TMN) with histamine as transmitters. In the awake state both systems are highly active (see Table) and the sleep/wake switch in the hypothalamus (LH), where the transmitter orexin (= hypocretin) activates the aminergic system (→ **A**).

Sleep is a state of physiologic recovery, regularly repeated at night. The day/night rhythm is associated with an altered state of consciousness. Here REM sleep shows considerable differences from NREM sleep (→ p. 336 and Table). These two forms of sleep are mutually exclusive, i.e., the sleeping brain can either process perceptions from endogenous sources (REM sleep with hallucinatory illusions; exogenous sensibility is blocked) or it can perceive and (persistently) "think over" external information (see Table) but not both at the same time.

Sleep is a **regulated process**. The central biological clock located in the suprachiasmatic nucleus (SCN) of the hypothalamus (→ p. 336 and 337 A) is responsible for timing this process. During REM sleep only the aminergic ARAS is switched off (and the cholinergic system is strongly activated), while during NREM sleep the central biological clock inhibits both systems equally (→ Table and **A**, bottom). At night the SCN controls, in particular, neurons in the ventrolateral preoptic nucleus (VLPO). Its activation causes the switchover to the "sleep" state by inhibiting both the stabilizing LH and ▶

	Awake	NREM sleep	REM sleep
Sensitivity, perception	Active (exogenic stimulation)	Sluggish to absent	Active (endogenic stimulation)
Thought	Logical, progressive	Logical, persistent	Illogical, bizarre
Motor system activity	Uninterrupted, deliberate	Episodic, involuntary	Brain pathways active but α motoneurons inhibited
ARAS activity	Cholinergic and aminergic ↑↑↑	Cholinergic and aminergic ↑	Cholinergic ↑↑↑ , aminergic 0
EEG wave type	α, β: high frequency, low	θ, δ: low frequency, high	β: high frequency, low

A. Control of sleep–wake cycle



▶ the aminergic ARAS (LC, RN, vPAG, TMN) via the transmitters galanin and gamma-aminobutyric acid (GABA; → **A**, bottom).

The **functions of sleep** are homeostasis (replenishment of energy reserves with high parasympathetic involvement) and consolidation (stabilization) of acquired procedural knowledge (spoken language, motor functions; see below). **Dreaming** appears to be involved in the consolidation process. Dreams include fragmentary episodic memories, which stem partly from experiences while awake during the previous 1 to 6 days and are emotionally structured. The high rate of REM sleep in infants (p. 336) suggests that it is important for development of the brain. In adults the extent of REM sleep phases increases throughout the night (p. 335 D) and without an alarm, we usually awake from REM sleep. Alertness is notably higher when awaking from REM sleep that when woken from deep sleep, so another function of REM sleep may be to prepare us for being awake (activation of brain stem activity).

Sleep disorders include (in addition to sleep rhythm abnormalities) hypersomnia, i.e. severe daytime tiredness despite sleeping at night. Narcolepsy is an example of such a disorder, in which (as a consequence of encephalitis or congenital Gélineau syndrome) ARAS stabilization by the LH is absent (**A**, bottom). Without any warning, sleeping spells of minutes at a time occur during the day, as the destabilized sleep/wake switch suddenly flips to "sleep." Insomnia (sleeplessness) can have numerous causes, including damage to the VLPO (e.g. encephalitis; **A**, top). Parasomnias are disturbed sleep behaviors such as sleepwalking (somnambulism) or bedwetting (nocturnal enuresis).

How easily one can be woken from sleep depends on the sleep phase, and generally we can quickly remember what was happening just before falling asleep. In contrast, during unconsciousness, whether brief (fainting, syncope) or prolonged (coma), such as following brain injury, O_2 or glucose deficiency, poisoning etc., the patient cannot be woken and will often have retrograde amnesia (see below).

Learning, Memory, Language


The **implicit memory** (procedural memory → **B**, brown area) stores skill-related information and information necessary for associative learning (conditioning of conditional reflexes; → p. 236) and non-associative learning (habituation and sensitization of reflex pathways). This type of unconscious memory involves the basal ganglia (procedural memory, e.g. learning of skills and procedures), cerebellum (motor reflexes in associated learning), neocortex (priming, e.g. ability to complete partial texts based on previously acquired knowledge), amygdaloid body (emotional reactions) and other structures of the brain.

The neuronal circuits of the implicit memory (→ **B**) are largely independent from those of the explicit memory. The latter is affected particularly by damage to the hippocampus (e.g., retrograde amnesia), while the implicit memory continues to function normally. Conversely, atrophy of the amygdala. e.g., in Urbach–Wiethe disease, leads to deficits of emotional memory (problems with interpretation and expression of emotions).


The **explicit memory** (declarative/knowledge memory) stores facts (semantic knowledge) and experiences (episodic knowledge, especially when experienced by selective attention) and *consciously* renders the data. Storage of information processed in the uni- and polymodal association fields is the responsibility of the temporal lobe system (hippocampus, perirhinal, entorhinal and parahippocampal cortex, → **B**, green area). It establishes the temporal and spatial *context* surrounding an experience and recurrently stores the information back into the *spines* of cortical dendrites in the association areas (→ **D**). The recurrence of a portion of the experience then suffices to recall the contents of the memory.

Explicit learning (→ **C**) starts in the *sensory memory*, which holds the sensory impression automatically for less than 1 s. A small fraction of the information reaches the *primary memory* (*short-term memory*), which can retain about 7 units of information (e.g., groups of numbers) for a few seconds. In most cases, the information is also verbalized. *Long-term storage* of information in the *secondary memory* (*long-term memory*) is achieved by repetition (*consolidation*). The *tertiary memory* is the place where frequently repeated impressions are stored (e.g., reading, writing, one's own name); these things are never forgotten, and can be quickly recalled throughout one's lifetime. ▶

B. Areas of the brain involved in memory



C. Storage of information in the brain (explicit memory)



▶ The mechanism correlating with primary (short-term) memory is likely to be the *impulses circulating in the neuronal tracts*, while *biochemical mechanisms* are predominantly involved in long-term memory. Repeated excitation causes reinforcement lasting hours or days of synaptic connections (early **LTP,** *long-term potentiation*) at the spines of cortical dendrites (→ **D**, top). Long-term genomic changes eventually result from this reinforcement (late-phase LTP). Synaptic transmission at specific synapses is thus enhanced and the learned information consolidated.


Mechanisms for LTP. Once ionotropic receptors for AMPA (α-amino-3-hydroxy-5-methyl-4-isoxazolepropionic acid), which are permeable for Na^+ but not for Ca^{2+}, are activated by the presynaptic release of glutamate at glutamatergic axodendritic synapses of cortical pyramidal cells (→ p. 55 F), influxing Na^+ depolarizes the postsynaptic membrane and a normal EPSP results (→ **D1** and p. 50ff). Glutamate also binds to the ionotropic NMDA (N-methyl–aspartic acid) receptor. The ion channels of the NMDA receptors are in principle permeable to Ca^{2+}, but at normal EPSP are blocked by Mg^{2+}. If the neuron is further depolarized by increased activity via the dendritic synapses, the Mg^{2+} is relieved and Ca^{2+} can flow into the cell. The cytosolic Ca^{2+} concentration $[Ca^{2+}]_i$ then rises. If this is repeated often enough, calmodulin mediates the autophosphorylation of CaM kinase II (→ **D2** and p. 36), which persists even after the $[Ca^{2+}]_i$ falls back to normal. CaM kinase II phosphorylates AMPA receptors (increases their conductivity) and promotes their insertion into the postsynaptic membrane, thereby enhancing synaptic transmission over longer periods of time (early LTP). Frequent, marked increases in $[Ca^{2+}]_i$ concentration results in long-term prolongation (late LTP), because this activates adenylate cyclase, and increased cAMP is released (→ **D3**). The cAMP and MAP (mitogen-activated protein) kinases are then activated and phosphorylate transcription factors (CREB = cAMP response element binding protein) in the cell nucleus. These in turn activate promoters (CRE), and in this manner resting synapses are mobilized and new proteins are synthesized.

Amnesia (memory loss). *Retrograde amnesia* (loss of memories of past events) is characterized by the loss of primary memory and (temporary) difficulty in recalling information from the secondary memory due to various causes (concussion, electroshock, etc.). *Anterograde amnesia* (inability to form new memories) is characterized by the inability to transfer new information from the primary memory to the secondary memory (*Korsakoff's syndrome*, which occurs mainly with alcoholism).

Language is a mode of *communication* used (1) to receive information through visual and aural channels (and through tactile channels in the blind) and (2) to transmit information in written and spoken form (see also p. 372). Language is also needed to form and verbalize *concepts and strategies* based on consciously processed sensory input. Memories can therefore be stored efficiently. The centers for formation and processing of concepts and language are unevenly distributed in the cerebral hemispheres. The left hemisphere is usually the main center of speech in right-handed individuals *("dominant" hemisphere*, large planum temporale), whereas the right hemisphere is dominant in 30–40% of all left-handers. The *non-dominant hemisphere* is important for word recognition, sentence melody, and numerous nonverbal capacities (e.g., music, spatial thinking, face recognition).

This can be illustrated using the example of patients in whom the two hemispheres are surgically disconnected due to conditions such as otherwise untreatable, severe epilepsy. If such a **split-brain patient** touches an object with the right hand (reported to the left hemisphere), he can name the object. If, however, he touches the object with the left hand (right hemisphere), he cannot name the object but can point to a picture of it. Since complete separation of the two hemispheres also causes many other severe disturbances, this type of surgery is used only in patients with otherwise unmanageable, extremely severe seizures.

D. Molecular mechanisms of long-term potentiation



(After E. R. Kandel)

The central nervous system contains around 10^{11} nerve cells and 10 times as many **glia cells** such as *oligodendrocytes, astrocytes, ependymal cells*, and *microglia* (→ **A**). **Oligodendrocytes** (ODC) form the myelin sheath that surrounds axons of the CNS (→ **A**).

Astrocytes (AC) are responsible for **extracellular K^+ and H^+ homeostasis** in the CNS. Neurons release K^+ in response to high-frequency stimulation (→ **B**). Astrocytes prevent an increase in the interstitial K^+ concentration and thus an undesirable depolarization of neurons (see Nernst equation, Eq. 1.18, p. 32) by taking up K^+, and intervene in a similar manner with H^+ ions. Since AC are connected by *gap junctions* (→ p. 16ff.), they can transfer their K^+ or H^+ load to nearby AC (→ **B**). In addition to forming a *barrier* that prevents transmitters from one synapse from being absorbed by another, AC also *take transmitters up*, e.g. glutamate (Glu). Intracellular Glu is converted to glutamine ($GluNH_2$), then transported out of the cell and taken up by the nerve cells, which convert it back to Glu (**transmitter recycling**; → **B**).

Some AC have **receptors for transmitters** such as Glu, which triggers a Ca^{2+} wave from one AC to another. Astrocytes are also able to modify the Ca^{2+} concentration in the neuronal cytosol so that the two cell types can "communicate" with each other. AC also mediate the transport of materials between capillaries and neurons and play an important part in *energy homeostasis* of the neurons by mediating glycogen synthesis and breakdown.

During **embryonal development**, the long processes of AC serve as *guiding structures* that help undifferentiated nerve cells migrate to their target areas. Glia cells also play an important role in CNS development by helping to control gene expression in nerve cell clusters with or without the aid of **growth factors** such as NGF (nerve growth factor), BDGF (brain-derived growth factor), and GDNF (glial cell line-derived neurotropic factor). GDNF also serves as a trophic factor for all mature neurons.

Cell division of glia cells can lead to scarring (*epileptic foci*) and tumor formation (*glioma*).

Immunocompetent **microglia** (→ **A**) assume many functions of macrophages outside the CNS when CNS injuries or infections occur (→ p. 94ff.). **Ependymal cells** line internal hollow cavities of the CNS (→ **A**).

Sense of Taste

Gustatory pathways. The *taste buds* (→ **D**) consist of clusters of 50–100 *secondary sensory cells* on the tongue (renewed in 2-week cycles); humans have around 5000 taste buds. Sensory stimuli from the taste buds are conducted to endings of the VIIth, IXth and Xth cranial nerves, relayed by the *nucleus tractus solitarii*, and converge at a high frequency on (a) the postcentral gyrus via the thalamus (→ p. 325 B, "tongue") and (b) the hypothalamus and limbic system via the pons (→ **C**).


The **qualities of taste** distinguishable in humans are conventionally defined as *sweet*, *sour*, *salty*, and *bitter*. The specific taste sensor cells for these qualities are distributed over the whole tongue but differ with respect to their densities. *Umami*, the sensation caused by monosodium-L-glutamate (MSG), is now classified as a fifth quality of taste. MSG is chiefly found in protein-rich foods.

Taste sensor cells distinguish the types of taste as follows: **Salty**: Cations (Na^+, K^+, etc.) taste salty, but the presence of anions also plays a role. E.g., Na^+ enters the taste sensor cell via Na^+ channels and depolarizes the cell. **Sour**: H^+ ions lead to a more frequent closure of K^+ channels, which also has a depolarizing effect. **Bitter**: A family of > 50 genes codes for a battery of bitter sensors. A number of sensory proteins specific for a particular substance are expressed in a single taste sensor cell, making it sensitive to different bitter tastes. The sensory input is relayed by the G-protein α-*gustducin*. No nuances but only the overall warning signal "bitter" is perceived. **Umami**: Certain taste sensor contain a metabotropic glutamate receptor, mGluR4, the stimulation of which leads to a drop in cAMP conc.


Taste thresholds. The threshold (mol/L) for recognition of taste stimuli applied to the tongue is roughly 10^{-5} for quinine sulfate and saccharin, 10^{-3} for HCl, and 10^{-2} for sucrose and NaCl. The relative *intensity differential threshold* $\Delta I/I$ (→ p. 358) is about 0.20. The concentration of the gustatory stimulus determines whether its taste will be perceived as pleasant or unpleasant (→ **E**). For the *adaptation* of the sense of taste, see p. 347 C.

Function of taste. The sense of taste has a protective function as spoiled or bitter-tasting food (low taste threshold) is often poisonous. Tasting substances also stimulate the secretion of saliva and gastric juices (→ pp. 238, 244).


A. Glia cells




B. Glia function




C. Gustatory pathways



D. Taste bud



E. Evaluation of taste stimuli



The neuroepithelium of the *olfactory region* contains ca. 10^7 *primary* **olfactory sensor cells** (→ **A1**) which are bipolar neurons. Their dendrites branch to form 5–20 mucus-covered cilia, whereas the axons extend centrally in bundles called *fila olfactoria* (→ **A1,2**). Olfactory neurons are replenished by basal cell division in 30–60-day cycles. *Free nerve endings* (trigeminal nerve) in the nasal mucosa also react to certain aggressive odors (e.g., acid or ammonia vapors).

Olfactory sensors. Odorant molecules (M_r 15–300) are transported by the inhaled air to the olfactory region, where they first dissolve in the mucous lining before combining with **receptor proteins** in the *cilial membrane*. These are coded by a huge family of genes (500–750 genes distributed in most chromosomes), whereby probably one olfactory sensor cell only expresses one of these genes. Since only a part of the sequence of about 40% of these genes is expressed, humans have roughly 200–400 different **sensor cell types**. Olfactory receptors couple with G_s-proteins (G_{olf} proteins; → **B** and p. 276ff.) that increase the conductivity of the sensor cell membrane to cations, thereby increasing the influx of Na^+ and Ca^{2+} and thus depolarizing the cell.

Sensor specificity (→ **A3**). Olfactory sensor cells recognize a very specific structural feature of the odorant molecules they are sensitive to.


The cloned receptor 17 of the rat, for example, reacts with the aldehyde *n*-octanal but not to octanol, octanoic acid, or aldehydes which have two methyl groups more or less than *n*-octanal. In the case of aromatic compounds, one sensor recognizes whether the compound is *ortho*, *meta* or *para*-substituted, while another detects the length of the substituent regardless of where it is located on the ring. The different molecular moieties of an odorant molecule therefore activate different types of sensors (→ **A3, top** right). Jasmine leaves and wine contain several dozens and hundreds of odorants, respectively, so their overall scent is a more complex perception (integrated in the rhinencephalon).

Olfactory pathway (→ **A2**). Axons of (ca. 10^3) same-type sensors distributed over the olfactory epithelium synapse to dendrites of their respective *mitral cells* (MC) and *bristle cells* (BC) within the glomeruli olfactorii of the olfactory bulb. The glomeruli therefore function as convergence centers that integrate and relay signals from the same sensor type. Their respective sensor protein also determines which glomerulus newly formed sensor axons will connect to. *Periglomerular cells* and *granular cells* connect and inhibit mitral and bristle cells (→ **A2**). Mitral cells act on the same *reciprocal synapses* (→ **A**, "+/–") in reverse direction to activate the periglomerular cells and granular cells which, on the other hand, are inhibited by efferents from the primary olfactory cortex and contralateral anterior olfactory nucleus (→ **A2**, violet tracts). These connections enable the cells to inhibit themselves or nearby cells (contrast), or they can be disinhibited by higher centers. The signals of the *axons of mitral cells* (1) reach the anterior olfactory nucleus. Its neurons cross over (in the anterior commissure) to the mitral cells of the contralateral bulb and (2) form the *olfactory tract* projecting to the *primary olfactory cortex* (prepiriform cortex, tuberculum olfactorium, nucleus corticalis amygdalae). The olfactory input processed there is relayed to the hypothalamus, limbic system (see also p. 332), and reticular formation; it is also relayed to the neocortex (*insula, orbitofrontal area*) either directly or by way of the thalamus.


Thresholds. It takes only 4×10^{-15} g of methylmercaptan (in garlic) per liter of air to trigger the vague sensation of smell (*perception* or *absolute threshold*). The odor can be properly identified when 2×10^{-13} g/L is present (*identification threshold*). Such thresholds are affected by air temperature and humidity; those for other substances can be 10^{10} times higher. The relative intensity differential threshold $\Delta I/I$ (0.25) is relatively high (→ p. 358). *Adaptation* to smell is sensor-dependent (desensitization) and neuronal (→ **C**).

The sense of smell has various **functions**. Pleasant smells trigger the secretion of saliva and gastric juices, whereas unpleasant smells warn of potentially spoiled food. Body odor permits hygiene control (sweat, excrement), conveys social information (e.g., family, enemy; → p. 332), and influences sexual behavior. Other aromas influence the emotional state.


A. Olfactory pathway and olfactory sensor specificity



B. Transduction of olfactory stimuli



C. Adaptation of smell and taste



Anatomy. Each of the three **semicircular canals** (→ **A1**) is located in a plane about at right angles to the others. The ampulla of each canal contains a ridge-like structure called the *crista ampullaris* (→ **A2**). It contains *hair cells* (secondary sensory cells), the *cilia* of which (→ **A3**) project into a gelatinous membrane called the *cupula* (→ **A2**). Each hair cell has a long *kinocilium* and ca. 80 *stereocilia* of variable length. Their tips are connected to longer adjacent cilia via the "*tip links*" (→ **A3**).

Semicircular canals. When the cilia are in a resting state, the hair cells release a transmitter (glutamate) that triggers the firing of action potentials (AP) in the nerve fibers of the vestibular ganglion. When the head is turned, the semicircular canal automatically moves with it, but *endolymph* in the canal moves more sluggishly due to inertia. A brief *pressure difference* thus develops between the two sides of the cupula. The resultant vaulting of the cupula causes the stereocilia to bend (→ **A2**) and shear against each other, thereby changing the cation conductance of the hair cell membrane. Bending of the stereocilia towards the kinocilium increases conductivity and allows the influx of K^+ and Na^+ along a high electrochemical gradient between the endolymph and hair cell interior (see also pp. 372). Thus, the hair cell becomes depolarized, Ca^{2+} channels open, more glutamate is released, and the AP frequency increases. The reverse occurs when the cilia bend in the other direction (away from the kinocilium). The semicircular canals **function** to detect *angular (rotational) accelerations* of the head in all planes (rotation, nodding, tilting sideways). Since normal head movements take less than 0.3 s (acceleration ⇒ deceleration), stimulation of the semicircular canals usually reflects the rotational *velocity*.

The pressure difference across the cupula disappears when the **body rotates for longer periods** of time. Deceleration of the rotation causes a pressure gradient in the opposite direction. When bending of the cilia increased the AP frequency at the start of rotation, it decreases during deceleration and vice versa. Abrupt cessation of the rotation leads to **vertigo** and **nystagmus** (see below).


The **saccule** and **utricle** contain **maculae** (→ **A1, A4**) with cilia that project into a gelatinous membrane (→ **A4**) with high density (≈ 3.0) calcite crystals called *statoconia, statoliths* or *otoliths*. They displace the membrane and thereby bend the embedded cilia (→ **A4**) due to changes of the direction of *gravity*, e.g. when the head position deviates from the perpendicular axis. The maculae respond also to other *linear (translational) accelerations or decelerations, e.g.* of a car or an elevator.

Central connections. The bipolar neurons of the vestibular ganglion synapse with the *vestibular nuclei* (→ **A, B**). Important tracts extend from there to the contralateral side and to *ocular muscle nuclei*, *cerebellum* (→ p. 328), *motoneurons* of the skeletal muscles, and to the *postcentral gyrus* (conscious spatial orientation). **Vestibular reflexes** (a) maintain the balance of the body (*postural motor function*, → p. 330) and (b) keep the visual field in focus despite changes in head and body position (*oculomotor control*, → **B** and p. 366).

Example (→ **C**): If a support holding a test subject is tilted, the activated vestibular organ prompts the subject to extend the arm and thigh on the declining side and to bend the arm on the inclining side to maintain balance (→ **C2**). The patient with an impaired equilibrium organ fails to respond appropriately and topples over (→ **C3**).

Since the vestibular organ cannot determine whether the head alone or the entire body moves (*sense of movement*) or changed position (postural *sense*), the vestibular nuclei must also receive and process visual information and that from proprioSensors in the neck muscles. Efferent fibers project bilaterally to the eye muscle nuclei, and any change in head position is immediately corrected by opposing *eye movement* (→ **B**). This *vestibulo-ocular reflex* maintains **spatial orientation**.

Vestibular organ function can be assessed by testing oculomotor control. *Secondary* or *postrotatory* **nystagmus** occurs after abrupt cessation of prolonged rotation of the head around the vertical axis (e.g., in an office chair) due to activation of the horizontal semicircular canals. It is characterized by slow horizontal movement of the eyes in the direction of rotation and rapid return movement. Rightward rotation leads to left nystagmus and vice versa (→ p. 366). Caloric stimulation of the horizontal semicircular canal by instilling cold (30 °C) or warm water (44 °C) in the auditory canal leads to *caloric nystagmus*. This method can be used for unilateral testing.


A. Equilibrium organ (vestibular organ)
1
Semi-circular canals
Utricle
Maculae
Saccule
2
Endolymph
Semicircular canal
Ampulla
Cupula
Cilia
Synapses
Crista
Vestibular ganglion
Head movement
3
Inhibitory
Stimulatory
Tip links
4
Statoconia
Statoconia membrane
Macula
Cilia
Synapses
Vestibular ganglion
B. Vestibular organ: effects on oculomotor control
Head movement
Vestibular organ
Eye muscle nuclei
Vestibular nuclei
To postural muscles
Eye muscles
Vertical positioning of eyes
C. Vestibular organ: effects on postural motor control
Normal
1
2
3
Impaired
(After Kornhuber)

Light entering the eye must pass through the *cornea, aqueous humor, lens* and *vitreous body*, which are collectively called the **optical apparatus,** before reaching the *retina* and its light-sensitive photosensors (→ **A**). This produces a *reduced and inverse image* of the visual field on the retina. All parts of the apparatus must be transparent and have a stable shape and smooth surface to produce an undistorted image, which is the main purpose of **tear fluid** in case of the cornea. Tears are secreted by *lacrimal glands* located in the top outer portion of orbit and their mode of production is similar to that of saliva (→ p. 238). Tears are distributed by reflex blinking and then pass through the lacrimal puncta and lacrimal canaliculi (or ducts) of the upper and lower eyelid into the lacrimal sac and finally drain into the nasal sinuses by way of the nasolacrimal duct. Tear fluid improves the optical characteristics of the cornea by smoothing uneven surfaces, washing away dust, protecting it from caustic vapors and chemicals, and protects it from drying out. Tears lubricate the eyelid movement and contain lysozyme and immunoglobulin A (→ pp. 96ff. and 234), which help ward off infections. In addition, tears are a well known mode of expressing emotions.

The entry of light into the eye is regulated by the **iris** (→ **A**; p. 359 C1), which contains annular and radial smooth muscle fibers. Cholinergic activation of the sphincter muscle of pupil leads to pupil contraction (*miosis*), and adrenergic activation of the dilator muscle of pupil results in pupil dilatation (*mydriasis*).

The **bulbus** (eyeball) maintains its shape due to its tough outer coat or **sclera** (→ **C**) and **intraocular pressure** which is normally 10–21 mmHg above the atmospheric pressure. The drainage of **aqueous humor** must balance its production to maintain a constant ocular pressure (→ **C**). Aqueous humor is produced in the *ciliary process* of the posterior ocular chamber with the aid of carbonic anhydrase and active ion transport. It flows through the pupil into the anterior ocular chamber and drains into the venous system by way of the trabecular meshwork and Schlemm's canal. Aqueous humor is renewed once every hour or so.

Glaucoma. Obstruction of humor drainage can occur due to chronic obliteration of the trabecular meshwork (open-angle glaucoma) or due to acute block of the anterior angle (angle-closure glaucoma) leading to elevated intraocular pressure, pain, retinal damage, and blindness. Drugs that decrease humor production (e.g. carbonic anhydrase inhibitors) and induce meiosis are used to treat glaucoma.


The **lens** is held in place by the *ciliary zonules* (→ **C**). When the eye adjusts for *far vision*, the zonules are stretched and the lens becomes flatter, especially its anterior surface (→ **D**, top). When looking at nearby objects (*near vision*), the zonules are relaxed due to contraction of the ciliary muscle, and the lens reassumes its original shape due to its elasticity (→ **D** , bottom, and p. 352).

The **retina** lines the interior surface of the bulbus except the anterior surface and the site where the *optical nerve* (→ **A**) exits the bulbus via the *optic papilla* (→ **A**). The *fovea centralis* (→ **A**) forms a slight depression across from the pupillary opening. The retina consists of several layers, named from inside out as follows (→ **E**): pigmented epithelium, photosensors (rods and cones), Cajal's horizontal cells, bipolar cells, amacrine cells, and ganglion cells. The central processes of the ganglion cells ($n \approx 10^6$) exit the bulbus as the optical nerve (retinal circuitry; → p. 361ff.).


Photosensors. Retinal rods and cones have a light-sensitive *outer segment*, which is connected to a inner segment by a thin connecting part (→ p. 355 C1). The inner segment contains the normal cell organelles and establishes synaptic contact with the neighboring cells. The outer segment of the rod cells contains ca. 800 membranous disks, and the plasma membrane of the outer segment of the cones is folded. *Visual pigments* are stored in these disks and folds (→ p. 354).

The **outer segment** is continuously **regenerated**; the old membranous disks at the tip of the cell are shed and replaced by new disks from the inner segment. The phagocytic cells of the pigmented epithelium engulf the disks shed by the rods in the morning, and those shed by the cones in the evening. Some ganglion cells contain a light-sensitive pigment (→ p. 336).


A. Right eye (horizontal plane)




B. Right eye: tear inflow and drainage




C. Inflow and drainage of aqueous humor



D. Accommodation



E. Retina



Physics. The production of an **optical image** is based on the refraction of light rays crossing a spherical interface between air and another medium. Such a **simple optical system** illustrated in plate **A** has an *anterior focal point* (F_a) in air, a *posterior focal point* (F_p), a *principal point* (P), and a *nodal point* (N). Light rays from a distant point (∞) can be regarded as parallel. If they enter the system parallel to its *optical axis*, they will converge at F_p (→ **A1**, red dot). If they enter at an angle to the axis, then they will form an image beside F_p but in the same *focal plane* (→ **A1**, violet dot). Light rays from a nearby point do not enter the system in parallel and form an image *behind* the focal plane (→ **A2**, green and brown dots).

The **optical apparatus** of the eye consists of multiple interfaces and media, and is therefore a *complex optical system*. It can, however, be treated as *a simple optical system*. Light rays from a focused object (O) pass through N and diverge at angle α until they reach the retina and form an image (I) there (→ **A2**).

Two points separated by a distance of 1.5 mm and located 5 m away from the eye (tan α = 1.5/5000; α = 0.0175 degrees ≈ 1′) will therefore be brought into focus 5 µm apart on the retina. In a person with normal vision (→ p. 356), these two points can be distinguished as separate because 5 µm corresponds to the diameter of three cones in the fovea (two are stimulated, the one in between is not).

Accommodation. When the eyes are adjusted for **far vision**, parallel light rays from a distant point meet at F_p (→ **B1**, red dot). Since the retina is also located at F_p, the distant point is clearly imaged there. The eye adjusted for far vision will not form a clear image of a nearby point (the light rays meet behind the retina, → **B1**, green dot) until the eye has adjusted for **near vision**. In other words, the curvature of the lens (and its refractive power) increases and the image of the nearby point moves to the retinal plane (→ **B2**, green dot). Now, the distant point cannot not be sharply imaged since F_p does not lie in the retinal plane any more (→ **B2**).

The **refractive power** of the eye is the reciprocal of the anterior *focal length* in meters, and is measured in *diopters* (**dpt**). In *accommodation for far vision*, focal length = anterior focal point (F_a)–principal point (P) = 0.017 m (→ **B1**). Thus, the corresponding refractive power is 1/0.017 = 58.8 dpt, which is mainly attributable to refraction at the air–cornea interface (43 dpt). In maximum *accommodation for near vision* in a young person with normal vision (emmetropia), the refractive power increases by around 10–14 dpt. This increase is called **range of accommodation** and is calculated as 1/near point −1/far point (m^{-1} = dpt). The **near point** is the closest distance to which the eye can accommodate; that of a young person with normal vision is 0.07–0.1 m. The **far point** is infinity (∞) in subjects with normal vision. The range of accommodation to a near point of 0.1 m is therefore 10 dpt since 1/∞ = 0.

The refractive power around the edge of the optical apparatus is higher than near the optical axis. This **spherical aberration** can be minimized by narrowing the pupils.


The range of accommodation decreases as we grow older (to 1–3.5 dpt in 50-year-olds) due to the loss of elasticity of the lens. This visual impairment of aging, called **presbyopia** (→ **C1–3**), normally does not affect far vision, but convex lenses are generally required for near vision, e.g., reading.

Cataract causes opacity of the lens of one or both eyes. When surgically treated, convex lenses (glasses or artificial intraocular lenses) of at least + 15 dpt must be used to correct the vision.


In **myopia** (near-sightedness), rays of light entering the eye parallel to the optical axis are brought to focus in front of the retina because the eyeball is too long (→ **C4**). Distant objects are therefore seen as blurred because the far point is displaced towards the eyes (→ **C5**). Myopia is corrected by *concave lenses* (negative dpt) that disperse the parallel light rays to the corresponding extent (→ **C6**). *Example*: When the far point = 0.5 m, a lens of [– 1/0.5] = [– 2 dpt] will be required for correction (→ **C7**). In **hyperopia** (far-sightedness), on the other hand, the eyeball is too short. Since the accommodation mechanisms for near vision must then be already used to focus distant objects (→ **C8**), the range of accommodation no longer suffices to clearly focus nearby objects (→ **C9**). Hyperopia is corrected by *convex lenses* (+ dpt) (→ **C10–11**).

Astigmatism. In regular astigmatism, the corneal surface is more curved in one plane (usually the vertical: astigmatism with the rule) than the other, creating a difference in refraction between the two planes. A point source of light is therefore seen as a line or oval. Regular astigmatism is corrected by *cylindrical lenses*. Irregular astigmatism (caused by scars, etc.) can be corrected by contact lenses.


A. Imaging of (1) far and (2) near points



B. Eye: Accommodation for (1) far vision and (2) near vision



C. Presbyopia, myopia and hyperopia



Visual acuity is an important measure of eye function. Under *well-lighted conditions*, the normal eye should be able to distinguish two points as separate when the light rays emitted by the point objects converge at an angle (α) of 1 min (1/60 degree) (→ **A** and p. 352). Visual acuity is calculated as $1/\alpha\,(\text{min}^{-1})$, and is 1/1 in subjects with normal vision.

Visual acuity testing is generally performed using charts with letters or other optotypes (e.g., Landolt rings) of various sizes used to simulate different distances to the test subject. The letters or rings are usually displayed at a distance of 5 m (→ **A**). Visual acuity is normal (1/1) if the patient recognizes letters or ring openings seen at an angle of 1 min from a distance of 5 m. *Example*: It should be possible to identify the direction of the opening of the middle ring from a distance of 5 m and that of the left ring from a distance of 8.5 m (→ **A**). If only the opening of the left ring can be localized from the test distance of 5 m, the visual acuity is 5/8.5 = 0.59.

Photosensors or **photoreceptors**. The light-sensitive sensors of the eye consist of approximately $6 \cdot 10^6$ **rods** and 20 times as many **cones** (→ p. 351 E) distributed at variable densities throughout the retina (→ **B1**). (Certain ganglion cells also contain a light-sensitive pigment; → p. 336). The fovea centralis is exclusively filled with cones, and their density rapidly decreases towards the periphery. Rods predominate 20–30 degrees away from the fovea centralis. Approaching the periphery of the retina, the density of the rods decreases continuously from $1.5 \times 10^5/\text{mm}^2$ (maximum) to about one-third this value. No photosensors are present on the *optic disk*, which is therefore referred to as the **blind spot** in the visual field.

Clear visualization of an object in daylight requires that the gaze be fixed on it, i.e., that an image of the object is produced in the *fovea centralis*. Sudden motion in the periphery of the visual field triggers a **reflex saccade** (→ p. 366), which shifts the image of the object into the fovea centralis. Thereby, the retinal area with the highest visual acuity is selected (→ **B2**, yellow peak), which lies 5 degrees temporal to the optical axis. Visual acuity decreases rapidly when moving outward from the fovea (→ **B2,** yellow field), reflecting the decreasing density of cone distribution (→ **B1**, red curve). In a *dark-adapted eye*, on the other hand, the sensitivity of the retina (→ **B2**, blue curve) is completely dependent on the rod distribution (→ **B1**, purple curve). The color-sensitive cones are therefore used for visual perception in daylight or good lighting (*day vision, photopic vision*), while the black and white-sensitive cones are used to visualize objects in darkness (*dim-light vision, night vision, scotoptic vision*). The high light sensitivity in night vision is associated with a high loss of visual acuity (→ p. 360).


Photosensor Function

Light-absorbing *visual pigments* and a variety of *enzymes* and *transmitters* in retinal rods and cones (→ **C1**) mediate the conversion of light stimuli into electrical stimuli; this is called **photoelectric transduction**. The membranous disks of the retinal rods contain *rhodopsin* (→ **C2**), a photosensitive purple-red chromoprotein (*visual purple*). Rhodopsin consists of the integral membrane protein *opsin* and the aldehyde *11-cis-retinal*. The latter is bound to a lysine residue of opsin which is embedded in this protein; it is stably kept in place by weak interactions with two other amino acid residues. *Photic stimuli* trigger a primary *photochemical reaction* in rhodopsin (duration, $2 \cdot 10^{-14}$ s) in which 11-*cis*-retinal is converted to all-*trans*-retinal (→ **C3**). Even without continued photic stimulation, the reaction yields bathorhodopsin, the intermediates lumirhodopsin and metarhodopsin I, and finally metarhodopsin II within roughly 10^{-3} s (→ **D1**).


Metarhodopsin II (MR-II) reacts with a G_s-protein (→ p. 276) called *transducin* (G_t-protein), which breaks down into α_s and $\beta\gamma$ subunits once GDP has been replaced by GTP (→ **D1**). Activated α_s-GTP now binds the inhibitory subunit of cGMP phosphodiesterase (I_{PDE}) (→ **D2**). The consequently disinhibited phosphodiesterase (PDE) then lowers the cytosolic concentration of cyclic guanosine monophosphate (cGMP). The activation of a single retinal rhodopsin molecule by a quantum of light can induce the hydrolysis of up to 10^6 cGMP molecules per second. The reaction cascade therefore has tremendous amplifying power.

In **darkness** (→ **D**, **left**), cGMP is bound to cation channels (Na^+, Ca^{2+}) in the outer segment of the photosensor, thereby keeping them open. Na^+ and Ca^{2+} can therefore enter ▶


A. Visual acuity



B. Retina: Photosensor distribution, sensitivity in darkness and visual acuity



C. Photosensors



▶ the cell and depolarize it to about – 40 mV (→ **D3, D4**). The Ca^{2+} entering the outer segment is immediately transported out of the cell by a 3 Na^+/Ca^{2+} exchanger (→ p. 36), so the cytosolic Ca^{2+} concentration **[Ca $^{2+}$]$_i$** remains constant at ca. 350–500 nmol/L in darkness (→ **D6**). If the cytosolic cGMP concentration decreases in response to a **light stimulus** (→ **D2**), cGMP dissociates from the cation channels, allowing them to close. The photosensor then hyperpolarizes to ca. – 70 mV (*sensor potential*: → **D**, **right**). This *inhibits* the release of *glutamate* (transmitter) at the sensor pedicle (→ **D5**), which subsequently causes changes in the membrane potential in downstream retinal neurons (→ p. 362).

Deactivation of Photic Reactions and Regeneration Cycles

◆ **Rhodopsin** (→ **E2**). *Rhodopsin kinase* (RK) competes with transducin for bindings sites on *metarhodopsin II* (MR-II); the concentration of transducin is 100 times higher (→ **E2**, right). Binding of RK to MR-II leads to phosphorylation of MR-II. As a result, its affinity to transducin decreases while its affinity to another protein, *arrestin*, rises. Arrestin blocks the binding of further transducin molecules to MR-II. All-*trans*-retinal detaches from opsin, which is subsequently dephosphorylated and re-loaded with 11-*cis*-retinal.

◆ **Vitamin A.** In the photosensor, all-trans-retinal (→ **E1**) is reduced to all-trans-retinol (= vitamin A), which is transported into the pigmented epithelium (PE). When light is present, it is esterified and with **m**embrane-bound **RPE65** (mRPE65) and an isomerohydrolase (IMH) ultimately restored to 11-cis-retinal which binds to opsin again in the photosensor (→ **E2**). In darkness, Vitamin A binds to the soluble protein RPE65 (sRPE65) in the PE and stored until required when light returns. Lecithin retinol acyltransferase (LRAT) is responsible for the sRPE65 to mRPE65 conversion.

A chronic deficiency of vitamin A_1 leads to night blindness (→ p. 358). RPE65 mutations cause certain forms of retinitis pigmentosa, e.g., congenital blindness.

◆ **Transducin** (→ **E3**). Since the GTPase activity of α_s-GTP breaks down GTP into GDP + P_i, the molecule deactivates itself. The α_s-GTP molecule and $\beta\gamma$ subunit then rejoin to form transducin. GAP (GTPase-activating protein) accelerates the regeneration of transducin. *Phosducin*, another protein, is phosphorylated in the dark (→ **D6**) and dephosphorylated in light (→ **D7**). The latter form binds to the $\beta\gamma$ subunit (→ **D7, E3**), thereby blocking the regeneration of transducin. This plays a role in light adaptation (see below).


◆ **Phosphodiesterase (PDE).** In the course of transducin regeneration, the inhibitory subunit of cGMP phosphodiesterase (I_{PDE}) is released again and PDE is thus inactivated.


◆ **cGMP.** Since the 3 Na^+/Ca^{2+} exchanger still functions even after photostimulation-induced closure of Ca^{2+} channels, the $[Ca^{2+}]_i$ starts to decrease. When a threshold of ca. 100 nmol/L is reached, the Ca^{2+}-binding protein GCAP (guanylyl cyclase-activating protein) loses its 4 Ca^{2+} ions and stimulates guanylyl cyclase, thereby accelerating cGMP synthesis. Thus, the cGMP concentration rises, the cation channels re-open, and the sensor is ready to receive a new light stimulus. This Ca^{2+} cycle therefore mediates a negative feedback loop for cGMP production.

Ca^{2+} Ions and Adaptation (see also p. 358)

In the dark, the $[Ca^{2+}]_i$ is high, and calmodulin-bound Ca^{2+} (→ p. 36) stimulates the phosphorylation of phosducin with the aid of cAMP and phosphokinase A (→ **D6**). In light, the $[Ca^{2+}]_i$ is low; phosducin is dephosphorylated and rapid regeneration of transducin is not possible (→ **D7, E3**). Moreover, Ca^{2+} accelerates the phosphorylation of MR-II in light with the aid of another Ca^{2+} binding protein, *recoverin* (→ **E2**). Ca^{2+} is therefore essential for the **adaptation of photosensors** (→ p. 358).

Although they contain similar enzymes and transmitters, the photosensitivity of the **cones** is about 100 times less than that of the rods. Thus, the cones are unable to detect a single quantum of light, possibly because photic reactions in the cones are deactivated too quickly.


D. Activation of photosensors and adaptation
Disk membrane
Rhodopsin
1
MR-II (metarhodopsin II)
Transducin
MR II
β γ
αs
–40 mV
PDE
IPDE
GDP
Inactive
Light
GTP
GDP
2
PDE
active
cGMP
Na+
3
Ca2+
ICF of rod
4
Darkness
5
Light stimulus
5'-GMP
cGMP
Channel closes
cGMP decreases
Channel closes
[Ca2+] decreases
Channel opens
Influx of Ca2+/Na+
De-polarization
Hyper-polarization
GCAP active
[Ca2+]i
[Ca2+]i = 350-500 nmol/L
–70 mV
Sensor potential
6
CaM
P
Phos-ducin-P
Dark-adapted
7
Phos-ducin
Light-adapted
Glutamate release
High
Low
Signal: "Light"
ECF
Plasma membrane
ICF
Plasma membrane
ECF


E. Regeneration cycles
1 Retinal cycle
All-trans-retinol (vitamin A)
Light
dark
LRAT "switch"
Light
Stored with sRPE65
Regeneration with mRPE65 and IMH
11-cis-retinol
11-cis-retinal
2 Rhodopsin cycle
All-trans-retinal
Arrestin
P
Recoverin
Ca2+
Light
RK (rhodopsin kinase)
Pigmented epithelium
Opsin
Rhodopsin
MR II
Transducin
3 Transducin cycle
Transducin
Dark-adapted
Light-adapted
Phos-ducin
GDP
IPDE
PDE
Pi
GAP
GTP

The eye is able to perceive a wide range of light intensities, from the extremely low intensity of a small star to the extremely strong intensity of the sun glaring on a glacier. The ability of the eye to process such a wide range of luminance ($1 : 10^{11}$) by adjusting to the prevailing light intensity is called **adaptation**. When going from normal daylight into a darkened room, the room will first appear black because its luminance value (measured in $cd \cdot m^{-2}$) is lower than the current ocular threshold. As the stimulus threshold decreases over the next few minutes, the furniture in the room gradually becomes identifiable. A longer period of adaptation is required to visualize stars. The maximum level of adaptation is reached in about 30 min (→ **A**). The minimum light intensity that can just be detected after maximum dark adaptation is the **absolute visual threshold**, which is defined as 1 in **A** and **B**.

The **retinal adaptation curve** exhibits a (Kohlrausch) break at roughly 2000 × the absolute threshold (→ **A**, blue curve). This corresponds to the point where the excitation threshold of the cones is reached (threshold for day vision). The remainder of the curve is governed by the somewhat slower adaptation of the rods (→ **A**, violet curve). The isolated rod adaptation curve can be recorded in patients with complete color blindness (*rod monochromatism*), and the isolated cone adaptation curve can be observed in night blindness (hemeralopia, → p. 356).


Differential threshold (or difference limen). The ability of the eye to distinguish the difference between two similar photic stimuli is an important prerequisite for proper eyesight. At the lowest limit of discriminative sensibility for two light intensities I and I′, the *absolute differential threshold* (Δ I) is defined as I minus I′. The *relative differential threshold* is calculated as Δ I/I, and remains relatively constant in the median stimulus range (*Weber's rule*). Under optimal lighting conditions (approx. 10^9 times the absolute threshold; → **B**), Δ I/I is very small (0.01). The relative differential threshold rises greatly in dark adaptation, but also rises in response to extremely bright light. Sunglasses decrease the differential threshold in the latter case.

The **mechanisms for adaptation** of the eye are as follows (→ **C**):


- **Pupil reflex** (→ **C1**). Through reflexive responses to light exposure of the retina (→ p. 365), the pupils can adjust the quantity of light entering the retina by a factor of 16. Thus, the pupils are larger in darkness than in daylight. The main function of the pupil reflex is to ensure rapid adaptation to sudden changes in light intensity.
- **Chemical stimuli** (→ **C2**) help to adjust the sensitivity of photosensors to the prevailing light conditions. Large quantities of light lead to a prolonged decrease in the receptor's *cytosolic Ca^{2+} concentration*. This in conjunction with the activity of *recoverin* and *phosducin* reduces the availability of rhodopsin (→ p. 354ff.). It therefore decreases the probability that a rhodopsin molecule will be struck by an incoming light ray (photon) or that a metarhodopsin II molecule will come in contact with a transducin molecule. When the light intensity is low, large concentrations of rhodopsin and transducin are available and the photosensors become very light-sensitive.
- **Spatial summation** (→ **C3**). Variation of retinal surface area (number of photosensors) exciting an optic nerve fiber causes a form of spatial summation that increases with darkness and decreases with brightness (→ p. 360).
- **Temporal summation** (→ **C4**). Brief subthreshold stimuli can be raised above threshold by increasing the duration of stimulation (by staring at an object) long enough to trigger an action potential (AP). Thereby, the product of stimulus intensity times stimulus duration remains constant.

Successive contrast occurs due to "local adaptation." When a subject stares at the center of the black-and-white pattern (→ **D**) for about 20 s and suddenly shifts the focus to the white circle, the previously dark areas appear to be brighter than the surroundings due to sensitization of the corresponding areas of the retina.

A. Adaptation




B. Differential threshold and luminance



(After G. Schubert)

C. Mechanisms for adaptation



D. Successive contrast ("local adaptation") (see text)



Light stimuli *hyper*polarize the **sensor potential** of photosensors (→ **A**, left) from ca. – 40 mV to ca. – 70 mV (maximum) due to a decrease in conductance of the membrane of the outer sensor segment to Na^+ and Ca^{2+} (→ p. 354ff.). The potential rises and falls much more sharply in the cones than in the rods. As in other sensory cells, the magnitude of the sensor potential is proportional to the logarithm of stimulus intensity divided by threshold-intensity (*Fechner's law*). Hyperpolarization decreases glutamate release from the receptor. When this signal is relayed within the retina, a distinction is made between "direct" **signal flow** for photopic vision and "lateral" signal flow for scotopic vision (see below). Action potentials (APs) can only be generated in ganglion cells (→ **A**, right), but stimulus-dependent amplitude changes of the potentials occur in the other retinal neurons (→ **A**, center). These are conducted electrotonically across the short spaces in the retina (→ p. 48ff.).

Direct signal flow from cones to bipolar cells is conducted via ON or OFF bipolar cells. Photostimulation leads to depolarization of ON bipolar cells (signal inversion) and activation of their respective ON ganglion cells (→ **A**). OFF bipolar cells, on the other hand, are hyperpolarized by photostimulation, which has an inhibitory effect on their OFF ganglion cells. **"Lateral" signal flow** can occur via the following pathway: rod ⇒ rod–bipolar cell ⇒ rod–amacrine cell ⇒ ON or OFF bipolar cell ⇒ ON or OFF ganglion cell. Both rod–bipolar cells and rod–amacrine cells are depolarized in response to light. Rod–amacrine cells inhibit OFF bipolar cells via a chemical synapse and stimulate ON bipolar cells via an electrical synapse (→ p. 50).

A light stimulus triggers the firing of an AP in ON ganglion cells (→ **A**, right). The AP frequency increases with the sensor potential amplitude. The APs of ON ganglion cells can be measured using microelectrodes. This data can be used to identify the retinal region in which the stimulatory and inhibitory effects on AP frequency originate. This region is called the **receptive field (RF)** of the ganglion cell. Retinal ganglion cells have concentric RFs comprising a central zone and a ringlike peripheral zone distinguishable during light adaptation (→ **B**). Photic stimulation of the center increases the AP frequency of ON ganglion cells (→ **B1**). Stimulation of the periphery, on the other hand, leads to a decrease in AP frequency, but excitation occurs when the light source is switched off (→ **B2**). This type of RF is referred to as an *ON field* (central field ON). The RF of OFF ganglion cells exhibits the reverse response and is referred to as an *OFF field* (central field OFF). *Horizontal cells* are responsible for the functional organization of the RFs (→ p. 350). They invert the impulses from photosensors in the periphery of the RF and transmit them to the sensors of the center. The opposing central and peripheral responses lead to a **stimulus contrast**. At a light–dark interface, for example, the dark side appears darker and the light side brighter. If the entire RF is exposed to light, the impulses from the center usually predominate.


Simultaneous contrast. A solid gray circle appears darker in light surroundings than in dark surroundings (→ **C**, left). When a subject focuses on a black-and-white grid (→ **C**, right), the white grid lines appear to be darker at the cross-sections, black grid lines appear lighter because of reduced contrast in these areas. This effect can be attributed to a variable sum of stimuli within the RFs (→ **C**, center).

During **dark adaptation**, the center of the RFs increases in size at the expense of the periphery, which ultimately disappears. This leads to an increase in spatial summation (→ p. 359 C3), but to a simultaneous decrease in stimulus contrast and thus to a lower visual acuity (→ p. 355 B2).


Color opponency. Red and green light (or blue and yellow light) have opposing effects in the RFs of β ganglion cells (→ p. 364) and more centrally located cells of the optic tract (→ p. 363 E). These effects are explained by **Hering's opponent colors theory** and ensure contrast (increase color saturation; → p. 362) in color vision. When a subject focuses on a color test pattern (→ p. 365 C) for about 30 min and then shifts the gaze to a neutral background, the complementary colors will be seen (*color successive contrast*).

RFs of **higher centers** of the optic tract (V1, V2; → p. 366) can also be identified, but their characteristics change. Shape (striate or angular), length, axial direction and direction of movement of the photic stimuli play important roles.


A. Potentials of photosensor, ON-bipolar and ON-ganglion cells



B. Receptive fields of ON-ganglion cells (1, 2) and OFF-ganglion cells (3, 4)



C. Receptive field-related contrast (ON-ganglion cells)



White light passing through a prism is split into a color spectrum ranging from red to violet (colors of the rainbow). *Red* is perceived at a wavelength (λ) of 650–700 nm, and violet at around 400–420 nm (→ **A**). The eye is sensitive to waves in this λ range. Perception of white light does not require the presence of all colors of the visible spectrum. It is sufficient to have the additive effects (mixing) of only two **complementary colors**, e.g., orange (612 nm) and blue light (490 nm).

A **color triangle** (→ **B**) or similar test panel can be used to illustrate this effect. The two upper limbs of the triangle show the visible spectrum, and a white dot is located inside the triangle. All straight lines passing through this dot intersect the upper limbs of the triangle at two complementary wavelengths (e.g., 612 and 490 nm). **Additive color mixing** (→ **C**): The color yellow is obtained by mixing roughly equal parts of red and green light. Orange is produced by using a higher red fraction, and yellowish green is obtained with a higher green fraction. These colors lie between red and green on the limbs of the color triangle. Similar rules apply when mixing green and violet (→ **B** and **C**). The combination of red with violet yields a shade of purple not contained in the spectrum (→ **B**). This means that all colors, including white, can be produced by varying the proportions of three colors—e.g. red (700 nm), green (546 nm) and blue (435 nm) because every possible pair of complementary colors can be obtained by mixing these three colors of the spectrum.

Subtractive color mixing is based on the opposite principle. This technique is applied when color paints and camera filters are used. Yellow paints or filters absorb ("subtract") the blue fraction of white light, leaving the complementary color yellow.

Light absorption. Photosensors must be able to absorb light to be photosensitive. **Rods** (→ p. 354) contain **rhodopsin**, which is responsible for (achromatic) night vision. Rhodopsin absorbs light at wavelengths of ca. 400–600 nm; the maximum absorption value (λ_{max}) is 500 nm (→ **E1**). Relatively speaking, greenish blue light therefore appears brightest and red appears darkest at night. Wearing red glasses in daylight therefore leaves the rods adapted for darkness. Three types of color-sensitive **cones** are responsible for (chromatic) day vision (→ **E1**): (1) *S cones*, which absorb short-wave (S) blue-violet light (λ_{max} = 420 nm); (2) *M cones*, which absorb medium-wave (M) blue-green to yellow light (λ_{max} = 535 nm), and (3) *L cones*, which absorb long-wave (L) yellow to red light (λ_{max} = 565 nm). (The physiological sensitivity curves shown in **E1** make allowances for light absorbed by the lens.) *Ultraviolet rays* ($\lambda_{max} < 400$ nm) and *infrared rays* ($\lambda_{max} > 700$ nm) are not visible.


Sensory information relayed by the three types of cones (peripheral application of the *trichromatic theory of color vision*) and transduction of these visual impulses to *brightness* and *opponent color channels* (→ **E2** and p. 360) in the retina and lateral geniculate body (LGB) enables the visual cortex (→ p. 364) to recognize different **types of colors**. The human eye can distinguish 200 shades of color and different degrees of color saturation. The absolute *differential threshold for color vision* is 1–2 nm (→ **D**, "normal").

Color perception is more complex. White paper, for example, will look white in white light (sunlight), yellow light (light bulb) and red light. We also do not perceive the different shades of color in a house that is partially illuminated by sunlight and partially in the shade. This **color constancy** is the result of retinal and central processing of the retinal signal.


There is a similar **constancy of size and shape**: Although someone standing 200 meters away makes a much smaller image on the retina than at 2 meters' distance, we still recognize him or her as a person of normal height, and although a square table may appear rhomboid in shape when viewed from the side, we can still tell that it is square.

Color blindness occurs in 9% of all men and in 0.5% of women. The ability to distinguish certain colors is impaired or absent in these individuals, i.e., they have a *high differential threshold for color* (→ **D**). Various types of color blindness are distinguished: *protanopia* (red blindness), *deuteranopia* (green blindness), and *tritanopia* (blue-violet blindness). Protanomaly, deuteranomaly and tritanomaly are characterized by decreased sensitivity of the cones to colored, green and blue, respectively. Color vision is tested using *color perception charts* or an *anomaloscope*. With the latter, the subject has to mix two color beams (e.g., red and green) with adjustable intensities until their additive mixture matches a specific shade of color (e.g. yellow, → **C**) presented for comparison. A protanomal subject needs a too high red intensity, a deuteranomal person a too high green intensity. Protanopes perceive all colors with wavelengths over approx. 520 nm as yellow.

A. Composition of sunlight




B. Color triangle




(After Kries)

C. Additive color mixing




D. Differential threshold for wavelength




E. Physiological sensitivity of rods and cones (1) and color opponency in neuronal processing (2)

1



(After J.K. Bowmarker and H.J.A. Dartnall)

2



(After J. Krauskopf et al.)

The **visual field** (→ **A**) is the area visualized by the *immobile* eye with the head fixed.

The visual field is examined by **perimetry**. The subject's eye is positioned in the center of the perimeter, which is a hollow hemispherical instrument. The subject must then report when laterally flashed points of light appear in or disappear from the visual field.

An area of lost vision within the visual field is a **scotoma**. Lesions of the retina, or of the central visual pathway can cause scotoma.

The **blind spot** (→ **A**) is a normal scotoma occurring at 15 degrees temporal and is caused by nasal interruption of the retina by the optic disk (→ p. 355 B). In binocular vision (→ p. 367 A), the blind spot of one eye is compensated for by the other. The visual field for color stimuli is smaller than that for light–dark stimuli. If, for example, a red object is slowly moved into the visual field, the movement will be identified more quickly than the color of the object.

The retina contains more than 10^8 photosensors connected by retinal neurons (→ p. 360) to ca. 10^6 retinal ganglion cells. Their axons form the **optic nerve**. The convergence of so many sensors on only a few neurons is particularly evident in the retinal periphery (1000 : 1). In the fovea centralis, however, only one or a few cones are connected to one neuron. Due to the low convergence of impulses from the fovea, there is a high level of visual acuity with a low level of light sensitivity, whereas the high convergence of signals from the periphery produces the reverse effect (*cf. spatial summation*; → p. 359 C3).

Ganglion cells. Three types of ganglion cells can be found in the retina: (1) 10% are ***M*** (or α or Y) **cells** of the *magnocellular system*; their fast-conducting axons emit short phasic impulses in response to light and are very sensitive to *movement*; (2) 80% are the ***P*** (or β or X) **cells** *of the parvicellular system*; their thin axons have small receptive fields (high spatial resolution), persistently react to constant light (tonic reaction), and therefore permit *pattern and color analysis*. Both types have equal densities of ON and OFF cells (→ p. 360). (3) 10% are γ *(or W) cells* of the *coniocellular system*; their very thin axons project to the mesencephalon and regulate pupil diameter (see below) and reflex saccades (→ pp. 354, 366).


Objects located in the nasal half of the visual field of each eye (→ **B**, blue and green) are imaged in the temporal half of each retina and vice versa. Along the **visual pathway**, fibers of the **optic nerve** from the temporal half of each retina remain on the same side (→ **B**, blue and green), whereas the fibers from the nasal half of each retina decussate at the **optic chiasm** (→ **B**, orange and red). Fibers from the fovea centralis are present on both sides.

Lesions of the left optic *nerve* for instance cause deficits in the entire left visual field (→ **B, a**), whereas lesions of the left optic *tract* produce deficits in the right halves of both visual fields (→ **B, c**). Damage to the median optic *chiasm* results in bilateral temporal deficits, i.e., *bitemporal hemianopia* (→ **B, b**).

Fibers of the optic tract extend to the **lateral geniculate body** (→ **B**) of the thalamus, the six layers of which are organized in a retinotopic manner. Axons of the ipsilateral eye terminate on layers 2, 3 and 5, while those of the contralateral eye terminate on layers 1, 4 and 6. The M cell axons communicate with cells of *magnocellular layers* 1 and 2, which serve as a relay station for *motion-related stimuli* that are rapidly conducted to the motor cortex. The P cell axons project to the *parvocellular layers* 3–6, the main function of which is to *process colors and shapes*. The neurons of all layers then project further through the **optic radiation** (arranged also retinotopically) to the *primary visual cortex* (V_1) and, after decussating, to further areas of the visual cortex ($V_{2–5}$) including pathways to the parietal and temporal cortex. Magnocellular input reaches the parietal cortex also via the superior colliculi (see below) and the pulvinar.

The **primary visual cortex** (**V_1**) is divided depth-wise (x-axis) into six retinotopic layers numbered I to VI (→ p. 335 A). Cells of the primary visual cortex are arranged as three-dimensional modular **hypercolumns** (3 × 1 × 1 mm) representing modules for analysis of all sensory information from corresponding areas of both retinas (→ p. 360). Adjacent hypercolumns represent neighboring retinal regions. Hypercolumns contain *ocular dominance columns* (y-axis), *orientation columns* (z-axis), and *cylinders* (x-axis). The dominance columns receive alternating input from the right and left eye, orientation columns process direction of stimulus movement and cylinders receive information of colors.

Color, high-resolution stationary **shapes**, **movement**, and stereoscopic **depth** are processed in some subcortical visual pathways, and from



V_1 onward in *separate information channels*. These individual aspects must be integrated to achieve visual perception. In diurnally active primates like humans, over half of the cortex is involved in processing visual information. On a simplified scale, the parietal cortex analyzes the "where" and involves motor systems, and the temporal cortex takes care of the "what" of visual input comparing it with memory.

Axons of the optic tract (especially those of M and γ cells) also project to **subcortical regions** of the brain such as the *pretectal region*, which regulates the diameter of the pupils (see below); the *superior colliculi* (→ **B**), which are involved in oculomotor function (→ p. 366); the *hypothalamus*, which is responsible for circadian rhythms (→ p. 336).

The **pupillary reflex** is induced by sudden exposure of the retina to light (→ p. 356). The signal is relayed to the pretectal region; from here, a parasympathetic signal flows via the Edinger–Westphal nucleus, the ciliary ganglion and the oculomotor nerve, and induces narrowing of the pupils (*miosis*) within less than 1 s. Since both pupils respond simultaneously even if the light stimulus is unilateral, this is called a *consensual light response*. Meiosis also occurs when the eyes adjust for near vision *(near-vision response* → p. 366).

The **corneal reflex** protects the eye. An object touching the cornea (afferent: trigeminal nerve) or approaching the eye (afferent: optic nerve) results in reflex closure of the eyelids.

Conjugated movement of the eyes occurs when the external eye muscles move the eyes in the same direction (e.g., from left to right), whereas *vergence movement* is characterized by opposing (divergent or convergent) eye movement. The axes of the eyes are parallel when gazing into the distance. Fixation of the gaze on a nearby object results in convergence of the visual axes. In addition, the pupil contracts (to increase the depth of focus) and accommodation of the lens occurs (→ p. 352). The three reactions are called **near-vision response** or convergence response.

Strabismus. A greater power of accommodation for near vision is required in hyperopia than in normal vision. Since accommodation is always linked with a convergence impulse, hyperopia is often associated with squinting. If the visual axes wander too far apart, vision in one eye will be suppressed to avoid double vision (diplopia). This type of visual impairment, called *strabismic amblyopia*, can be either temporary or chronic.

Saccades. When scanning the visual field, the eyes make jerky movements when changing the point of fixation, e.g., when scanning a line of print. These quick movements that last 10–80 ms are called *saccades*. Displacement of the image is centrally suppressed during the eye due to *saccadic suppression*. A person looking at both of his or her eyes alternately in a mirror cannot perceive the movement of his or her own eyes, but an independent observer can. The small, darting saccades function to keep an object in focus.

Objects entering the field of vision are reflexively imaged in the fovea centralis (→ p. 354). Slow **pursuit movements** of the eyes function to maintain the gaze on moving objects. **Nystagmus** is characterized by a combination of these slow and rapid (saccade-like) opposing eye movements. The direction of nystagmus (right or left) is classified according to the type of rapid phase, e.g., *secondary nystagmus* (→ p. 348). *Optokinetic nystagmus* occurs when viewing an object passing across the field of vision, e.g., when looking at a tree from inside a moving train. Once the eyes have returned to the normal position (return saccade), a new object can be brought into focus.


Damage to the cerebellum or organ of balance (→ p. 348) can result in *pathological nystagmus*.

The brain stem is the main center responsible for **programming** of eye movements. Rapid horizontal (conjugated) movements such as saccades and rapid nystagmus movement are programmed in the pons, whereas vertical and torsion movements are programmed in the mesencephalon. The cerebellum provides the necessary fine tuning (→ p. 328). Neurons in the region of the Edinger–Westphal nucleus are responsible for vergence movements.


In near vision, **depth vision** and **three-dimensional vision** are primarily achieved through the coordinated efforts of both eyes and are therefore limited to the **binocular field of vision** (→ **A**). If both eyes focus on point A (→ **B**), an image of the fixation point is projected on both foveae (A_L, A_R), i.e., on the *corresponding areas of the retina*. The same applies for points B and C (→ **B**) since they both lie on a circle that intersects fixation point A and nodal points N (→ p. 353 B) of the two eyes (**Vieth–Müller horopter**). If there were an imaginary middle eye in which the two retinal regions (in the cortex) precisely overlapped, the retinal sites would correspond to a central point $A_C \triangleq A_L + A_R$ (→ **C**). Assuming there is a point D outside the horopter (→ **C**, left), the middle eye would see a double image (D′, D″) instead of point D, where D′ is from the left eye (D_L). If D and A are not too far apart, central processing of the double image creates the perception that D is located behind D, i.e., *depth perception* occurs. A similar effect occurs when a point E (→ **C**, right) is closer than A; in this case, the E′ image will arise in the right eye (E'_R) and E will be perceived as being closer.

Depth perception from a distance. When viewing objects from great distances or with only one eye, contour overlap, haze, shadows, size differences, etc. are cues for depth perception (→ **D**). A nearby object moves across the field of vision more quickly than a distant object, e.g., in the case of the sign compared to the wall in plate **D**). In addition, the moon appears to migrate with the moving car, while the mountains disappear from sight.


A. Binocular visual field




B. Horopter




C. Three-dimensional vision (binocular vision)



D. Cues for depth vision





Sound waves are the adequate stimulus for the organ of hearing. They arise from a sound source such as a gong (→ **A1**) and are conducted in gases, liquids, and solids. The air is the main carrier of sound.

The air pressure rises and falls rhythmically at the sound source. These pressure waves (sound waves) travel at a characteristic **sound velocity** (**c**) in different materials, e.g., at 332 m/s in air of 0 °C. A graphic recording of sound waves (→ **A1**) will produce waveform curves. The **wavelength** (λ) is the distance between the top of one wave and the identical phase of the succeeding one, and the maximum deviation of pressure from baseline is the **amplitude** (**a**) (→ **A1**). Enlargement (reduction) of wavelength will lower (raise) the tone, whereas a fall (rise) in amplitude will produce a quieter (louder) tone (→ **A1**). The **pitch** of a tone is defined by its **frequency** (**f**), i.e., the number of sound pressure oscillations per unit time. Frequency is measured in **hertz** (Hz = s^{-1}). Frequency, wavelength and the sound velocity are related:

$$f\,(Hz) \cdot \lambda\,(m) = c\,(m \cdot s^{-1}). \qquad [12.1]$$

A **pure tone** has a simple sinus waveform. The tones emanating from most sound sources (e.g., musical instrument, voice) are mixtures of different frequencies and amplitudes that result in complex periodic vibrations referred to as **sound** (→ **A2**). The fundamental (lowest) tone in the complex determines the *pitch* of the sound, and the higher ones determine its *timbre* (overtones). An a^1 (440 Hz) sung by a tenor or played on a harp therefore has a different sound than one produced on an organ or piano. The overlap of two very similar tones produces a distinct effect characterized by a *beat tone* of a much lower frequency (→ **A3**, blue/red).

Audibility limits. Healthy young persons can hear sounds ranging in frequency from 16 to 20 000 Hz. The upper limit of audibility can drop to 5000 Hz due to aging (*presbycusis*). At 1000 Hz, the **absolute auditory threshold** or lowest sound pressure perceived as sound is $3 \cdot 10^{-5}$ Pa. The threshold of sound is frequency-dependent (→ **B**, green curve). The threshold of hearing for a tone rises tremendously when other tones are heard simultaneously. This phenomenon called *masking* is the reason why it is so difficult to carry on a conversation against loud background noise. The ear is overwhelmed by sound pressures over 60 Pa, which corresponds to $2 \cdot 10^6$ times the sound pressure of the limit of audibility at 1000 Hz. Sounds above this level induce the sensation of pain (→ **B**, red curve).

For practical reasons, the *decibel (dB)* is used as a logarithmic measure of the **sound pressure level (SPL)**. Given an arbitrary reference sound pressure of $p_o = 2 \cdot 10^{-5}$ Pa, the sound pressure level (SPL) can be calculated as follows:

$$SPL\,(dB) = 20 \cdot \log\,(p_x/p_o) \qquad [12.2]$$

where p_x is the actual sound pressure. A tenfold increase in the sound pressure therefore means that the SPL rises by 20 dB.


The **sound intensity (I)** is the amount of sound energy passing through a given unit of area per unit of time ($W \cdot m^{-2}$). The sound intensity is proportional to the *square* of p_x. Therefore, dB values cannot be calculated on a simple linear basis. If, for example, two loudspeakers produce 70 dB each ($p_x = 6.3 \cdot 10^{-2}$ Pa), they do *not* produce 140 dB together, but a mere 73 dB because p_x only increases by a factor of $\sqrt{2}$ when the intensity level doubles. Thus, $\sqrt{2} \cdot 6.3 \cdot 10^{-2}$ Pa has to be inserted for p_x into Eq. 12.2.

Sound waves with different frequencies but equal sound pressures are not *subjectively* perceived as *equally loud*. A 63 Hz tone is only perceived to be as loud as a 20 dB/1000 Hz reference tone if the sound pressure of the 63 Hz tone is 30-fold higher (+ 29 dB). In this case, the sound pressure level of the reference tone (20 dB/1000 Hz) gives the loudness level of the 63 Hz tone in **phon** (20 phon) as at a frequency of 1000 Hz, the phon scale is numerically equals the dB SPL scale (→ **B**). Equal loudness contours or **isophones** can be obtained by plotting the subjective values of equal loudness for test frequencies over the whole audible range (→ **B**, blue curves). The absolute auditory threshold is also an isophone (4 phons; → **B**, green curve). Human hearing is most sensitive in the 2000–5000 Hz range (→ **B**).


Note: Another unit is used to describe how a tone of constant frequency is subjectively perceived as louder or less loud. *Sone* is the unit of this type of loudness, where 1 sone = 40 phons at 1000 Hz. 2 sones equal twice the reference loudness, and 0.5 sone is $^1/_2$ the reference loudness.

The **auditory area** in diagram **B** is limited by the highest and lowest audible frequencies on the one side, and by isophones of the thresholds of hearing and pain on the other. The green area in plate **B** represents the range of frequencies and intensities required for comprehension of ordinary speech (→ **B**).

A. Wavelength, wave amplitude and wave types



B. Sound pressure, sound pressure level and loudness level



Sound waves are transmitted to the organ of hearing via the *external ear* and the *auditory canal*, which terminates at the *tympanic membrane* or *eardrum*. The sound waves are conducted through the air (**air conduction**) and set the eardrum in vibration. These are transmitted via the *auditory ossicles* of the tympanic cavity (*middle ear*) to the membrane of the *oval window* (→ **A 1,2**), where the *internal* or *inner ear* (labyrinth) begins.

In the **middle ear**, the *malleus, incus* and *stapes* conduct the vibrations of the tympanic membrane to the oval window. This ensures that the sound is conducted from the low wave resistance/impedance in air to the high resistance in fluid with as little loss of energy as possible. This **impedance adaptation** occurs at $f < 2400$ Hz and is based on a 22-fold pressure amplification (tympanic membrane area/oval window area is 17 : 1, and leverage arm action of the auditory ossicles amplifies force by a factor of 1.3).

Impairment of impedance transforming capacity due, e.g., to destruction of the ossicles, causes roughly 20 dB of hearing loss (*conduction deafness*).

Muscles of the middle ear. The middle ear contains two small muscles—the *tensor tympani* (insertion: manubrium of malleus) and the *stapedius* (insertion: stapes)—that can reflectively attenuate low-frequency sound (i.e., protect the ear from loud sounds, among other functions).

Bone conduction. Sound sets the skull in vibration, and these bone-borne vibrations are conducted directly to the cochlea. Bone conduction is fairly insignificant for physiological function, but is useful for testing the hearing. In **Weber's test**, a vibrating tuning fork (a^1) is placed in the middle of the head. A person with normal hearing can determine the location of the tuning fork because of the symmetrical conduction of sound waves. A patient with *unilateral conduction deafness* will perceive the sound as coming from the affected side (lateralization) because of the lack of masking of environmental noises in that ear (bone conduction). A person with *sensorineural deafness*, on the other hand, will perceive the sound as coming from the healthy ear because of sound attenuation in the affected internal ear. In **Rinne's test**, the handle of a tuning fork is placed on one mastoid process (bony process behind the ear) of the patient (bone conduction). If the tone is no longer heard, the tines of the tuning fork are placed in front of the ear (air conduction). Individuals with normal hearing or sensorineural deafness can hear the turning fork in the latter position anew (positive test result), whereas those with conduction deafness cannot (test negative).


The **inner ear** consists of the *equilibrium organ* (→ p. 348) and the **cochlea**, a spiraling bony tube that is 3–4 cm in length. Inside the cochlea is an endolymph-filled duct called the *scala media* (*cochlear duct*); the ductus reuniens connects the base of the cochlear duct to the endolymph-filled part of the equilibrium organ. The scala media is accompanied on either side by two perilymph-filled cavities: the *scala vestibuli* and *scala tympani*. These cavities merge at the apex of the cochlea to form the *helicotrema*. The scala vestibuli arises from the oval window, and the scala tympani terminates on the membrane of the round window (→ **A2**). The composition of perilymph is similar to that of plasma water (→ p. 93 C), and the composition of endolymph is similar to that of the cytosol (see below). Perilymph circulates in Corti's tunnel and Nuel's spaces (→ **A4**).

Organ of Corti. The 10 000–12 000 external and 3500 internal **hair cells** (**HC**s) that both sit upon the basilar membrane are the sensory cells of the hearing organ (→ **A4**). Their structure is very similar to the HCs of the vestibular organ (→ p. 348). Every HC has approx. 80 stereocilia, but the kinocilia are absent or rudimentary.

There are three rows of slender, cylindrical **outer hair cells.** The tips of their stereocilia are firmly attached to the tectorial membrane and surrounded by endolymph, whereas their cell bodies float in perilymph of Nuel's spaces (→ **A4**). The outer hair cells are principally innervated by efferent, mostly cholinergic neurons from the spiral ganglion (N_M-cholinoceptors; → p. 82). The pear-shaped **inner hair cells** are arranged in a single row and are almost completely surrounded by supporting cells. Only their cilia project freely into the endolymph. The inner hair cells are secondary sensory cells and synapse with over 90% of the afferent fibers of the spiral ganglion.

Inner ear potentials (→ p. 375 C). On the cilia side, the hair cells border with the endolymph-filled space, which has a potential difference (*endocochlear potential*) of ca. +80 to +110 mV relative to perilymph (→ p. 375 C). This potential difference is maintained by an active transport mechanism in the *stria vascularis*. Since the cell potential of outer (inner) hair cells is −70 mV (−40 mV), a potential difference of roughly 150–180 mV (120–150 mV) prevails across the cell membrane occupied by cilia (cell interior negative). Since the K^+ conc. in the endolymph and hair cells is roughly equal ▶

A. Reception and conduction of sound stimuli



▶ (≈140 mmol/L), the prevailing K^+ equilibrium potential is ca. 0 mV (→ p. 32).

Sound conduction in the inner ear. The stapes moves against the membrane of the oval window membrane, causing it to vibrate. These are transmitted via the perilymph to the membrane of the round window (→ **A2**). The walls of the endolymph-filled cochlear duct, i.e. Reissner's membrane and the basilar membrane (→ **D1**) give against the pressure wave (**migrating wave**, → **B** and **C**). It can therefore take a "short cut" to reach the round window without crossing the helicotrema. Since the cochlear duct is deformed in waves, Reissner's membrane and the basilar membrane vibrate alternately towards the scala vestibuli and scala tympani. The velocity and wavelength of the migrating wave that started at the oval window decrease continuously (→ **B**), while their *amplitude* increases to a *maximum* and then quickly subsides (→ **B**, envelope curve). (The wave velocity is not equal to the velocity of sound, but is much slower.) The **site** of the maximum excursion of the cochlear duct is characteristic of the wavelength of the stimulating sound. The higher the frequency of the sound, the closer the site is to the stapes (→ **C**).


Outer hair cells. Vibration of the cochlear duct causes a discrete shearing (of roughly 0.3 nm) of the tectorial membrane against the basilar membrane, causing *bending of the stereocilia* of the *outer hair cells* (→ **D1**). This exerts also a shearing force between the cilia of the individual external hair cell. This bending in one direction activates the "*tip links*" (→ p. 349 A3), and causes mechanosensitive cation channels (MET channels) in the stereociliary membranes to open allowing K^+ ions driven by the 150–180 mV mentioned above to enter and depolarize the outer hair cells (**mechanoelectric transduction MET**). This causes the outer hair cells to *shorten* in sync with stimulation. Repolarization is achieved by the opening of tension-dependent K^+ channels (KCNQ4) on the perilymph side of the HC. The outflowing K^+ is taken up by K^+-Cl^- cotransporters (KCC4) in supporting cells and recirculated via gap junctions to the stria vascularis. The subsequent bending of the stereocilia in the opposite direction causes hyperpolarization (closure of the MET channels) and extension of the outer HCs. This extremely fast tension-sensitive **electromotility of the outer hair cells** (up to 20 kHz, i.e. $2 \cdot 10^4$ times/s) is produced by the motor protein *prestin*. Cl^- and HCO_3^- ions are stored in prestin, dependent on the tension, and therefore act as tension sensors. Their presence changes the densely packed conformation of the prestin, which results in extension of the outer HCs. At the site of maximum reaction to the sound frequency the electromotility of the outer HCs causes endolymph waves in the subtectorial space, which in turn also bends the stereocilia of the inner hair cell (→ **D3**). Their depolarization triggered by the opening of the MET channels is the sensor potential for the inner HCs, which via opening of basolateral Ca^{2+} channels increases the cytosolic Ca^{2+} concentration. This leads to transmitter release (*glutamate* coupling to AMPA receptors; → p. 55 F) and the subsequent conduction of impulses to the CNS (→ **D2**, **3**).

The outer hair cell electromotility contributes to the **cochlear amplification** (ca. 100-fold or 40 dB amplification), which occurs before sound waves reach the actual sound sensors, i.e. inner hair cells. This explains the very low threshold within the very narrow location (0.5 mm) and thus within a very small frequency range.


The vibrations in the internal ear set off an outward emission of sound. These **evoked otoacoustic emissions** can be objectively measured by placing a microphone in front of the tympanic membrane, e.g., to test internal ear function in infants and other individuals incapable of reporting their hearing sensations.

Subjective hearing tests are performed using an **audiometer**. The patient is presented sounds of various frequencies and routes of conduction (bone, air). The sound pressure is initially set at a level under the threshold of hearing and is raised in increments until the patient is able to hear the presented sound (*threshold audiogram*). If the patient is unable to hear the sounds at normal levels, he or she has an hearing loss, which is quantitated in decibels (dB). In **audiometry**, all frequencies at the normal threshold of hearing are assigned the value of 0 dB (unlike the diagram on p. 369 B, green curve). Hearing loss can be caused by presbycusis (→ p. 368), middle ear infection (impaired air conduction), and damage to the internal ear (impaired air and bone conduction) caused, for example, by prolonged exposure to excessive sound pressure, by ototoxic medication (blockage of stria vascularis by loop diuretics), or by defects of the KCNQ4 or KCC4 genes.


B. Migrating wave in cochlea: maximum amplitude and 3-D topography snapshot



C. Frequency imaging in cochlea



D. Stimulation of hair cells by membrane deformation



Various qualities of sound must be coded for signal transmission in the acoustic pathway. These include the frequency, intensity and direction of sound waves as well as the distance of the sound source from the listener.

Frequency imaging. Tones of various frequencies are "imaged" along the cochlea (→ p. 373 C), conducted in separate fibers of the auditory pathway and centrally identified. Assuming that a tone of 1000 Hz can just be distinguished from one of 1003 Hz (resembling true conditions), the frequency difference of 3 Hz corresponds to a relative *frequency differential threshold* of 0.003 (→ p. 358). This fine differential capacity is mainly due to frequency imaging in the cochlea, amplification by its outer hair cells (→ p. 372), and neuronal contrast along the auditory pathway (→ p. 315 D). This fine **tuning** ensures that a certain frequency has a particularly low threshold at its "imaging" site. Adjacent fibers are not recruited until higher sound pressures are encountered.


Intensity. Higher intensity levels result in higher action potential frequencies in afferent nerve fibers and recruitment of neighboring nerve fibers (→ **A**). The relative *intensity differential threshold* is 0.1 (→ p. 358), which is very crude compared to the frequency differential threshold. Hence, differences in loudness of sound are not perceived by the human ear until the intensity level changes by a factor of over 1.1, that is, until the sound pressure changes by a factor of over $\sqrt{1{,}1} = 1{,}05$.

Direction. *Binaural hearing* is needed to identify the direction of sound waves and is based on the following two effects. (1) Sound waves that strike the ear obliquely reach the averted ear later than the other, resulting in a *lag time*. The change in direction that a normal human subject can just barely detect (*direction threshold*) is roughly 3 degrees. This angle delays the arrival of the sound waves in the averted ear by about $3 \cdot 10^{-5}$ s (→ **B**, left). (2) Sound reaching the averted ear is also perceived as being *quieter*; differences as small as 1 dB can be distinguished. A lower sound pressure results in delayed firing of actions potentials, i.e., in increased *latency* (→ **B**, right). Thus, the impulses from the averted ear reach the CNS later (nucleus accessorius, → **D5**). Effects (1) and (2) are additive effects (→ **B**). The external ear helps to decide whether the sound is coming from front or back, above or below. Binaural hearing also helps to distinguish a certain voice against high background noise, e.g., at a party. Visibility of the speaker's mouth also facilitates comprehension.


Distance to the sound source can be determined because high frequencies are attenuated more strongly than low frequencies during sound wave conduction. The longer the sound wave travels, the lower the proportion of high frequencies when it reaches the listener. This helps, for instance, to determine whether a thunderstorm is nearby or far away.

Auditory pathway (→ **D**). The auditory nerve fibers with somata positioned in the *spiral ganglion* of the cochlea project from the cochlea (→ **D1**) to the anterolateral (→ **D2**), posteroventral and dorsal cochlear nuclei (→ **D3**). Afferents in these three nuclei exhibit *tonotopicity*, i.e., they are arranged according to tone frequency at different levels of complexity. In these areas, *lateral inhibition* (→ p. 315 D) enhances *contrast*, i.e., suppresses noise. Binaural comparison of intensity and transit time of sound waves (direction of sound) takes place at the next-higher station of the auditory pathway, i.e. in the *superior olive* (→ **D4**) and *accessory nucleus* (→ **D5**). The next stations are in the *nucleus of lateral lemniscus* (→ **D6**) and, after most fibers cross over to the opposite side, the *inferior quadrigeminal bodies* (→ **D7**). They synapse with numerous afferents and serve as a reflex station (e.g., muscles of the middle ear; → p. 372). Here, sensory information from the cochlear nuclei is compared with spatial information from the superior olive. Via connections to the superior quadrigeminal bodies (→ **D8**), they also ensure coordination of the auditory and visual space. By way of the thalamus (medial geniculate body, MGB; → **D9**), the afferents ultimately reach the *primary* **auditory cortex** (→ **D10**) and the surrounding secondary auditory areas (→ p. 313 E, areas 41 and 22). Analysis of complex sounds, short-term memory for comparison of tones, and tasks required for "eavesdropping" are some of their functions.


A. Loudness processing in acoustic nerve (at constant sound frequency)




B. Binaural hearing: lag time and latency differences



C. Cochlear potentials and electrolyte distribution (see text on p. 370)



D. Afferent auditory pathway



The human voice primarily functions as a **means of communication**, the performance of which is based on the human capacity of hearing (→ p. 369 B). As in wind instruments, the body contains a *wind space* (trachea, bronchi, etc.). Air is driven through the space between the *vocal cords* (rima glottidis) into the *air space* (*passages above the glottis*), which sets the vocal cords into vibration. The air space consists of the throat and oronasal cavities (→ **A**). The range of the human voice is so immense because of the large variety of muscles that function to modulate the intensity of the airstream (*loudness*), tension of the vocal cords, shape/width of the vocal cords (*fundamental tone*) and size/shape of the air space (*timbre, formants*) of each individual.

Joints and muscles of the **larynx** function to adjust the vocal cords and rima glottidis. A stream of air opens and closes the rima glottidis and sets off the rolling movement of the vocal cords (→ **B**). When a deep tone is produced, the fissure of the glottis remains closed longer than it opens (ratio of 5 : 1 at 100 Hz). This ratio drops to 1.4 : 1 in higher tones (400 Hz). The rima glottidis remains open when whispering or singing falsetto (→ **C**, blue).

Motor signals originate in the motosensory cortex (→ p. 327 C/B, tongue/throat) and are conducted via the vagus nerve to the larynx. Sensory impulses responsible for voice production and the cough reflex are also conducted by the vagus nerve. Sensory fibers from the mucosa and muscle spindles of the larynx (→ p. 318) continuously transmit information on the position and tension of the vocal cords to the CNS. These reflexes and the close connection of the auditory pathway with bulbar and cortical motor speech centers are important for **fine adjustment of the voice**.

Vowels (→ **D**). Although their fundamental frequencies are similar (100–130 Hz), spoken vowels can be distinguished by their characteristic overtones (*formants*). Different formants are produced by modifying the shape of oral tract, i.e., mouth and lips (→ **D**). The three primary vowels [a:], [i:], [u:] make up the *vowel triangle;* [œ:], [ɔ:], [ø:], [y:], [æ:], and [ɛ] are intermediates (→ **D**).

The phonetic notation used here is that of the *International Phonetic Society*. The symbols mentioned here are as follows: [a:] as in glass; [i:] as in beat; [u:] as in food; [œ:] as in French *peur*; [ɔ:] as in bought; [ø:] as in French *peu* or in German *hören*; [y:] as in French *menu* or in German *trüb*; [æ:] as in bad; [ɛ:] as in head.

Consonants are described according to their site of articulation as *labial* (lips, teeth), e.g. P/B/W/F/M; *dental* (teeth, tongue), e.g. D/T/S/M; *lingual* (tongue, front of soft palate), e.g. L; *guttural* (back of tongue and soft palate), e.g. G/K. Consonants can be also defined according to their manner of articulation, e.g., *plosives* or *stop consonants* (P/B/T/D/K/G), *fricatives* (F/V/W/S/Ch) and *vibratives* (R).

The **frequency range** of the voice, including formants, is roughly 40–2000 Hz. Sibilants like /s/ and /z/ have higher-frequency fractions. Individuals suffering from presbyacusis or other forms of sensorineural hearing loss are often unable to hear sibilants, making it impossible for them to distinguish between words like "bad" and "bass." The **tonal range** (fundamental tone, → **C**) of the *spoken voice* is roughly one octave; that of the *singing voice* is roughly two octaves in untrained singers, and over three octaves in trained singers.


Language (see also p. 342). The main components of verbal communication are (a) auditory signal processing (→ p. 374), (b) central speech production and (c) execution of motor speech function. The centers for *speech comprehension* are mainly located in the posterior part of area 22, i.e., **Wernicke's area** (→ p. 313 E).

Lesions of it result in a loss of language comprehension capacity (sensory aphasia). The patient will speak fluently yet often incomprehensibly, but does not notice it because of his/her disturbed comprehension capacity. The patient is also unable to understand complicated sentences or written words.


The centers for *speech production* are mainly located in areas 44 and 45, i.e., **Broca's area** (→ p. 313 E). It controls the primary speech centers of the sensorimotor cortex.

Lesions of this and other cortical centers (e.g., gyrus angularis) result in disorders of speech production (*motor aphasia*). The typical patient is either completely unable to speak or can only express himself in telegraphic style. Another form of aphasia is characterized by the forgetfulness of words (*anomic* or *amnestic aphasia*). Lesions of executive motor centers (corticobulbar tracts, cerebellum) cause various *speech disorders*. Auditory feed back is extremely important for speech. When a person goes deaf, speech deteriorates to an appreciable extent. Children born deaf do not learn to speak.


A. Larynx (cross-section)



B. Motion of vocal cords




(After Smith)




(After Paulsen)

C. Vocal range and singing range



(After Stockhausen-Spiess)

D. Vowel production



(After Grützner and Freystedt)

Physiology is the science of life processes and bodily functions. Since they are largely based on physical and chemical laws, the investigation, understanding, assessment, and manipulation of these functions is inseparably linked to the measurement of physical, chemical, and other **parameters**, such as blood pressure, hearing capacity, blood pH, and cardiac output. The **units** for measurement of these parameters are listed in this section. We have given preference to the *international system of SI units* (Système International d'Unités) for uniformity and ease of calculation. Non-SI units will be marked with an asterisk. *Conversion factors* for older units are also listed. Complicated or less common physiological units (e.g., wall tension, flow resistance, compliance) are generally explained in the book as they appear. However, some especially important terms that are often (not always correctly) used in physiology will be explained in the Appendix, e.g., concentration, activity, osmolality, osmotic pressure, oncotic pressure, and pH.

The seven base units of the SI system.

Unit	Symbol	Dimension
Meter	m	length
Kilogram	kg	mass
Second	s	time
Mole	mol	amount of substance
Ampere	A	electric current
Kelvin	K	temperature (absolute)
Candela	cd	luminous intensity

The base units are precisely defined autonomous units. All other units are derived by multiplying or dividing base units and are therefore referred to as **derived units**, e.g.:

— Area (length · length): $m \cdot m = m^2$

— Velocity (length/time): $m/s = m \cdot s^{-1}$.

If the new unit becomes too complicated, it is given a new name and a corresponding symbol, e.g., force = $m \cdot kg \cdot s^{-2} = N$ (→ **Table 1**).

Fractions and Multiples of Units

Prefixes are used to denote decimal multiples and fractions of a unit since it is both tedious and confusing to write large numbers. We generally write 10 kg (kilograms) and 10 μg (micrograms) instead of 10 000 g and 0.00001 g, for example. The prefixes, which are usually varied in 1000-unit increments, and the corresponding symbols and conversion factors are listed in **Table 2**. Prefixes are used with base units and the units derived from them (→ **Table 1**), e.g., 10^3 Pa = 1 kPa. Decimal increments are used in some cases (e.g., da, h, d, and c; → **Table 2**). **Time** is given in conventional nondecimal units, i.e., *seconds* (s), *minutes* (min), *hours* (h), and *days* (d).

Length, Area, Volume

The *meter* (m) is the SI unit of **length**. Other units of length have also been used.

Examples:

1 ångström (Å) = 10^{-10} m = 0.1 nm

1 micron (μ) = 10^{-6} m = 1 μm

1 millimicron (mμ) = 10^{-9} m = 1 nm

American and British units of length:

1 inch = 0.0254 m = 25.4 mm

1 foot = 0.3048 m

1 yard = 3 feet = 0.9144 m

1 (statute) mile = 1609.344 m ≈ 1.61 km

1 nautical mile = 1.853 km

The *square meter* (m^2) is the derived SI unit of **area**, and the *cubic meter* (m^3) is the corresponding unit of **volume**. When denoting the fractions or multiples of these units with prefixes (**Table 2**), please note that there are some peculiarities.

Examples:

1 m = 10^3 mm, but

1 mm^2 = 10^6 mm^2, and

1 m^3 = 10^9 mm^3

The *liter* (L or l)* is often used as a unit of *volume* for liquids and gases:

1 L = 10^{-3} m^3 = 1 dm^3

1 mL = 10^{-6} m^3 = 1 cm^3

1 μL = 10^{-9} m^3 = 1 mm^3.

Table 1 Derived units based on SI base units m, kg, s, cd, and A

Coulomb	C	electrical charge	$s \cdot A$
Farad	F	electrical capacitance	$C \cdot V^{-1} = m^{-2} \cdot kg^{-1} \cdot s^4 \cdot A^2$
Hertz	Hz	frequency	s^{-1}
Joule	J	heat, energy, work	$N \cdot m = m^2 \cdot kg \cdot s^{-2}$
Lumen	lm	light flux	$cd \cdot sr$
Lux	lx	light intensity	$lm \cdot m^{-2} = cd \cdot sr \cdot m^{-2}$
Newton	N	force	$m \cdot kg \cdot s^{-2}$
Ohm	Ω	electrical resistance	$V \cdot A^{-1} = m^2 \cdot kg \cdot s^{-3} \cdot A^{-2}$
Pascal	P	pressure	$N \cdot m^{-2} = m^{-1} \cdot kg \cdot s^{-2}$
Siemens	S	conductivity	$\Omega^{-1} = m^{-2} \cdot kg^{-1} \cdot s^3 \cdot A^2$
Steradian	sr	measure of solid angle[1]	$1 (m^2 \cdot m^{-2})$
Tesla	T	magnetic flux density	$Wb \cdot m^{-2} = kg \cdot s^{-2} \cdot A^{-1}$
Volt	V	electric potential	$W \cdot A^{-1} = m^2 \cdot kg \cdot s^{-3} \cdot A^{-1}$
Watt	W	electric power	$J \cdot s^{-1} = m^2 \cdot kg \cdot s^{-3}$
Weber	Wb	magnetic flux	$V \cdot s = m^2 \cdot kg \cdot s^{-2} \cdot A^{-1}$

[1] The solid angle of a sphere is defined as the angle subtended at the center of a sphere by an area (A) on its surface times the square of its radius (r^2). A steradian (sr) is the solid angle for which r = 1 m and A = 1 m^2, that is, 1 sr = 1 m^2/m^{-2}.

Table 2 Prefixes for fractions and multiples of units of measure

Prefix	Symbol	Factor	Prefix	Symbol	Factor
deca-	da	10^1	deci-	d	10^{-1}
hecto-	h	10^2	centi-	c	10^{-2}
kilo-	k	10^3	milli-	m	10^{-3}
mega-	M	10^6	micro-	µ	10^{-6}
giga-	G	10^9	nano-	n	10^{-9}
tera-	T	10^{12}	pico-	p	10^{-12}
peta-	P	10^{15}	femto-	f	10^{-15}
exa-	E	10^{18}	atto-	a	10^{-18}

Conversion of American and British volume units into SI units:

1 fluid ounce (USA) = 29.57 mL
1 fluid ounce (UK) = 28.47 mL
1 liquid gallon (USA) = 3.785 L
1 liquid gallon (UK) = 4.546 L
1 pint (USA) = 473.12 mL
1 pint (UK) = 569.4 mL

Velocity, Frequency, Acceleration

Velocity is the *distance traveled per unit time* ($m \cdot s^{-1}$). This is an expression of **linear velocity**, whereas **"volume velocity"** is used to express the *volume flow per unit time*. The latter is expressed as $L \cdot s^{-1}$ or $m^3 \cdot s^{-1}$.

Frequency is used to describe how often a periodic event (pulse, breathing, etc.) occurs per unit time. The SI unit of frequency is s^{-1} or *hertz* (Hz). min^{-1} is also commonly used:

$min^{-1} = 1/60$ Hz ≈ 0.0167 Hz.

Acceleration, or *velocity change per unit time*, is expressed in $m \cdot s^{-1} \cdot s^{-1} = m \cdot s^{-2}$. Since *deceleration* is equivalent to negative acceleration, acceleration and deceleration can both be expressed in $m \cdot s^{-2}$.

Force and Pressure

Force equals *mass times acceleration*. **Weight** is a special case of force as weight equals *mass times acceleration of gravity*. Since the unit of mass is kg and that of acceleration $m \cdot s^{-2}$, force is expressed in $m \cdot kg \cdot s^{-2}$ = *newton* (N). The older units of force are converted into N as follows:

1 dyn = 10^{-5} N = 10 μN
1 pond = $9.8 \cdot 10^{-3}$ N = 9.8 mN.

Pressure equals *force per unit area*, so the SI unit of pressure is $N \cdot m^{-2}$ = *pascal* (Pa). However, the pressure of bodily fluids is usually measured in *mm Hg*. This unit and other units are converted into SI units as follows:

1 mm $H_2O \approx 9.8$ Pa
1 cm $H_2O \approx 98$ Pa
1 mm Hg = 133.3 Pa = 0.1333 kPa
1 torr = 133.3 Pa = 0.1333 kPa
1 technical atmosphere (at) ≈ 98.067 kPa
1 physical atmosphere (atm) = 101.324 kPa
1 dyne $\cdot$ cm^{-2} = 0.1 Pa
1 bar = 100 kPa.

Work, Energy, Heat, Power

Work equals *force times distance*, $N \cdot m = J$ (*joule*), or *pressure times volume*, $(N \cdot m^{-2}) \cdot m^3 = J$. **Energy** and **heat** are also expressed in J.

Other units of work, heat, and energy are converted into J as follows:

1 erg = 10^{-7} J = 0.1 μJ
1 cal ≈ 4.185 J
1 kcal ≈ 4185 J = 4.185 kJ
1 Ws = 1 J
1 kWh = $3.6 \cdot 10^6$ J = 3.6 MJ.

Power equals *work per unit time* and is expressed in *watts* (W), where $W = J \cdot s^{-1}$. Heat flow is also expressed in W. Other units of power are converted into W as follows:

1 erg $\cdot$ s^{-1} = 10^{-7} W = 0.1 μW
1 cal $\cdot$ h^{-1} = $1.163 \cdot 10^{-3}$ W = 1.163 mW
1 metric horse power (hp) = 735.5 W = 0.7355 kW.

Mass, Amount of Substance

The base unit of **mass** is the kilogram (kg), which is unusual insofar as the base unit bears the prefix "kilo". Moreover, 1000 kg is defined as a *metric ton** instead of as a megagram. **Weight** is the product of mass and gravity (see above), but weight scales are usually calibrated in units of mass (g, kg).

British and American units of mass are converted into SI units as follows.

Avoirdupois weight:
1 ounce (oz.) = 28.35 g
1 pound (lb.) = 453.6 g
Apothecary's and troy weight:
1 ounce = 31.1 g
1 pound = 373.2 g.

The mass of a molecule or an atom (**molecular** or **atomic mass**) is often expressed in *daltons* (Da)*. 1 Da = 1/12 the mass of a ^{12}C atom, equivalent to 1 g/Avogadro's constant = $1 \text{ g}/(6.022 \cdot 10^{23})$:

1 Da = $1.66 \cdot 10^{-24}$ g
1000 Da = 1 kDa.

The **relative molecular mass (M_r)**, or *molecular "weight"*, is the molecular mass of a substance divided by 1/12 the mass of a ^{12}C atom. Since M_r is a ratio, it is a dimensionless unit.

The **amount of substance**, or *mole* (mol), is related to mass. One mole of substance contains as many elementary particles (atoms, molecules, ions) as 12 g of the nuclide of a ^{12}C atom = $6.022 \cdot 10^{23}$ particles. The *conversion factor between moles and mass* is therefore: 1 mol equals the mass of substance (in grams) corresponding to the relative molecular, ionic, or atomic mass of the substance. In other words, it expresses how much higher the mass of the atom, molecule, or ion is than 1/12 that of a ^{12}C atom.

Examples:

- Relative molecular mass of H_2O: 18
  → 1 mol H_2O = 18 g H_2O.
- Relative atomic mass of Na: 23
  → 1 mol Na^+ = 23 g Na^+.
- Relative molecular mass of $CaCl_2$:
  = 40 + (2 · 35.5) = 111
  → 1 mol $CaCl_2$ = 111 g $CaCl_2$.

($CaCl_2$ contains 2 mol Cl^- and 1 mol Ca^{2+}.)

The **equivalent mass** is calculated as moles divided by the valency of the ion in question and expressed in *equivalents* (Eq)*. The mole and equivalent values of *monovalent ions* are identical:

1 Eq Na^+ = 1/1 mol Na^+.

For bivalent ions, equivalent = $^1/_2$ mole:

1 Eq Ca^{2+} = $^1/_2$ mole Ca^{2+} or 1 mole Ca^{2+} = 2 Eq Ca^{2+}.

The **osmole (Osm)** is also derived from the mole (see below).

Electrical Units

Electrical **current** is the flow of charged particles, e.g., of electrons through a wire or of ions through a cell membrane. The number of particles moving per unit time is measured in *amperes* (A). Electrical current cannot occur unless there is an **electrical potential difference**, in short also called potential, voltage, or tension. Batteries and generators are used to create such potentials. Most electrical potentials in the body are generated by ionic flow (→ p. 32). The *volt* (V) is the SI unit of electrical potential (→ **Table 1**).

How much electrical current flows at a given potential depends on the amount of **electrical resistance**, as is described in *Ohm's law* (voltage = current · resistance). The unit of electrical resistance is *ohm* (Ω) (→ **Table 1**). *Conductivity* is the reciprocal of resistance ($1/\Omega$) and is expressed in *siemens* (S), where S = Ω^{-1}. In membrane physiology, resistance is related to the membrane surface area ($\Omega \cdot m^2$). The reciprocal of this defines the **membrane conductance** to a given ion: $\Omega^{-1} \cdot m^{-2} = S \cdot m^{-2}$ (→ p. 32).

Electrical **work** or **energy** is expressed in *joules* (J) or *watt seconds* (Ws), whereas electrical **power** is expressed in *watts* (W).

The electrical **capacitance** of a capacitor, e.g., a cell membrane, is the ratio of *charge* (C) to *potential* (V); it is expressed in *farads* (F) (→ **Table 1**, p. 379).

Direct current (DC) always flows in one direction, whereas the direction of flow of **alternating current** (AC) constantly changes. The **frequency** of one cycle of change per unit time is expressed in *hertz* (Hz). Mains current is generally 60 Hz in the USA and 50 Hz in Europe.

Temperature

Kelvin (K) is the SI unit of temperature. The lowest possible temperature is 0 K, or *absolute zero*. The **Celsius** or **centigrade** scale is derived from the Kelvin scale. The temperature in degrees Celsius (°C) can easily be converted into K:

°C = K - 273.15.

In the USA, temperatures are normally given in degrees Fahrenheit (°F). Conversions between Fahrenheit and Celsius are made as follows:

°F = (9/5 · °C) + 32

°C = (°F - 32) · 5/9.

Some important Kelvin, Celsius, and Fahrenheit temperature equivalents:

	K	°C	°F
Freezing point of water	+ 273	0°	+ 32°
Room temperature	293–298	20°–25°	68°– 77°
Body core temperature	310	37°	98.6°
Fever	311–315	38°–42°	100°–108°
Boiling point of water (at sea level)	373	100°	212°

Concentrations, Fractions, Activity

The word **concentration** is used to describe many different relationships in physiology and medicine. Concentration of a substance X is often abbreviated as [X]. Some concentrations are listed below:

—*Mass concentration*, or the mass of a substance per unit volume (e.g., g/L = kg/m^3)

—*Molar concentration*, or the amount of a substance per unit volume (e.g., mol/L)

—*Molal concentration*, or the amount of substance per unit mass of solvent (e.g., mol/kg H_2O).

The SI unit of **mass concentration** is g/L (kg/m^3, mg/L, etc.). The conversion factors for older units are listed below:

1 g/100 mL = 10 g/L
1 g% = 10 g/L
1 % (w/v) = 10 g/L
1 g‰ = 1 g/L
1 mg% = 10 mg/L
1 mg/100 mL = 10 mg/L
1 μg% = 10 μg/L
1 γ% = 10 μg/L.

Molarity is the **molar concentration**, which is expressed in mol/L (or mol/m^3, mmol/L, etc.). Conversion factors are listed below:

1 M (molar) = 1 mol/L
1 N (normal) = (1/valency) · mol/L
1 mM (mmolar) = 1 mmol/L
1 Eq/L = (1/valency) · mol/L.

In highly diluted solutions, the only difference between the molar and molal concentrations is that the equation "1 L H_2O = 1 kg H_2O" holds at only one particular temperature (4°C). Biological fluids are not highly diluted solutions. The volume of solute particles often makes up a significant fraction of the overall volume of the solution. One liter of plasma, for example, contains 70 mL of proteins and salts and only 0.93 L of water. In this case, there is a 7% difference between molarity and molality. Differences higher than 30% can occur in intracellular fluid. Although molarity is more commonly measured (volumetric measurement), molality plays a more important role in biophysical and biological processes and chemical reactions.

The **activity** (a) of a solution is a thermodynamic measure of its physicochemical efficacy. In physiology, the activity of ions is measured by ion-sensitive electrodes (e.g., for H^+, Na^+, K^+, Cl^-, or Ca^{2+}). The activity and molality of a solution are identical when the total **ionic strength** (μ) of the solution is very small, e.g., when the solution is an ideal solution. The ionic strength is dependent on the charge and concentration of all ions in the solution:

$$\mu \equiv 0.5\,(z_1^2 \cdot c_1 + z_2^2 \cdot c_2 + \ldots + z_i^2 \cdot c_i) \qquad [13.1]$$

where z_i is the valency and c_i the molal concentration of a given ion "i", and 1, 2, etc. represent the different types of ions in the solution. Owing to the high ionic strength of biological fluids, the solute particles influence each other. Consequently, the activity (a) of a solution is always significantly lower than its molar concentration (c). Activity is calculated as $a = f \cdot c$, where f is the **activity coefficient**.

Example: At an ionic strength of 0.1 (as it is the case for a solution containing 100 mmol NaCl/kg H_2O), f = 0.76 for Na^+. The activity important in biophysical processes is therefore roughly 25% lower than the molality of the solution.

In solutions that contain weak electrolytes which do not completely dissociate, the molality and activity of free ions also depend on the **degree of electrolytic dissociation.**

Fractions ("fractional concentrations") are relative units:

— *Mass ratio*, i.e., mass fraction relative to total mass
— *Molar ratio*
— *Volume ratio*, i.e. volume fraction relative to total volume. The volume fraction (F) is commonly used in respiratory physiology.

Fractions are expressed in units of g/g, mol/mol, and L/L respectively, i.e. in "units" of 1, 10^{-3}, 10^{-6}, etc. The unabbreviated unit (e.g., g/g) should be used whenever possible because it identifies the type of fraction in question. The fractions %, ‰, ppm (parts per million), and ppb (parts per billion) are used for all types of fractions.

Conversion:
1% = 0.01
1‰ = $1 \cdot 10^{-3}$
1 vol% = 0.01 L/L
1 ppm = $1 \cdot 10^{-6}$
1 ppb = $1 \cdot 10^{-9}$

Osmolality, Osmotic / Oncotic Pressure

Osmolarity (Osm/L), a unit derived from molarity, is the *concentration of all osmotically active particles* in a solution, regardless of which compounds or mixtures are involved.

However, measurements with osmometers as well as the biophysical application of osmotic concentration refer to the number of osmoles per unit volume of *solvent* as opposed to the total volume of the solution. This and the fact that volume is temperature-dependent are the reasons why **osmolality** (Osm/kg H_2O) is generally more suitable.

Ideal osmolality is derived from the molality of the substances in question. If, for example, 1 mmol (180 mg) of glucose is dissolved in 1 kg of water (1 L at 4°C), the molality equals 1 mmol/kg H_2O and the ideal osmolality equals 1 mOsm/kg H_2O. This relationship changes when electrolytes that dissociate are used, e.g., $NaCl \rightleftharpoons Na^+ + Cl^-$. Both of these ions are osmotically active. When a substance that dissociates is dissolved in 1 kg of water, the ideal osmolality equals the molality times the number of dissociation products, e.g., 1 mmol NaCl/kg H_2O = 2 mOsm/kg H_2O.

Electrolytes weaker than NaCl do not dissociate completely. Therefore, their *degree of electrolytic dissociation* must be considered.

These rules apply only to ideal solutions, i.e., those that are extremely dilute. As mentioned above, bodily fluids are **nonideal (or real) solutions** because their real osmolality is lower than the ideal osmolality. The real osmolality is calculated by multiplying the ideal osmolality by the *osmotic coefficient* (g). The osmotic coefficient is concentration-dependent and amounts to, for example, approximately 0.926 for NaCl with an (ideal) osmolality of 300 mOsm/kg H_2O. The real osmolality of this NaCl solution thus amounts to 0.926 · 300 = 278 mOsm/kg H_2O.

Solutions with a real osmolality equal to that of plasma (≈ 290 mOsm/kg H2 O) are said to be isosmolal. Those whose osmolality is higher or lower than that of plasma are hyperosmolal or hyposmolal.

Osmolality and Tonicity

Each osmotically active particle in solution (cf. real osmolality) exerts an **osmotic pressure** (π) as described by *van't Hoff's equation*:

$$\pi = R \cdot T \cdot c_{osm} \qquad [13.2]$$

where R is the universal gas constant (8.314 J · K^{-1} · Osm^{-1}), T is the absolute temperature in K, and c_{osm} is the real osmolality in Osm · (m^3 $H_2O)^{-1}$ = mOsm · (L $H_2O)^{-1}$. If two solutions of different osmolality (Δc_{osm}) are separated by a water-permeable **selective membrane**, Δc_{osm} will exert an **osmotic pressure difference** ($\Delta\pi$) across the membrane in steady state if the membrane is less permeable to the solutes than to water. In this case, the *selectivity* of the membrane, or its relative impermeability to the solutes, is described by the **reflection coefficient** (σ), which is assigned a value between 1 (impermeable) and 0 (as permeable as water). The reflection coefficient of a *semipermeable membrane* is $\sigma = 1$. By combining **van't Hoff's** and **Staverman's equations**, the osmotic pressure difference ($\Delta\pi$) can be calculated as follows:

$$\Delta\pi = \sigma \cdot R \cdot T \cdot \Delta c_{osm}. \qquad [13.3]$$

Equation 13.3 shows that a solution with the same osmolality as plasma will exert the same osmotic pressure on a membrane in steady state (i.e., that the solution and plasma will be *isotonic*) only if $\sigma = 1$. In other words, the membrane must be strictly semipermeable.

Isotonicity, or equality of osmotic pressure, exists between plasma and the cytosol of red blood cells (and other cells of the body) in steady state. When the red cells are mixed in a urea solution with an osmolality of 290 mOsm/kg H_2O, isotonicity does not prevail after urea ($\sigma < 1$) starts to diffuse into the red cells. The interior of the red blood cells therefore becomes hypertonic, and water is drawn inside the cell due to osmosis (→ p. 24). As a result, the erythrocytes continuously swell until they burst.

An **osmotic gradient** resulting in the subsequent flow of water therefore occurs in all parts of the body in which dissolved particles pass through water-permeable cell membranes or cell layers. This occurs, for example, when Na^+ and Cl^- pass through the epithelium of the small intestine or proximal renal tubule. The extent of this water flow or *volume flow* Jv ($m^3 \cdot s^{-1}$) is dependent on the *hydraulic conductivity* k ($m \cdot s^{-1} \cdot Pa^{-1}$) of the membrane (i.e., its permeability to water), the *area* A of passage (m^2), and the pressure difference, which, in this case, is equivalent to the osmotic pressure difference $\Delta\pi$ (Pa):

$$\mathbf{Jv = k \cdot A \cdot \Delta\pi}\ [m^3 \cdot s^{-1}]. \qquad [13.4]$$

Since it is normally not possible to separately determine k and A of a biological membrane or cell layer, the product of the two ($k \cdot A$) is often calculated as the *ultrafiltration coefficient* K_f ($m^3\,s^{-1}\,Pa^{-1}$) (cf. p. 152).

The transport of osmotically active particles causes water flow. Inversely, flowing water drags dissolved particles along with it. This type of *solvent drag* (→ p. 24) is a form of convective transport.

Solvent drag does not occur if the cell wall is impermeable to the substance in question ($\sigma = 1$). Instead, the water will be retained on the side where the substance is located. In the case of the aforementioned epithelia, this means that the substances that cannot be reabsorbed from the tubule or intestinal lumen lead to osmotic diuresis (→ p. 174) and diarrhea respectively. The latter is the mechanism of action of saline laxatives (→ p. 264).

Oncotic Pressure / Colloid Osmotic Pressure

As all other particles dissolved in plasma, macromolecular proteins also exert an osmotic pressure referred to as *oncotic pressure* or *colloid osmotic pressure*. Considering its contribution of only 3.5 kPa (25 mm Hg) relative to the total osmotic pressure of the small molecular components of plasma, the oncotic pressure on a strictly semipermeable membrane could be defined as negligible. However, within the body, oncotic pressure is so important because the **endothelium** that lines the blood vessels allows small molecules to pass relatively easily ($\sigma \approx 0$). According to equation 13.3, their osmotic pressure difference $\Delta\pi$ at the endothelium is virtually zero. Consequently, only the oncotic pressure difference of proteins is effective, as the endothelium is either partly or completely impermeable to them, depending on the capillary segment in question. Because the protein reflection coefficient $\sigma \gg 0$ and the protein content of the plasma (ca. 75 g/L) are higher than that of the interstitium, these two factors *counteract filtration*, i.e., the blood pressure-driven outflow of plasma water from the endothelial lumen, making the endothelium an effective volume barrier between the plasma space and the interstitium.

If the blood pressure drives water out of the blood into the interstitium (filtration), the plasma protein concentration and thus the oncotic pressure difference π will rise (→ pp. 152, 210). This rise is much higher than equation 13.3 leads one to expect (→ **A**). The difference is attributable to specific biophysical properties of plasma proteins. If there is a pressure-dependent efflux or influx of water out of or into the bloodstream, these relatively high changes in oncotic pressure difference automatically exert a counterpressure that limits the flow of water.

pH, pK, Buffers

The **pH** indicates the hydrogen ion [H^+] concentration of a solution. According to *Sörensen*, the pH is the negative common logarithm of the molal H^+ concentration in mol/kg H_2O.

Examples:

1 mol/kg H_2O = 10^0 mol/kg H_2O = pH 0,
0.1 mol/kg H_2O = 10^{-1} mol/kg H_2O = pH 1,
and so on up to 10^{-14} mol/kg H_2O = pH 14.

Since glass electrodes are normally used to measure the pH, the **H^+ activity** of the solution is actually being determined. Thus, the following rule applies:

$pH = -\log (f_H \cdot [H^+])$,

where f_H is the activity coefficient of H^+. Considering its ionic concentration (see above), the f_H of plasma is ≈ 0.8.

The logarithmic nature of pH must be considered when observing pH changes. For example, a rise in pH from 7.4 (40 nmol/kg H_2O) to pH 7.7 decreases the H^+ activity by 20 nmol/kg H_2O, whereas an equivalent decrease (e.g., from pH 7.4 to pH 7.1) increases the H^+ activity by 40 nmol/kg H_2O.

The **pK** is fundamentally similar to the pH. It is the negative common logarithm of the *dissociation constant* of an acid (K_a) or of a base (K_b):


$pK_a = -\log K_a$
$pK_b = -\log K_b$.

For an acid and its corresponding base, $pK_a + pK_b = 14$, so that the value of pK_a can be derived from that of pK_b and vice versa.

The *law of mass actions* applies when a weak acid (AH) dissociates:

$$AH \rightleftharpoons A^- + H^+ \qquad [13.5]$$

It states that the product of the molal concentration (indicated by square brackets) of the dissociation products divided by the concentration of the nondissociated substance remains constant:



A. Physiological signification of deviations on oncotic pressure of plasma from van't Hoff's equation. A loss of water from plasma leads to a disproportionate rise in oncotic pressure, which counteracts the water loss. Conversely, the dilution of plasma due to the influx of water leads to a disproportionate drop in oncotic pressure, though less pronounced. Both of these are important mechanisms for maintaining a constant blood volume and preventing edema. (Adapted from Landis EM u. Pappenheimer JR. *Handbook of Physiology.* Section 2: Circulation, Vol. II. American Physiological Society: Washington D.C. 1963, S. 975.)

$$K_a = \frac{[A^-] \cdot [H^+]}{[AH]} \qquad [13.6]$$

Converted into logarithmic form (and inserting H^+ activity for $[H^+]$), the equation is transformed into:

$$\log K_a = \log \frac{[A^-]}{[AH]} + \log ([H^+] \cdot f_H) \qquad [13.7]$$

or

$$-\log ([H^+] \cdot f_H) = -\log K_a + \log \frac{[A^-]}{[AH]} \qquad [13.8]$$

Based on the above definitions for pH and pK_a, it can also be converted into

$$\mathbf{pH = pK_a + \log \frac{[A^-]}{[AH]}} \qquad [13.9]$$

Because the concentration and not the activity of A^- and AH is used in equation 13.9, pK_a is concentration-dependent in nonideal solutions.

Equation 13.9 is the general form of the **Henderson–Hasselbalch equation** (→ p. 138ff.), which describes the relationship between the pH of a solution and the concentration ratio of a dissociated to an undissociated form of a solute. If $[A^-] = [AH]$, then the concentration ratio is 1/1 = 1, which corresponds to $pH = pK_a$ since the log of 1 = 0.

A weak acid (AH) and its dissociated salt (A^-) form a **buffer system** for H^+ and OH^- ions:

Addition of H^+ yields $A^- + H^+ \rightarrow AH$

Addition of OH^- yields $AH + OH^- \rightarrow A^- + H_2O$.


The *buffering power* of a buffer system is greatest when $[AH] = [A^-]$, i.e., when the pH of the solution equals the pK_a of the buffer.

Example: Both $[A^-]$ and [AH] = 10 mmol/L and pK_a = 7.0. After addition of 2 mmol/L of H^+ ions, the $[A^-]$/[AH] ratio changes from 10/10 to 8/12 since 2 mmol/L of A^- are consequently converted into 2 mmol/L of AH. Since the log of 8/12 ≈ -0.18, the pH decreases

by 0.18 units to pH 6.82. If the initial $[A^-]$ /[AH] ratio had been 3/17, the pH would have dropped from an initial pH 6.25 (7 plus the log of 3/17 = 6.25) to pH 5.7 (7 + log of 1/19 = 5.7), i.e., by 0.55 pH units after addition of the same quantity of H^+ ions.

The titration of a buffer solution with H^+ (or OH^-) can be plotted to generate a **buffering curve** (→ **B**). The steep part of the curve represents the range of the best buffering power. The pK_a value lies at the *turning point* in the middle of the steep portion of the curve. Substances that gain (or lose) more than one H^+ per molecule have more than one pK value and can therefore exert an optimal buffering action in several regions. Phosphoric acid (H_3PO_4) donates three H^+ ions, thereby successively forming $H_2PO_4^-$, HPO_4^{2-}, and PO_4^{3-}. The buffer pair $HPO_4^{2-}/H_2PO_4^-$ with a pK_a of 6.8 is important in human physiology (→ p. 177ff.).

The absolute slope, $d[A^-]/d(pH)$, of a buffering curve (plot of pH *vs.* $[A^-]$) is a measure of **buffering capacity** ($mol \cdot L^{-1} \cdot [\Delta pH]^{-1}$; → p. 138).



B. Buffering Curve. Graphic representation of the relationship between pH and the concentration ratio of buffer acid/buffer base [AH]/$[A^-]$ as a function of pH. The numerical values are roughly equivalent to those of the buffer pair *acetic acid/acetate* (pK_a = 4.7). The buffering power of a buffer system is greatest when [AH] = $[A^-]$, i.e., when the pH of the solution equals the pK_a of the buffer (broken lines).

Powers and Logarithms

Powers of ten are used to more easily and conveniently write numbers that are much larger or smaller than 1.

Examples:

$100 = 10 \cdot 10 = 10^2$

$1000 = 10 \cdot 10 \cdot 10 = 10^3$

$10\,000 = 10 \cdot 10 \cdot 10 \cdot 10 = 10^4$, etc.

In this case, the exponent denotes the amount of times ten is multiplied by itself. If the number is not an exact power of ten (e.g., 34 500), divide it by the next lowest decimal power (10 000) and use the quotient (3.45) as a multiplier to express the result as $3.45 \cdot 10^4$.

The number 10 can also be expressed exponentially (10^1). Numbers much smaller than 1 are annotated using negative exponents.

Examples:

$1 = 10 \div 10 = 10^0$

$0.1 = 10 \div 10 \div 10 = 10^{-1}$

$0.01 = 10 \div 10 \div 10 = 10^{-2}$, etc.

Similar to the large numbers above, numbers that are not exact powers of ten are expressed using multipliers, e.g.,

$0.04 = 4 \cdot 0.01 = 4 \cdot 10^{-2}$.

Note: When writing numbers smaller than 1, the (negative) exponent corresponds to the position of the 1 after the decimal point; therefore, $0.001 = 10^{-3}$. When writing numbers greater than 10, the exponent corresponds to the number of decimal positions to the left of the decimal point minus 1; therefore, $1124.5 = 1.245 \cdot 10^3$.

Exponents can also be used to represent **units of measure**, e.g., m^3. As in the case of 10^3, the base element (meters) is multiplied by itself three times ($m \cdot m \cdot m$; → p. 378). Negative exponents are also used to express units of measure. As with $1/10 = 10^{-1}$, 1/s can be written as s^{-1}, mol/L as $mol \cdot L^{-1}$, etc.

There are specific **rules for performing calculations with powers of ten**. Addition and subtraction are possible only if the exponents are identical, e.g.,

$(2.5 \cdot 10^2) + (1.5 \cdot 10^2) = 4 \cdot 10^2$.

Unequal exponents, e.g., $(2 \cdot 10^3) + (3 \cdot 10^2)$, must first be equalized:

$(2 \cdot 10^3) + (0.3 \cdot 10^3) = 2.3 \cdot 10^3$.

The exponents of the multiplicands are added together when multiplying powers of 10, and the denominator is subtracted from the numerator when dividing powers of ten.

Examples:

$10^2 \cdot 10^3 = 10^{2+3} = 10^5$

$10^4 \div 10^2 = 10^{4-2} = 10^2$

$10^2 \div 10^4 = 10^{2-4} = 10^{-2}$

The usual mathematical rules apply to the multipliers of powers of ten, e.g.,

$(3 \cdot 10^2) \cdot (2 \cdot 10^3) = (2 \cdot 3) \cdot (10^{2+3}) = 6 \cdot 10^5$.

Logarithms. There are two kinds of logarithms: common and natural. Logarithmic calculations are performed using exponents alone. The **common** (**decimal**) **logarithm** (log or lg) is the power or exponent to which 10 must be raised to equal the number in question. The common logarithm of 100 (log 100) is 2, for example, because $10^2 = 100$. Decimal logarithms are commonly used in physiology, e.g., to define pH values (see above) and to plot the pressure of sound on a decibel scale (→ p. 369).

Natural logarithms (ln) have a natural base of 2.71828…, also called *base e*. The common logarithm (log x) equals the natural logarithm of x (ln x) divided by the natural logarithm of 10 (ln 10), where ln 10 = 2.302585. The following rules apply when converting between natural and common logarithms:

$\log x = (\ln x)/2.3$

$\ln x = 2.3 \cdot \log x$.

When performing mathematical operations with logarithms, the type of operation is reduced by one rank—multiplication becomes addition, potentiation becomes multiplication, and so on.

Examples:

$\log (a \cdot b) = \log a + \log b$

$\log (a/b) = \log a - \log b$

$\log a^n = n \cdot \log a$

$\log \sqrt[n]{a} = (\log a)/n$

Special cases:

$\log 10 = \ln e = 1$

$\log 1 = \ln 1 = 0$


$\log 0 = \ln 0 = \pm \infty$

Graphic Representation of Data


Graphic plots of data are used to provide a clear and concise representation of measurements, e.g., body temperature over the time of day (→ **C**). The axes on which the measurements (e.g., temperature and time) are plotted are called **coordinates**. The vertical axis is referred to as the *ordinate* (temperature) and the horizontal axis is the *abscissa* (time). It is customary to plot the first variable *x* (time) on the abscissa and the other dependent variable *y* (temperature) on the ordinate. The abscissa is therefore called the *x-axis* and the ordinate the *y-axis*. This method of graphically plotting data can be used to illustrate the connection between any two related dimensions imaginable, e.g., to describe the relationship between height and age, lung capacity and intrapulmonary pressure, etc. (→ p. 117).

Plotting of data makes it easier to determine whether two variables correlate with each other. For example, the plot of height (ordinate) over age (abscissa) shows that the height increases during the growth years and reaches a plateau at the age of about 17 years. This means that height is related to age in the first phase of life, but is largely independent of age in the second phase. A correlation does not necessarily indicate a causal relationship. A decrease in the birth rate in Alsace-Lorraine, for example, correlated with a decrease in the number or nesting storks for a while.

When plotting variables of wide-ranging dimensions (e.g., 1 to 100 000) on a coordinate



C. Illustration of how to plot data on a coordinate system. The plot in this example shows the relationship between body temperature (rectal, at rest) and time of day.



D. Types of functions. D1: Linear function (violet), exponential function (red), logarithmic function (blue), and power function (green) showing linear plotting of data on both axes. The three curves can be made into a straight line (linearized) by logarithmically plotting the data on the y-axis (**D2:** exponential function) or on the x-axis (**D4:** logarithmic function) or both (**D3:** power function).

system, it can be impossible to plot small values individually without having the axes become extremely long. This problem can be solved by plotting the data as powers of 10 or logarithms. For example, 1, 10, 100, and 1000 are written as 10^0, 10^1, 10^2, and 10^3 or as logarithms 0, 1, 2, and 3. This makes it possible to obtain a relatively accurate graphic representation of very small numbers, and all the numbers fit on an axis of reasonable length (cf. sound curves on p. 369 B).

Correlations can be either linear or nonlinear. *Linear correlations* (→ **D1**, violet line) obey the linear relationship

$y = ax + b$,

where a is the slope of the line and b is the point, or *intercept* (at x = 0), where it intersects the y-axis.

Many correlations are nonlinear. For simpler functions, graphic linearization can be achieved via a nonlinear (logarithmic) plot of the x and/or y values. This allows for the extrapolation of values beyond the range of measurement (see below) or for the generation of calibration curves from only two points. In addition, this method also permits the calculation of the "mean" correlation of scattered x-y pairs using *regression lines*.

An **exponential function** (→ **D1**, red curve), such as

$y = a \cdot e^{b \cdot x}$,

can be linearized by plotting ln y on the y-axis (→ **D2**):

$\ln y = \ln a + b \cdot x$,

where b is the slope and ln a is the intercept.

A **logarithmic function** (→ **D1**, blue curve), such as

$y = a + b \cdot \ln x$,

can be linearized by plotting ln x on the x-axis (→ **D4**), where b is the slope and a is the intercept.

A **power function** (→ **D1**, green curve), such as

$y = a \cdot x^b$,

can be graphically linearized by plotting ln y and ln x on the coordinate axes (→ **D3**) because

$\ln y = \ln a + b \cdot \ln x$,

where b is the slope and ln a is the intercept.

Note: The condition x or y = 0 does not exist on logarithmic coordinates because $\ln 0 = \infty$. Nevertheless, ln a is still called the intercept in the equation when the logarithmic abscissa (→ **D3,4**) is intercepted by the ordinate at ln x = 0, i.e., x = 1.

Instead of plotting ln x and/or ln y on the x- and/or y-axis, they can be plotted on **logarithmic paper** on which the ordinate or abscissa (semi-log paper) or both coordinates (log-log paper) are plotted in logarithmic units. In such cases, a is no longer treated as the intersect because the position of a depends on site of intersection of the x-axis by the y-axis. All values > 0 are possible.

Other nonlinear functions can also be graphically linearized using an appropriate plotting method. Take, for example, the **Michaelis–Menten equation** (→ **E1**), which applies to many enzyme reactions and carrier-mediated transport processes:


$$J = J_{max} \cdot \frac{C}{K_M + C} \qquad [13.10]$$

where J is the actual rate of transport (e.g., in $mol \cdot m^{-2} \cdot s^{-1}$), J_{max} is the maximal transport rate, C ($mol \cdot m^{-3}$) is the actual concentration of the substance to be transported, and K_M is the concentration (half-saturation concentration) at $^1/_2 J_{max}$.

One of the three commonly used linear rearrangements of the Michaelis–Menten equation, the *Lineweaver–Burk plot*, states:

$$1/J = (K_M/J_{max}) \cdot (1/C) + 1/J_{max}, \qquad [13.11]$$

Consequently, a plot of 1/J on the y-axis and 1/C on the x-axis results in a straight line (→ **E2**). While a plot of J over C (→ **E1**) does not



E. Two methods of representing the Michaelis–Menten equation: The data can be plotted as a curve of J over C (**E1**), or as 1/J over 1/C in linearized form (**E2**). In the latter case, Jmax and K_M are determined by extrapolating the data outside the range of measurement.

permit accurate extrapolation of J_{max} (because an infinitely high concentration of C would be required), the linear rearrangement (→ **E2**) makes it possible to generate a regression line that can be *extrapolated* to C = ∞ from the measured data. Since 1/C is equal to 1/∞ (= 0), 1/Jmax lies on the y-axis at x = 0 (→ **E2**). The reciprocal of this value is J_{max}. Insertion of 1/J = 0 into equation 13.11 yields

$$0 = (K_M/J_{max}) \cdot (1/C) + 1/J_{max} \qquad [13.12]$$

or $1/K_M = -1/C$, so that K_M can be derived from the negative reciprocal of the x-axis intersect, which corresponds to 1/J = 0 (→ **E2**).

The Greek Alphabet

α	A	alpha
β	B	beta
γ	Γ	gamma
δ	Δ	delta
ε	E	epsilon
ζ	Z	zeta
η	H	eta
ϑ, θ	Θ	theta
ι	I	iota
ϰ	K	kappa
λ	Λ	lamda
μ	M	mu
ν	N	nu
ξ	Ξ	xi
ο	O	omicron
π	Π	pi
ρ	P	rho
σ, ς	Σ	sigma
τ	T	tau
υ	Y	upsilon
ϕ	Φ	phi
χ	X	chi
ψ	Ψ	psi
ω	Ω	omega

Reference Values in Physiology

Total body and cells

Chemical composition of 1 kg fat-free body mass of an adult	720 g water, 210 g protein, 22.4 g Ca, 12 g P, 2.7 g K, 1.8 g Na, 1.8 g Cl, 0.47 g Mg
Distribution of water in adult (child) as percentage of body weight (cf. p. 168)	Intracellular: 40% (40%); interstitium: 15% (25%); plasma: 5% (5%)
Ion concentrations in ICF and ECF	See p. 93 C

Cardiovascular system

Weight of heart	250–350 g
Cardiac output at rest (maximal)	5–6 L/min (25 L/min); cf. p. 188
Resting pulse = sinus rhythm	60–75 min^{-1} or bpm
AV rhythm	40–55 min^{-1}
Ventricular rhythm	25–40 min^{-1}
Arterial blood pressure (Riva–Rocci)	120/80 mm Hg (16/10.7 kPa) systolic/diastolic
Pulmonary artery pressure	20/7 mm Hg (2.7/0.9 kPa) systolic/diastolic
Central venous pressure	3–6 mm Hg (0.4–0.8 kPa)
Portal venous pressure	3–6 mm Hg (0.4–0.8 kPa)
Ventricular volume at end of diastole/systole	120 mL/40 mL
Ejection fraction	0.67
Pressure pulse wave velocity	Aorta: 3–5 m/s; arteries: 5–10 m/s; veins: 1–2 m/s
Mean velocity of blood flow	Aorta: 0.18 m/s; capillaries: 0.0002–0.001 m/s; venae cavae: 0.06 m/s

Blood flow in organs at rest		
(*See also pp. 189 A, 215 A*)	% of cardiac output	per gram of tissue
Heart	4%	0.8 mL/min
Brain	13%	0.5 mL/min
Kidneys	20%	4 mL/min
GI tract (drained by portal venous system)	16%	0.7 mL/min
Liver (blood supplied by hepatic artery)	8%	0.3 mL/min
Skeletal muscle	21%	0.04 mL/min
Skin and miscellaneous organs	18%	—

Lungs and gas transport	**Men**	**Women**
Total lung capacity (TLC)	7 L	6.2 L
Vital capacity (VC); cf. p. 112	5.6 L	5 L
Tidal volume (V_T) at rest	0.6 L	0.5 L
Inspiratory reserve volume	3.2 L	2.9 L
Expiratory reserve volume	1.8 L	1.6 L
Residual volume	1.4 L	1.2 L
Max. breathing capacity in 30 breaths/min	110 L	100 L
Partial pressure of O_2	Air: 21.17 kPa	(159 mm Hg)
	Alveolar: 13.33 kPa	(100 mm Hg)
	Arterial: 12.66 kPa	(95 mm Hg)
	Venous 5.33 kPa	(40 mm Hg)
Partial pressure of CO_2	Air: 0.03 kPa	(0.23 mm Hg)
	Alveolar: 5.2 kPa	(39 mm Hg)
	Arterial: 5.3 kPa	(40 mm Hg)
	Venous: 6.1 kPa	(46 mm Hg)
Respiratory rate (at rest)	16 breaths/min	
Dead space volume	150 mL	
Oxygen capacity of blood	180–200 mL O_2/L blood = 8–9 mmol O_2/L blood	
Respiratory quotient	0.84 (0.7–1.0)	

Kidney and excretion	
Renal plasma flow (RPF)	480–800 mL/min per 1.73 m^2 body surface area
Glomerular filtration rate (GFR)	80–140 mL/min per 1.73 m^2 body surface area
Filtration fraction (GFR/RPF)	0.19
Urinary output	0.7–1.8 L/day
Osmolality of urine	250–1000 mOsm/kg H_2O
Na^+ excretion	50–250 mmol/day
K^+ excretion	25–115 mmol/day
Glucose excretion	< 300 mg/day = 1.67 mmol/day
Nitrogen excretion	150–250 mg/kg/day
Protein excretion	10–200 mg/day
Urine pH	4.5–8.2
Titratable acidity	10–30 mmol/day
Urea excretion	10–20 g/day = 166–333 mmol/day
Uric acid excretion	300–800 mg/day = 1.78–6.53 mmol/day
Creatinine excretion	0.56–2.1 g/day = 4.95–18.6 mmol/day

Nutrition and metabolism	Men	Women
Energy expenditure during various activities		
• Bed rest	6500 kJ/d (1550 kcal/d)	5400 kJ/d (1300 kcal/d)
• Light office work	10 800 kJ/d (2600 kcal/d)	9600 kJ/d (2300 kcal/d)
• Walking (4.9 km/h)	3.3 kW	2.7 kW
• Sports (dancing, horseback riding, swimming)	4.5–6.8 kW	3.6–5.4 kW
Functional protein minimum	1 g/kg body weight	
Vitamins, optimal daily intake (IU = international units)	A: 10 000–50 000 IU; D: 400–600 IU E: 200–800 IU; K: 65–80 μg; B_1, B_2, B_5, B_6: 25–300 mg of each; B_{12}: 25–300 μg; folate: 0.4–1.2 mg; H: 25–300 μg; C: 500–5000 mg	
Electrolytes and trace elements, optimal daily intake	Ca: 1–1.5 g; Cr: 200–600 μg; Cu: 0.5–2 mg; Fe: 15–30 mg: I: 50–300 μg; K^+: 0.8–1.5 g; Mg: 500–750 mg; Mn: 15–30 mg; Mo: 45–500 μg; Na^+: 2 g; P: 200–400 mg; Se: 50–400 μg; Zn: 22–50 mg	

Nervous Systems, muscles	
Duration of an action potential	Nerve: 1–2 ms; skeletal muscle: 10 ms; myocardium: 200 ms
Nerve conduction rate	See p. 49 C

Blood and other bodily fluids	*(see also Table p. 88)*	
Blood (in adults)	**Men:**	**Women:**
Blood volume (also refer to table on p. 88)	4500 mL	3600 mL
Hematocrit	0.40–0.54	0.37–0.47
Red cell count (RBC)	$4.5–5.9 \cdot 10^{12}$/L	$4.2–5.4 \cdot 10^{12}$/L
Hemoglobin (Hb) in whole blood	140–180 g/L (2.2–2.8 mmol/L)	120–160 g/L (1.9–2.5 mmol/L)
Mean corpuscular volume (MCV)	80–100 fL	
Mean corpuscular Hb concentration (MCHC)	320–360 g/L	
Mean Hb concentration in single RBC (MCH)	27–32 pg	
Mean RBC diameter	7.2–7.8 μm	
Reticulocytes	0.4–2% ($20–75 \cdot 10^9$/L)	
Leukocytes (also refer to table on p. 88)	$3–11 \cdot 10^9$/L	
Platelets	$170–360 \cdot 10^9$/L	$180–400 \cdot 10^9$/L
Erythrocyte sedimentation rate (ESR)	< 10 mm in first hour	< 20 mm in first hour
Proteins		
Total	66–85 g/L serum	
Albumin	35–50 g/L serum	55–64 % of total
α_1-globulins	1.3–4 g/L serum	2.5–4 % of total
α_2-globulins	4–9 g/L serum	7–10% of total
β-globulins	6–11 g/L serum	8–12% of total
γ-globulins	13–17 g/L serum	12–20% of total
Coagulation	(*See p. 102 for coagulation factors*)	
Thromboplastin time (Quick)	0.9–1.15 INR (international normalized ratio)	
Partial thromboplastin time	26–42 s	
Bleeding time	< 6 min	

Parameters of glucose metabolism		
Glucose concentration in venous blood	3.9–5.5 mmol/L	(70–100 mg/dL)
Glucose concentration in capillary blood	4.4–6.1 mmol/L	(80–110 mg/dL)
Glucose concentration in plasma	4.2–6.4 mmol/L	(75–115 mg/dL)
Limit for diabetes mellitus in plasma	> 7.8 mmol/L	(> 140 mg/dL)
HBA_{1c} (glycosylated hemoglobin A)	3.2–5.2%	
Parameters of lipid metabolism		
Triglycerides in serum	< 1.71 mmol/L	(< 150 mg/dL)
Total cholesterol in serum	< 5.2 mmol/L	(< 200 mg/dL)
HDL cholesterol in serum	> 1.04 mmol/L	(> 40 mg/dL)
Substances excreted in urine		
Urea concentration in serum	3.3–8.3 mmol/L	(20–50 mg/dL)
Uric acid concentration in serum	150–390 μmol/L	(2.6–6.5 mg/dL)
Creatinine concentration in serum	36–106 μmol/L	(0.4–1.2 mg/dL)
Bilirubin		
Total bilirubin in serum	3.4–17 μmol/L	(0.2–1 mg/dL)
Direct bilirubin in serum	0.8–5.1 μmol/L	(0.05–0.3 mg/dL)
Electrolytes and blood gases		
Osmolality	280–300 mmol/kg H_2O	
Cations in serum:	Na^+	135–145 mmol/L
	K^+	3.5–5.5 mmol/L
	Ionized Ca^{2+}	1.0–1.3 mmol/L
	Ionized Mg^{2+}	0.5–0.7 mmol/L
Anions in serum:	Cl^-	95–108 mmol/L
	$H_2PO_4^- + HPO_4^{2-}$	0.8–1.5 mmol/L
pH		7.35–7.45
Standard bicarbonate		22–26 mmol/L
TotaL buffer bases		48 mmol/L
Oxygen saturation		96% arterial; 65–75% mixed venous
Partial pressure of O_2 at half saturation ($P_{0.5}$)		3.6 kPa (27 mmHg)

Cerebrospinal fluid	
Pressure in relaxed horizontal position	1.4 kPa (10.5 mmHg)
Specific weight	1.006–1.008 g/L
Osmolality	290 mOsm/kg H_2O
Glucose concentration	45–70 mg/dL (2.5–3.9 mmol/L)
Protein concentration	0.15–0.45 g/L
IgG concentration	< 84 mg/dL
White cell count	< 5 WBC/ μL

1. Fick's law of diffusion for membrane transport (see also p. 20ff.)

$$J_{diff} = F \cdot D \cdot \frac{\Delta C}{\Delta x} \; [mol \cdot s^{-1}]$$

J_{diff} = net diffusion rate [mol · s^{-1}];
A = area [m^2];
D = diffusion coefficient [m^2 · s^{-1}];
ΔC = concentration difference [mol · m^{-3}];
Δx = membrane thickness [m]

Alternative 1:

$$\frac{J_{diff}}{F} = P \cdot \Delta C \; [mol \cdot m^{-2} \cdot s^{-1}]$$

P = permeability coefficient [m · s^{-1}];
J_{diff}, A and ΔC; see above

Alternative 2 (for gas diffusion)

$$\frac{\dot{V}_{diff}}{F} = K \cdot \frac{\Delta P}{\Delta x} \; [m \cdot s^{-1}]$$

$\dot{V}_{diff}$ = net diffusion rate [m^3 · s^{-1}];
K = Krogh's diffusion coefficient [m^2 · s^{-1} · Pa^{-1}]
ΔP = partial pressure difference [Pa]

2. Van't Hoff–Stavermann equation (see also p. 388)

$$\Delta\pi = \sigma \cdot R \cdot T \cdot \Delta c_{osm} \; [Pa]$$

$\Delta\pi$ = osmotic pressure difference [Pa]
σ = reflection coefficient [dimensionsless]
R = universal gas constant [8.3144 J · K^{-1} · mol^{-1}];
T = absolute temperature [K];
Δc_{osm} = concentration difference of osmotically active particles [mol · m^{-3}].

3. Michaelis-Menten equation (see also pp. 28, 389ff.)

$$J_{sat} = J_{max} \cdot \frac{C}{K_M + C} \; [mol \cdot m^{-2} \cdot s^{-1}],$$

J_{sat} = substrate transport (turnover) [mol · m^{-2} · s^{-1}];
J_{max} = maximum substrate transport (turnover) [mol · m^{-2} · s^{-1}];
C = substrate concentration [mol · m^{-3}];
K_M = Michaelis constant = substrate concentration at $^1/_2$ J_{max} [mol · m^{-3}].

4. Nernst equation (see also p. 32)

$$E_x = -61 \cdot z_x^{-1} \cdot \log \frac{[X]_i}{[X]_a} \; [mV]$$

E_x = equilibrium potential of ion X [mV];
z_x = valency of ion X;
$[X]_i$ = intracellular concentration of ion X [mol · m^{-3}]
$[X_o]$ = extracellular concentration of ion X [mol · m^{-3}].

5. Ohm's Law (see also pp. 32, 188)

a. *For ion transport at membrane*

$$I_x = g_x \cdot (E_m - E_x) \; [A \cdot m^{-2}]$$

I_x = ionic current of ion X per unit area of membrane [A · m^{-2}];
g_x = conductance of membrane to ion X [S · m^{-2}];
E_m = membrane potential [V];
E_x = equilibrium potential of ion X [V]

b. *For blood flow:*

$$\dot{Q} = \frac{\Delta P}{R} \; [L \cdot min^{-1}]$$

$\dot{Q}$ = flow rate (total circulation: cardiac output, CO) [L · min^{-1}]
ΔP = mean blood pressure difference (systemic circulation: $\overline{P}_{aorta} - \overline{P}_{vena\ cava}$; lesser circulation: $\overline{P}_{pulmonary\ artery} - \overline{P}_{pulmonary\ vein}$) [mmHg]
R = flow resistance (systemic circulation: total peripheral resistance = TPR) [mmHg · min · L^{-1}].

6. Respiration-related equations (see also pp. 106, 120)

a. *Tidal volume (V_T):*
$V_T = V_D + V_A$ [L]

b. *Respiratory volume per time ($\dot{V}_E$ oder $\dot{V}_T$):*
$\dot{V}_E = f \cdot V_T = (f \cdot V_D) + (f \cdot V_A) = \dot{V}_D + \dot{V}_A$ [L · min^{-1}]

c. *O_2 consumption, CO_2 emission, and RQ (total body:)*
$\dot{V}_{O_2} = \dot{V}_T (F_{IO_2} - F_{EO_2}) = CO \cdot {}_{av}D_{O_2}$ [L · min^{-1}]
$\dot{V}_{CO_2} = \dot{V}_T \cdot F_{ECO_2}$ [L · min^{-1}]

$$RQ = \frac{\dot{V}_{CO_2}}{\dot{V}_{O_2}}$$

V_D = dead space [L];
V_A = alveolar fraction of V_T [L];
f = respiration rate [min^{-1}];
$\dot{V}_D$ = dead space ventilation [$L \cdot min^{-1}$];
$\dot{V}_A$ = alveolar ventilation [$L \cdot min^{-1}$];
$\dot{V}_{O_2}$ = O_2 consumption [$L \cdot min^{-1}$];
$\dot{V}_{CO_2}$ = CO_2 emission [$L \cdot min^{-1}$];
F_{IO_2} = inspiratory O_2 fraction [L/L];
F_{EO_2} = exspiratory O_2 fraction [L/L];
F_{ECO_2} = exspiratory CO_2 fraction [L/L];
RQ = respiratory quotient (dimensionless)

d. *O_2 consumption and CO_2 emission (organ)*:
$\dot{V}_{O_2} = \dot{Q} \cdot {}_{av}D_{O_2}$ [$L \cdot min^{-1}$]
$\dot{V}_{CO_2} = \dot{Q} \cdot {}_{av}D_{CO_2}$ [$L \cdot min^{-1}$]

$\dot{Q}$ = blood flow in organ [$L \cdot min^{-1}$]
${}_{av}D_{O_2}$, ${}_{av}D_{CO_2}$ = arteriovenous O_2 and CO_2 difference in total circulation and organ circulation [L/L blood]

e. *Fick's principle:*

$$CO = \frac{\dot{V}_{O_2}}{{}_{av}D_{O_2}} \text{ [L} \cdot \text{min}^{-1}\text{]}$$

CO = cardiac output [$L \cdot min^{-1}$]>

f. *Gas partial pressure ↔ gas concentration in liquids:*
$[X] = \alpha \cdot P_x$ [mmol/L plasma]
[X] = concentration of gas X [$mmol \cdot L^{-1}$]
α = (Bunsen's) solubility coefficient [$mmol \cdot L^{-1} \cdot kPa^{-1}$]
P_X = partial pressure of gas X [kPa]

g. *Bohr's formula* (see also p. 115)

$$V_D = V_T \frac{(F_{ACO_2} - F_{ECO_2})}{F_{ACO_2}}$$

V_D = dead space [L];
V_T = tidal volume [L];
F_{ACO_2} = alveolar CO_2 fraction
F_{ECO_2} = exspiratory CO_2 fraction [L/L]

h. *Alveolar gas equation* (see also p. 136)

$$P_{AO_2} = P_{IO_2} - \frac{P_{ACO_2}}{RQ} \text{ [kPa]}$$

P_{AO_2} and P_{IO_2} = alveolar and inspiratory partial pressure of O_2 [kPa]
P_{ACO_2} = alveolar partial pressure of CO_2 [kPa]
RQ = respiratory quotient [dimensionless].

7. Henderson–Hasselbalch equation
(see also pp. 138ff., 385)

a. *General equation:*

$$pH = pK_a + \log \frac{[A^-]}{[AH]}$$

b. *for bicarbonate/CO_2 buffer (37 °C):*

$$pH = 6{,}1 + \frac{[HCO_3^-]}{\alpha \cdot P_{CO_2}}$$

pH = negative common logarithm of H^+ activity
pK_a = negative common logarithm of dissociation constant of buffer acid in denominator (AH or CO_2)
$[A^-]$ and $[HCO_3^-]$ = buffer base concentration; $\alpha \cdot P_{CO_2} = [CO_2]$; see Equation 6f.

8. Equations for renal function
(see also p. 150ff.)

a. *Clearance of a freely filtrable substance X (C_X):*

$$C_X = \dot{V}_U \cdot \frac{U_X}{P_X} \text{ [L} \cdot \text{min}^{-1}\text{]}$$

b. *Renal plasma flow*

$$RPF = \dot{V}_U \cdot \frac{U_{PAH}}{0{,}9 \cdot P_{PAH}} \text{ [L} \cdot \text{min}^{-1}\text{]}$$

c. *Renal blood flow (RBF):*

$$RBF = \frac{RPF}{1 - HCT} \text{ [L} \cdot \text{min}^{-1}\text{]}$$

d. *Glomerular filtration rate* (GFR):

$$GFR = \dot{V}_U \cdot \frac{U_{In}}{P_{In}} \text{ [L} \cdot \text{min}^{-1}\text{]}$$

e. *Free water clearance* (C_{H2O})

$$C_{H_2O} = \dot{V}_U \cdot \left(1 - \frac{U_{osm}}{P_{osm}}\right) \text{ [L} \cdot \text{min}^{-1}\text{]}$$

f. *Filtration fraction*

$$FF = \frac{GFR}{RPF} \text{ [dimensionless]}$$

g. *Fractional excretion of substance* X (FE_X):

$$FE_X = \frac{C_X}{GFR} \text{ [dimensionless];}$$

h. *Fractional reabsorption of substance* X (FR_X):
$FR_X = 1 - FE_X$ [dimensionslos];

$\dot{V}_U$ = urinary excretion rate [$L \cdot min^{-1}$]
U_X, U_{PAH}, U_{In} = urinary concentration of substance X, para-aminohippuric acid, and indicator (e.g., inulin, endogenous creatinine) [$mol \cdot L^{-1}$] or [$g \cdot L^{-1}$]

U_{osm} = osmolality of urine [Osm · L^{-1}]
P_X, P_{PAH}, P_{In} = plasma concentration of substance X, para-aminohippuric acid, and indicator (e.g., inulin, endogenous creatinine) [mol · L^{-1}] or [g · L^{-1}]
P_{osm} = osmolality of plasma [Osm · L^{-1}]
HCT = hematocrit [L of blood cells/L of blood]

9. Equations for filtration
(see also pp. 152, 208)

a. *Effective filtration pressure at capillaries (P_{eff})*
$$\mathbf{P_{eff} = P_{cap} - P_{int} - \pi_{cap} + \pi_{int}}\ [\text{mmHg}]$$

b. *Effective filtration pressure at capillaries of renal glomerulus:*
$$\mathbf{P_{eff} = P_{cap} - P_{Bow} - \pi_{cap}}\ [\text{mmHg}]$$

c. *Filtration rate ($\dot{Q}$ at glomerulus = GFR)*
$$\mathbf{\dot{Q} = P_{eff} \cdot F \cdot k}\ [m^3 \cdot s^{-1}]$$

P_{cap} (P_{int}) = hydrostatic pressure in capillaries (interstitium) [mm Hg]
π_{cap} (π_{int}) = oncotic pressure in capillaries (interstitium) [mm Hg]
P_{eff} = mean effective filtration pressure [mm Hg]
A = area of filtration (m^2)
k = permeability to water (hydraulic conductance) [$m^3 \cdot s^{-1} \cdot mm\ Hg^{-1}$]

10. Law of Laplace
(see also pp. 118, 188, and 210)

a. *Elliptical hollow body (with radii r_1 and r_2)*
$$\mathbf{P_{tm} = T \left(\frac{1}{r_1} + \frac{1}{r_2}\right)}\ [\text{Pa}];$$

b. *Elliptical hollow body, considering wall thickness:*
$$\mathbf{P_{tm} = S \cdot w \left(\frac{1}{r_1} + \frac{1}{r_2}\right)}\ [\text{Pa}];$$

c. *Spherical hollow body ($r_1 = r_2 = r$):*
$$\mathbf{P_{tm} = 2\,\frac{T}{r}}\ [\text{Pa}]\ \textbf{or}\ \mathbf{P_{tm} = 2\,\frac{S \cdot w}{r}}\ [\text{Pa}];$$

d. *Cylindrical hollow body ($r_2 \rightarrow \infty$, therefore $1/r_2 = 0$):*
$$\mathbf{P_{tm} = \frac{T}{r}}\ [\text{Pa}]\ \text{or}\ \mathbf{P_{tm} = \frac{S \cdot w}{r}}\ [\text{Pa}]$$

P_{tm} = transmural pressure [Pa]
T = wall tension [N · m^{-1}]
S = wall tension [N · m^{-2}]
w = wall thickness [m]

11. Equations for cardiovascular function
(see also items 2, 5b, 6c, and 9 as well as p. 188ff.)

a. *Cardiac output* (CO):
$$\mathbf{CO = f \cdot SV}\ [l \cdot min^{-1}]$$

b. *Hagen–Poiseuille equation*
$$\mathbf{R = \frac{8 \cdot l \cdot \eta}{\pi \cdot r^4}};$$

f = heart rate [min^{-1}]
SV = stroke volume [L]
R = flow resistance in a tube [Pa · s · m^{-3}] of known length l [m] and inner radius r [m]
η = viscosity [Pa · s]

Further Reading

Physiology

Boron WF, Boulpaep EL. *Medical Physiology: A Cellular and Molecular Approach*. Philadelphia: Saunders; 2004

Guyton AC, Hall JE.*Textbook of Medical Physiology*. Philadelphia: Saunders 2005

Hall JE. *Guyton & Hall Physiology Review*. St. Louis: C.V. Mosby; 2005

Koeppen BM, Stanton BA. *Berne and Levy Physiology*. St. Louis: Mosby; 2008

Levy MN, Stanton BA, Koeppen BM. *Berne and Levy Principles of Physiology*. St. Louis: Mosby; 2005

Widmaier EP, Raff H, Strang KD. *Vander, Sherman, Luciano's Human Physiology: The Mechanisms of Body Function.* New York: McGraw Hill; 2003

Cell Physiology

Alberts B, Bray D, Lewis J. *Molecular Biology of the Cell.* 4th ed. Taylor & Francis; 2002

Lodish H, Berk A, Kaiser CA, Krieger M. *Molecular Cell Biology*. New York: Palgrave Macmillan; 2007

Neurophysiology, Muscle

Bear M, Paradiso M, Connors BW. *Neuroscience: Exploring the Brain.* Baltimore: Lippincott Williams & Wilkins; 2006

Kandel ER, Schwartz JH, Jessell T. *Principles of Neural Science*. New York: McGraw-Hill; 2000

Respiration

West JB. *Respiratory Physiology: The Essentials.* Baltimore: Lippincott Williams & Wilkins; 2008

Exercise and Work Physiology

McArdle WD, Katch FI, Katch VL. *Exercise Physiology: Energy, Nutrition, and Human Performance.* 6th ed. Philadelphia: Lippincott Williams & Wilkins; 2006

West JB, Schoene RB, Milledge JS. *High Altitude Medicine and Physiology*. London: Hodder Arnold; 2007

Wilmore JH, Costill DL. *Physiology of Sport and Exercise.* London: Human Kinetics; 2005

Heart and Circulation

Hurst JW, Alexander RW, Schlant RC. *Hurst's The Heart, Companion Handbook*. New York: McGraw-Hill 2003

Katz AM. *Physiology of the Heart*. Philadelphia: Lippincott Williams and Wilkins 2005

Renal, Electrolyte and Acid-Base Physiology

Alpern RJ, Hebert SC. *Seldin and Giebisch's The Kidney. Vols. 1 & 2: Physiology and Pathophysiology*. Amsterdam: Elsevier Books 2007

Halperin ML, Goldstein MB. *Fluid, Electrolyte and Acid-Base Physiology: A Problem-Based Approach*. Philadelphia: Saunders; 2006

Navar LG, Eaton DC, Pooler JP. *Vander's Renal Physiology*. New York: McGraw Hill; 2008

Gastrointestinal Physiology

Barret KE. *Gastrointestinal Physiology*. New York: McGraw-Hill; 2006

Johnson R, Barrett KE, Ghishan FK. *Physiology of the Gastrointestinal Tract: Vols 1 & 2*. Leonard Academic Press 2006

Johnson LR. *Gastrointestinal Physiology*. Leonard Mosby; 2006

Endocrinology

Kronenberg HM, Melmed S, Kenneth S. Polonsky KS, Larsen PR. *Williams Textbook of Endocrinology*. Philadelphia: Saunders; 2007

Strauss JF und Barbieri RL. *Yen & Jaffe's Reproductive Endocrinology. Physiology, Pathophysiology and Clinical Management*. Philadelphia: Saunders; 2004

Reproduction an Sexual Physiology

Leung PCK, Armstrong DT, Ruf KB, Moger WH. *Endocrinology and Physiology of Reproduction*. Heidelberg: Springer 2007

Neill JD. *Knobil and Neill's Physiology of Reproduction*. Amsterdam: Academic Press; 2005

Animal Physiology

Hill RW, Wyse GA, Anderson M. *Animal Physiology*. Palgrave Macmillan; 2004

Randall DJ, Burggren W, French K. *Eckert Animal Physiology*. Palgrave Macmillan; 2002

Pathophysiology, Pathology

Kumar V, Abbas AK, Fausto N, Mitchell R. *Robbins' Basic Pathology*. Philadelphia: Saunders 2007

McPhee SJ, Ganong WF. *Pathophysiology of Disease: An Introduction to Clinical Medicine*. New York: McGraw-Hill; 2005

Price SA, McCarty Wilson L. *Pathophysiology. Clinical Concepts of Disease Processes*. Elsevier, Oxford 2003

Silbernagl S, Lang F. *Color Atlas of Pathophysiology (Flexibook)*. Thieme Medical Publishers 2000

Pharmacology

Brunton LL, Lazo JS, Parker K. *Goodman and Gilman's the Pharmacological Basis of Therapeutics*. B& T 2005

Champe PC, Finkel R, Cubeddu L. *Pharmacology* Philadelphia: Lippincott Raven; 2008

Rang P, Dale MM, Ritter JM, Flower RJ. *Pharmacology*. Edinburgh: Churchill Livingstone; 2007

Dictionaries

Dorland NW. *Dorland's Illustrated Medical Dictionary*. Philadelphia: Saunders; 2007

Dumith K, Breskin M, Seeman R. *McGraw-Hill Medical Dictionary for Allied Health*. New York: McGraw Hill; 2007

Martin E. *Concise Medical Dictionary*. Oxford University Press; 2007

Index, Abbreviations

A

a (atto-, submultiple of a unit) 379
A (ampere), unit 381
  band, muscle 60
AA (amino acids) 184, 298
Abdominal muscles 108
  pressure 108, 266
  reflex 322
Aberration, spherical 352
AB0 system 100
Absolute threshold, eye 358
    smell 346
    ear 368
Absorption, intestinal, of amino acids 260
    carbohydrates 260
    electrolytes 264
    fat 254
    iron 90
    lipids 254
    peptides 260
    vitamins 262
Abstract thinking 340
ABP (androgen-binding protein) 308
ACAT (acyl-CoA-cholesterol acyl transferase) 258
Acceleration (unit) 380
  angular (rotational) 348
  detection 348
  linear (translational) 348
  sensor 316, 348
Accessory nucleus 374
Accident, electrical 202
Acclimatization 226
Accommodation, eye 348, 352
  range 348, 352
  reflex, intestine 246
    rectum 266
    stomach 242
ACE (angiotensin-converting enzyme) 186
  inhibitor 186
A cells, islets of Langerhans 284, 286
Acenocumarol 104
Acetate, conjugates 160
Acetazolamide 174
Acetone 286
Acetylcholine 34, 52, **78 ff.,** 238, 244
  antagonists 82
  cerebral cortex 334
  control of circulation 214 ff.
  coronary vasodilatation 212
  esophagus 240
  esterase 56, 82
Acetylcholine (cont.)
  gastrointestinal tract 236
  heart action 196
  motor end plate 56
  NO-synthase activation 82
  pankreas 248
  parietal cells 244
  release 82
  receptors → cholinoceptors
    second messenger 55 F, 276, 278
  synthesis 82
Acetylcholinesterase 56, 82
  synaptic cleft 82
Acetyl coenzyme A 286
A chain, insulin 284
Achalasia 240
Acetylsalicylic acid 104
    cyclooxygenase inhibition 271
Achromat 362
Acid, fixed 176
  production 176
  titratable 176, 180
Acid–base balance 138, 142
    compensatory mechanisms 142
    disturbances 142, 146, 178
    kidney 176
    liver 178
    metabolic disturbances 142
    normal parameters 142
    regulation 142
    respiratory disturbances 144
  status, assessment 146
Acidosis **142**
  hyperkalemic 182
  influence on protein-bound Ca^{2+} 292
  K^+ concentration, plasma 182
  lact- 76
  metabolic 142, 264, 286
  nonrespiratory (metabolic) 142, 264, 286
  in diarrhea 264
  phosphaturia 180
  renal tubular 142, 178
  respiratory 126, 142, 144
Acini, salivary gland 238
Acne 308
Aconitase, iron absorption 90
Acoustic information, central processing 374
  pathways 374
  thresholds 368, 374
Acrosomal reaction 310
ACTH → corticotropin
ACTH reserve 296
Actin 14, 30, 56, 58, 62, 70, 82
Actin (cont.)
  filament 14, 60
  molecular structure 60
  myosin interaction 68
  smooth muscle 70
  skeletal muscle 60
Action potential 42, 62
    all-or-none depolarization 46
    depolarization phase 46
    heart 59 A, 194, 196
    overshoot 46
    pacemaker, heart 194
    postsynaptic neurons 82
    propagation 48
    purkinje fibers 202
    repolarization phase 46
    retina 360
    skeletal muscle 56, 59 A
    smooth muscle 59 A
Activating energy 40
Activation system, subcortical 340
Active immunization 94
  transport 26, 44
Activin, FSH secretion 308
Activity coefficient 382
Acuity, visual 354
Acyl-CoA-cholesterol acyl transferase (ACAT) 258
Adam-Stokes attack 202
Adaptation, eye 360,
  sensors 314
  smell 346
  taste 344
  thermosensation 316
ADCC (antigen-dependent cell-mediated cytotoxicity) 96
Addison's disease 184
Adenin 8
Adenohypophysis 270, 282
Adenosine, coronary vasodilatation 212
  second messenger of 276
Adenosine diphosphate → ADP
  monophosphate → AMP
  triphosphate → ATP
Adenylate cyclase 37 C1, 276, 278
    inhibition with acetylcholine 82
ADH → adiuretin
Adhesion molecule (VLA-4) 98
Adhesion, platelets 102
Adiadochokinesis 330
Adiuretin 24, 162, 271, 282
  activated Cl^--channels 162
  deficiency 166
  effects 214, 282

Adiuretin (cont.)
receptor types 24, 55 F, 166, 282
salt/water homeostasis 173 E
second messenger 24, 55 F
secretion 220
ADP 72
role in autoregulation 214
ADP-ribosylation factor (ARF) 30
Adrenal cortex 256, 274, 296, 305, 308
androgens 308
fetal 306
glucocorticoids 298
HDL receptors 256
hormone synthesis 296 ff., 306
progesterone 305
zones 296, 298
medulla 78, **86,** 270, 274, 298
hormones 86
Adrenaline → epinephrine
Adrenergic transmission 84
Adrenoceptors 84, 214, 216
α- 84, 214 f.
α_1- 80 ff., 216, 278, 306
renin secretion 186
α_2- 52, 80 ff., 86, 146, 232, 250
insulin secretion 284
second messenger 55, 276
agonists 87 B
antagonists 87 B
β- 86, 214 f.
β_1-, renin secretion 186
second messenger 85 ff., 276
β_2-, 85 ff., 286
coronary vasodilatation 212
second messenger 55, 85 ff., 276
salivary glands 238
β_3-, fatty tissue 84, 224
second messenger 55, 276
stomach 244
distribution 81, 87 B
G- proteins 55, 87 B
kidney 216
localisation 81 ff.
receptor types 84 ff.
skin 216
types 84, 87 B
uterus 306
Adrenocortical hormones 296
insufficiency 184
tumor 218
Adrenocorticotropic hormone → corticotropin
AE1 (= Anion exchanger 1) 176
Aerobic glucose metabolism 72
Affinity, transport system 28
Afterload, heart 206
maxima, curve 205
Afterloaded contraction 66
heart 204
Agglutination, red blood cells 100
Aggregation, platelets 102
AIP (aldosterone-induced proteins) 184
Air, composition 107 A, 391
sound conduction 370
Air space, voice 376
Airway resistance 134
A-kinase (proteinkinase A, PKA) 84, 276
Akinesia 328
Alanine, glucagon secretion 286
Alarm reaction 86, 332
Albumin 92, 154, 158, 270, 308
bilirubin binding 252
calcium binding 292
pressure, oncotic 210
renal filtration 154
reabsorption 158
testosterone binding 308
T_3/T_4 transport 290
Alcohol, energy source 228
Aldosterone 162, 170, **184 ff.,** 186, 218
antagonists 174
deficiency 184
deficit 172
degradation 185 D
effects 184
induced protein (AIP) 184
K^+ metabolism 182
Na^+-transport, intestinal 264
tubular 182 ff.
receptor 174
glucocorticoids 298
secretion 184, 185 D
synthesis 296
Alkaline phosphatase 252
Alkalosis 142
Ca^{2+} concentration, serum 292
hypokalemic 174, 182
K^+ plasma concentration 182
metabolic 142
non-respiratory 142
phosphate reabsorption, renal 180
respiratory 142, 144
high altitude 136
vomiting 240
Allergens 98, 100
Allergy 100
anaphylactic shock 220
delayed type hypersensitivity 100
immediate reaction 100
Allodynia 320
All-or-none-response 46, 66, 194
all-*trans*-retinal 354, 356
Alternating current 50, 381
Altitude gain 136
Alveolar gas 114
Alveolar gas (cont.)
partial pressures 120
equation 120, 136, 395
exchange 120, 124
pressure (P_A) 108, 116
Alveolar ventilation 106, 114, 120 ff.
Alveoli 106, 118 ff.
cell types 118
contact time 120
diffusion distance 120
surface 118
tension 118
Amacrine cells, retina 350, 360
Ambient temperature pressure H_2O-saturated (ATPS) 112
Amenorrhea 232
Amiloride 174
L-Amino acid decarboxylase 84
Aminoaciduria 260
Amino acids (AA) 242, 260, 184, 186, 298
co-transport with Na^+ 158, 260
essential 228
glucagon secretion 286
gluconeogenesis from 284
influence on insulin release 284 ff.
intestinal absorption 260, 264
metabolism, cortisol effect 298
pylorus, effect on 242
renal transport 156, 158
storage 286
transmitter 55 F
γ-aminobutyric acid (GABA) 52, 322
p-aminohippurate 150, 160
Aminopeptidases, small intestine 260
Ammonia → NH_3
Ammonium → NH_4^+
Amnesia 340
Amount of substance, unit 381
5'-AMP 278
AMP, cyclic 84, 288
adrenergic transmission 84
TSH 288
AMPA receptors → glutamate
Ampere (A), unit 381
Amplification, cochlear 372
Ampulla, labyrinth 348
Amygdala 346
α-amylase 260
Amylopectin 260
Amylose 260
Anabolic action 282
insulin 286
STH 282
testosterone 308

Anaerobic glycolysis 72
  threshold 72
Analgesic action 320
Anal sphincters 266
Anaphylaxis 100
Anastomoses, arteriovenous 226
Androgen-binding protein 308
Androgens 302, 308
  adrenal cortex 296
  synthesis 296, 308
    follicle 302
Androstenedione 302
Anemia 228, 262
  hyperchromic 90
  hypochromic, iron deficiency 90
  pernicious 262
  sickle cell 92
Anergy 98
ANF → Atriopeptin
Angina pectoris 320
    ECG 200
Angiotensin I 186
  lung 106
Angiotensin II (AT II) 158, 170, 184, **186,** 214
  aldosterone secretion 184
  effects 186, 214, 218
  CSF 168
  degradation, renal 158
  receptors 186
  second messenger 276
  thirst 172
Angiotensin-converting enzyme (ACE) 186
Angiotensinogen 186
  synthesis, cortisol effect 298
Ångström (unit) 378
Anion exchange, red blood cells 124
Anion exchanger 1 (= AE1) 176
Anode 50
Anomaloscope 362
Anovulatory cycle 300
Anoxia (→ also hypoxia) 130, 134
ANP → Atriopeptin
ANS (Autonomic nervous system) 78 ff., 196, 214 ff., 236, 268, 332
Anterior pituitary 270, 282
Anterolateral funiculus, tracts 320, 324
Antibodies (→ also immunoglobulins) 94, 98, 100
Anticoagulants 104
Anticodon 8, 10
Antidiuresis 164, 166
Antidiuretic hormone → adiuretin
Antigen-antibody complex 98
    allergy 100
    presentation 96, 98
Antigen-dependent cell-mediated cytotoxicity (ADCC) 96
Antigens 94, 98
  incomplete 100
  presentation 96, 98
  thymus-dependent (TD) 98
  thymus-independent (TI) 98
Antihemophilic factors 102
Antiovulatory effect 305
α_2-Antiplasmin 104
Antiport, definition 26
Antipyrine 168
Antithrombin 104
Antrum, stomach 242
α_1-Antitrypsin 104
Anulospiral endings 318
Anuria 164
Anus 266
Aorta 190
  blood flow velocity 192
  flow rate 193 A
  pressure 192, 206
    influence on heart functions 206
    sensors 216
  valves 192
APC (antigen-presenting cells) 96, 97 B, 98
Aphasia 376
Apnea 108, 132
Apolipoproteins 92, 256
Apomorphine 240
Apoptosis 98, 274, 302
Apotransferrin 90, 92
Apparatus, juxtaglomerular 174, 186
Aprotinin 105 C
AQP → Aquaporins
Aquaporins 24, 166, 176
Aqueous humor 350
Arachidonic acid 270, 278
Arachnoid villi 312
ARAS (ascending reticular activating system) 324, 334, 338 ff.
Archeocerebellum 328
Area prostrema, chemosensors 240
Areflexia 322, 330
ARF (ADP-ribosylation factor) 30
Arginine 176, 228, 260, 284, 286
  glucagon secretion 286
  intestinal absorption 260
  insulin release 284
Aromatase 302, 308
Arousal activity 334
Arrhenius 40
Arrhythmia 220ff
  absolute 202
Arrestin 356
Arsenic (As) 228
Arteries (→ also artery) 188 ff., 190
  arcuate 150
  bronchial 188
  compliance 190
Arteries (cont.)
  coronary, myocardial perfusion 188
  interlobular 150
  pressure 208
  umbilical 222
Arteriole 188 ff.
  afferent 186
  efferent 186
Arteriosclerosis 210, 212, 304
  coronary artery 212
  hypertension 218
Artery (→ also arteries), carotid,
  pressure sensors 216
  interlobular 150
  pulmonary 122
    pressure 122
      fetus 221 B
Ascending reticular activating system (ARAS) 324, 334
Ascites 210
Ascorbate → vitamin C
Aspartate 176, 260
  intestinal absorption 260
  receptor types 55 F
  second messenger 55 F
Aspirin® 104, 270, 320
Associative cortex 326, 331, 340
Asthma 100, 118
Astigmatism 352
Astrocytes 344
Astrup method 146
at, conversion into SI unit 380
AT I receptor 186
AT II (Angiotensin II) 158, 170, 184, **186,** 214
  receptor 186
Ataxia 330
Atelectasis 118
Atenonol 87 B
Atherosclerosis → Arteriosclerosis
atm, conversion into SI unit 380
Atmosphere, physical, 380
  technical, 380
Atomic mass 380
ATP 41, 64, 72, 86, 230
  control of K^+ channels 284
  coronary vasodilatation 212
  cotransmitter 84
  creatine phosphate 230
  free enthalpy 41
  gain, glucose 73 B
  neurotransmitter 86
  production 12
    aerobic 41, 72
    anaerobic 72
  supply of energy, muscle 72
  synthesis 12
  transport, active 26
  tubular epithelium 154
ATPase (→ also Na^+-K^+-ATPase, Ca^{2+}-ATPase) 26, 58, 72, 84

ATPS (Ambient temperature pressure H_2O-saturated) 112
ATP-synthetase 17
Atrial fibrillation 202
  flutter 202
  septal defect 222
  tachycardia 202
Atriopeptin (ANF, ANP) 152, 162, 172 184, 220
  aldosterone secretion 184
  receptor 280
Atrioventricular (AV) block 162, 202
  node 194, 196
  valves 192
Atrophy, compensatory 274
Atropine 82
  transport, tubular 160
Attention 328, 340
  automated 340
  EEG 334
  selective 340
Atto- (submultiple of a unit) 379
Audiometer 372
Auditory canal 370
  pathway 374
  threshold 345
Auerbach plexus (myenteric plexus) 246
Autoantibody 100
  TSH receptor 290
Autogenous inhibition 318
Autoimmune disease 94
Automaticity, heart 194
Autonomic nervous system (ANS) 78 ff., 196, 214 ff., 236, 268, 332
Autophagia 12
Autophagic vacuole 12
Autophagosomes 12
Autophosphorylation, receptor tyrosine kinase 280
Autoreceptor 86
  presynaptic 52, 82, 146
Autoregulation 4, 214
  coronary 212
  gastrointestinal 234
  renal 150
Auxotonic contraction 66
AV → atrioventricular
avD_{O_2} (arterial venous O_2 difference) 106, 107 A
aVF (ECG leads) 198
aVL (ECG leads) 198
Avogadro's constant (N_A) 20, 380
aVR (ECG leads) 198
Axolemma 42
Axon 42
  capacitive flow of charge 48
  conduction velocity 48, 49 C
  diameter 48
  hillock 42
  membrane capacity 48
Axon (cont.)
  myelin sheath 42
  nodes of Ranvier 42
  reflexes 216
  saltatory conduction 48
Axonal transport 42, 282

B

B7 protein 98
B cells, islets of Langerhans 284
  lymphocytes 94, 98
B chain, insulin 284
B lymphocytes 94, 98
Bacteria, defense 94 ff., 244
  intestinal 234, 242, 252, 266
  lysis 94
Bainbridge reflex 218
Balance, body 330, 348
  glomerulo-tubular 166
Bar (unit) 380
Barbiturates, tubular secretion 160
Barium contrast medium 266
Barotrauma 134, 110
Barrier, blood–brain 18, 232, 240, 312, 332
  blood-CSF 18, 312
Basal body temperature 300
Basal ganglia 312, 326
  labyrinth of tubule cells 154
  metabolic rate 228
Base, DNA 8
  excess 142
    measurement 146
  triplet, mRNA 8
  units, SI system
Basilar membrane 370, 372
Basket cells 330
Basolateral membrane, tubule cell 162
Basophilic granulocytes 100
Bathorhodopsin 354
Bayliss effect 214
BDGF (brain-derived growth factor) 344
Beat tone 368
Behavior, defensive 332
  nutritive 332
  programmed, hypothalamus 332
  reproductive 332
  thermoregulation 226, 332
BEI → iodine
Bel 345
Beriberi 228
Bicarbonate → HCO_3^-
Bicycle ergometry 76
Bilayer of membranes 14
Bile 234, **250 ff.,** 258, 262
  acid → bile salts
Bile (cont.)
  bilirubin excretion 252
  canaliculi 250
  components 250
  ductules 250
  excretory function 250
  formation 250
  hepatic 250
  salts 160, 248, **250, 254,** 258
    absorption, terminal ileum 254
    body pool 250
    carrier 250
    conjugated 250, 254
    enterohepatic circulation 254
    function 254
    primary 250
    secondary 250
    synthesis 250
  steroid hormone excretion 296
Bilirubin 250, 252
  direct 252
  diglucuronide 252
  excretion 252
  indirect 252
Biliverdin 252
Binary digit 314
Biologic clock 226, 336
Biotin, intestinal absorption 262
Biotransformation 234, 252
Bipolar cells, retina 350
Birth 94, 306, 222
  circulation during 222
2,3-Bisphosphoglycerate (2,3 BPG) 128, 138
Bit 314
Bitemporal hemianopia 364
Bitter sensors 344
Bladder, urinary 70, 79 ff., 148
  control 79 ff., 310
Bleeding 220
  time 102
Blind spot, eye 354, 364
Blindness 350
Blinking 350
Blood 88 ff.
  brain barrier 18, 232, 240, 282, 312, 332
  cells 88
  clotting 102
    activation 102, 104
      endogenous 102
      exogenous 104
  coagulation disorders 228
    estrogen effects 304
    factors 102
  composition 88
  CSF barrier 18, 126, 312
  fibrinolysis 102
Blood flow 122, 214, 234
  brain, control 214

Blood flow (cont.)
central regulation 216
coronaries 212, 214
gastrointestinal 234
lungs 122, 188
muscle 216
properties 92
rate 190
regulation, neuronal 216
renal 150
skin 214, 216, 226
velocity 92, 190, 192
vessel segments 191 A
function 88 ff.
glucose 284, 286
groups 100
HCO_3^- concentration 142, 146
hormone transport 270
lipids 258
loss 90, 175, 220
pH 138
puffer 138, 144
normal range 142
measurement 146
pressure 74, 86, 186, 190, 204, **208**, 214, 216
arterial 208
amplitude 208
angiotensin II effect 186
fetal 222
mean 190, 191 A, 208
measurement 208
normal range 208
physical work 74
regulation 218
renin-angiotensin system 186
salt deficit 172
sensors 216
shock 220
control 216, 218
diastolic 208
pulmonary 122, 208
sensors 216
systolic 192, 208
venous 206
sugar 284 ff.
testis barrier 308
transfusion 100
vessels 190, 214 ff.
autoregulation 214
chemosensors 214
cross-sectional area 191 A
diameter 191 A
function 190 ff.
holding capacity 191 A
nervous control 216
precapillary sphincter 190
skin 226
wall tension 190
viscosity 92, 190
high altitudes 136
Blood flow (cont.)
volume 88, 184, 188, 190, 208
central 206
determination 168
distribution 189 A
endurance athletes 77 C
measurement 168
sensors 216
total 188
B-lymphocytes 94, 98
BMAL1 336
BMI (body mass index) 232
BMR (basal metabolic rate) 228
Body fluids 92, **168**
compartments 168
measurement 168
homeostasis 168
osmolality 170
mass index (BMI) 232
plethysmography 114
temperature 132, 224, 226, 300, 332, 381, 387 C
circadian variation 226, 387 C
measurement 226
menstrual cycle 300
pressure saturated (BTPS) 112
respiration 132
set point 226
water → body fluids
weight 232
regulatory mechanism 232, 282
Bohr effect 128
equation, dead space 114, 115 A
Boiling point, water 381
Bomb calorimeter 230
Bone 292, 294
break down 292
calcitonin effect 294
calcitriol effect 294
conduction, sound 370
estrogen effects 304
growth 304
marrow 88, 90, 94
Fe homeostasis 90
megakaryocytes 102
preprocessed precursor cells 94
metabolism 292
mineralization 294
PTH effect 292
Botulinum toxin 56
Bowman's capsule 148
Bradycardia, sinus 202
Bradykinesia 328
Bradykinin 186, 210, 216, 271, 320
coronary vasodilatation 212
salivary glands 238
second messenger 278
Bradypnea 108
Brain 312 ff.
anatomy 312
blood flow 188
regulation 214
cortex
afferents 326
area 1 311 E, 326, 327 C
area 2 311 E, 326, 327 C
area 3 311 E, 326, 327 C
area 4 311 E, 326, 327 C
area 5 311 E, 326, 327 C
area 6 331 E, 326, 327 C
area 7 311 E, 326, 327 C
area 22 311 E, 376
area 44 311 E, 376
area 45 311 E, 376
area MI 326, 327 C
area PM 326, 327 C
area S1 320, 324, 325 A
area S2 320, 325 A
area SMA 326, 327 C
asssociation areas 330, 340
auditory 374
Brodman's areas 313 E
columns 334
corticocortical signal loops 326
cortical afferents 326
efferents 326
ultrastructure 334
motor 326, 330
motosensory 376
neuronal circuitry 334
orbitofrontal area 346
organisation 334
potentials 334
prefrontal association 326
premotor area (PMA) 326
prepiriform 346
primary motor area (MI) 326
pyramidal cells 334
scarring 344
sensory association 326
input 324
supplementory motor area (SMA) 326
death, diagnosis 334
derived growth factor (BDGF) 344
glucose deficit 244
glutamate, transmitter 340
hemisphere, dominant 342
metabolism 284
nerve cells 344, 346, 365
stem (→ also medulla oblongata, pons, and midbrain) 312, 320
motor centers 326, 330
survival time, anoxia 130
visual areas 330, 360, 362, 364

Breathing capacity, maximum (MBC) 118
flat 120
gas (→ also O_2 and CO_2) 106
mechanics 108
Breast 304, 305
development 306
estrogen effect 304
progesterone effect 305
prolactin effect 305
enlargement 306
feeding 305
iodine 290
Brightness channel, visual pathways 362
Bristle cell, olfactory bulb 346
Broca's area 376
Brodman's map 312
Bronchi 376
epithelium 110
innervation 79 ff.
Bronchial mucus 110
tree 188
Bronchitis 118
Brown fat 226, 290
Brown–Sequard syndrom 324
Brunner's glands 246
Brush border 9 f., 154, 158
intestinal mucosa 246
renal tubule 154
stomach, parietal cells 244
BSC (bumetanide-sensitive co-transporter) 162
NH_4^+ reabsorption 178
BSEP (bile salt export pump) 250, 252
BTPS (body temperature pressure saturated) 112
α-BTX (α-bungarotoxin) 56
Buffer 124, 138, 140, 142, 144, 384 f.
base 140
blood 138
concentration 138, 142
total 146
capacity 138, 140
closed system 140
curve 386 B
hemoglobin 124, 128
non-bicarbonate 126, 140, 144
open system 140
titration curve 386
Bulb, ocular 350
Bumetanide 174
Bundle of His 194
Bundle-branch 202
block 202
α-bungarotoxin (α-BTX) 56
Bunsen solubility coefficient 126
Bunte glass burette 114
Burning 220
Butanol-extractable iodine (BEI) 290
Byte 314

C

c (submultiple of a unit) 373
C17/C20-lyase 302
C cells, thyroid gland 294
°C, conversion to °F 381
Ca^{2+} (→ also Calcium) 36, 228, 264
absorption, intestine 264, 280, 292, 294
antagonists 196
ATPase 17 A, 17 B2, 26, 36, 180, 294
heart 196
muscle 64
renal 180
balance 292
calmodulin-dependent protein kinase II 36, 50
cell regulation 36
channels 36, 62, 180, 354
activation 278
β-adrenoceptors 84
hair cells 348
heart muscle 63 B3, 65 D, 196
inhibition 84, 278
muscle 62
photosensors 354
regulation 36
renal 180
ryanodine-sensitive 196
voltage-gated 196
clotting process 102
complexed 292
concentration 50
cytosolic 36, 66, 238
adrenergic transmission 84
electromechanical coupling 62, 196
epinephrine 87 B
exocytosis 30
extracellular 36, 46
heart 196
intracellular 36, 278
muscle 63B
smooth 70, 71B
norepinephrine 87 B
oscillations 36
photosensors 356, 358
muscle fibers 62, 64, 196
neurons 340, 344
serum 292
conductance, $GABA_B$ receptors 322
daily requirement 228, 292
Ca^{2+} (cont.)
darkness-induced 356
deficiency 292
equilibrium potential 44
excretion 180, 292
exocytosis 30
fat absorption 254
fetal 292
free 180, 292
hormone release 282
intake 292
intestinal absorption 264, 292, 294
intracellular stores 36
ionized 180, 292
light sensors 358
metabolism 180, 292
milk 292
muscle contraction 60ff
/3 Na^+ antiport 36
plasma 180, 292
pregnancy 292
protein bound 180, 290, 292, 294
reabsorption, renal 156, 180
paracellular 174
renal excretion 180
saliva 238
sensors 36, 294
kidney 180
serum 292
smooth muscle 70
solubility 292
store, intracellular 10,36
IP_3 278
myocard 196
skeletal muscle 60
third messenger 278
trigger effect 62
urine 292, 180
CaBP (calcium-binding protein) 264, 280, 294
Cabrera circle (ECG) 200
Caffeine 278
Caisson disease 134
Cajal cells 242, 246
Cajal's horizontal cells, retina 350, 360
cal (calorie), unit 380
Calcidiol (25-OH-cholecalciferol) 158, 294
Calciol (= cholecalciferol = Vitamin D) 262, 294
Calcitonin 36, 37 C2, 276, 288, 292, 294
gene-related peptide (CGRP) 216, 236, 308, 320
Calcitriol (1,25-$(OH)_2$ -cholecalciferol, D-hormone) 158, 264, 270, 280, **292 f.**, 294
deficiency 292
nuclear receptor 280

Calcitriol (cont.)
PTH effect on formation 292
Calcium → also Ca^{2+}
Calcium-binding protein (CaBP) 264, 280, 294
Calcium oxalate, urinary stones 180
Calcium phosphate, solubility product 292
urinary stones 180
Caldesmon 70
Calmodulin 36, 278, 280, 340
smooth muscle 70
photo sensors 356
Calmodulin-dependent protein kinase II 36, 50
neurons 340
Caloric equivalent 230
value, physical 230
Calorie 230
conversion into SI unit 380
Calorimetry 230
cAMP → AMP, cyclic
Canaliculi 250
bile 250
lachrymal 350
parietal cells 244
Canals, semicircular 348
Can sugar → saccharose 260
Capacitation of sperm 304, 310
Capacitive current, membrane 48
Capacity, buffering 140
electric, nerve 48
Capillaries 190
blood pressure in 150, 211 B
lung 210
characteristics 190
diffusion processes 210
exchange processes 210, 383
filtration 210
fluid exchanges 210
glomerular 150
peritubular 150, 151 A, 166
permeability 210, 383
pulmonary 106, 122
reabsorption 210
Capsaicin sensors 316, 320
Carbamate, CO_2 transport in blood 124
Carbohydrate 228, 230, 248, 260, 284, 298
absorption, intestinal 260
caloric equivalent 230
digestion 260
pancreatic enzymes 248
energy substrate 230
metabolism 284
cortisol effect 298
nutrition 228
Carbon dioxide → CO_2
monoxide (CO) 128
Carbonic anhydrase 124, 176, 238
gastric 244
inhibitors 142, 174, 350
pancreas 248
red blood cells 124
renal 176
salivary glands 238
γ-carboxylation 102
Carboxylesterase 248, 254, 258
Carboxypeptidase 260
Cardia 242
Cardiac (→ also heart)
arrest 202
arrhythmias 182, 202
cycle 192
failure 206
index 188
muscle 68
output (CO) 70, 74, 122, 136, 188, 190, 206, 208, 220, 222
fetus 222
paralysis 200
valves 192
work 204
Carnosine 158
Carrier 22
affinity to 28
free fatty acids 254
liver cells 252
passive 28
transport 158
CART (cocaine and amphetamine-regulated transcript) 232
Cartilage 282
Catabolism, cortisol 298
Catalase 14, 96
Cataract 352, 364
Catecholamines **84,** 270, 276
receptor types 55 F
Catechol-O-methyltransferase (COMT) 86
Cathode 50
cBAT (canalicular bile acid transporter) 250
CBG (cortisol binding-globulin = transcortin) 298, 305
C cells, parafollicular 36, 288
CCK → Cholecystokinin
CD4 protein 98
CD8 protein 98
CD28 protein 98
CD40 ligand 98
CD40 protein 98
CD45 receptor 280
CD95 protein (= Fas) 98
Cecum 234, 266
Cell(s) 8 ff.
antigen-presenting (APC) 98
body 42
chief 242
dendritic 96
dedifferentiation 274
Cell(s) (cont.)
differentiation 274
division 8
excitable 42
expansion 170
fat 256
ganglion, retina 350, 364
granular 328
granulosa 302
killer 96, 98
Leydig, interstitial 308
mast 100, 258
membrane 2, 8, 14
function 2, 14
ion conductance 32
proteins 14
structure 14
permeability 2
migration 30, 58
neuroendocrine 268
nuclear pores 10
nucleus 8, 290
structure and function 8 ff.
organelles 8 f.
pacemaker 246
parietal 242, 244
principal (chief) 162, 182
replacement 246
retina 364
Sertoli 308
shrinkage 170
structure and function 8 ff.
T-helper 98
Cellulose 228, 266
Celsius, conversion to °F 381
Centi- (submultiple of a unit) 379
Central blood volume 206
canal 312
chemosensors 126
nervous system (CNS) 305, 312 ff.
anatomy 312
autonomic centers 78
venous pressure 188, **192,** 206
shock 220
Centralization, circulation 220
Centrosome 14
Cerebellum 312, 324, 326, **328 ff.,** 330, 348, 366, 376
eye movement 366
lesions 330
nystagmus 366
speech 376
Cerebrosides 14
Cerebrospinal fluid (CSF) 126, 144, 168, 312
CO_2 126, 144
pH 126, 144
Cerebral cortex 312
function, glucocorticoid effect 298

Ceruloplasmin, iron oxidation 90
Cervix uteri 300, 304
  menstrual cycle 300
  os 300, 305
  progesterone effects 305
cGMP → GMP, cyclic
cGMP phosphodiesterase, retina 354
CGRP (calcitonin gene-related peptide) 216, 236, 308, 320
  gallbladder 250
  second messenger 276
  stomach 244
Chamber, eye 350
Channels, ion 34
Chaperone protein 10
Chemokines 94, 268, 276
  receptors 94
Chemosensors 142
  area postrema 240
  central 126, 132, 144
  for glucose 284
  respiratory control 132
  small intestine 242
Chemotaxis 94, 310
Chenodeoxycholic acid 250
Chest 108
Chest leads (ECG) 198
Chiasma, optic 364
Chief (principal) cells, kidney 162
    stomach 242, 244
Chinin, taste 344
Chloramphenicol 252
Chloride → Cl^-
CHO (cholesterol) 14, 114, 256, 270, 296, 305
Cholagogue 250
Cholates (→ also bile salts) 250
Cholecalciferol (calciol = Vitamin D) 262, 294
  formation in skin 294
25-OH-cholecaliferol (calcidiol) 158
1,25 $(OH)_2$ -cholecalciferol (calcitriol, D-hormone) 294
Cholecystokinin (CCK) 232, 236, 242, 250
  cerebral cortex 334
  esophagus 240
  gallbladder 250
  pancreas secretion 248
  receptors
    gallbladder 250
    hypothalamus 332
    pancreas 248
    stomach 244
    types 55 F
  second messenger 55 F, 278
  stomach 244
Cholera toxin 264, 278
Choleresis 250
Cholesterol (CHO) 14, 114, 256, 270, 296, 305
Cholesterol (CHO) (cont.)
  bile 250
  crystals 250
  esters 254, 258
    hydrolase 254
    LDL 256
    lipoproteins 256
  feces 258
  LDL 256
  lipoproteins 258
  membranes 14
  micelles 250
  steroid hormone synthesis 296
  storage 257 B
  synthesis 258
Cholesterol-7α-hydroxylase 250
Cholic acids (cholates) 250
Choline 82, 160
  acetyl transferase 82
  nerve terminals 82
  tubular transport 160
Cholinesterase 56
  inhibitors 56
Cholinoceptors 82
  antagonist 82
  heart 196
  ionotropic 56
  M-types, second messenger 276, 278
  nicotinergic 56
  salivary glands 238
  stomach 244
  types 55 F, 56
Chorda tympani 345 C
Chorionic gonadotropin, human (HCG) 306
Choroid plexus 312
Christmas factor 102
Chromium (Cr) 228, 230
Chromatin 8
Chromosomes 8
  single set (haploid) 308
Chronotropism, heart 196
Chylomicron 256, 262
  remnants 256, 258
Chyme 234, 260
  pH 242
Chymotrypsin 248, 260
Chymotrypsinogen 248
Cilia, bronchial 58, 110
  hair cells 348, 370
Ciliary body 70
  muscle 350
  process 350
  zonules 350
Circulation, blood 188 ff., 214 ff.
    autoregulation 214
      Bayliss-effect 214
      hormonal 214
      myogenic effect 214
      neuronal 216
Circulation, blood (cont.)
      local metabolic effect 214
      sympathetic nervous system 216
  birth 222
  centralisation, flow 216, 220
  control 214
  coronary 212
  fetal 222
  portal 234
  pulmonary 188, 190
  pulse wave velocity 192
  regulation 214, 216 ff.
  resistances 187 A, 190, 208
  total peripheral resistance 208
  venous return 206
cholehepatic 250
enterohepatic 250, 254
  bile salts 254
  bilirubin 252
Circulatory "center" 216
  failure 218
  reflexes, homeostatic 218
  sensors 216
  shock 220
Circumventricular organs 282, 312, 332
11-*cis* retinal 354
Cisterns, endoplasmic reticulum 10
Citrate 12, 102
  complex former 180
  cycle 12, 73 B3
  inhibition of blood clotting 102
  renal excretion 176
Citric acid → citrate
Cl^- 384
  absorption in intestine 264
  balance, body 172
  channels, lysosomes 14
    tubular 162
  concentration, intracellular 44
  conductance, membrane 34, 44
  distribution, active/passive 34
  equilibrium potential 44
  excretion 162
  renal handling 156, 162
  secretion in intestine 264
    in pancreas 248
    salivary glands 238
  stomach, parietal cells 244
Clarifying factor → Heparin
Clathrin 14, 28
Claudins 18
Clearance factor (heparin) 258
  esophagus 240
  renal 152
Cleft, synaptic 42, 56, 82
Climacteric 300
Climax 310

Climbing fibres, cerebellum 330
Clitoris 310
CLOCK 336
Clock, biologic 226, 242, 336, 360
Clonal selection 98
Clonidine 84, 87 B
Closed system, thermodynamics 41
  buffer 140
Clothing 226
Clotting, blood (→ also coagulation) 102 ff.
  disorders 228
cmH_2O, conversion into SI unit 380
cMOAT (canalicular multispecific organic anion transporter) 252
CNS → central nervous system
CO (carbon monoxide) 128
  binding to hemoglobin 129 C
CO → also cardiac output
CO_2 (carbon dioxide) 106, 120, 266
  binding, blood 124 ff.
  buffer system 138
  concentration
    blood 124 ff.
      influence of O_2 saturation 126
    cerebrospinal fluid 126, 144
    influence O_2 saturation 126
  chemosensors 134, 144
  chronic retention 132
  diffusion, tissue 130
  dissociation curve 126
  dissolved in plasma 124 ff.
  distribution in blood 124
  elimination 106
  /HCO_3^- buffer 138, 140
  Krogh's diffusion coefficient 120
  large intestine 266
  partial pressure 124
    alveolar 120
      diving 134
    blood 126
      increased 144
      chemical respiratory stimulant 132
      chronical increase 132
      hyperventilation 120
      normal range 142
      regulation by respiration 140
    venous blood 120
  plasma 124 ff., 138, 144
  production 142, 230
  response curve 132
  solubility coefficient 126
  total 126
  transport, blood 124
α-γ-Coactivation 318, 322
Coagulation, disseminated intravascular 104
Coated pits 28
Coatomer 30
Coatomer-coated vesicles 30
Cobalamines (vitamin B 12) 90, 92, 228, 262
  absorption 262
  deficiencies 90, 262
  receptor 28
  storage 262
  transport proteins 262
Cobalt (Co) 228
Cocaine and amphetamine-regulated transcript (CART) 232
Cochlea 370, 374
Cochlear duct → scala media
  amplifier 372
  nucleus 374
Code, genetic 8
Coding, neuronal signals 314
Codogen 8
Codon 10
Coital capacity, testosterone 308
Cold sensors 226, 316
Colipase 248, 254
Collaps, orthostatic 206
Collagen 102, 103 A
Collaterals, axon 42
Collecting duct 148, 162, 166, 176
Colliculus superior 328
Colloid, thyroid 288
Colloidal osmotic pressure 92, 384
Colon 264, 266
  H_2O absorption 264
  K^+ secretion 264
Color blindness 358, 362
  constancy 362
  opponency 360
  perception 362
  triangle 362
  vision 362
    contrast 360
Colors, additive mixture 362
  complementary 362
  subtractive mixture 362
Comfort zone (ambient temperature) 226, 228
Compensation, renal 144
  respiratory 142
Compensatory atrophy 274
  hypertrophy 274
  pause 202
Competitive inhibition 56
Complement cascade 96
  factors 94, 96
Complementary colors 362
Compliance
  blood vessels 190, 208
  lung and thorax 116, 118
    measurement 112
COMT (catechol-O-methyltransferase) 86
Concentration, units 378 f.
Conception 310
Conditioned reflexes 238, 244
Conductance 46, 381
  electrical 22
  for Cl^- 44
  for K^+ 44
  hydraulic 24
  ionic 32
  unit 381
Conduction, atrioventricular (ECG) 200
  deafness 370
  defects, heart 202
  heart 194, 196, 202
  heat 224
  nerve fibres 42, 50
  saltatory, nerve 48
  velocity, measurement 50
Conductivity → conductance
Cones 350, 354, 356, 362
  adaptation 358
  classes 362
  density 354
  light absorption maximum 362
Conjugate eye movement 366
Conjugation processes 160
  with glucuronic acid in liver 150, 252
  with glutathione in liver 160, 252
Connectin (= titin) 60, 66
Connexin 16, 19 C
Connexons 16
Conn's syndrome 184
Consciousness 324, 338
Consensual light response 365
Consolidation, memory 340
Consonants 376
Constancy, of color 362
  of shape 362
  of size 362
Constipation 266
Contact phase, blood clotting 103 B2
Contraceptives 302, 305
Contractility, heart muscle 196
Contraction, afterloaded 66
  auxotonic 66
  isometric 64, 66
  isotonic 64, 66
  velocity, skeletal muscle 68
    myocard 206
Contracture 66
Contrast, auditory pathway 374
  enhancement 374
  of stimuli 314, 330
  retina 360
  simultanous 360
  successive 358, 360
Control circuit 4
    humoral 274

Control circuit (cont.)
system 4
Controller 4
Convection 24, 224
Converting enzyme, angiotensin- (ACE) 186
Convergence of signals 364
response, eyes 366
Cooperativity, positive, hemoglobin 128
Copper (Cu) 228
Coprosterol 258
Core sleep 336
temperature 224, 226
Cornea 350, 352
Corneal reflex 322, 364
Corona radiata 310
Coronary blood flow 212
insufficiency 212
reserve 212
Corpus amygdaloideum 312, 332, 340
callosum 312
geniculatum laterale 362, 364
mediale 374
luteum 300, 302
pregnancy 306
progesterone production 305
stomach 242
Correlations 389
Corresponding areas, retina 366
Cortex, auditory 374
associative 328
cerebellum 328
cerebral 334, 312, 328
frontal 332
Corticoids, albumin binding 270
globulin binding 270, 305
Corticoliberin (= CRH) 232, 271, 274, 276, 282, 298, 306
birth 306
cortisol secretion 298
placenta 306
receptors, hypothalamus 332
second messenger 276
secretion, interleukin effect 298
Corticosterone 184
synthesis 296
Corticotropin (ACTH) 271, 274, 282, 296, 298
aldosterone synthesis 184
cortisol synthesis 298
receptors, hypothalamus 332
second messenger 276
releasing factor → corticoliberin
hormone → corticoliberin
Corti's tunnel 370
Cortisol 92, 184, 258, 274, 282, 298
binding-globulin (CBG) 298, 305
Cortisol (cont.)
effect, permissive 298
fight or flight 332
hypothalamus 332
precursors 298
stress 298
synthesis 298
transport 298
Cortisone 298
Cotransmitter 52, 84, 86, 328
Cotransport, definition 26
Costimulatory signal 98
Coughing 132, 322, 376
Coumarin 104
Countercurrent exchange, heat 226
kidney 164
system 164
Countertransport 26
Coupling, electromechanical 62
COX (cyclooxygenase) 104, 264, 271
CPPV (continuous positive pressure ventilation) 110
Creatine 72
Creatine phosphate 72, 76, 230
muscle reserve 73 B
standard free enthalpy 41
clearance, endogenous 152
Cretinism 290
CRF → cortiboliberin
CRH → corticoliberin
Crigler-Najjar syndrome 252
Cristae, mitochondria 12
Crista, ampulla 348
Cross test, blood types 100
Crypts, large intestine 266
small intestine 246, 264
Crypts of Lieberkühn 246, 264
CSF → cerebrospinal fluid
Cupula 348
Curare 56,110
Current, alternating 50, 381
direct 50, 381
endplate 56
miniature endplate 56
unit 381
Current-voltage curve 33 B3, 34
CVP (central venous pressure) 192, 206
Cyanide 130
Cyanosis 110, 130
Cyclic AMP → AMP, cyclic
GMP → GMP, cyclic
Cyclooxygenase (COX) 244, 271
inhibitors 104
Cyclosporin A 98
Cystic fibrosis 110, 248
Cystine 158, 176
Cystinuria 158, 260
Cytochrome oxidase 130
Cytochrome P450-epoxygenase 271
Cytokines 268, 270, 276
cortisol 298
receptors 280
Cytokinesis 58
Cytolysis 96
Cytoplasm 8
Cytosin 8
Cytosis 28, 58
Cytoskeleton, migration 30
Cytosol 8
ions 45 B, 93 C

D

d (submultiple of a unit) 379
da (multiple of a unit) 379
DAG (Diacylglycerol) 36, 82, 84, 276, **278**
Dalton (Da), unit 380
Dalton's law 106
Dark adaptation, eye 354, 358, 360
receptive field 360
Darkness-induced Ca^{2+} 356
Dead space, artificial respiration 110
functional, respiration 114, 122, 134
increase 120
functions 114
snorkel breathing 134
ventilation 106
volume (V_D) 114
Deafness 370 f., 376
Debré-Toni-Fanconi syndrome 158
Deca- (multiple of a unit) 379
D cells, islets of Langerhans 284, 286
stomach 244
DCT (distal convoluted tubule) 148
DCT1 (= Divalent cation transporter 1) 90
Deceleration, unit 380
Deci- (submultiple of a unit) 379
Decibel (dB), unit 368
Decompression sickness 134
Decurarinization 56
Dedifferentiation, cells 274
Defecation 266
Defense mechanism 96 ff., 234, 332
intestine 234
Defensins 96
Defibrillation 202
Deflation reflex 132
Deglutition 240
Degrees Celcius 381
Fahrenheit 381
7-dehydrocholesterol 294

Dehydroepiandrosterone (DHEA) 297, 306, 308
  adrenal cortex 298
  sulfate (DHEA-S) 306
Deiodinase 288, 290
Deiter's nucleus 328, 330
Delayed immune reaction 100
Deletion, clonal 94
Dendrites 42
Deoxycholate 250
Depth perception, visual 364
Depolarization 46, 66
  action potential 46
  permanent, muscle 56, 60
  smooth muscle 70
Derepression 8
Dermatitis, allergy 100
Dermographism 216
Desensitization 52, 278, 320
  smell sensors 346
Desmin filaments 14
Desoxycorticosterone 297
Desoxyribonucleic acid → DNA
Desoxyribose 8
Detoxication processes 160
Deuteranomaly 362
Deuteranopia 362
Dextrin, α-limit 260
DHEA → dehydroepiandrosterone
DHPR (dihydropyridine receptor) 62, 63 B, 65 D
DHT (5α-dihydrotestosterone) 308
Diabetes insipidus 166, 220
  mellitus 142, 158, 220, 232, 286
    coma 220
    osmotic diuresis 174
    type II, obesity 232
Diacylglycerol (DAG) 36, 82, 84, 276, **278**
Diacylglycerol lipase 271, 278
Diadochokinesia 330
Diapedesis 94
Diaphragm 108
Diarrhea 138, 142, 173, 260, 264, 266
  acid–base balance 138
  lactase deficiency 260
  salt and water homeostasis 175 B
Diastole, heart 192
Diastolic depolarization 194
Diathermy 50
Dicarboxylates, tubular transport 158, 160
Diencephalon 312
Diet 228
  induced thermogenesis (DIT) 230
  vegetarian 142
Differential threshold, sound, frequency 374
    intensity 374
  optical 358
  smell 346
  taste 344
Differentiation, cells 274
Diffusion 20, 210
  capacity 22
  capillaries 210
  coefficient (D) 20
    Krogh's (K) 22
  conductance 22
  distance 20
  driving force 20, 22
  equilibrium 20
  faciliated 23, 158, 260
  Fick's first law 20, 22, 120
  gas 22
  ions 22
  net 20
  non-ionic 22, 156, 178
  potential 22, 32, 44
  rate 20
  "simple" 20
  unidirectional 20
Digestion 234, 238, 254, 260
  carbohydrates 238, 260
  impaired 248
  lipids 254
  organs 234
  proteins 260
Digitalis 196
Dihydropyridine receptor (DHPR) 62, 63 B, 65 D
    heart 196
5α-Dihydrotestosteron (DHT) 308
  synthesis 296
  testes 308
1,25-dihydroxycholecaliciferol → calcitriol
Diiodotyrosin residues (DIT) 288
Dilator muscle, pupil 350
Dim-light vision 354
Diopters (dpt) 352
Dipeptidases 260
Dipeptides 158, 260
Diplopia 366
Direct bilirubin 252
Disaccharide, digestion 260
Disinhibition 346
  thalamus 328
Dissociation constant 384 f.
Distal stomach 242
  tubule 148, 162, 166, 180
Distant hearing 374
  vision 366
DIT (diet-induced thermogenesis) 230
DIT (diiodotyrosine residues) 288
Diuresis 164, 174
Diuresis (cont.)
  osmotic 174, 178
    influence on K^+ excretion 184
  salt and water homeostasis 175 B
Diuretics 174, 184, 220
  influence on Ca^{2+} reabsorption 180
    K^+ excretion 174, 184
  osmotic 174
  tubular secretion of 156, 160, 174
Diurnal rhythm 336
Divalent cation tranporter (= DCT1) 90
Divalent metal transporter (= DMT1) 90
Diving 134
  oxygen toxicity 136
DMT1 (= Divalent metal transporter) 90
DNA (desoxyribonucleic acid) 8
  double helix 8
DNAses, pancreas 248
Döderlein bacilli 304
Dominance columns, ocular 364
L-Dopa 84
Dopamine 84, 270, 271, 276, 282, 305, 328
  cerebral cortex 334
  menstrual cycle 300
  neurons 332
  receptor, striatum 328
  second messenger 276
  synthesis 84
  transmitter 328
Dopamine-β-hydroxylase 84
Dorsal root, spinal cord 324
Double helix, DNA 8
  vision 366
Down regulation, hormon receptors 30
  Na^+-phosphate symport carrier 180
Drinking 170
Driving "force" 20, 38
    pressure difference 108
Dromotropism, heart 196
D (differential)-Sensor 314, 316, 318
Dubin–Johnson syndrome 252
Duchenne muscular dystrophy 60
Duct, collecting 176
Ductus arteriosus 222
    patent 222
  venosus 222
Duodenum (→ also intestine) 236, 246, 260
  gastrin production 236
  GIP production 236
  secretin production 236

Dwarfism, T_3/T_4 deficiency 290
Dynamic work, negative 74
positive 74
Dyne, conversion into SI unit 380
Dynein 58
Dynorphin 86, 320
Dysmetria 330
Dyspnea 108
Dystrophin 60

E

E (multiple of a unit) 379
E1 → estrone
E2 → estradiol
E3 → estriol
Ear 368, 370, 372, 374
drum 370
in diving 134
Eavesdropping 374
ECF → extracellular fluid
ECL (enterochromaffin-like cells) 244
ECG (electrocardiogram) 192, 198 ff.
atrial depolarization 198
cardiac cycle 192
electrical axis 200
electrolyte disturbances 200
integral vector 198
leads 198
myocardial infarction 200
ventricular depolarization 198
repolarisation 198
Ectopic pacemaker, heart 202
Edema 174, 210
causes 210
extracellular 174, 210
intracellular 174
local 304
pulmonary 118, 120, 122, 132, 144, 174, 210
Edinger–Westphal nucleus 366
EDHF (endothelium-derived hyperpolarizing factor) 216
EDTA (ethylen-dinitrilotetraacetat), blood clotting 102
EDV (end diastolic volume) 192, 204
EEG (electroencephalogram) 334
11,12-EET (Epoxyeicosatrienoate) 216, 271
EGF (epidermal growth factor) 280
Eicosanoids 216, **271,** 274, 278
Einthoven leads (ECG) 198, 200
Ejaculate 310
Ejaculation 310
Ejaculatory center 310
Ejection fraction 192
phase, heart 192, 204
Elastase 260
Electrocardiogram → ECG
Electrochemical gradient 26
potential 32
Electrodiffusion 22, 34
Electroencephalogram → EEG
Electrolyte homeostasis 168 ff.
Electromotility, outer hair cells 372
Electrophoresis 93 B
Electrotonic transmission 48, 54 D
Embolisms 104
diving 134
Eminence, median 282
Emission, sperms 310
Emissions, evoked otoacoustic 372
Emotions 340
expression 332
limbic system 332
Emphysema 114, 118
Emptying rates, gastrointestinal tract 235, 242
Emulsification of fats 254
Encoding, information 314
End diastolic pressure 204
volume (EDV) 192, 204
systolic volume (ESV) 192, 204, 222
Endergonic reaction 38
Endings, annulospiral 318
Endocrine cells 270
gland 270
growth 274
system 268 ff.
Endocytosis 12, 28, 90, 288
receptor-mediated 12
kidney 158
thyroid gland 288
transferrin 90
Endolymph 348, 370
Endometrium 305
Endopeptidases 244, 248, 260
gastric juice 244
renal tubule 158
Endoplasmic reticulum 10, 12, 26
Endorphin 282, 320
Endosomes 12
receptors 28
transcytosis 28
Endothel(ium) 102, 168
exchange processes 210
function 18
heparin source 256
lipoprotein lipase (LPL) 256, 258
NO synthase 82
Endothelium-derived hyperpolarizing factor (EDHF) 216
Endothelin 214, 282
second messenger 278
Endothermic reaction 38
Endplate current 56
motor 56
blocking substances 56
reversal potential 56
potential (EPP) 56
Endurance limit 72
Enema 266
Energy, activating 39
basic daily 228
chemical 230
expenditure, total (TEE) 228
homeostasis 232
metabolism 38, 224, 230, 284
cortisol effect 298
need 228
production 38, 230
reserves 284
sources 228
storage 232
substrates 72, 228 ff., 256, 284
turnover 38, 228, 230
units 380
Enkephalin 52, 86, 236, 260, 328
ENS (enteric nervous system) 236
Enteroglucagon (= GLP-1) 284, 286
Enterohepatic circulation 250, 252
Enteropeptidase 248
Enthalpy 38
Entrainment, brainwaves 334
Entropy 38
Enuresis, nocturnal 338
Environment, internal 2, 78, 268
Enzyme, function 40
Ependymal cells 344
EpETrE (= Epoxyeicosatrienoates EE) 271
Epidermal growth factor (EGF) 280
Epilepsy, EEG 334
Epinephrine (= adrenalin) **84 ff.,** 160, 196, 214, 258, 270, 276, 284, 290
adrenal medulla 86
circulatory shock 220
coronary vasodilatation 212
defensive behavior 332
heart 196
influence on insulin release 284
on K^+ uptake 182
lipolysis 220
metabolic effect 285 A, 287 C
pheochromocytoma 218
production, cortisol influence 298
receptor types → adrenoceptors
second messengers → adrenoceptors

Epinephrine (= adrenalin) (cont.)
synthesis 84
tubular transport 160
vasoactivity 214
Epiphysis (= pineal gland) 336
Epiphysis (of bones), estrogens 304
testosterone 308
Epithel, function 18
Epithelium 168
Epoxyeicosatrienoates (EpETrE = EE) 271
11,12-Epoxyeicosatrienoic acid (11,12 EET) 216
EPP (endplate potential) 56
EPSP (excitatory postynaptic potential) 52, 56, 82, 322
cerebral cortex 334
early 82
late 82
peptidergic 82
Eq (equivalent), unit 381
Equilibrium organ 330, 348
nystagmus 366
concentration 32
constant (K) 40
potential 32, 44
ions 45 B
Equivalent, caloric 230
mass 381
ER → endoplasmic reticulum
Erection, genital organs 216, >310
Erg, conversion into SI unit 380
Ergocalciferol 294
Ergometry 76
Erogenous areas 310
Erythroblasts 90
Erythrocytes 88, 90
crenation 92
effect of hypertonicity 88, 100, 124, 128
fluidity 92
life span 88
maturation 88
mean corpuscular hemoglobin (MCH) 88
concentration (MCHC) 88
volume (MCV) 88
metabolism 284
pH 126
proliferation 88
viscosity 92
Erythropoiesis 90
cobalamin 90
folic acid 90
high altitude 136
inefficient 90
Erythropoietin 88, 148, 220
Escalator, cilial 110
Esophagus 234, 240, 242
ECG leads 198
Esophagus (cont.)
pleural pressure, measurement 108
sphincter 240
Essential amino acids 228
fatty acids 228
Estradiol (E_2) 296, 300, 302, **304,** 308
synthesis 296
testis 308
Estriol (E_3) 296, 302, 304, 306
Estrogens 270, 296, 300, 302, **304,** 306
actions 304
comparison 304
degradation 304
menstrual cycle 300
oral therapy 304
placenta 306
synthesis 296, 304
Estrone (E_1) 302, 304
synthesis 296
ESV (end systolic volume) 192, 204
Euler–Liljestrand mechanism → Hypoxic vasoconstriction
Euphoria, diving 134
Evans blue, indicator 168
Evaporation of water, heat loss 224
Exa- (multiple of a unit) 379
Exchange carrier, Na^+/H^+ 26 f., 162, 176 f., 278
Excitable cells 42, 44, 46
Excitatory postsynaptic potential (EPSP) 52, 56, 82, 322
Excretion (→ also kidney) 160, 176
fractional 152
Exercise 72, 76, 107, 120, 284
cardiac output 76, 74
O_2 uptake 74
respiration 74
Exergonic reaction 38
Exocrine glands 248
Exocytosis 28 f., 30, 50, 86, 288
epinephrine 86
constitutive 30
glucagon 286
salivary enzymes 238
thyroid glands 288
Exopeptidases 248
Exothermic Reaction 38
Expansion, clonal 94, 98
Expectancy potential, cortical 326
Expiration 108
maximum flow rate 118
muscle 108, 132
pressure difference, driving force 108
work 116
Expiratory curves, maximal 117
Expiratory curves, maximal (cont.)
flow, maximum 118
volume, forced 118
first second (FEV_1) 118
relative 118
Expired air 107 A
Exponent, calculation with 386 f.
Export protein, synthesis 12
External auditory canal 370
intercostal muscle 108
Extracellular fluid (ECF) (→ also H_2O) 34, 93 C, 148, 152, 168
indicators 168
ions 93 C
Extrafusal fibers, muscle 318
Extrasystole 202
Eye (→ also visual, retina and opt…), accommodation 350, 352
adaptation to light 358
blind spot 354
color vision 362
dark adaptation 362
far point 350
focal lenght 352
point 352
intraocular pressure 352
light rays, physics 352
movements 366
muscles, external 366
near point 350
nodal point 350
optical axis 352
photochemistry 354
postural motor control 330
reflex movements 348
refraction 352
structure 350
Eyelids 365

F

F (Faraday constant) 22, 32
F (fluorine) 228
f (submultiple of a unit) 379
°F, conversion to °C 381
Facilitated diffusion 158
Fåhraeus–Lindqvist effect 92
Fahrenheit, conversion 381
Fallopian tube 310
Falsetto 352
Fanconi–Debré-Toni syndrome 158
Faraday constant (F) 22, 32
Far point, vision 350, 352
Farsightedness 352
Fas (= CD95) 98
ligand 98
Fascicular zone, adrenal cortex 296
Fasting 284
T3 synthesis 290

Fat 230, 254, 258, 284
absorption, intestine 254
brown 226, 290
caloric equivalent 230
cells 258
chemical structure 229 B
daily intake 254
depots 232, 284
digestion 238, **254**
phases 255 B
emulsification 242, 254
energy substrate 230
metabolism, insulin 286
Fatigue 72, 76
Fat-soluble vitamins 254, 262
Fattened animals 286
Fatty acids 212, 254, 256, 264, 284, 286
cyclooxygenase 271
essential 228
free (FFA) 284
carrier 254
glucagon action 286
lipoprotein lipase 256
myocard metabolism 212
sources 259 D
storage 259 D
target sites 258
transport in blood 256
uptake in cells 256
supply of energy 72
liver 256, 286
Fe (iron) 88, 90, 92, 128, 228, 264
absorption in intestine 90
carrier, intestinal mucosa 90
deficiency 90
functional 90
hemoglobin 128
degradation 252
intake 90, 228
metabolism 90
overload 90
poisoning 90
pool 90
recycling 90
storage 90
transferrin 90
transport, plasma 90
FE (fractional excretion) 152
Feces 252, 264, 266
Fechner's law 360
Feedback, control, hormones 274
negative 4, 274, 288, 302, 308, 320
TSH secretion 290
neuroendocrine 274
positive 274, 302, 306
tubuloglomerular (TGF) 174, 186
Feet, conversion into SI unit 378
Femto- (submultiple of a unit) 379
Ferrireductase 90
Ferritin 90
Ferroportin 1 (= IREG1) 90
Fertility 308
Fertilization 310
Fetal circulation 222
zone, adrenal cortex 306
Fetoplacental unit 306
Fetus 222
O_2 supply 222
FEV_1 (forced expiratory volume, first second) 118
Fever 100, 226, 290
FF (filtration fraction) 24, 152, 395
FGF (fibroblast growth factor) 280
Fiber → nerve, neuron, motor neuron and muscle
Fibers, diet 266
Fibrillation, atrial 202
ventricular 202
Fibrin 102, 104
Fibrinogen 102, 104
Fibrinolysis 102, 104
Fibrinopeptides 104
Fibrin-stabilizing factor 102, 104
Fibroblast 94
interferons, release 96
migration 30
Fibroblast growth factor (FGF) 280
Fibronectin 102
Fick's first law of diffusion 20, 120, 394
Fick's principle 106, 130, 395
kidney 150
Field, receptive 316, 360
visual 364
Fila olfactoria 346
Filament sliding, smooth muscle 71 B
striated muscle 62
Filling phase, heart 192
pressure, receptors for, heart 216
Filtration 24
capillaries 210
coefficient 210
equilibrium 150
fraction, glomerular (FF) 24, 152, 395
glomerular 148
pressure, effective 210
kidney 152
shock 220
First messenger → hormones
Fitzgerald factor 102
Fixed acids 176
Fletcher factor 102
Flexion reflex 322
Flexor muscles 330
withdrawal reflex 322
Floccunodular lobe 328
Flow rate, blood 190
unit 380
resistance, blood circulation 190
velocity 190
unit 380
Fluid compartments 168
measurement 168
Fluid exchange, capillaries 210
extracellular 168
intracellular 92, 168
ounce, conversion into SI unit 380
Fluidity of erythrocytes 92
Fluorine (F) 228
Flutter, atrial 202
Folic acid 90, 228, 262
absorption, intestine 262
daily requirement 262
deficiencies 90
storage 262
Follicle, dominant 300, 302, 305
graafian 300
primordial 300
progesteron synthesis 305
stimulating hormone → follitropin
thyroid gland 288
Follicle-stimulating hormone-releasing hormone → gonadoliberin
Follicular phase 300, 302
Follitropin (FSH) 271, **300,** 302, 308
man 308
menstrual cycle 300
peak 302
receptor density 302
second messenger 276
secretion, activin 308
DHT 308
estrogens 302, 308
inhibin 302, 308
neuropeptid Y 302
norepinephrine 302
progesterone 302
pulsatile 300
testosterone 308
Food deprivation, energy reserve 284
Foot, conversion into SI unit 378
Foramen ovale 222
patent 222
Force, unit 380
Forced expiratory volume (FEV) 118
vital capacity 118
Force–velocity curve, muscle 68
Forgetfulness of words 376
Formant 376
Formatia reticularis 240, 324, 330, 346

Formatia reticularis (cont.)
vomiting center 240
Formic acid, non-ionic diffusion 22
Forskolin 278
Fovea centralis, retina 350, 354, 364
Fraction, respiration gas 106
units 382
Fractional concentration → fraction
excretion (FE) 152, 154
Frank–Starling mechanism, heart 68, 204, **206,** 218, 220
FRC (functional residual capacity) 112, 114, 116
Free enthalpy 38
fatty acids 212, 254, 256
water, urine 174
Freezing point, H_2O 381
Frequency, fundamental 368, 376
inotropism 196, 206
unit 380
Fructose, intestinal absorption 260
renal reabsoption 158
FSF (fibrin-stabilizing factor) 102
FSH → follitropin
/LH-RH → gonadoliberin
Fuel value, physiological 230
Functional minimum, protein intake 228
residual capacity (FRC) 112, 114, 116
Fundamental frequency, vowels 376
Fundus, stomach 242
Fungi, defense against 94
Funicular myelosis 262
Furosemide 174
Fusimotor set 318

G

ΔG (free enthalphy) 38
G (multiple of a unit) 379
g (membrane conductance) 32
GABA (γ-aminobutyric acid) 34, 52, 286, 322, 328 f.
cerebral cortex 334
Gn-RH secretion 302
receptors 52, 55 F, 322
second messenger 55 F, 276
Galactorrhea 305
Galactose, intestinal absorption 260
renal reabsorption 158
Galanin 52, 86
insulin secretion 284
Gall bladder 250
stones 250
posthepatic jaundice 252
Gallon, conversion into SI unit 380
Ganglia, vegetative 78, 83 A
neurotransmission 83 A
Ganglion cells, retina 350, 360, 364
vestibular 348
GAP (GTPase-activating protein) 356
Gap junction 18, 58
astrocytes 344
heart muscle 194
regulation 37 A
smooth muscle 70
uterus 306
Gas constant 20, 24, 32
equation, alveolar 120, 136, 395
ideal 112
exchange 106, 120
impairment 120
Gases 106, 266
Gastric (→ also stomach) acid 244
function, glucocorticoid effect 298
inhibitory peptide (obsolete name for GIP) 242
juice 240, 244, 260
pH 244
reflux 240
mucosa, protection 244
secretion 244
ulcers 244
Gastrin 236, 242, 244
esophagus 240
insulin secretion 284
second messenger 278
stomach 236, 242
Gastrin-releasing peptide → GRP
Gastrocolic reflex 266
Gastrointestinal (GI) tract 78, **234 ff.**
bacteria 242, 266
blood flow 188, 234
hormones 236
interdigestive phase 242
neuronal and hormonal integration 236
neurotransmitters 236
passage time 234, 235 A
Gauer–Henry reflex 172
GCAP (guanylyl cyclase-activating protein) 356
G cells, antrum 244
GDNF (glial cell line-derived neurotropic factor) 344
GDP (guanosine diphosphate) 276, 278
transducin 354
Gene expression 8
regulation 12
Genetic code 8
Genital tract 216, 300, 308
female 300
male 308
innervation 79 ff.
Germ cell 308
Gestagens 305
GFR → glomerular filtration
GH (growth hormone) → somatotropin
GH-IH → somastotatin
GH-RH → somatoliberin
GI → gastrointestinal
Gibbs–Donnan distribution 44
Gibbs-Helmholtz equation 38
Giga- (multiple of a unit) 379
GIP (glucose-dependent insulinotropic peptide) 236, 242
esophagus 240
insulin seretion 284
stomach 244
Glands, Brunner 246
bulbo-urethral 311
endocrine 270
exocrine 248
gastrointestinal 234 ff., 246, 264
parathyroid 238
pineal 336
salivary 216
sublingual 206, 238
submandibular 238
sweat 224
Glasses 352
Glaucoma 350
Glia 344
Glial cell line-derived neurotropic factor (GDNF) 344
Glioma 344
Globulin 92
cortisol-binding 298
testosterone-binding 309
thyroxin-binding 290
Globus pallidus 312
Glomera aortica 132
carotica 132
Glomerular filter 148
zone, adrenal cortex 296, 298
Glomeruli olfactorii 346
Glomerulotubular balance 166
Glomerulus, renal 148
filtration 154, 156
pressure 150
rate (GFR) 152
GLP-1 (glucagon-like peptide = enteroglucagon) 284, 286
Glucagon 232, 258, 274, 276, 284, **286,** 290
actions 283 A, 286, 287 C
gluconeogenesis 286
influence on insulin release 284

Glucagon (cont.)
lipolysis 258
second messenger 276
secretion 286
Glucagon-like peptide (GLP-1) 232, 284, 286
Glucocorticoids (→ also cortisol) 298
receptors 10, 298
synthesis 296, 298
Gluconeogenesis 72, 284, 286
renal 148
Glucose 72, 154 ff., 174, 212, 230, 260, 286
aerobic oxidation 72, 284
anaerobic degradation 142, 284
blood 284
caloric equivalent 230
value 230
carriers 22, 26, 156, 158, 260, 264, 286
chemosensors 284
co-transport with Na^+ 264
deficiency 244
energy substrate 72, 212
glucagon secretion 286
intestinal absorption 260, 264
metabolism 72, 284, 298
influence of cyclic AMP 276
muscle 72
myocard 212
osmotic diuresis 174
plasma concentration 284
pregnancy 306
regulation 274
production 72, 148, 284, 286
renal reabsorption 156, 158
storage 284
uptake 86
Glucose-dependent insulinotropic peptide (GIP) 236
Glucose-6-phosphate 41, 72
Glucosuria 158, 174, 286
Glucuronic acid 160, 252, 296
conjugates, carrier 252
steroid hormones 296
Glucuronides 156, 160
Glucuronyl transferase 252
GLUT (Glucose transporter) 23, 158, 260, 286
GLUT2 158, 260
GLUT4 286
GLUT5 158, 260
Glutamate 34, 52, 176, 260, 276
AMPA-receptors 55 F, 340
cochlear transmitter 372
astrocytes 344
dehydrogenase, renal 178
genetic code 8
intestinal absorption 260
long-term potentiation 340
Glutamate (cont.)
NH_4^+ excretion 180
NMDA receptor 52, 55 F, 340
receptor types 55 F
second messenger 55 F, 276, 278
taste quality 344
transmitter function 328, 340
hair cells 348
photosensors 356, 360
Glutaminase, kidney 178
Glutamine 178
astrocytes 344
formation, hepatic 180
gluconeogenesis 284
renal metabolism 178
Glutathione 158, 160, 288
conjugates 252
secretion 160
conjugation 160, 252
S-transferase 252
Glycerol 284, 286
Glycine 34, 52, 250, 257
conjugation 252
receptor 52, 55 F
second messenger 55 F
transmitter function 322
Glycocalyces 12, 14
Glycogen 58, 72, 248, 284
metabolism 284
phosphorylase 276
skeletal muscle 58, 73 B
synthase 276
synthesis 276
Glycogenesis 284, 286
Glycogenolysis 72, 85, 276, 284, 286
STH 282
Glycolipids 14
Glycolysis 142, 284
anaerobic 72
muscle 72
Glycoprotein 276, 288
hormones 276
Glycosylation 12
GMP, cyclic 270, 276, 280, 354, 356
photosensors 356
GnRH → gonadoliberin
GNRP (guanine nucleotide-releasing protein) 30
Goal-directed movement 330
Goblet cells 246, 266
Goiter 274, 288, 290
Goldberger leads, ECG 198, 200
Golgi apparatus 12, 288
cells, cerebellum 330
tendon organs 318
Gonadoliberin (GnRH) 232, 271, 282, 300, 302, 308
menstrual cycle 300, 302
Gonadotropic hormone-releasing hormone → gonadoliberin
Gonatropin-releasing hormone (GnRH) → gonadoliberin
Gonads 296, 308
G proteins 37 C1, 55 F, 84, 276, 278, 344
adrenoceptors 84, 87 B
subunits 276
types, G_i 36, 82, 84, 276
G_o 36, 278
G_{olf} 346
G_q 82, 278
G_s 84, 276, 346, 354
G_t (transducin) 354
Graafian follicle 300
Gradient, electrochemical 26, 32, 44
Granular cells, cerebellum 330, 346
olfactory bulb 346
Granular mesangial cells 186
Granules, secretory 270
Granulocytes 88, 104
basophilic 100, 256
eosinophilic 94
neutrophilic 30, 94
allergy 100
immune defense 94
migration 30
production 94
Granulosa cells 302
Granzyme B 98
Graves' diseases 290
Grey matter, spinal cord 312
GRH → somatoliberin
Growth 284, 286, 290, 308, 332
factors 88, 234, 270, 280, 282, 344
nerval 344
receptor types 270, 280
hormone → somatotropin
release-inhibiting hormone (or factor) → somatostatin
releasing factor (or hormone) → somatoliberin
influence of thyroid hormones 290
insulin 286
T_3/T_4 290
GRP (gastrin-releasing peptide) 86, 232, 236, 242, 244
second messenger 278
stomach 244
GSC (glomerular sieving coefficient) 154
GTP (guanosine triphosphate) 276, 278, 280
transducin 354
GTPase 278
transducin 356
GTPase-activating protein (GAP) 356
Guanine 8

Guanine nucleotide-releasing protein (GNRP) 30
Guanosine
  diphosphate → GDP
  monophosphate, cyclic → GMP, cyclic
  triphosphate → GTP
Guanosylmonophosphate → GMP
Guanylyl cyclase-activating protein (GCAP) 356
Guanylyl cyclase, coronary arteries 212
  cytoplasmatic 280
  retina 356
α-gustducin 344
Gut 236 ff.
  absorption, amino acids 264
  Ca^{2+} 264
  Cl^- 264
    mechanisms 265 D
  glucose 264
  Mg^{2+} 264
  Na^+ 264
    mechanisms 265 D
  phosphate 264
  H_2O 264
    mechanism 265 B
  bacteria 234, 252, 266
  Brunner's glands 246
  calcitriol effect 294
  CCK production 236
  defecation 266
  gases 266
  motility 246
  structure 246
Gynecomastia 296
Gyrus, angularis 376
  cingulate 312, 332
  parahippocampal 332
  postcentral 324, 344

H

h (multiple of a unit) 379
H zone, muscle 62
H^+ 138, 140, 142, 144, 244
  buffering 138, 140, 142, 144
  chemosensors 132
  concentration, blood 138
    normal range 142
  excretion 176
    renal 142
  gradient 158
  Na^+ antiport 26 ff., 161 C, 162, 176 ff.
  secretion, renal 176
  symport 158, 260
  uniporter (UCP) 224, 232
H^+-K^+-ATPase 26 f., 28, 176, 184, 244
  collecting duct 176, 184
H^+-K^+-ATPase (cont.)
  colon 264
  production 176
  renal excretion 176
  secretion, gastric 244
  renal tubular 176
H^+-ATPase 14, 26, 176
  lysosomes 14
H^+-iron cotransport 90
H^+-peptide cotransport 26 ff., 158, 260
H^+-phosphate cotransport 17 B2
H^+-pyruvate cotransport 17 B2
H_2 (hydrogen), large intestine 266
Habituation 340
Hageman factor 102
Hagen–Poiseuille's equation 190, 396
Hair cells 58, 348
  inner 370
  outer 370, 374
    electromotility 372
  vestibular ganglion 348
  follicle sensors 316
Haldane effect 124, 126
Hamburg shift 124
Haptenes 100
Haptoglobin 90
Haustration 266
Hay fever 100
hBSEP (human bile salt export pump) 250
H (histamine) cells, stomach 244
hCG (human chorionic gonadotropin) 306
hCL (human placental lactogen) 306
HCl (hydrochloric acid) 142, 240
  gastric 240, 244, 260
  production in metabolism 176
HCO_3^- (bicarbonate) 124, 126, 140, 146, 238, 264
  blood 142
    concentration, actual 142, 146
      measurement 146
    normal range 142, 146
    standard 142
      measurement 146
  buffer system 138
  /Cl^- antiport 124
  /CO_2 buffer 140, 144
  CO_2 transport, blood 124
  erythrocytes 124
  excretion 138, 142, 144, 174, 178
  high altitude 136
  gastric mucosa 244
  intestinal absorption 264
  loss, diarrhea 264
  plasma 142, 146
  production, amino acid metabolism 178
HCO_3^- (bicarbonate) (cont.)
  renal 145 B2
  renal reabsorption 156, 176
  saliva 238
  secretion 244, 248
    bile ducts 250
    pancreas 248
    salivary glands 238
  stomach 244
  titration curve 147
HCP1 (= Heme carrier protein 1) 90
hCS (human chorionic somatotropin) 306
HDL (high density lipoproteins) 256, 258
  estrogen effect 304
Head's reflex 132
Head's zones 320
Hearing (→ also sound) 368 ff.
  audibility limit 368
  auditory cortex 374
    pathway 374, 376
  binaural 374
  cochlear amplification 372, 374
  direction 374
    threshold 374
  loss 370, 372
  sensors 370 ff.
  thresholds 368, 372, 374
Heart (→ also cardiac and myocard) 86, 188, 212
  action potential 194, 195 A
  afterload 204, 206
  all-or-none contraction 68, 194
  arrhythmias 182
  atrial contraction 192
    flutter 202
    fibrillation 202
    septum defect 222
    tachycardia 202
  atrioventricular block 202
    node 194
    valves 192
  automaticity 194
  autonomic nervous system 196
  beats → heart rate
  bundle of His 194
  cholinergic transmission 83 B
  conduction 194, 196, 202
    disturbances 202
    system 194
    velocity 197 C
  contractility 196, 206
    influences 196, 298
  coronary blood flow 188, 192, 214, 212
    vessels 212, 214
  cycle 192
  diastolic time 192
  ejection fraction 192
    phase 204

Heart (cont.)
electric activity, action potential 58, 194
arrhythmias 182, 202
AV block 202
AV rhythm 194
bundle branch block 202
cholinoceptors 82
chronotropism 196
dromotropism 196
ECG 198
ectopic 202
electrolyte disturbances 200
extrasystoles 202
impulse generation 194
disturbances 202
inotropism 196, 206
pacemaker 194
diastolic depolarization 194
ectopic 194
potential 194
reentry 196, 202
spreading time 197 C
vulnerable phase 195 A, 202
electrical axis 200
end diastolic volume (EDV) 192, 204
systolic volume (ESV) 192, 204
influence of aortic pressure 206
energy sources 212
exercise 74
failure 210, 218, 220
cause of edema 210
salt and water homeostasis 175 E
filling phase 204
Frank–Starling mechanism 68
frequency → heart rate
glycosides 196
influence of Ca^{2+} 196
inotropism 196, 206
isovolumetric contraction 192, 204
muscle 46, 58, 68, 194 ff.
action potential 46, 59 A
adrenoceptors 216
blood flow 188
Ca^{2+}-ATPase 196
Ca^{2+} channels 196
Ca^{2+} concentration, cytosolic 196
contraction 59 A
isovolumetric 192
velocity 206
dihydro-pyridine receptors 196
ECG 198
Heart (cont.)
electromechanical coupling 196
frequency inotropism 206
impulse generation 194
infarction 220
ECG 200
influence of Ca^{2+} 196
contractility 196
inotropism 196, 206
ischemia, ECG 200
isotonic peaks 205
isovolumetric peaks 205
metabolism 212
Na^+/Ca^{2+} exchange carrier 196
Na^+-K^+-ATPase 196
O_2 supply 212
tension-time index 212
mechanics 204
metabolic activity 212
O_2 supply 212
output, cardiac (CO) 74, 106, 122, 188, 190, 220
fetus 222
high altitude 136
maximum 77 C
endurance, athletes 77 C
physical work 74
shock 220
power 204
preload 204, 206
pressure–volume diagram 68
relation 204
work 204
Purkinje fibers 194
rate 74, 136, 188, 196, 290
AV block 202
blood pressure regulation 4, 220
fetus 222
high altitude 136
influence of Ca^{2+} influx 196
maximum 77 C
endurance, athlet 77 C
normal 188
physical work 74
shock 220
T_3/T_4 effect 290
reentry 196
reflexes 218
resting pressure–volume curve 204
semilunar valves 192
sinoatrial node 194
rhythmicity 194
threshold potential 194
sounds 192, 193 A
stroke volume 188, 192, 204, 206
maximum 77 C
Heart (cont.)
endurance, athlet 77 C
measurement 106
regulation 206
training 76
ventricles, stretch sensors 216
ventricular diastolic volume 192
pressure 192
curve 193 A
work diagram 204
volume load 206
weight, endurance athlet 77 C
work 204
Heat 224, 230, 290
countercurrent exchange 164
flow, external 224
internal 224
loss by evaporation of water 224
of maintenance 74
production 224, 230, 290
energy metabolism 230
influence of thyroid hormones 290
sensors (→ also warm sensors) 316
unit 381
Heat shock proteins (HSP) 280
Hecto- (multiple of a unit) 379
Helicine arteries 310
Helicotrema 370, 372
Helium 114
Helium dilution, measurement of residual volume 114
Helper cells, T- 98
Hematocrit 88, 150, 168
blood viscosity 92
high altitude 136
Hematopoiesis 88
testosterone 308
Heme 88, 128
Fe(II) 90
oxygenase 90
Heme carrier protein 1 (= HCP1) 90
Hemeralopia → night blindness
Hemochromatosis 90
Hemoglobin **88**, 90, 92, 124, 126, **128**, 138, 140, 146, 252
blood puffer 124, 128, 138, 140, 146
carbamate 124
concentration, blood 128
degradation 252
fetal 128
synthesis 10, 90
types 128
Hemolysis 88, 100, 252
fetus 100
prehepatic jaundice 252
Hemopexin 90

Hemophilia 104
Hemoproteins 252
Hemorrhage 220
Hemorrhagic diatheses 104
Hemosiderin 90
Hemostasis 102 ff.
Henderson–Hasselbalch equation 138, 139 A, 140, 146, 385, 395
Henry-Gauer reflex 172, 220
Heparin 104, 256
Hepatic → liver
Hepatocyte growth factor (HGF) 280
Hepcidin 90
Hephaestin 90
Hering–Breuer reflex 132
Hering's opponent color theory 360
Hertz, unit 368, 380
HGF (hepatocyte growth factor) 280
hGH → chorionic growth hormone
HLA protein (human leukocyte antigen) 96, 98
High altitude 130, 132
  respiration 136
  erythropoietin secretion 88
  hypoxic hypoxia 130
  density lipoproteins (HDL) 258
  pressure system 188
Hippocampus 332, 340
Hippurate, transcellular secretion, renal 156
Histamine 70, 100, 160, 210, 214, 216, 220, 236, 244, 271, 276, 278
  allergy 100
  cerebral cortex 334
  coronary vasodilatation 212
  gastrointestinal tract 236
  gastric juice secretion 244
  influence on vessel permeability 216
  receptors, types 55 F
    H_1 – 214, 278
    H_2- 244, 276
  second messenger 276
  shock 220
  tubular transport 160
  vasodilator 216
Histidine 176, 228
3-HMG-CoA-reductase 258
HMK (high-molecular-weight kininogen) 102
hNaDC-1 (human Na^+-dicarboxylate transporter) 160
hNBC (human Na^+-bicarbonate cotransporter) 162, 176
H_2O (→ also extracellular fluid and body fluid), balance 148, 166, **168**
H_2O (cont.)
  disturbances 174, 175 E
  clearance 164
  concentration 24
  daily intake 168, 264
  deficit 170, 182
  diffusion 24
  diuresis 164, 166, 174
    maximum 166
    urea excretion 166
  excess 172
  excretion, feces 264
    renal → kidney, excretion
  flow, osmotic 24
  free, urine 164, 174
  homeostasis 168
  intake 168
  intestinal absorption 264
  intoxication 172
  losses 170
  partial pressure 106
  permeability 210
  reabsorption 154, 164
  renal handling 166, 170
  regulation 170
  transport 24
  turnover 168
Hoffmann's reflex 318
Homeostasis 2, 4, 214, 268
Homeothermy 224
Horizontal cells, retina 350, 360
Hormone(s) 236, 268, 270
  abbreviations 270, 271
  adrenocorticotropic (= ACTH) 271
  aglandotropic 268, 282
  anabolic 308
  autocrine 268
  binding proteins 270
  catecholamines 276
  chemical structure 270
  down regulation 30
  endocrine 268, 270
  feedback mechanism 274
  femal sex 296, 300, 304
  follicle-stimulating (= FSH) 271
  gastrointestinal 236
  gland, atrophy 274
    hypertrophy 274
    influence of hormonal medication 274
  glandotropic 268, 271, 282
  glycoprotein 276, 270
  hierarchy 270
  hypothalamic 270, 282
  lactogenic 271
  lipophilic 270
  male sex 308
  mammotropic 271
  medication 274
  α-melanocyte-stimulating hormone (α-MSH) 271
Hormone(s) (cont.)
  menstrual cycle 302
  natriuretic 172
  nomenclature 271
  pancreatic 284
  paracrine 268, 270
  peptide 270, 276
    placenta 306
  pregnancy 306
  principle functions 274
  receptors 268, 270, 276 ff.
  second messengers 276 ff.
  steroid 250, 270
    placenta 306
  therapeutic administration 274
  thyroid 288
    stimulating (TSH) 271
  tissue 270
  transport, blood 270
  types 270
Horopter 366
Horse power (hp), metric, unit 380
5-HPETE (= 5-hydroperoxyeicosatetraenoate) 271
hPL (human placental lactogen) 306
H_2SO_4 (sulfuric acid) production 142, 176
HSP (heat shock protein) 280
H_1(istamine)-receptor, second messenger 55 F, 214, 278
H_2-receptor, second messenger 55 F, 276
Hüfner number 128
Human chorionic gonadotropin (hCG, HCG) 306
  somatotropin (hCS) 306
  leukocyte-associated antigen (HLA) 96
  Na^+-bicarbonate cotransporter (hNBC) 162, 176
  placental lactogen (hPL, HPL) 306
Humidity, air 224, 226
Humor, aqueous 350
Hunger 142
  edema 210
  energy reserves 284
  metabolic effect 285 A
Hydraulic filter, arteries 190
Hydrocarbon continuum 254
Hydrocephalus 312
Hydrochloric acid → HCl
Hydrocortisone → cortisol
Hydrogen ion → H^+ and pH
  peroxide 94
β-Hydroxybutyrate 142
1α-Hydroxylase, calcitriol synthesis 294
11-Hydroxylase
  adrenal cortex 296

17-Hydroxylase
adrenal cortex 296
21-Hydroxylase
adrenal cortex 296
24-Hydroxylase, calcidiol 294
17β-Hydroxysteroid dehydrogenase 302
11β-Hydroxysteroid oxidoreductase 184, 298
Hyperalgesia 320
Hyperaldosteronism 184, 240
Hyperaminoaciduria 158
Hyperbicarbonaturia, osmotic diuresis 174
Hypercalcemia 180, 200, 292, 294
ECG 200
renal phosphate reabsorption 180
Hypercapnia 144
Hypercholesterolemia 258
Hypercolumns, cerebral cortex 364
Hyperemesis gravidarum 240
Hyperemia, reactive 214
Hyperglycemia 286
osmotic diuresis 174
Hyperkalemia 62, 142, 182 ff., 200
ECG 200
Hyperlipoproteinemia 258
Hypermagnesiemia 180
Hyperopia 352
Hyperosmolality, extracellular fluid 174
Hyperoxia 136
Hyperparathyroidism 294
Hyperpnea 108
Hyperpolarization, action potential 46
afterpotential 46
photo sensors 360
Hyperprolactinemia 305
Hyperreflexia 322
Hypersensitivity, delayed type 100
immediate type 100
Hypertension 186, 208, **218**
renal 186, 218
resistance 218
Hyperthermia, malignant 62
Hyperthyreoidism 290
Hypertrophy, compensatory 274
Hyperventilation 108, 120, 136, 144, 292
diving 134
high altitude 136
H_2O losses 168
non-respiratory acidosis 142
salt and water homeostasis 175 E
Hypervitaminosis 228
Hypervolemia 180
Hypocalcemia 180, 200, 292, 294
ECG 200
renal phosphate reabsorption 180
Hypocapnia 144
Hypoglycemia 86, 286
glucagon secretion 286
Hypokalemia 174, 200, 264
diarrhea 264
ECG 200
vomiting 240
Hyponatremia 172
Hypoparathyroidism 292, 294
Hypophosphatemia 292, 294
Hypopnea 108
Hypotension 208
orthostatic 184
Hypothalamus 78, 134, 170, 226, 232, 268, 270, 282, 302, 312, **332,** 364, 365
afferents 332
angiotensin II 186
body weight 232
function 268
hormones, regulation 270, 282
limbic system 346
nuclei, arcuate 232
dorsomedial 232
lateral 232
paraventricular 226
magnocellular 282
ventromedial 226
osmosensors 170
smell 346
somatostatin secretion 288
testosterone effect 308
thermoregulation 224, 226
TRH secretion 288
Hypothyreosis 290, 305
Hypoventilation 108, 144
Hypovitaminosis 228
Hypovolemia 220
chronic vomiting 240
shock 220
Hypoxia **130,** 136, 142
autoregulation 212
brain 188
fetus 222
vasoconstriction 122, 214, 222
Hypoxic vasoconstriction, lung 122
Hz, unit 380

I

I band, muscle 62
ICAM (intercellular adhesion molecule) 96
ICF → intracellular fluid
ICSH (= LH) → lutropin
Icterus 252
IDDM (insulin-dependent diabetes mellitus) 286
IDL (intermediate-density lipoproteins) 256, 258
IEL (intraepithelial lymphocytes) 234
IgA (immunoglobulin A) 98, 234, 238, 350
IgE (immunoglobulin E) 93, 98, 100
IGF-1 (insulinlike growth factor) 280, 282
IgG (immunoglobulin G) 93, 98
IgM (immunoglobulin M) 93, 98, 100
IL → Interleukin
Ileum (→ also intestine) 234, 246
bile salt reabsorption 250
cobalamin absorption 262
Immune defense 94 ff., 234, 246
antigen presentation 96
cellular 94, 234
gastrointestinal 234, 246
specific 98
cellular 96
humoral 98
unspecific 94
response, delayed 96
secondary antigen contact 100
Immunity 94
nonspecific 94
specific 98
Immunization 100
active 94
passive 94
Immunoglobulins (Ig) 93 f., 94, 98, 234
class switching 98
concentration, serum 93 D
IgA 98, 234, 350
saliva 238
IgE 93, 98, 100
IgG 93, 98
IgM 93, 98
AB0 system 100
function 94
placental barrier 92
receptors 96
infections 94
Immunologic tolerance, central 94
peripheral 98
Immunological memory 94
Immunosuppression 98
Impedance matching, middle-ear 370
Implantation of fertilized ovum 300
Impotence 305
Inch, conversion into SI unit 378
Incus 370

Indicator dillution technique 168
Indifference point, hydrostatic 206
Indirect bilirubin 252
Indoor climate 226
Induction, hormon-dependent 280
Infarction, myocardial 200
Inflammation 96, 100, 271, 320
  neurogenic 320
Information 314
  encoding 314
  storage 340
  unit 314
Inhibin 302, 308
  FSH secretion 308
  menstrual cycle 300
Inhibition, antagonistic 322
  autogenic 318
  competitive 28, 56
  descending 320
  feed-forward 322
  lateral 314, 374
    acoustic pathway 374
  postsynaptic 322
  presynaptic 322
  recurrent 318, 322
Inhibitory postsynaptic potential (IPSP) 52
Inner ear 370 ff.
Inositol-1,4,5-trisphosphate (IP_3) 82, 84, 270, 276, 278
Inotropism, heart muscle 196, 206
Inspiration 108, 110, 206
  pressure differences, driving force 108
  work 116
Inspiratory pressure, maximum 116
Inspired air, composition 107 A
Instinctive behavior, limbic system 332
Insulin 182, 232, 256 ff., 258, 270, 274 ff., 276, **284ff,** 286, 290
  anabolic effects 286
  deficiency, diabetes 286
  degradation 284
  effects 182, 285 A, 286, 287 C
  half-life 284
  K^+ homeostasis 182
  lipoproteinlipase 256
  lipolysis 258
  overdose 220
  receptor 270, 280
  regulation of secretion 284
  secretion 284
    amino acids 284
    β_2-adrenoceptors 84
    GIP 236
    inhibition 332
  synthesis 284
Insulin-like growth factors (IGFs) 280, 282
Insulin receptor substrate-1 (IRS-1) 280, 286
Integration of body functions 268, 312
Intention tremor 330
Intercalated cells, tubule 176, 184
Intercellular adhesion molecule (ICAM) 96
Intercostal muscles 108
Intercourse 310
Interdigestive phase 242
  motility 236
Interferon (IFN) 95 f.
  IFNγ 95, 98
Interleukin (IL) 94, 226, 234
  IL1 298
  IL2 98, 298
  IL4 98
  IL5 98
  IL6 90, 98
  IL8 94
Intermediate filaments 14
  type, heart axis 200
Internal clock 242, 336
  heat flow 224, 226
  intercostal muscles 108
  milieu 268
  tissue respiration 130
Interneuron 318, 322, 326
  inhibitory 322
  stimulatory 322
Interstice 45 B, 92, 93 C, 168
Interstitial cell-stimulating hormone (ICSH) → lutropin
  fluid 92, 93 C, 168
Internode region 48
Intestinal absorption (→ also absorption) 246 ff.
    amino acids 260
    Ca^{2+} 264, 294
    electrolytes 264
    glucose 260
    vitamins 262
    water 264
  bacteria 266
  blood flow 234
  glands 246, 264
  lymph 234, 256
  movements 246
  neurons 246
  phase in gastric secretion 244
Intestine 234
  Cl^- secretion 265
  defense mechanism 234
  lymphatics 234
  mucosal surface 246
  small 242
    structure 246
  passage time 234
Intracellular fluid 168
    composition 92
Intracellular fluid (cont.)
    ions 93 C
Intraesophageal leads (ECG) 198
Intrafusal fibers, muscle 318
Intrapleural pressure 108
Intrapulmonic pressure 108
Intrathoracic pressure 108
Intrinsic factor 262
  cobalamin deficiency 90
  gastric juice 244
Intron 8
Inulin, indicator for extracellular space 168
  kidney, clearance 152, 154
5-iodinase 288
Iodine/Iodide, butanol-extractable (BEI) 288 ff.
  daily requirement 228, 290
Ion channels 32, 34
    control 34, 278
      with ligands 34, 55 F
  diffusion 22
  open-probability 34, 46, 50
  pump (ATPases) 26
Ionic conductance 32, 381
  current 32, 381
Ions (→ also individual ions) 381
  body fluid 93 C
  concentrations 45 B
IP_3 (inositol-1,4,5-trisphophate) 82, 276, 278
  IP_3 receptor-associated cGMP kinase substrate (IRAG) 280
IPPV (intermittant positive pressure ventilation) 110
IPSP (inhibitory postsynaptic potential) 52
  cerebral cortex 334
  peptidergic 82
IRAG (= IP_3 receptor-associated cGMP kinase substrate) 280
IREG1 (= Ferroportin 1) 90
Iris 350
Iron (→ also Fe)
Iron lung 110
IRS-1 (insulin receptor substrate-1) 280
Ischemia 130, 200
Islets of Langerhans 284
Isoleucin 228
Isomaltase 260
Isophones 368
Isoprenaline 84, 87 B
Isotonic peak curve 204
Isovolumetric contraction, heart 192
  relaxation, heart 192
      work diagram 205
  peak curve 204
IP_3 (inositol-1,4,5-trisphosphate) 276, 278
  receptor-associated cGMP kinase substrate 280

J

J (Joule), unit 300, 380
JAM (junction adhesion molecule) 18
Jaundice 252
Jejunum (→ also intestine) 236, 246
Jet lag 336
JGA (juxtaglomerular apparatus) 174, 186
Joint position, information on 318
Joule (J), unit 300, 380
J sensors 132
Junctions, tight 154
Juxtaglomerular apparatus (JGA) 174, 186

K

k (multiple of a unit) 379
K (dissociation constant) 384 f.
K (Kelvin), unit 381
K^+, absorption 182
  balance 182
  in intestine 264
  adaptation 184
  balance 184
    effect of aldosterone 184
  cellular uptake, influences on 182
  channels, activation 32 ff.
    adrenoceptors 84
      G-proteins 278
    ATP-controlled 284
    collecting duct 182
    conductance, action potential 44, 46
    $GABA_B$ receptors 322
    hair cells 348
    pacemaker cells, heart 194
    resting potential 44
    voltage-gated 46
    renal 162, 182
  concentration, intracellular 26, 44
  contracture, skeletal muscle 66
  deficiency 174, 182
  diffusion 32
  distribution 286
  equilibrium potential 44
  excretion 174, 182, 184
    diuretics 174
    influence 184
  intake, high 182
  loss 264
  outflow, motor end plate 56
  renal handling 156, 182 ff.
  role in autoregulation 214
  secretion, intestine 264
K^+, absorption (cont.)
    saliva 238
    tubule 174
  stomach, parietal cells 244
K_M (Michaelis–Menten constant) 28
Kallidin 216
Kallikrein 104, 216
  salivary gland 238
Karyocytes 88
Karyolymph 8
kcal, conversion into SI unit 380
Kelvin (K), unit 381
Keratin filaments 14
Kerckring's fold 246
α-Ketoglutarate, renal production 178
  renal transport 160
Ketosis 286
17-ketosteroids 296, 304, 308
  synthesis 296
Kidney (→ also tubule and renal) 148 ff., 294
  acid base balance 138, 176
  α_1-adrenoceptors 216
  ADH receptors 166
  aldosterone effect 184
  anatomy 148, 149 A, B
  aquaporin (AQP) 166
  ATP 154
  atriopeptin effect 152
  autoregulation 150, 214
    range of 151 C
  balance glomerulotubular 166
  blood flow 150, 188
      measurement 150
      medullary 174
  Ca^{2+} excretion 180, 294
    sensors 180
  calcitriol synthesis 294
  capillaries 148 f., 151 A, 164, 186
    pressure 151 B
    hypertension 218
  circulation 150
  clearance 152, 395
    ratio of 152
    water 164
  concentration and dilution 164, 395
    mechanism 164, 166
  conjugation process 160
  connecting tubule 166
  cortex 164, 166
  countercurrent exchange 164
  diuresis 174, 178
  endopeptidase 158
  energy metabolism 150
  excretion
    ammonia/ammonium 76, 176
    Ca^{2+} 180
Kidney (cont.)
    electrolytes 157 D
    fractional (FE) 152 f.
    H^+ 142, 176
      titratable acid 180
    HCO_3^- 138, 144
    Mg^{2+} 180
    organic substances 157 D, 158, 160
    phosphate 178 f.
    steroid hormones 296
    urobilinogen 252
    water 154, 157 D, 164
      glucocorticoid effect 298
  extraction fraction 152
  filtration 148, 152
    amount of a substances 158
    dissolved substances 154
    equilibrium 152
    fraction (FF) 152
    pressure, effective 152, 396
  function 148 ff.
  glomerular filtration rate (GFR) 150
    glucocorticoid effect 298
  glomerulotubular balance
  glomerulus 148 ff.
  glucocorticoid effect 298
  glutaminase 178
  glutamine 178
  H^+-K^+-ATPase 176, 183 B4
  H^+-ATPase 176
  H^+-excretion 142, 176
  H^+-secretion 176
  handling of amino acids 158
      angiotensin 158
      Ca^{2+} 180, 294
      diuretics 156
      drugs 156
      glucose 158
      glucuronides 156
      glutathione 158
      H^+ 144, 176
      HCO_3^- 142, 176
      K^+ 156, 182 ff.
      lactate 158
      Na^+ 156, 162, 172
      oxalate 158
      peptides 158
      phosphate 178, 180, 292, 294
      proteins 158
      urea 166
      uric acid 156, 158
  inulin clearance 152, 154
  juxtaglomerular apparatus 186
  juxtamedullary nephrons 150
  K^+ channels 162
    homeostasis 182
  loop of Henle 164
  loss 174
    Ca^{2+}-reabsorption 180

Kidney (cont.)
Mg^{2+} reabsorption 180
Na^+ transport 162
water permeability 166
medulla 150
medullary blood flow 166, 174
metabolism 150, 284
Mg^{2+} sensors 180
Na^+ channels 174
Na^+-K^+-ATPase 154, 156, 162
function 154
nephron types 148, 166
O_2 consumption 150
PAH clearance 150
pH homeostasis 142, 176
plasma flow 150
potential, transepithelial 156, 162
PTH effect 180
reabsorption
Ca^{2+} 174, 292
Cl^- 162
electrolytes 157 D
fractional 154
D-glucose 158
HCO_3^- 176
K^+ 182
Mg^{2+} 174
Na^+ **162**
collecting duct 184
driving force 156
organic substances 157 D, 158
phosphate 180
PTH effect 294
water 154, 164
renal failure 142, 178
vitamin D 294
renin 186
secretion 156
K^+ 174, 182
organic substances 160
solvent drag 162
structure 148
tight junctions 154
transport processes 154 ff., 155 B,C
tubuloglomerular feedback (TGF) 174
ultrafiltrate 154
urea 166
Killer cells, natural 94, 96
T-killer cells 98
Kilo- (multiple of a unit) 379
Kilowatt hour (kWh), conversion into SI unit 380
Kinase cascades 276
Kinesia 240
Kinesin 42, 58, 62
Kininogen 102, 216, 238
high-molecular-weight (HMK) 102
salivary gland 238
Kinocilium 348
Knee jerk reflex 318
Kohlrausch's fold 266
Kohlrausch break 358
Korotkow sounds 208
Korsakoff syndrome 342
Krebs cycle → citrate cycle
Krogh's diffusion coefficient 22, 120, 394
Krogh's cylinder model 130
Kupffer cells 96, 234
kWh (kilowatt hour), unit 380

L

Labia minora, glands 310
Labyrinth 370
basal, tubulus epithelium 154
Labyrinth reflexes, tonic 330
Lacrimal canaliculi 350
glands 350
sac 350
Lactacidosis 72, 76
Lactase 260
Lactate 72, 73 B2, 74, 142, 176, 284
concentration in plasma 76
glugoneogenesis from 284
muscle metabolism 72
myocard metabolism 212
physical work 76
renal reabsorption 156, 158
vagina 304
Lactation 294
reflex 305
Lactic acid → lactate
Lactogenesis 305, 306
Lactose 260
Lamellipodia 30
L-amino acids → amino acids
Landolt rings 355 A
Langerhans cells 96
Language 340, 342, 376
Lanosterol 296
Laplace's law 118, 190, 204, 212, 396
Large intestine 234, 266
Larynx 376
testosterone 308
Lateral geniculate body 362, 364
lemniscus 374
signal flow, retina 360
Lateralization, sound 370
Latency, hearing 374
Law of mass actions 385
Laxatives 264
LCCS (limited capacity control system) 340
LCAT (lecithin cholesterol acyl transferase) 256
LDL (low density lipoproteins) 256, 258, 304
LDL (low density lipoproteins) (cont.)
estrogen effect 304
receptors 256, 258
L-dopa 84
Learning 340
Lecithin 14, 250, 254
bile 250
cholesterol acyl transferase (LCAT) 256
Left axis deviation (heart) 200
Lemniscus, medial 324
trigeminalis 324
Length, units 378
Lens 350, 352
Leptin 232
receptors 232, 332
Leucine 228
insulin release 284
Leu-enkephalin 236
Leukocytes 88
interferon secretion 96
Leukotriene 270, 271
allergy 100
second messenger 278
Lewis's response 216
Leydig cells 304, 308
LFA 1 (lymphocyte function-associated antigen 1) 98
LH → lutropin
LHRH → gonadoliberin
Libido 308
Lids 350
Light, adaptation 356, 360
sensors 350
stimuli 360
wavelength 362
Light chain protein, myosin II 60
Lignin 228, 266
Limb leads (ECG) 198
Limbic system 312, 332
α-limit dextrin 248, 260
Limited capacity control system (LCCS) 340
Linear velocity, unit 380
Linoleic acid 228
Lipase 248, 254, 258
acid 258
gastric fundus 254
hepatic 256
in human milk 254
lingual 254
non-specific 254
pancreatic 254
saliva 238
Lipid membrane 14
Lipids 254, 258
absorption 254
digestion 254
distribution 256
storage 256
synthesis 12, 13 F, 284

Lipogenesis 284
Lipolysis 86, 224, 248, 258, 284, 286
  influence 258
  insulin effect 286
  STH effect282
  stimulation, thermoregulation 224
Lipoproteinlipase (LPL) 256, 258
  insulin effect 286
  thermoregulation 224
Lipoproteins 256 ff.
  receptors 28, 256
Lipostasis 232
Lipoxygenase 271
Liter, definition 378 f.
Lithocholate 250
Liver 90, 160, 178, 234, 250, 252, 284
  acid–base homeostasis 144, 178
  bypass 234
  calcidiol synthesis 294
  coagulation factors, synthesis 102
  conjugation process 160
  damage, blood clotting 104
  excretory function 160, 250 ff.
  fatty 256
  Fe homeostasis 90
  fetal blood cell formation 88
  formation of 7-dehydro-cholesterol 294
  gluconeogenesis 284
  glutamine formation 178
  glycogenesis 284
  icterus 252
  jaundice 252
  metabolism 284
  steroid hormones, degradation 296
  urea production 178
Load, filtered 158
Locus coeruleus 330
Logarithms, calculations 386 f.
Longitudinal tubules, muscle 60
Long-term potentiation (LTP) 340
Loop, cortico-thalamo-cortical 328
  diuretics 174, 180
  oculomotor 326, 328
  skeletomotor 328
Loop of Henle 148, 164, 166, 180
Loudness 368, 376
  level 368
  voice 376
Low density lipoproteins (LDL) 258
Low pressure system 188
LRH → gonadoliberin
LTH → prolactin
LTP (long-term potentiation) 340
Luminous intensity, unit 378
Lumirhodopsin 354
Lung (→ also pulmonary) 106, 108, 110, 112
  acid base balance 138 ff.
  alveolar contact time 141 B
  blood flow 106, 122, 188
    fetus 222, 221 B
  bronchial, obstruction 120
  capacity, total (TCL) 112, 113 A
  capillaries 106
    blood pressure 122
  disease, obstructive 118
    restrictive 118
  edema 118, 120, 122, 132, 144, 174, 210
  fetal 222
  function tests, dynamic 112, 118
  gas exchange 120 ff.
  hypoxic vasoconstriction 122
  inflation 118
  iron 110, 111 A2
  O_2 diffusion capacity 22
  opening pressure 118
  perfusion → lung, blood flow122
  stretch receptors 132
  surface tension 118
  total capacity (TCL) 112
  ventilation/perfusion ratio 122
  volumes 112 ff.
    measurement 112 ff.
Lung and thorax
  compliance 116, 118
  pressure–volume relationship 116
Luteal phase 300, 302
Luteinization 302
Luteinizing hormone (LH) → lutropin
  releasing hormone (LTH) → gonadoliberin
Luteotropic hormone (LTH) → prolactin
Luteotropin (LTH) → prolactin
Lutropin 271, 282, 296, 308
  menstrual cycle 300
  peak 302
  receptor, cells of Leydig 308
  secretion, pulsatile 300
Lymph flow 210, 211 B
  intestinal 234, 256
  nodes 88, 96
  vessels 246
Lymphocyte function-associated antigen 1 (LFA 1) 98
Lymphocytes 88, 94
  B- 94, 98
    activation 98
    clonal selection 98
    differentiation 98
  clonal deletion 94
Lymphocytes (cont.)
    expansion 94
    selection 94
  intraepithelial (IEL) 234
  naive 94
  T- 94
    "armed" 94, 96
    CD4 98
    CD8 98
    cytotoxic cells 98
    clonal expansion 98
      selection 98
    differenziation 98
    naive 96
    T helper cells 98
    T_{H1} cells 98
    T_{H2} cells 98
    T killer cells 94, 98, 234
    receptor 98
Lymphocytopoiesis 88
Lymphokins, cortisol 298
Lysine 176, 228, 260
  intestinal absorption 260
Lysis, bacterial 94
Lysosomes 12, 14, 26 f., 28, 288
Lysozyme 94, 96, 234
  renal rabsorption 158
  saliva 238
  tears 350

M

μ (submultiple of a unit) 379
M (multiple of a unit) 379
m (submultiple of a unit) 379
M line, muscle 60
α_2-Macroglobulins 104
Macrophages 30, 94, 96, 98, 226, 252
  activation 96
  break down of red blood cells 88
  hemoglobin degradation 252
  immune defense 94, 96
  iron metabolism 90
  migration 30
  respiratory tract 110
Macula densa 148, 174, 186
Maculae 348
Magnesium → Mg^{2+}
Magnetoencephalography (MEG) 334
Maintenance heat 74
Major histocompatibility complex (MHC) 96, 98
Malabsorption, folic acid 90
Maldigestion, enzyme deficit 248
Malpighian bodies 148
Malleus 370
Maltase 260
Maltose 248, 260

Maltotriose 248, 260
Mammary glands 294
Mammatropic hormone → prolactin
Manganese (Mn) 228
Mannitol, osmotic diuresis 174
Mannose-6-phosphate 12, 14
Mannose-binding protein (MBP) 96
MAO (monoamine oxidase) 86
MAP kinase (mitogen-activated protein kinase) 278
Margination 94
Masking, sound 368
Masklike facial expression 328
Mass, units 380
Mass actions, law 385
Mass concentration 382
Mass movement, large intestine 266
Mast cells 104, 258
  allergy 100
Maturation, influence of thyroid hormones 290
  sexual 300, 308
Matrix, extracellular 14
Maximal breathing capacity (MBC) 118
Maximum diastolic potential (MDP) 194
MBC (maximal breathing capacity) 118
MBP (mannose-binding protein) 96
M cells, mucosal epithelium 234
MCH (mean corpuscular hemoglobin) 88 f., 89 C
MCHC (mean corpuscular hemoglobin concentration) 88, 89 C
MCV (mean corpuscular volume) 88, 89 C
MDR1 (multidrug resistance protein 1) 252
MDR3 252
Measles 94
Mechano-electric transduction (= MET) 372
Mechanosensors, skin 316, 318
Medial geniculate body 374
Mediators 270
Medications, bile excretion 250
Medulla, adrenal 274
  oblongata 132, 312, 324
    circulatory "center" 216
    rhythm generator, respiration 132
    vomiting center 240
MEG (magnetoencephalography) 334
Mega- (multiple of a unit) 379
Megakaryocytes 88, 102
Meiosis 308
Meiotic division, spermatocyte 308
    first, ovum 302
    second, ovum 310
Meissner's corpuscles 316
Meissner's plexus (plexus submucous) 246
α-Melanocortin (=α-MSH = α-melanotropin) 232, 271, 282
Melanocortin receptor (MC4 receptor) 232
Melanocytes 282
Melanocyte-stimulating hormone → melanotropin
α-Melanocyte-stimulating hormone (α-MSH) 232, 271, 282
Melanopsin 336
Melanotropin (α-MSH) 232, 271, 282
  release-inhibiting factor → melanostatin
  releasing hormone → melanoliberin
Melatonin 336
  second messenger 276, 278
Membrane
  basolateral 162, 182
  capacity, nerve 48
  conductance 32
    fractional 32
  electric properties 42, 52
  function 2
  permeability for K^+ 46, 182
      influence of cyclic AMP 276
    for Na^+ 46, 56, 162
  postsynaptic 42, 50
  potential 32, 44, 48
    photosensors 360
    renal tubule 156
    smooth muscle 70
  presynaptic 42, 50
  proteins, glycosylation 12
    synthesis 12
  structure 14
  transport 16 ff.
    active 26 f.
    carrier-mediated 22 f.
    intracellular 16
    non-ionic 22
    paracellular 18
    passive 20
    potential, driving force 22, 32
Memory 340
  immunological 94
  knowledge 340
  loss 340
  motoric 328
  short-term 340, 374
Menaquinone (Vitamin K_2) 262
Menarche 300
Menopause 300, 304
Menses 282, 300 f.
Menstrual cycle 226, 300, 302, 305
    body temperature 226, 300
    hormonal control 302
    interactions 302
Menstruation 282, 300 f.
Mercapturic acids 252
Merkel's cells 316
Merosin 60
Mesencephalon 312
Mesentery 246
Messenger, first (→ also hormones) 270, 276
  ribonucleic acid → mRNA
  second 270, 276
  substances 268
  third 270
MET (= Mechano-electric transduction) 372
MET channels 372
Metabolic alkalosis, 142
  rate 228, 230
    basal (BMR) 228
    total 228
Metabolism, amino acids 158
  bone 176, 294
  carbohydrate 284, 298
  energy 72, 286
  glucose 284, 298
  heart 212
  iron 90
  lipids 256, 284
  muscle 256
Metarhodopsin I 354
Metarhodopsin II 354, 358
  phosphorylation 356
Metastasization 30
Met enkephalin 236
Methan, intestine 266
Methemoglobin (MetHb) 128
  reductase 128
Methionine 176, 228
Methotrexate 262
5-Methyltetrahydrofolic acid 262
Methopyrapone 296
Metopyrone 296
Mg^{2+} 180, 264, 276
  absorption, intestine 264
  inhibition of Ca^{2+} channels, 50
  CNS 340
  excretion, renal 180
  plasma concentration 180
  renal reabsorption 156, 174, 180
  sensors, kidney 180
mGLU-receptors, second messenger 276, 278
$MgSO_4$ 250
MHC (major histocompatibility complexes) 96

MHC proteins 96, 98
MI (cortex area) 326
Micelle, bile 250
  intestine 254, 262
Michaelis constant 28
Michaelis-Menten constant (K_M) 28, 158, 389 f., 394
  kinetics 28, 158, 389 f., 394
  renal glucose tranport 158
Micro- (submultiple of a unit) 379
Microfilaments 14, 16
Microglia 96, 344
Micrography 328
α_1-Microglobulin, renal reabsorption 158
β_2-Microglobulin, renal reabsorption 158
Micron, conversion into SI unit 378
Microtubules 14
Micturition 79 ff., 148
Middle ear 370
MIF → melanostatin
Migrating motor complex (MMC) 242
Migrating wave 372
Migration 30
  phagocytes 94
MIH → melanostatin
Mile, conversion into SI unit 378
Milk 254, 262, 292
  Ca^{2+} 292
  ejection 282, 305
  fat 254
  human, lipase 254
  lactation reflex 305
  oxytocin 305
  production 305
  prolactin 305
  sugar (lactose) 260
Milli (submultiple of a unit) 379
Mineralcorticoids (→ also aldosterone) 184, 298
  production 296
Minerals, intake 228
  intestinal absorption 264
  nutrition 228
Miniature endplate current 56, 57 B2
Mini-pill 305
Miosis 350, 364 f.
MIT (monoiodotyrosine residue) 288
Mitochondria 12, 290
  critical O_2 pressure 130
  skeletal muscle 58, 63 A
  structure and function 12
  T_3/T_4 effect 290
  thermal balance 224
Mitral cells, olfactory bulb 346
  valves 192
MLCK (myosin light chain kinase) 36
MMC (migrating motor complex) 242
mm Hg, conversion into SI unit 380
Mobilferrin 90
Modification, posttranscriptional 10
  posttranslational 12, 270
Mol, unit 380 f.
Molality 380 ff.
Molarity 380 ff.
Molecular layer 328, 330
  "weight", unit 380 f.
Molybdenum (Mo) 228
2-Monoacylglycerol 248, 254
Monoamine oxidase (MAO) 86
Monoaminergic pathways system 332
Monocytes 88, 94, 96
Monoiodotyrosin residue (MIT) 288
Mononuclear phagocytotic system (MPS) 96
Monosaccharides (→ also glucose) 260
Monooxigenases 252
Monosynaptic stretch reflex 318
Morning sickness 240
Morphine 320
  tubular transport 160
Moss fibre, cerebellum 330
Motilin 242
  esophagus 240
  interdigestive motility 236
  secretion 236
Motility, molecular basis 58
Motion sickness 240
Motivation, limbic system 332
Motor activity 56 ff., 318 ff., **326**
    basal ganglia 326
    cerebellum 328 f.
    influence on circulation 74
    pyramidal tract 326
    voluntary motor function 326
    postural motor control 330
  aphasia 376
  cortex 326 ff.
  end-plate 56
  function, control center 328
    supportive 328
  neuron 42, 58
    α- 322, 326
    γ- 318, 322
  paralysis 324
    proteins 58, 62
  system 326
  unit 58, 66
    recruitment 58
    types 58
Mouth-to-mouth resuscitation 110
MPS (mononuclear phagocytotic system) 96
MRF → melanoliberin
MRH → melanoliberin
mRNA (messenger ribonucleic acid) 8
MRP2 (multi-drug-resistance protein type 2) 160, 252
MSH → also melanotropin
α-MSH (α-melanocyte-stimulating hormone) 232, 271, 282
Mucoviscidosis 248
Mucus 110, 238, 246
  bronchial 110
  cervical os 300
  intestine 244, 246, 266
  neck cells (MNC), stomach 242
  saliva 238
  stomach 244
Müller's maneuver 116
Multidrug resistance protein 1 (MDR1) 160, 252
    3 (MDR3) 252
Multi organ failure 220
Muramidase → lysozyme
Muscarine 82
Muscle(s) 42, 44, 46, 56 ff., 58, 59 A, 256
  abdominal 108
  activity, heat production 226
  ATP 72
  afterloaded contraction 66
  bulbocavernosus 310
  cardiac 46, 194 ff.
  ciliary 350
  contractile machinery 60 ff.
  contraction 66
    afterloaded 66, 204
    auxotonic 66 ff.
    isometric 66
    isotonic 66
    role of Ca^{2+} 64
  dilator 350
  energy supply 72, 256, 285
  extensibility 66
    titin 68
  fatigue 76
  fiber 60 ff.
  force-velocity diagram 68
  hypertrophy 76
  inspiratory 108
  intercostal 108
  ischiocavernosus 310
  length-force curve 68
  length, regulation 318
  mechanical features 66
  metabolism 284
  middle ear 370
  multi-unit type 70
  myofibrils 60

Muscle(s) (cont.)
O_2 extraction 72
pump 206
puborectal 266
reflexes 318
relaxants 56
respiratory 108, 132
resting length 68
force 68
tension curve 66
single-unit type 70
short-term high performance 72
skeletal 56 ff.
smooth 70
action potential 59 A
caldesmon 70
contraction 70
M_3-receptors 82
softening effect of ATP 64
soreness 76
spindle 318
sphincter 350
stapedius 370
stiffness 76
striated (→ also skeletal muscle, heart muscle) 59 ff.
contraction, molecular mechanism 62
cycle 64
summation of excitation 66
tension, regulation 318
tensor tympani 370
tone 66
types of contractions 66
weakness 56
Muscular dystrophies 60
Myasthenia gravis 118
Mycobacteria, immune defense 96
Mydriasis 350
Myelin 42, 48
sheath, nerve fibers 42, 48
Myelopoiesis 88
Myelosis, funicular 262
Myenteric plexus 246
Myocard → heart
Myocardial function 192 ff.
infarction 200, 220
metabolism 212
O_2 consumption 212
oxygen supply 212
Myofibrils 60
Myogenic tonus 70
Myoglobin 58, 72, 90, 128
Myometrium → uterus
Myopia 352
Myosin 58, 60
light chain kinase (MLCK) 36
smooth muscle 70
Myosin I 30
Myosin II 58, 60
Myosin II (cont.)
striated muscle 60 ff.
smooth muscle 70
Myotonia 62

N

n (submultiple of a unit) 379
N (newton), unit 380
N (nitrogen), balance 228
N_2 dissolved in plasma 134
role in diving 134
toxicity 134
Na^+ 56, 158, 162, 172, 184, 186, 260, 384
absorption in intestine 264
antiport carrier 26 f.
balance, effect of aldosterone 184
bicarbonate cotransporter 3 (= NBC3) 176
body content, total 172
channels 46, 56, 174, 264, 354
activation 46
collecting duct 162, 182
conductance 46
action potential 46
inactivation 46
intestine 264
kidney 162, 174
photosensors 354
resting potential 46
voltage-gated, heart 194
Cl^- symportcarrier 26
concentration, cytosolic 26, 44
co-transport 260
distribution 93
excretion, renal 162
feces 264
/H^+ antiport carrier (= Na^+/H^+ exchanger, NHE) 26, 28, 162, 176, 178, 248
kidney 176
PKC (protein kinase C) 278
stomach, parietal cells 244
influx, motor end plate 56
intake, hypertension 218
renal reabsorption 156
handling 162
retention 218
saliva 238
symport carrier 26 f.
amino acids 260
bile salts 250
Cl^- 28, 162, 174, 238
glucose 156 f., 260
HCO_3^- (hNBC) 162, 176
intestine 264
iodide (NIS) 288
Na^+ (cont.)
phosphate (NaPi) 180
vitamins 262
transport 44, 162, 172, 268
paracellular 238
tubular resorption 162
Na^+-Ca^{2+} antiport carrier 36, 196
kidney 180, 184
myocard 196
photosensors 356
Na^+-2 Cl^--K^+-cotransport 238
inhibition 174
kidney 162
saliva 238
Na^+-K^+-ATPase (→ also ATPase) 26, 28, 46, 182, 244, 290
cardiac glycosides 26, 196
electrogenicity 46
hyperpolarizing afterpotential 46
heart muscle 196
ouabain 26
phosphorylation 26
renal collecting duct 182
tubule 154, 156, 162
resting potential 44
salt reabsorption, intestine 264
stomach, parietal cells 244
T_3/T_4 effect 290
transport cycle 26
Na^+-taurocholate cotransporting polypeptide (NTCP) 250
NaCl, homeostasis 172
disturbances 174
regulation 172
deficiency 172
excess, counter regulation 172
hypertension 218
reabsorption, salivary glands 238
sense of taste 344
uptake 172
NADH 39 C
NaP_i (Na^+-phosphate symport carrier) 180
nano- (submultiple of a unit) 379
Narcolepsy 340
Natriuretic hormone 172
Natural killer cells 94, 96
Nausea 240, 330
NBC (= Na^+-bicarbonate cotransporter) 176, 248
Near point, eye 324, 352
sightedness 352
vision 350
response 365, 366
Necrosis 98
Neck reflex, tonic 330
Neocerebellum 328
Neostigmine 56
Nephrine 148
Nephrocalcin 180

Nephron 148, 150
cortical 150
juxtamedullary 150
sections 148
structure 148
transport processes 154
Nernst equation 32, 44, 394
Nerve (→ also neuron and nervus) 78, 84, 312
antidromic conduction 48
cell 42
cholinergic 78, 82
conduction velocity 48
endings, free, smell 346
fiber 42, 48
diameter 42, 49 C
myelinated 42, 48
unmyelinated 42, 48
fibers Ia 318
Ib 318
Iia 318
glossopharyngeal 132
neurosecretory 282
optical 350
pelvic splanchnic 310
stimulation 50
structure 42
trigeminal 320, 324, 346, 365
Nerve growth factor (NGF) 42, 280, 344
Nervous system 42
autonomic 78 ff., 80/81 A, 82, 268
centers 78
cotransmitter 86
innervation, organs 78
peripheral 268
central 268, 312
enteric 236, 268
somatic 268
Nervus opticus 350, 365
vagus 132, 244, 250, 376
Net diffusion 20
Neuroendocrine system 268 ff., 282 ff.
Neurofibrils 42
Neurofilaments 14
Neurogenic tonus 70
Neurohypophysis 270, 282
Neuron (→ also nerve) 42, 50
Aδ 320
adrenergic 78 ff., 332
axolemma 42
axon 42
axon hillock 42
axonal transport 42
Ca^{2+} conductance 44
cholinergic 78 ff.
Cl^--conductance 44
collaterals 42
conduction velocity 48, 49 C
cortex area 334
Neuron (cont.)
dendrites 42
diameter 49 C
dopaminergic 328, 332
GABAergic 328
glutamatergic 328
Ia- 318, 322, 326
Ib- 318
II- 318
instestinal 246
internal longitudinal resistance 48
membrane capacity 48
α-motor 322
γ-motor 322
motoric 326, 330
neurosecretory 282
nitrogenergic 280
parasympathetic 78, 82
postganglionic 78, 82
preganglionic 78, 82
sensoric 314 ff.
serotoninergic 332
soma 42
summation, spatial 52
temporal 52
structure 42, 43 A1
sympathetic 78, 82, 84
terminal buttons 42
action potential 48
transmission, electrotonic 48
visceral afferent 78, 236, 268
Neuropeptid Y (NPY) 84, 86, 232, 282, 302
cotransmitter 84
receptor types 55 F
second messenger 55 F, 276
Neurosecretion 282
Neurotensin 55 F
second messenger 278
Neurotransmitter 42, 50, 52, 55 F, 236, 268
autonomic nervous system 78 ff.
excitatory 52
exozytosis50
function 42
inhibitory 52
ionotropic 34, 55 F
metabotropic 34, 55 F
release 50
re-uptake 52
termination of action 54 E
Neurotubuli 42
Newborn 93 D, 94, 118, 128, 136, 222, 226, 252, 290, 307
distress syndrome 118
Newton (N), unit 380
NF-κB (necrosis factor) 278
NGF (nerve growth factor) 42, 280, 344
NH_3 22, 156, 176, 180
NH_3 (cont.)
diffusion 22
production 178
renal cellular secretion 156, 176 f.
renal excretion 176
secretion, renal tubular 178
transporter 178
NH_4^+ 145 B2, 176 ff.
excretion 178 ff.
nonionic transport 176
production 178
NHE3 → Na^+/H^+Antiportcarrier 248
Niacin, intestinal absorption 262
Niacinamide 228
Nickel (Ni) 228
Nicotine 82
Nidation 300, 305
NIDDM (non-insulin dependent diabetes mellitus) 286
Night blindness 228, 356, 358
Nipples, erection 310
NIS (2 Na^+-I^--symport carrier) 288
Nitric oxide → NO synthase (NOS) 82, 280
Nitrogen → N and N_2
N_M-receptors 82
N_N-receptors 82
NO 74, 86, 94, 212, 214, 216, 240, 280
coronary vasodilatation 212
erection 310
immune defense 94
synthase 82, 280
Nociception 320, 322, 324
tract 320
Nocisensors 320, 324
Nodal point, eye 352
Nodes of Ranvier 42, 48
Noise suppression, auditory pathway 374
Non-bicarbonate buffers 126, 138, 140, 144 f.
Non-ionic diffusion 22, 156, 178
Norepinephrine (→ also catecholamines) 52, 78, **84,** 196, 232, 238, 270, 282, 302
adrenal medulla 86
cerebral cortex 334
coronary vasodilatation 212
extraneuronal uptake 86
heart 196
inactivation 86
insulin secretion 284
intestinal tract 236
neurons 332
pheochromocytoma 218
receptor types 55 F
release 84

Norepinephrine (cont.)
re-uptake 86
saliva secretion 238
second messenger 55 F, 276, 278
synthesis 84
thermoregulation 224
NOS (nitric oxide synthase) 82, 280
NPY (Neuropeptid Y) 84, 86, 232, 282, 302
cotransmitter 84
receptor types 55 F
second messenger 55 F, 276
NREM (non-REM) sleep 336
NTCP (Na^+ taurocholate cotransporting polypeptide) 250
Nuclear bag fibers 318
chain fibers 318
envelope 10
pores 10
function 16
signal sequences 10
receptors, calcitriol 294
Nucleolus 8, 10
Nucleotides 8
Nucleus/nuclei, accessory 374
amygdaloid 332
anterior olfactory 346
arcuate 232
caudate 312, 328
cuneatus 324
Deiter 328, 330
dentate 330
emboliformis 330
fastigial 330
gracilis 324
lateral, lemniscus 374
localisation signal 10
olivaris superior lateralis 370
paraventricular 232
pedunculus pontinus 328
RNA synthesis 8
red 330
septal 332
subthalamic 328
suprachiasmatic (SCN) 336
thalamic, anterior 332
tractus solitarii 170, 344
vestibular 348
Nuel's spaces 370
Nursing mother, Ca^{2+} requirement 292
Nutrition 228
integration 236, 332
passage time, stomach 235, 242
reflex 322
vegetarian 142
Nystagmus 366
caloric 348
Nystagmus (cont.)
optokinetic 366
pathological 366
postrotatory 348

O

Ω (ohm), unit 381
O_2 (Oxygen) 72, 106
arterio-venous difference 132, 212
in myocard 212
artificial respiration 132
binding curve
in blood 126, 128
fetal hemoglobin 222, 129 C
myoglobin 129 C
breathing 136
capacity of blood 126, 128
chemosensors 132, 136
concentration, blood, maximum 128
difference, heart muscle 212
consumption 106, 120, 150, 230, 290
heart muscle 212
maximum 74, 76
measurement 112, 120
organs 130, 189 A
renal 150
T_3/T_4 effect 290
debt 72
deficiency 72,130, 136, 212, 214
ventilation 136
demands 72, 74, 130
heart muscle 212
increased 130
organ difference 130
difference, alveolar-arterial 122
arteriovenous 74, 106, 130
diffusion 21 A, 130
lung 22
tissue 130
dissociation curve 128
fetal hemoglobin 222
dissolved in plasma 128
extraction 72 f., 130, 212
coefficient 212
heart muscle 212
exercise 74
organs, difference 130
skeletal muscle 72
half saturation pressure 128
high altitude 136
Krogh's diffusion coefficient 22, 120
partial pressure 20
alveolar 120, 128
diving 134
arterial blood 128
O_2 (Oxygen) (cont.)
chemical respiratory stimulant 132
critical, mitochondria 130
high altitude 136
hyperventilation 120
mixed venous blood 120, 128
plasma 132
radicals, immune defense 94
role in autoregulation 214
saturation (S_{O_2}) 126, 128
fetus 222, 221 A
influence on CO_2 binding curve 126
solubility coefficient 128
in plasma 126
supply, fetus 222
myocard 212
therapy 136
toxicity 134, 136
diving 136
transport in blood 128
uptake, exercise 74
maximum 72, 76, 77 C
endurance athlet 77 C
OAT1 (organic anion transporter type 1) 160, 270
Obesity 232
Occludins 18
OCT (organic cation transporter) 160
Ocular chamber 350
muscle, nuclei 348
pressure, internal 322
Oculomotor control 328, 331, 348
Odorant molecules 346
OFF-bipolar cells 360
field (central) 360
ganglion cells 360, 364
OH^--ions 138 ff.
Ohm (Ω), unit 381
Ohm's law 32, 116, 190
ion transport 32, 394
circulation 190, 394
ventilation 116
Oil-and-water partition coefficient 20
Olfactory epithelium 346
pathway 346
sensor cells, primary 346
tract 346
Oligodendrocytes 42, 344
Oligopeptides, digestion 260
renal handling 158
Oligosaccharides 260
Oliguria 164
shock 220
Olive inferior 330
superior 374
Oncotic pressure 24, 94, 152, 166, 210, 384

Oncotic pressure (cont.)
influence on capillary fluid exchange 210, 385
plasma 152
One-half maximum velocity constant (K_M) 28
ON-bipolar cells 360
field (central) 360
ganglion cells 360, 364
Oocyte stage, primary 300
Oogenesis 300
Oogonia 300, 308
Open-probability, ion channels 34
Open system, thermodynamics 40
Opioids 276, 282
endogenous 320
exogenous 320
Gn-RH secretion 302
receptor types 55 F
gastointestinal tract 236
second messenger 55 F, 276
Opponent color channel 362
Opsin 354, 356
Opsonization 94, 96
Optic chiasm 364
nerve 364
lesion 364
tract 360, 364
Optical apparatus 350
nerve 350
system, simple 352
Optokinetic nystagmus 366
Orexin 232
Organ of balance 366
Corti 370
Organelles 8
Organs, blood flow 187 A, 214, 216
fetus 221 A
transplanted 98
Organum vasculosum laminae terminalis (OVLT) 282, 312, 332
Orgasm 310
Orgasmic cuff 310
Ornithine 260
Orthopnea 108
Orthostasis 5 C, 6 f., 206, 218
Orthostatic hypotension 184
reflex 7 E, 206, 218
Oscillation, unstable 6
Osmol 383
Osmolality, plasma 92
unit 383
urine 164, 174
Osmolarity 383
saliva 238
unit 383
Osmolytes, organic 170
Osmometer 383
Osmoregulation 170
Osmosensors 170, 274, 332
Osmosis 24
Osmotic coefficient 383 ff.
diuresis 174, 178
effect on K^+ excretion 184
pressure 24, 383
colloidal 92, 383
Ossicles, auditory 370
Osteoclasts 292, 294
Osteolysis, malignant 294
Osteomalacia 294
Osteoporosis 304
Otoliths 348
Ouabain 26, 172
Ounce, conversion into SI unit 380
Outer ear 370
Oval window 370, 372
Ovaries 256, 270, 296, 300, 308
HDL receptor 256
menstrual cycle 300
pregnancy 306
production, fertiliziable egg 300
testosterone production 308
Overshoot, action potential 46
Overtone 368
Overweight 228, 232
OVLT (organum vasculosum laminae terminalis) 170, 282, 312, 332
Ovulation 300, 302, 304
antiovulatory effect 305
inhibitors 302
Ovum 300, 304
first meiotic division 302
second meiotic division 310
implantation 300, 305
Oxalate 102, 158, 160, 264
inhibition, blood clotting 102
renal secretion 158, 160
Oxidation, biological molecules 41
of glucose, aerobic 72
β-oxidation 258
2-oxoglutarate 178
β-oxybutyric acid (286
Oxygen → O_2
Oxygenation 128
Oxyntic cells → parietal cells
Oxytocin 172, 271, 276, 282, **305,** 306
receptors 55 F
second messenger 55 F, 276, 278
uterus 306, 310

P

P → progesterone
$P_{0.5}$ (half saturation pressure) 128
P_A (alveolar pressure) 108
P (proportional)-Sensors 316
P (multiple of a unit) 379
p (submultiple of a unit) 379
P wave, ECG 198
Pa (Pascal), unit 380
Pacemaker 70, 242
heart 194, 196, 202
artifical 202
tertiary 194
ventricular 194, 202
intestine, motility 246
potential, heart 194
stomach 242
Pacinian corpuscles 316
PAF (platelet-activating factor) 100, 102
PAH → p-aminohippurate
Pain 320, 322, 324
assessments 320
components 320
post-exercise muscle ache 77 D
related behavior 320
Palaeocerebellum 328
Pallidum 312, 328
Pancreas 234, 248
cell types 284, 286
enzymes 248
exocrine 248
gastrin release 254
hormones 284, 286
islets 270
juice 248, 254
somatostatin 286
Pancreatic lipase 254
necrosis, acute 248
polypeptide 284
secretions 248
Pantothenic acid 228
Papilla nervi optici 350, 364
Para-aminohippurate (PAH) 150, 160
Paracellular transport 154
Paracrine action of hormones 284
Paraflocculus 328
Parallel fibres, cerebellum 330
Paralysis 62
dissociated 324
Paraplegia 322, 330
Parasites, defense against 94
Parasympathetic fibers, genital tract 216
heart 196
innervated organs 82
ganglia 78 ff.
nervous system, gastrointestinal tract 236

Parasympathetic fibers, genital tract (cont.)
saliva secretion 238
stimuli, salivary glands, blood flow 216
Parathormone → parathyrin
Parathyrin (PTH) 36, 37 C3, 180, 292
calcitriol 294
chemistry 292
deficiency 292
effects 292
influence on Ca^{2+} and phosphate excretion 180
regulation 292
renal Ca^{2+} reabsorption 180
Parathyroid glands, 270 292
hormone → parathyrin
Paravertebral ganglionic chain 78
Parkinson's disease 328
Parietal cells, gastric 242, 244
Parotid glands 238
Pars recta, renal tubule 148
Partial pressure 106, 120
Dalton law 106
Parvalbumin, muscle fibers 64
Pascal (Pa), unit 380
PAS domains 336
Passive immunization 94
Patch-clamp technique 34
Pause, compensatory 202
post-extrasystolic 202
PBI → iodine
PCT (proximal convoluted tubule) 164
PDGF (platelet-derived growth factor) 102, 280
PD-Sensors 314, 316
Peak expiratory pressure 116
inspiratory pressure 116
Pendrin 176
Pendular movements, intestine
motility 246
nystagmus 330
Penicillin, tubular secretion 156
Penis 310
erection 280
REM sleep 336
Pepsins 240, 244, 260
Pepsinogens 244, 260
PepT1 (peptide transporter 1), intestine 260
PepT2, kidney 158
Peptidase 158, 244, 248, 260
Peptide(s), catabolism, renal 148
carrier PepT1 260
PepT2 158
digestion 260
hormones 270, 276, 306
placenta 306
messenger 276
renal reabsorption 156, 158
Peptide(s), catabolism, renal (cont.)
handling 128
transmitter 55 F
Peptide-H^+-symport carrier 28, 158, 260
PER 336
Perception, visual 314
color 362
form 316
shape 316
spatial nature 316
Perfusion, cerebral 188
pulmonary 120
imbalance 120, 122, 130
Performance limit 76
Periglomerular cells 346
Perilymph 370, 372
Perimeter 364
Peripheral resistance 190, 208
influence on heart function 208
Peristalsis 236
esophagus 240
intestine 246
large 266
stomach 242
ureter 148
Permeability, Ca^{2+} 82
Cl^- 44
coefficient (P) 22
K^+ 44, 56, 82
Na^+ 44, 56, 82
Peroxidase, thyroid (TPO) 288
Peroxisomes 14
Perspiratio insensibilis 224
Perspiration 224
water losses 168
Pertussis toxin 278
Peta- (multiple of a unit) 379
Peyer's patches 234
pH 138, 146, 384
blood 132, 138
buffer 138
normal range 142
cerebrospinal fluid 126, 132
clearance, esophagus 240
erythrocytes 126
esophagus 240
homeostasis, kidney 176
role of liver 178
influence on diffusion 22
on protein bound Ca^{2+} 292
measurement 146
plasma 126, 136, 138, 142
K^+ metabolism 182
saliva 238
tubule lumen 176
urine 156
Phagocytes 94
Phagocytosis 12, 28, 96
Phase, vulnerable, heart 202
Phenol red, tubular secretion 160
Phenprocoumon 104
Phentolamine 84
Phenylalanine 228
Phenylephrine 87 B
Phenylethanolamine-N-methyl-transferase 84
Pheochromocytoma 218
Phon 368
Phosducin 356, 358
Phosphatase 278
alkaline 252
Phosphate 138, 158, 177, 180, **292,** 294
absorption, intestine 264
blood buffer 138
calcium complex former 180
concentration, serum 292
deficiency 180, 294
DNA 8
excess 180
excretion 178, 180, 294
H^+ secretion 178
homeostasis 292
intake 292
intestinal absorption 294
metabolism 292
plasma 292
renal reabsorption 158
solubility 292
Phosphadidylcholine (lecithin) 14, 250, 254
bile 250
Phosphatidylethanolamine 14
Phosphadidylinositol-4,5-bis-phosphate (PIP_2) 278
Phosphatidylserine 14
Phosphaturia 180
Phosphodiesterase 278, 354, 356
cGMP-specific 280
Phospholipase A2 248, 254
Phospholipase Cβ (PLCβ) 37 C1, 82, 84, 278
Phospholipids 254, 256
blood clotting 102
lipoproteins 256
cell membrane 14
Phosphoric acid (→ also phosphate) 142, 176
Phosphorylation 276
Photochemistry, eye 354
Photosensors 350, 352, 354
retinal distribution 354
sensor potential 360
Photopic vision 354
Phyllochinone 262
Physical activity 72 ff.
energy reserve 284
exercise capacity 76
core temperature 226
energy supply 228
heat production 224

Physical activity (cont.)
measure 74
measurement 76
work **72 ff.,** 142, 284
activation of the sympathetic nervous system 74
heat production 224
O_2 consumption 74
threshold, aerobic 76
anaerobic 76
ventilation 74
respiratory control 74, 133 A5
unit 380
Physiologic integration 268
Phytin 264
Pico- (submultiple of a unit) 379
PIF → prolactostatin
Pigmented epithelium 350
PIH (prolactin-release inhibiting hormone) → dopamine
Pineal body (= pineal gland = epiphysis) 336
Pinocytosis 28
PIP_2 (phosphadidylinositol-4,5-bisphosphate) 278
Pirenzepine 82
Pituitary gland **282,** 288
anterior 270, 282
influence of neurotransmitters 282
TSH secretion 288
TRH receptors 288
hormones 270
posterior 182, 270, 282
ADH secretion 172
hormone secretion 282
testosterone effect 308
pK_a value 138, 140, 384 f.
PKA (proteinkinase A = A kinase) 84, 276
PKC (proteinkinase C) 36, 37 C1, 70, 84, 278
PKG (proteinkinase G) 280
PKK (prekallikrein) 102
Placenta 100, 222, 294, 304, 306
Placental barrier, function 306
hormones 306
immunoglobulins 92
transfusion 222
Plasma 88, 92
albumin 92
cells 94, 98
CO_2 124
components 88, 92
factors 100
globulins 92
osmolality 92, 171
proteins 88, 92, 154, 158, 383 f.
binding 24, 25 C, 88, 154
Ca^{2+} 180, 292
blood puffer 138
Plasma (cont.)
function 88, 92, 383 f.
types 92
pH 126
thromboplastin antecedent (PTA) 102
volume 172
measurement 168
salt deficiency 172
Plasmin 104
Plasminogen 104
Plasticity of smooth muscle 70
pyramidal cells 334
Platelet(s) (→ also Thrombocytes) 88, 102
activating factor (PAF) 100, 102
activation 102
aggregation 102
inhibitors 104
derived growth factor (PDGF) 102, 280
PLC (Phospholipase C) 37 C1, 82, 84, 278
Plethysmography 114
Pleura 108
pressure (P_{pl}) 108
Plexus myentericus (Auerbach) 236, 246
submucous (Meissner) 236, 246
PMA (premotor area) 326
Pneumothorax 110
diving 134
types 110
Podocytes, glomerulus 148
Poikilothermy 224
Point, low 72
Polkissen 186
Polyethylene glycol, intestine 264
Polypeptide, pancreatic 284
Polyribosomes 10
Polysaccharides, chemical structure 227 B
digestion 260
Polysomes 10
Polysynaptic reflexes 322
Polyuria 164
POMC (pro-opiomelanocortin) 232, 282
placenta 306
Pond, conversion into SI unit 380
Pons 132, 312
eye movement 366
Pontocerebellum 328
Porphyrin 128
Portal circulation 234, 250
hypothalamus 282
vein 210, 234
Positive pressure ventilation
continuous (CPPV) 110
intermittent (IPPV) 110
Postcentral gyrus 324
Posterior funiculus, nuclei 324
Postextrasystolic pause 202
Postsynaptic inhibition 322
membrane 42, 50
Posttranslational modification 10, 12
Posttranscriptional modification 12
Postural control 330
motor function 326, 328, **330,** 348
system 326
reflex 330
labyrinthine 330
Posture 326, 330
maintaining 326
Potassium → K^+
Potentia coeundi 308
Potential, action 46 ff., 48
unit 381
diffusion 44
electrochemical 32
end-plate 56
equilibrium 44
excitatory postsynaptic (EPSP) 52, 56, 322
inhibitory prostynaptic (IPSP) 52, 82, 334
maximum diastolic, heart pacemaker 194
resting membrane 44
reversal 47 B, 56
threshold 46, 48
transepithelial 156, 182
lumen-neagtive (LNTP) 162, 238, 264
lumen-positive (LPTP) 162, 174, 180, 182
Pound, conversion into SI unit 380
Power, unit 380
Powers of ten, calculation with 386 f.
PP (pulse pressure) 196, 208
ppb (parts per billion), unit 382
ppm (parts per million), unit 382
P_{pl} (pleural pressure) 108
PQ interval, ECG 198
PQ segment, ECG 198
Prader-Willi syndrome 232
Prazosin 87 B
Prealbumin, thyroxin-binding (TBPA) 290
Precapillary sphincter 190
Pregnancy 90, 262, 292, 294, 302, 304
Ca^{2+} 292
central venous pressure 206
hormon concentrations 304
hormonal control 306, 332
nausea 240
Rh system 100

Pregnancy (cont.)
tests 296, 306
vitamin D-binding protein 294
vomiting 240
Pregnanediol 296, 305, 306
Pregnenolone 296, 305
17-OH 296
Prekallikrein (PKK) 102
Preload, heart 204, 206
Prepotential, heart 194
Preproinsulin 284
Presbyacusis 368, 372, 376
Presbyopia 352
Presentation of antigens 96
Pressure (unit) 380
Pressure, arterial sensors 216
capillary 210
central venous (CVP) 192, 206
colloidal osmotic 384
diuresis 172, 174
hydrostatic 210
feet 210
internal ocular 350
intrapleural 108
intrapulmonic 108
intrathoracic 108
oncotic 24, 210, 166, 384
peritubular capillaries 166
plasma 152
osmotic 24, 384
transmural 190
transpulmonary 108
transthoracic 108
ventricular 192, 204
volume curve, heart 68
lung and thorax 116
wave, pulse wave 192
Pressosensors, arterial 316
skin
Prestin 372
Presynaptic inhibition 322
membrane 42, 50
Pretectal region 365
Previtamin D 294
Primary, response, antigen contact 94
saliva 238
urine 164
Principal cells, kidney 162, 182
point, optical apparatus 352
PRL → prolactin
Proaccelerin 102
Probenecid 160
Procarboxypeptidase 248
Process, ciliary 350
Procolipase 248, 254
Proconvertin 102
Procreative capacity 308
Proelastase 248
Progesterone 132, 296, 300, 302, **305,** 306
actions 294, 305, 306
Progesterone (cont.)
chemistry 305
degradation 305
esophagus sphincter 240
menstrual cycle 300
17-OH- 296
placenta 306
plasma concentration 304
transport 305
production 296, 305
respiration 132
secretion rate 305
Proglucagon 286
intestinal 284
Proinsulin 282, 284
Prolactin 270, 271, 276, 282, **305**, 308
lactation reflex 305
menstrual cycle 300
receptor 280
release inhibiting hormone → prolactostatin 270 ff., 282, 300, 305
secretion, pulsatile 300
TRH effect 305
Prolactostatin (PIH = dopamine) 270 ff., 282, 300, 305
Proliferation 274
lymphocytes 94
Proliferative phase, menstrual cycle 300
Prolipase 248
Pro-opiomelanocortin (POMC) 232, 282, 306
Prophospholipase A2 254
Proportional sensors 314, 316, 318
Proprioception 316, 318, 324
Propriosensors 318, 326
neck 330
Prostacyclin (PGI_2) 104, 216, 270, 271
Prostaglandin(s) (PG) 162, 234, 236, 244, 270, 276, 278
autoregulation 214
E_2 216, 320
fever 226
effects 271
$F_2\alpha$ 216
fetal circulation 222
HCO_3^- secretion, stomach 244
I_2 (Prostacyclin) 104, 216, 270, 271
coronary vasodilatation 212
intestine 264
prostate 310
second messenger 276, 278
synthesis 271
inhibition 271, 320
uterus 306, 310
Prostate 308, 310
Protanomaly 362
Protanopia 362
Proteases, pancreatic juice 248, 260
Protective reflexes 240, 322
Protein C 104
S 104
Protein 154, 148, 228, 230
absorption, intestine 260
binding 24, 154
bound iodine 288, 290
caloric equivalent 230
capillary permability 210
catabolism, renal 148
chemical structure 229 B
concentration in cerebrospinal fluid 144
digestion 248, 260
enzymes 244, 248
energy supply 230
filtrability, glomerulus 154
functional minimum 228
hormones 270
kinase A (PKA) 84, 276
kinase C (PKC) 36, 37 C1, 70, 84, 278
kinase G (PKG) 280
kinase II (calmodulin-dependent protein) 36, 50
kinase, tyrosine specific 284
minimum intake 228
nuclear, nuclear pores 10
nutrition 228
phosphorylated 276
plant 228
plasma 92, 158
renal reabsorption 156
synthesis 10, 13 F
influence of cyclic AMP 276
Proteinuria 158, 210
Proteolysis 248
Prothrombin 102, 104
Protons → H^+
Proximal stomach 242
P (proportional)-Sensors 314, 316, 318
Pseudohypoparathyroidism 292
Psychotropic drugs 332
PTA (plasma thromboplastin antecedent) 102
Pteroylglutamate acid 262
Pteroylpolyglutamate hydrolase 262
PTH → parathyrin
Ptyalin 238, 260
Puberty 304
spermatogonia 308
Puborectal muscles 266
Pudendal nerve 266
Pulmonary (→ also lung) artery 122, 188, 192
partial pressures 122
pressure 120, 192, 208

Pulmonary artery (cont.)
blood flow 122
capillaries 106, 122, 124
circulation 188, 190
resistance 208
edema 118, 120, 122, 132, 144, 174, 210
infarction 120
stretch receptors 132
valves 192
ventilation, exercise 74
ventilation/perfusion ratio 122
Pulse pressure (PP) 192, 208
receptors 216
wave, velocity (PWV) 192
Puncts, lacrimal 350
Pupilla 350, 352
contraction 350
dilatation 350, 358, 364
role in adaptation to light 358
Pupillary reflex 358, 364
Purine, receptor types 55 F
second messenger 55 F
Purkinje cells, cerebellum 328, 330
fibers 194
action potential 202
Pursuit eye movement 366
Putamen 316, 326, 328
P wave (ECG) 192, 198
PWV (pulse wave velocity) 192
Pylorus 242
Pyramidal cells, motosensory cortex 334
tract 326
Pyridoxal 262
Pyridoxamine 262
Pyridoxine 262
Pyrogens 226
Pyruvate 73 B2
Pyruvic acid 73 B2

Q

Q10 value 40
QRS axis, ECG 200
QRS complex, ECG 198
QRS vector, mean 198, 200
QT interval, ECG 198, 200
Quinidine, tubular transport 160
Quinine 344
Quotient, respiratory 120, 136, 230
Q wave, ECG 198, 200
abnormalities 200

R

R (gas constant) 20, 32, 34, 112
R wave, ECG 198
Radiation 224, 226
Rahn valve 114
Raphe nuclei 330
RAS (renin-angiotensin system) 170, 186, 220
RA sensor (rapidly adapting pressure sensor) 316
Rate constant 40
RBC (red blood cell) → erythrocyte
RBF (renal blood flow) → kidney
RCC (red cell count) 90
Reabsorption, capillaries 210
renal tubule 148, 152 ff., 162, 176 ff., 182 ff.
Reaction, acrosomal 310
coupled 41
endergonic 38
endothermic 38
equilibrium constant 40
exergonic 38
exothermic 38
hypersensitivity (allergy) 100
rate of 40
constant 40
Reactive hyperemia 214
Reading 340
presbyopia 352
Rebound effect 274
phenomenon 330
Receptive field 316, 360
retina 360
relaxation 240, 242
Receptor (sensory receptors → sensors) 6, 55 F, 270, 314
acetylcholin → cholinoceptor
second messenger 276 f.
ADH 55 F, 214
adrenalin → adrenoceptors
adrenergic → adrenoceptors
angiotensin II 214
CCK 55 F
gallbladder 250
stomach 244
cobalamine 28
cholinergic 82
dopamin 250
epinephrine → adrenoceptors
endothelin 214
G protein-dependent 52
guanylyl cyclase 280
histamin 55 F, 214, 244, 276, 278
hormone 268, 270, 276
immunoglobulins 96
insulin 270, 284
internalization 52
ionotropic 52, 55 F, 82

Receptor (cont.)
LDL 28
mediated endocytosis 12 f.
metabotropic 52, 55 F, 82
noradrenaline → adrenoceptors
norepinephrin → adrenoceptors
proteins 270, 280, 298
recycling 12, 13 F, 29 C
serine/threonine kinase 280
synapse 50, 55 F
transferrin 90
tyrosinkinase 280, 284
tyrosine phophatases 280
Recoverin 356, 358
Recruitment, motoric unit 58
acoustic neurons 374
Rectum 234, 266
Recurrent inhibition 318, 322
Red blood cells → erythrocytes
5α-Reductase, testosteron 308
Reentry, excitation, heart 196, 202
Reference values 396 ff.
Reflection coefficient (σ) 24, 210, 383
Reflex 78, 318 ff.
abdominal 322
absence of 322
accomodation 242
arc 78
autonomic 322
conditioned 238, 244
saliva secretion 238
consensual 365
corneal 322
crossed 322
diagnostic 322
endogenous 236
extensor 322
flexion 322
gastrocolic 266
gastrointestinal tract 236
Henry–Gauer 220
Hoffmann's 318
knee jerk 318
labyrinthine postural 330
load compensation 318
locomotor 322
monosynaptic 318
neck, tonic 330
nutrition 322
orthostatic 206
peristaltic 236, 246
plantar 322
polysynaptic 322
postural 330
proprioceptive 318
protective 240, 322
pupillary 365

Reflex (cont.)
spreading 322
statokinetic 330
time 318, 322
tone 66
labyrinth 330
vagovagal, esophagus 240
vestibulo-ocular 348
withdrawal 322
Refraction, eye 352
Refractive power 352
Refractory period (action potential) 46
absolute 46
relative 46
heart 202
Regulation 4, 268
Reissner's membrane 372
Relaxation, receptive 240, 242
Relaxin 170
Release-inhibiting hormones 270, 271, 282
Releasing hormones 270, 271, 282
REM sleep (rapid eye movement) 336
Remnants of chylomicrons 258
of VLDL 256
Renal (→ also kidney) artery, stenosis 186
blood flow 150
failure 142, 178
function, glucocorticoid effect 298
Renin 148, 186
hypertension 218
Renin-angiotensin system (RAS) 170, 186, 220
control 186
Renshaw cells 318, 322, 326
Replication, cell 8
Repolarisation (action potential) 46
Repressor protein 8
Reproduction 300 ff., 332
RES (Reticuloendothelial system) (→ also macrophage and mononuclear phagocytotic system) 96
Reserve volume, expiratory 112
inspiratory 112
Residual capacity, functional (FRC) 112, 114, 116
volume (RV) 112, 114
Resistance peripheral 188, 208
hypertension 218
unit 381
vessels 188, 190
Respiration (→ also respiratory) 106
artificial 110
control 132
Respiration (cont.)
dead space 110, 114
effects of diving 134
functions 106
high altitude 132, 136
influence on venous return 110
internal 106
mechanical 110
mechanics 108, 110, 112, 144, 116
mouth-to-mouth 110
muscles 108
pressure–volume relationships 116
work of breathing 116
Respiratory acidosis 144
alkalosis 142, 144
air, purification 110
chain 12, 73 B3
compensation 142
control 132, 216
drive, high altitude 136
insufficient 144
equivalent 74, 106
exchange rate 120
muscles 132
quotient (RQ) 120, 136, 230
rate 106, 118
sensors 132
stimulants 132
volumes 112
conversion 112
standardization 112
ways, flow resistance 116
Response, local 46
Resting expiratory level 112
membrane potential 44
metabolic rate 228
position, respiration 112
pressure–volume curve, heart 204
lung and thorax 116
skeletal muscle 66
tidal volume 112, 114, 118
tremor 228
Resuscitation 110
Reticular zone, adrenal cortex 298
Reticuloendothelial system (RES) (→ also macrophage) 96
Reticulocytes 88
Reticulum, endoplasmic 10, 12, sarcoplasmic 60, 196
Retina (→ also visual and eye) 350, 352, 362, 364
contrast of a stimulus 360
corresponding points 366
ganglion cells 360, 364
processing of visual stimuli 360
receptive field 360
Retina (cont.)
sensors 350, 354
potential 360
11-*cis*-Retinal 354
Retinol 262, 356
Return, venous 206
Reversal potential 47 B, 56
Reverse-T_3 (rTr_3) 290
Rhesus system 100
Rhinencephalon 346
Rhodopsin 354, 356, 358, 362
kinase 356
Rhythm, circardian 298, 336
diurnal 336
generator 336
Rhythmicity, heart 194
Riboflavin, intestinal absorption 262
Ribonucleic acid → RNA
Ribose 8
Ribosomal ribonucleic acid → rRNA
Ribosomes 10
Rickets 228, 294
Rigidity, decerebrate 330
Right axis deviation (heart) 200
Rigor complex 64
mortis 64, 328
Rinne's test 370
Riva-Rocci (blood pressure measurement) 208
RNA (ribonucleic acid) 8 ff.
RNA polymerases 8
RNAses, pancreas 248
Rods 350, 354, 356, 362
adaptation 358
monochromatism 358
light absorption maximum 362
Roots, spinal cord 312
Rotation, sensors 348
Round window, ear 370, 372
RPF (renal plasma flow) → kidney
RQ → respiratory quotient
rRNA (ribosomal ribonucleic acid) 8, 10
rTr_3 (reverse-T_3) 290
Ruffini's corpuscle 316
RV (residual volume) 112, 114
R wave (ECG) 198
Ryanodine receptors (RYR) 62, 64
RYR 65 D
RYR1 63 B
RYR2 63 B

S

σ (reflection coefficient) 24, 383
S hormones → glucocorticoids and cortisol
S wave, ECG 198

S (siemens), unit 381
SA → sinoatrial
SA1 (slow adapting pressosensor) 316
SA2 316
Saccadic eye movement 366
Saccharin, taste 344
Saccharase 260
Saccharose 260
Saccule 348
Salbutamol 87 B
Saliva 234, 238, 260, 262
  primary 238
  secondary 238
Salivary glands 238
  blood flow 216
Salt (→ also Na^+ and Cl^-), balance 148, 162, 170
    disturbances 170, 174, 175 E
    regulation 170
  excretion 162, 172
    role in hypertension 218
  retention 172, 184
Saltatory conduction 48
Saluretics 174
Sarcoglycans 60
Sarcolemma 56, 60
Sarcomere 60 f.
  resting length 68
Sarcoplasm 60
Sarcoplasmic reticulum 60
Sarcosomes 60
Satiety peptides 232
Scala media 370
  tympani 370, 372
  vestibuli 370, 372
Scalene muscles 108
Scavenger receptors, LDL 258
Schlemm's canal 350
Schwann cells 42
Sclera 350
Sclerosis 218
SCN (suprachiasmatic nucleus) 336
Scotoma 364
Scotopic vision 354
Scurvy 228
Second messenger 270, 276, 278
    adrenoceptors 84 f.
    M-cholinoceptors 82
    neurotransmitter receptors 52, 55 C
Secondary active cotransport
  with Na^+ 26, 260
      of Cl^- 264
  response, immune defense 94
  saliva 238
Secretin 236, 242, 248, 276
  esophagus 240
  insulin secretion 284
  pancreas secretion 248
  second messenger 276
  stomach 244
Secretion, renal → kidney
  constitutive 13 F
Secretory granules 12, 270
  phase, menstrual 300
Segmentation (intestine) 246
Seizures 136
Selectins 14, 98
Selection, clonal 98
Selenium (Se) 228
Self-awareness 340
Semen emission 310
  production 308
Semilunar valves, heart 192
Seminal vesicles, testosterone effect 308, 310
Seminiferous tubules 308
Senses 314, 316, 324, 344, 346, 348
  balance 348
  chemical 344
  hearing 368 ff.
  movement 318, 348
  position 318, 348
  smell 346
  somatovisceral 316
  strength 318
  taste 344
  touch 316
  vision 350 ff.
Sensibility, somatovisceral 316
Sensitization 94, 320
  reflex pathways 340
  Rh blood groups 100
Sensor(s) 314, 342
  blood pressure 216
    volume 216
  cold 226
  D- 316, 318
  filling pressure 216
  heat 316
  light sensitive 350
  olfactory 346
  potential 314
    photosensors 356, 360
  primary 314, 346
  P- 316
  pressure 316
  proprioceptive 318
  pulse rate 216
  retina 350, 354
  secondary 314, 344, 348
    organ of corti 370
  skin 316
  smell 346
  touch 316
  vibration 316
  warm 316
Sensory aphasia 376
  impression 314
  input, central processing 324
  modality 314
  physiology 314 ff.
  receptors → sensors
SERCA (sarcoplasmic endoplasmic reticulum Ca^{2+}-transporting ATPase) 16, 64
Serotonin 102, 160, 232, 276, 278, 332, 334
  cerebral cortex 334
  neurons 332
  platelets 102, 103 A
  receptor types 55 F, 276, 278
  second messenger 55 F, 276, 278
  tubular tranport 160
Sertoli cells 308
Serum 88
  disease 100
  electrolytes, ECG 200
  sickness 100
Servocontrol 6
Servomechanism 6
Set point, variation 6
    value 4
Sex characteristics, female 304
    male 308
  chromosomes 308
  genetic 308
  hormones, binding globulin 270, 304, 308
    female 296, 300, 302
    male 296, 306, 308
    synthesis 296
Sexual arousal 310
  behavior 332
  development 308
    delayed 290
  differentiation 308
  maturation 300
  reflexes 310
  response 310
SFO (= Subfornical organ) 170
SGLT1 (sodium glucose transporter, type 1) 158
SGLT2 26, 158
SH2 (src[sarcoma]-homology) domains 280, 284, 286
SHBG (sex hormone-binding globulin) 270, 304, 308
Shear force 92
Shivering, thermoregulation 224 f.
Shock 100, 188, 208, **220**
  anaphylactic 100, 220
  causes 220
  compensation mechanisms 220
  hypoglycemic 220, 286
  index 220
  irreversibel 220
  lung 122
  manifest (progressive) 220
Shunt 120
  alveolar 120
  arteriovenous 122

Shunt (cont.)
blood flow 122, 222
extra-alveolar 120
left-to-right 222
right-to-left 222
SI units 378 f.
Sickle cell anemia 92
Siemens (S), unit 381
Sieving coefficient 24
glomerular (GSC) 154
Siggaard–Andersen nomogram 146, 147 C
Signal recognition particle (SRP) 12
Signal sequence 12
transduction 276
Sildenafilcitrate (Viagra®) 280
Silibants, voice 376
SIH → somatostatin
Silicon (Si) 228
Simultaneous contrast 360
Singing 376
Single-unit, muscle typ 70
Sinoatrial (SA) node 192, 194, 202
Sinus arrhythmia 202
bradycardia 202
rhythm 194
tachycardia 202
Skeletal growth, STH 282
Skeletal muscle 56 ff., 326 ff.
actin–myosin interaction 68
action potential 56, 59 A
all-or-none response 66
blood flow 74
regulation 216
Ca^{2+} concentration, cytosolic 66
contracture 66
difference cardiac/smooth muscle 68
fibers
extrafusal 318
intrafusal 318
stimulation 62
types 58
glycogen concentration 58
glycogenesis 284
gradation of contraction force 66
lactate production 76
length–force curve 68
mechanical features 66
mitochondria 63 A
motor units 58, 66
myoglobin function 72, 128
persistant local depolarization 66
reflex tone 66
rigor 66
complex 64
summation 66
Skeletal muscle (cont.)
superposition 66
tetanus 58, 66
Skin 74, 224, 226
α_1 -adrenoceptors 216
blood flow 188, 224
physical work 74
regulation 216
formation of cholecalciferol 294
mechanosensors 316
nocisensors 320
sensibility 316
sensory functions 224 ff., 316, 324
temperature 224, 226
thermosensors 224 ff.
Sleep 334, 336
deprivation 336
disorders 340
functions 340
phases 336
regulation 338
stages 336
Sleep–wake cycle 336
Sliding filament hypothesis 62, 64
Slit membrane, glomerular 148
SMA (suplementary motor area) 326
Small intestine 234, 242
Ca^{2+} absorption 292
cell replacement 246
function 246
motility 246
stucture 246
Smell 346
Smooth muscle 70
intestine 246
M_3 -receptors 82
SNAP-25 (synaptosome-associated protein 25) 50
SNARE (synaptosome-associated protein receptor) 30
Sneezing 132, 322
Snorkel diving 134
S_{O_2} (O_2 saturation) 126
Sodium → Na^+
Softening effect, ATP 64
Solubility coefficient, CO_2 126
O_2 128
Solubility product, calcium phosphate 292
Solutes, activity 24, 382
Solutions 382
Solvent drag 24, 156, 162
Soma, nerve cell 42
Somatic sensory functions 316
Somatoliberin 232, 236, 270, 271, 282
Somatomedins 282, 286
Somatosensory centers 316, 324
Somatostatin (SIH) 84 ff., 232, 236, 242, 270 ff., 282 ff., **286 f.**
actions 286
cotransmitter 84
effects 286
influence on glucagon secretion 274, 286
on insulin release 274, 284, 286
pancreas 284
receptors 55 F
second messenger 55 F, 276
secretion 286
stomach 236, 244
Somatotopic representation 324, 326
Somatotropin (= STH = growth hormone = GH) 271, 280, 282, 286, 290, 305
influence on insulin release 286
receptor 280
release-inhibiting hormone → somatostatin
releasing hormone → somatoliberin
Somatovisceral senses 316
Sone 368
Sorbitol 264
Sorting 12, 13 F
Sound 368
analysis 374
central processing 374
conduction 370, 372
air 370
deafness 370
direction 374
distance 374
frequencies 368, 374
intensity 368, 374
loudness 368
perception 368
physics of 368
pressure 368, 372, 374
level 368
sensors 370, 372
speech 376
stimulus 368
Space travel 136
Spatial orientation 348, 374
Spatial summation 52, 322, 358, 360, 364
Specific dynamic action → diet-induced thermogenesis
Spectrum, visible 362
Speech 238, 368, 376
fundamental frequencies 376
Sperm 30, 304, 308
capacitation 304, 310
emmision 310
estrogens 304
fertilization 310

Sperm (cont.)
maturation 308
motility 30, 58
testosterone 308
uterus 304 f.
Spermatids 308
Spermatocytes 308
Spermatogonia 308
Spermatogenesis 308
Spermatozoa 308
Spherical aberration 352
Sphincter, esophagus 240
precapillar 190
pupil 350
Spines, cerebral cortex 334
Spinal cord 78, 312, 322, 324, 326, 328
anterior roots 312
dorsal roots 312
grey matter 312
hemisection 324
ipsilateral paralysis 324
reflexes 322
segments 312
transection 330
white matter 312
ganglion 312, 320
nerves 312
shock 330
Spinocerebellum 328
Sphingomyelin 14
Spinnbarkeit of cervix mucus 300
Spiral ganglion 374
Spirometer 112, 116
Spironolactone 174
SPL (sound pressure level) 368
Spleen 234
blood cell formation 88
Spliceosome 10
Splicing 8
variable 270
Split-brain patient 342
Spot, blind 354, 364
Squalene 296
Src (sarcoma) protein 280
SRF → somatoliberin
SRH → somatoliberin
SRP (signal recognition particle) 12
Standard bicarbonate concentration 142
measurement 146
Standard temperature pressure dry (STPD) 112
Stapedius muscle 370
Stapes 370
Starch, digestion 248, 260
Starling relationship 210
Start codon 10
Starvation 142
Static (postural) work 74
Statoliths 348
Steady state 41
Stellate cells 330
Stem cells 88, 308
Step test, Margaria 76
Stercobilin 252
Stercobilinogen 252
Stereocilia 348
Stereognosis 316
Steroid diabetes 298
Steroid hormones → steroids
Steroids 250, 252, 270, 306
biosynthesis 296
degradation 296
metabolism 296
placenta 306
producing glands 296
receptors 280
secretion 250, 252, 296
sex, male 308
STH → somatotropin
Stimulus 42
adequate 314
contrast 360
transduction 314
transformation 314
Stokes–Einstein equation 20
Stomach (→ also gastric) 242, 244, 254, 260, 266
anatomy 242
chief cells 242
digestive activity 260
distal 234, 242
emptying time 234
rate 242
function 242
gastric acid 244
gastrin production 236
glands 244
juice 244
motility 242
mucus neck cells 242
parietal cells 242, 244
protein digestion 260
proximal 234, 242
secretion 244
size 242
ulcer 244
Stool 264, 266
color 252
Stop codon 10
Storage in memory 340
of energy 284
STPD (standard temperature pressure dry) 112
Strabismus 366
amblyopia 366
Strength, ionic 382
training 76
Streptokinase 104
Stress, CRH secretion 298
cortisol secretion 298
hyperprolactinemia 305
Stretch sensors 216
rectum 266
reflex 318, 330
Stria vascularis372
Striatum 328
Stroke volume (SV), heart 76, 106, 188, 192, 204, 206
increased afterload 206
preload 206
physical work 74
Strophantin 196
Struma 288
STS → somatostatin
ST segment (ECG) 198
elevation 200
Stuart–Prower factor 102
Subfornical organ 282
Sublingual gland 238
Submandibular gland 238
Substance P 52, 86, 250, 320, 326, 328
gallbladder 250
Substantia nigra 326, 328
Subsynaptic Potential 50
Successive contrast 358
color 360
Succinate, tubular transport 160
Suckling 238, 282, 305
reflex 322, 332
Sucrose, digestion 260
Sugar hormones → glucocorticoids and cortisol
Sulci, brain 312
Sulfate 156, 158, 160, 252, 264, 296
conjugates 160, 252
carrier 252
tubular secretion 156, 160
steroids 296
transcellular secretion 156, 160
intestinal absorption 264
Sulfuric acid (→ also sulfate) 142, 176
Summation 322
skeletal muscle 66
spatial 322, 360, 364
neuron 52
vision 358
temporal 322
neuron 52
vision 358
Superoxide dismutase 96
Superposition, skeletal muscle 66
Suppository 266
Suppression, saccadic 366
T helper cells 98
Supraventricular arrhythmias 202
Surface sensitivity 316
tension 118

Surfactant (surface-active agent) 118, 122
  hyperoxia 136
Suxamethonium 46, 56
SV (stroke volume), heart 76, 106, 188, 192, 204, 206
Swallowing 132, 238, 240, 242, 322
S wave (ECG) 198
Sweat 224, 226
  glands 216, 224
    innervation 78, 79 ff., 226
  secretion 226
SWS (slow-wave sleep) 336
Symbiosis hypothesis, mitochondria 12
Sympathetic → also adrenergic and autonomic
Sympathetic nervous system, activation 74
  constriction, veins 220
  flight or fight behavior 332
  gallbladder 250
  gastrointestinal tract 236
  heart 196
  physical work 74
  regulation of circulation 216
  saliva secretion 238
Symport, definition 26
Synapse 42, 50 ff., 268
  axoaxonic 322
  electrical 18, 50
  latency 52
  postsynaptic receptors 50, 55 F
  functions 42
  reciprocal 346
  valve-like function 48
Synaptic cleft 42, 50
  delay 52
  facilitation 50
  inhibition 322
  knobs 42
  pontentiation 50
  transmission 42
    termination 52, 56
Synapsin 50
Synaptobrevin 50
Synaptosome-associated protein 25 (SNAP-25) 50
Synaptosome-associated protein receptor (SNARE) 30
Synaptotagmin 50
Synchronization to day-night cycle 336
Syncytium 16, 18
Synovial A-cells 96
System, closed 40
  conicellular 364
  endocrine 268 ff.
  limbic 312, 332
  magnocellular 364
System, closed (cont.)
  opened 40
  parvicellular 364
Systole 192

T

t (ton), unit 380
T (multiple of a unit) 379
T wave, ECG 198
T_3 → triiodothyronine and thyroid hormones
T_4 → thyroxine and thyroid hormones
Tachycardia 202, 220
  atrial 202
  in shock 220
  sinus 202
  ventricular 202
Tachykinin 55 F
  second messenger 278
Tachypnea 108
Tactile motor function 316
TAL (thick ascending limb) 162
Tanning lamps, calcitriol synthesis 294
Target value (control circuit) 4
Taste 344
Taurine 250
Tawara's bundle branches 194
TBG (thyroxine-binding globulin) 290
TBPA (thyroxine-binding prealbumin) 290
TCT (thyrocalcitonin) → calcitonin
Tears 350
Tectorial membrane 370
Tectum 328
TEE (total energy expenditure) 228
Telencephalon 312
Temperature 381
  body 132, 224, 226
    circadian variation 226, 387 C
  regulation 224 ff.
  skin 224
  unit 381
Temporal lobe system 340
Temporal summation, visual receptors 358
Tendon, Golgi organs 318
Tension time index, heart muscle 212
Tensor tympani muscle 370
Terminal button 42
Testis 256, 270, 296, 308
  FSH effect 308
  HDL receptors 256
Testosteron, 5-α-dihydro 308
Testosterone 270, 302, **308**
  receptor 308
  synthesis 296
Tetanus 56
  skeletal muscle 66
  smooth muscle 70
Tetany 46, 292, 294
Tetrahydrofolate 262
Tetraiodothyronine (T_4) 288
Tetrodotoxin (TTX) 47 B
TF (= Tissue factor) 104
TFPI (= Tissue factor pathway inhibitor) 104
TGF(tubuloglomerular feedback) 174, 186
TGF(transforming growth factor)-β receptor 280
Thalamus 312, 320, 324, 344, 346, 374
  auditory pathway 374
  disinhibition 328
  visual pathway 364
Theca cells 302
Theophylline 278
Thermal balance 224
    neural factors in 227 D
Thermodynamics, laws 38 ff.
Thermogenin 224, 232, 290
Thermogenesis, non-shivering 226
Thermoneutral zone 226
Thermoregulation 224, 226
  TRH release 288
Thermosensors 226, 316
  hypothalamus 332
  central 226
Thiamine, intestinal absorption 262
Thiazide 162, 174
Thick ascending limb (TAL) 162
Thiocyanate 288
Thiouracil 288
Thirst 170, 226, 238
  shock 220
Thorax 108 ff.
Three-dimensional vision 366
Threonin 228
Threshold(s) 314, 346
  aerobic 76
  anaerobic 72, 76
  audiogram 372
  auditory 368 ff.
  potential 46, 48, 194
  recognition, smell 346
    taste 344
  visual 358
Thrombin 102, 104
Thrombocyte (→ also platelet) 88, 102 f.
  aggregation 102
    inhibition 85, 104

Thrombocytopathia 104
Thrombocytopenia 100, 104
Thrombopoietin 88, 148
Thromboprotection 104
Thrombosis 104
Thromboxane A_2 102, 216, 271, 278
  second messenger 278
Thrombus 102, 104
Thymine 8
Thymosin 268
Thymus 88, 94
Thyreotropic hormone-releasing hormone (TRH) → thyroliberin
Thyrocalcitonin → calcitonin
Thyroglobulin 288
Thyroid gland 36, 288
  hormones 288
    nuclear receptors 280, 290
    actions 290
    control of release 290
  parafollicular C cells 36, 288, 294
  peroxidase (TPO) 288
Thyroid-stimulating hormone → thyrotropin
Thyroliberin 270, 271, 282, 288, 305
  second messenger 276, 278
Thyrotropic hormone (TSH) → thyrotropin
Thyrotropin (TSH) 271, 282, 288
  receptor, autoantibody 290
  releasing hormone → thyroliberin
  second messenger 276, 278
Thyroxine (T_4) 270, 288
Thyroxine-binding globulin (TBG) 290
  prealbumin (TBPA) 290
Tidal volume 106, 112, 114, 118, 120
    alveolar part (V_A) 114, 120
    exercise 74
    maximum 77 C
    physical work 74
    training 76
Tiffeneau test 118
Tight junction, function 18
    renal tubule 154
Timbre 368
Tin (Sn) 228
Tip links 348, 372
Tissue factor (TF) 104
Tissue factor pathway inhibitor (= TFPI) 104
Tissue, hormones 270
  injury, blood clotting 103 B1
  plasminogen activator (tPA) 104
  respiration 106, 130
  thrombokinase 104
Tissue, hormones (cont.)
  thromboplastin 102
    inhibitor 104
Titin 60, 66
Titratable acid 176
Titration curve 386
T-killer cells 94, 98, 234
TLC (total lung capacity) 112, 113 A
TNF(tumor necrosis factor)α, effect on CRH secretion 298
Tocopherol 262
Tolerance, immunologic, peripheral 98
    central 94
Ton, unit 380
Tone (sound) 368
Tongue 344
Tonicity 383 f.
Tonotopicity, auditory pathway 374
Tonus, skeletal muscle 330
  smooth muscle 70
    myogenic 70
    neurogenic 70
Tonus fibers 66
  neurogenic 70
Torr, conversion into SI unit 380
Touch sensor 316
tPA (tissue plasminogen activator) 104
TPO (thyroid peroxidase) 288
TPR (total peripheral resistance) 188 f.
Trace elements 228
Trachea 376
Tractus, corticospinalis lateralis 326
  olfactoius 346
  opticus 364
  reticulospinalis lateralis 330
    medialis 330
  retinohypothalamic 336
  rubrospinalis 330
  spinocerebellaris anterior 330
  spinoreticular 320
  spinothalamicus ventralis 320, 324
  vestibulospinalis 330
Training 76
Tranexamic acid 104, 105 C
Transcellular transport 18, 154
Transcobalamine 92, 262
Transcortin 92, 298
Transcription factor, hormon-activated 280, 290
Transcytosis 18, 28
Transducin 278, 354, 356, 358
Transduction 314, 354
  channels, hair cells 372
  photoelectric 354
  signal 276
  stimulus 314
Transfer ribonucleic acid → tRNA
Transferrin 90
Transformation 314
Transforming growth factor (TGF)-β 280
Transfusion, placental 222
Translation 10
Translocation, hormone-receptor protein complex 280
Translocator protein 12
Transmembrane proteins 12
Transmission, hereditary 8 f.
Transmitter → neurotransmitter
Transplant rejection, primary 100
    immunosuppression 98
Transport, active 26
  axoplasmic 42, 58, 282
  convection 24
  electrogenic 26, 28
  electroneutral 28
  energy-dependent 26
  non-ionic 176
  paracellular 18, 154
  passive 20
  primary active 26
  rate, maximal (J_{max}) 389 f.
  rheogenic 26, 28
  saturable 28
  secondary active 26
  specific 28
  tertiary active 29 B
  transcellular 18, 154
  transmembrane 16
all-trans-retinal 354
Treadmill ergometry 76
Trehalase 260
Trehalose 260
Tremor, intention 330
  of resting 328
TRF → thyroliberin
TRH → thyroliberin
Triacylglycerol 254, 256
  absorption 254, 256
  chemical structure 229 B
  digestion 248, 256
  hydrolase 254
  lipoproteins 256
  source 259 D
  fate 259 D
  synthesis, from free fatty ecids 258
Triads 60, 62
Trigger effect, Ca^{2+}, heart 62, 196
Trigger zone, chemosensory 240
Triglycerides → Triacylglycerol
Triiodothyronine (T_3) 270, 280, 288
Trimetaphan 82
Tripalmitin 230
Tripeptides, intestinal absorption 260
Tricuspid valve 192
Tritanomaly 362

Tritanopia 362
tRNA (transfer ribonucleic acid) 8
Tropomyosin 60
Troponin 60, 62
Troponin-tropomyosin complex 64
Trypsin 248, 254, 260, 262
  activation 249 D
  CCK secretion 248
  colipase activation 254
  phospholipase A_2 activation 254
  effects 249 D
Trypsinogen 248
Tryptophan 228
TSC (thiazide sensitive co-transporter) 162
TSH → thyrotropin
T(ransversal tubules) system, skeletal muscle 60
TTX (Tetrodotoxin) 47 B
Tube, uterine 310, 311 A
Tuberculum olfactorium 346
Tubocurarine 56, 82
Tubular excretion 154
  reabsorption 154, 158
  secretion 154
Tubule (→ also Kidney), distal 148
    convoluted (DCT) 148
  driving forces for resorption 162
  epithelium, structure 154
  proximal 148, 162, 166, 176
    convoluted (PCT) 164
Tubules, longitudinal, skeletal muscle 60
  seminiferous 308
  transverse, skeletal muscle 60
Tubulin 30, 58
Tubuloglomerular feedback (TGF) 174, 186
Tumor cells, immune defense 96
Tumor necrosis factor (TNF)α 298
Tuning, hearing 374
T wave, ECG 198, 200
Two-point discrimination 316, 324
TXA_2 (thromboxane A_2) 102, 271
Tympanic cavity 370
Tyrosine 84
  derivates, hormonal 270
Tyrosine kinase-associated receptors 280

U

UCP (uncoupling protein) 232
UDP(uridindinucleotid)-glucuronic acid 252
Ulcer, gastric 244
Ultrafiltrate 154
Ultrafiltration coefficient 152
Umami 344
Umbilical artery 222
  vein 222
Unconsciousness, anoxia 130
Uncoupling protein (UCP) 232
Uniporter 28
Units, basic 378
  derived from SI units 378
  information 314
  multiples 379
  SI 378
  submultiples 379
Unmyelinated nerve fibers 48
Uracil 8
Urate → uric acid
Urea 158, 166, 178
  carrier 166
  excretion 166
  production 178
  reabsorption, renal 156, 158
  recirculation 166
  urine concentration 166
Ureter 148
  innervation 79 ff.
Urethra 310
Uric acid 158, 178
    excretion, renal 176
    reabsorption 156, 158
    secretion 156,
Urinary bladder 70, 148, 310
    innervation 79 ff.
  calculi 158, 180
Urine 148 ff., 186
  Ca^{2+} 292
  concentration mechanism 164, 166
    disorders 166
  flow rate 152
  17-ketosteroids 296
  NH^+_4 178
  osmolality 166
  pH 156, 176, 178
  primary 164
  titratable acid 176
  volume 152
Urobilinogen 252
Urokinase 104
UT1 (urea transporter Typ 1) 166
UT2 166
Uterine tube 310, 311 A
Uterus 70, 305, 306
  α_1-adrenoceptor 306
  contractions 282
  erection 310
  estrogens 304
  gap junctions 306
  menstrual cycle 300
  muscle 305
  oxytocin 305
  progesteron 305
  prostaglandins 306, 310
UTP (uridine triphosphate) 252
Utricle 348
UV light, exposure 294
    formation of vitamin D 294
    deficiency 294
Uvula, cerebellum 328

V

$\dot{V}_{O_2}$ → O_2 utilization
V_A (alveolar part of tidal volume) 114
V_D (dead space volume) 114
V_E (expiratory volume) 114
V_T (tidal Volume) 114
Vaccination 94
Vagina 304, 310
  estrogens 304
  pH 304
Vagus nerve (→ also cholinergic) 244, 250, 376
val, unit 381
Valence, ion 381
Valine 228
Valsalva's maneuver 116
Vanadium (V) 228
Vanilloid receptor Typ 1 (VR1) 316
Van't Hoff's law 24, 389, 394
    Staverman 24
Vas afferens, glomerulus 148, 186
  deferens 310
  efferens, glomerulus 148, 186
Vasa recta, renal medulla 150, 164
Vasoactive intestinal peptide (VIP) 52, 86, 234, 236, 238, 264, 276, 282
    cerebral cortex 334
    neurons 242
    rectum 266
    second messenger 276
  substances 214
Vasoconstriction 122, 214, 215 B, 216, 222
  cortisol 298
  hypoxic 122, 214, 222
    fetus 223 C
  shock 220
  thermoregulation 226
  veins 220
Vasodilatation 214, 215 B, 216, 280
  NO 280
  thermoregulation 226
Vasomotion 210
Vasopressin (→ also adiuretin) 166, 276, 278
Vegetarian diet 142
Vectorcardiogram 198
Vein(s) 190, 206

Vein(s) (cont.)
pulmonary 188
umbilical 222
valves 206
Velocity, blood flow 190
of conduction, in nerve fibres 48
detectors 316, 318
linear, unit
volume 380
Venae cavae 190
Venoles 189 A
postcapillary 190
Venous central pressure 188, **192,** 206, 220
circulation 206
flow 206
pressure 206
curve 193 A
indifference point 206
influence on capillary fluid exchange 210
shock 220
return 110, 206
artificial respiration 110
Bainbridge reflex 218
driving forces 206
respiration 206
artificial 110
Ventilation (→ also lung) 74, 106, 108, 120, 130
alveolar 106, 120
high altitude 136
peak expiratory pressure 116
inspiratory pressure 116
pressure differences 108
dead space 106, 114
diving 134
driving force for 108
exercise 74
high altitude 136
mechanical 110
muscle 108, 132
/perfusion ratio 122
regulation 126
chemosensors 126
rhythm generator 132
total 106
acidosis 142
hypoxia 136
maximum 77 C
endurance athletes 77
physical work 74
hypoxia 136
venous return 206
Ventilation–perfusion ratio 122
Ventricles, cerebrospinal fluid 312
Ventricular (→ also heart)
arrhythmias 202
fibrillation 202
pressure 192, 204
Ventricular arrhythmias (cont.)
tachycardia 202
volume 204
work diagram 204
Veratridine 47 B
Verbalization 340
Vergence, eye movement 366
Vermis 328
Vertical type (heart) 200
Vertigo 330, 348
Very low density lipoproteins (VLDL) 256, 258, 262
Vesicles 28
chromaffin 84
secretory 12, 30
Vessels, capacitance 190
wall tension 190
Vestibular ganglia 348
nuclei 330, 348
organ 348
reflex 348
Vestibulocerebellum 328
Viagra® (sildenafilcitrate) 280
Vibration, sensors 316
Vieth–Müller horopter 366
Villi, intestinal 246
Vimentin 14
VIP → vasoactive intestinal peptide
Virilization 308
Virus, immune defense 94, 96, 98
Visceral afferents 78, 236
Viscosity, blood 92, 190
Viscous-isotropic phase, lipid digestion 254
Visible spectrum 362
Vision (→ also eye and retina) 352
binocular 364, 366
color 362
day 354
threshold 358
depth 366
dim-light 354
movement 364
night 354
photopic 354
scotopic 354
three dimensional 366
Visual (→ also eye and retina)
acuity **354,** 360, 364
cortex 364
field 364
binocular 366
pathways 364
pigment 350, 354, 356
role in adaptation 356
sensors, spatial summation 358
temporal summation 358
Visual acuity (cont.)
thresholds 358
absolute 358
Vital capacity (VC) 112
forced (FVC) 118
Vitamin A 228, 254, 262, 356
deficiency 356
intestinal absorption 262
B_1 (thiamin) 228, 262
B_2 (riboflavin) 228, 262
B_6 (pyridoxin) 228, 262
B_{12} (cobalamines) 90, 228
absorption 262
C 90, 228, 262
intestinal absorption 262
renal reabsorption 156
D 228, 254, 294
daily intake 294
deficiency 264, 294
optimal 392
binding protein (DBP) 158, 294
D_2 (= ergocalciferol) 228, 294
D_3 (= cholecalciferol = calciol) 228, 262, 294
E (D-α-tocopherol) 228, 254, 262
H (biotin) 228, 262
K (Phytonadion) 102, 104, 228, 254, 266
antagonists 104
deficiency 104
K_1 228, 262
K_2 228, 262
Vitamins 228
absorption 262
deficiencies 228
fat-soluble 228, 254, 262, 304
toxicitiy 228
water-soluble 262
Vitrous body 350
opacification 136
VLA-4 (adhesion molecule) 98
VLDL (very low density lipoproteins) 256, 258, 262
estrogen effect 304
remnants 256
Vocal cord 376
paralysis 118
Voice 376
change 308
Volume clearance, esophagus 240
deficit 170, 175 E
compensation 220
shock 220
excess 170, 175 E
extracellular → ECF 168
hypertension 218
interstitial 168
intracellular → ICF 168

Volume clearance, esophagus (cont.)
ratio 382
regulation 170
unit 378
velocity 380
Voluntary motor function 326
inhibition 328
Voltage clamp 34
Vomiting 78, 142, 240
center 240
salt and water homeostasis 175 E
von Willebrand factor 102, 103 A
Vowels 376
V_1 receptor (ADH), second messenger 278
V_2 receptor (ADH) 24
second messenger 278
VR1 receptor (vanilloid receptor type 1) 316
Vulnerable phase (myocard) 202

W

W (watt), unit 380 f.
Wakefulness 324, 334
Warfarin 104
Warm sensors 224 ff., 316
Water → H_2O
Watt second, unit 380 f.
Waves, EEG 334
paroxysmal 334
slow, intestine 246
stomach motiltity 242
W cells, retina 364
Weber's rule 358
Weber's test 370
Weight, unit 380
Wernicke's area 376
Whispering 376
White matter, spinal cord 312
Wilson leads (ECG) 198
Window, oval/round 370, 372
Wind space 376
Windkessel 190, 204
Withdrawal reflex 322
Work, muscle 74
negative dynamic 74
physical 74, 142
positive dynamic 74
pressure/volume, heart 204
static postural 74
unit 380
Writing 332, 340
Ws, unit 380

X

X cells, retina 364
X-chromosome 8, 309 B,C
Xenobiotics 160

Y

Yard, conversion into SI unit 378
Yawning 132
Y cells, retina 364
Y-chromosome 8, 309 B,C
Yohimbin 87 B

Z

Zeitgeber, external 336
Zero-current potential 34
Z-plates, muscle 60
Zona fasciculata → adrenal cortex
glomerulosa → adrenal cortex
pellucida 310
reaction 310
reticularis → adrenal cortex
Zone, comfort 226, 228
thermoneutral 226
Zonulae occludentes → Tight junctions 18
Zonular fibers 350